

**PERFORMANCE OF EXPERIMENTAL
APPROACH EMBANKMENTS AT
SALT FORK RIVER BRIDGES
ON US 177**

By

SHANNON A. KOENINGER

Bachelor of Science

Oklahoma State University


Stillwater, Oklahoma

1995


**Submitted to the Faculty of the
Graduate College of
Oklahoma State University
in partial fulfillment of
the requirements for
the Degree of
MASTER OF SCIENCE
May, 1997**


**PERFORMANCE OF EXPERIMENTAL
APPROACH EMBANKMENTS AT
SALT FORK RIVER BRIDGES
ON US 177**

Thesis Approved:



Thesis Adviser







Dean of the Graduate College

ACKNOWLEDGMENTS

First of all, I would like to thank Dr. D.R. Snethen, my advisor, for his support in both my undergraduate and my graduate studies. I appreciate the faith he showed in me by allowing me to take part in this research project, and I feel I am fortunate to have had the opportunity to work for him on this research project. I am also very thankful for his continual guidance in both my studies as well as many other aspects of my life. I want to thank Dr. R.K. Hughes and Dr. V.A. Mast for serving on my thesis committee. They have both shown me constant support and encouragement throughout my academic career, for which I am grateful. I would also like to express appreciation to the Oklahoma Department of Transportation for funding this research.

I would like to express sincere thanks to my husband, Jason, for his willingness to stay in Stillwater while I pursued a Master's Degree, and his unending support throughout the process. Jeremy Hill and Shannon Hudson deserve thanks for their willingness to travel to the project site to gather data, no matter what the weather was like. Finally, I want to thank my parents for their lifelong encouragement and their unfailing belief that I could do absolutely anything.

TABLE OF CONTENTS

| Chapter | Page |
|--|------|
| 1. Introduction | 1 |
| Research Project Description | 1 |
| Purpose of Thesis | 2 |
| 2. Literature Review | 4 |
| 3. Embankment Design | 10 |
| Backfill Design and Construction | 10 |
| Instrumentation | 18 |
| 4. Data Presentation | 23 |
| North of A, A2 | 23 |
| South of B, B1 | 27 |
| North of B, B2 | 33 |
| South of C, C1 | 37 |
| North of C, C2 | 40 |
| 5. Discussion of Results | 44 |
| Performance | 44 |
| Conclusions | 50 |
| References | 53 |
| Appendix A - As-Built Instrument Locations | 55 |
| Appendix A1 - A1 Instrument Locations | 56 |
| Appendix A2 - A2 Instrument Locations | 61 |
| Appendix A3 - B1 Instrument Locations | 66 |
| Appendix A4 - B2 Instrument Locations | 71 |
| Appendix A5 - C1 Instrument Locations | 76 |
| Appendix A6 - C2 Instrument Locations | 81 |

| | |
|---|------------|
| Appendix B - Instrumentation Data..... | 86 |
| Appendix B1 - A1 Instrumentation Data..... | 87 |
| Appendix B2 - A2 Instrumentation Data..... | 93 |
| Appendix B3 - B1 Instrumentation Data..... | 100 |
| Appendix B4 - B2 Instrumentation Data..... | 107 |
| Appendix B5 - C1 Instrumentation Data | 114 |
| Appendix B6 - C2 Instrumentation Data | 121 |
| Appendix C - Instrumentation Data Plots..... | 128 |
| Appendix C1 - A1 Instrumentation Data Plots | 129 |
| Appendix C2 - A2 Instrumentation Data Plots | 137 |
| Appendix C3 - B1 Instrumentation Data Plots | 147 |
| Appendix C4 - B2 Instrumentation Data Plots | 157 |
| Appendix C5 - C1 Instrumentation Data Plots | 167 |
| Appendix C6 - C2 Instrumentation Data Plots | 177 |

LIST OF TABLES

| Table | Page |
|---|-------------|
| 1. Inclinometer Telescoping Settlement Summary for A2 | 26 |
| 2. Inclinometer Telescoping Settlement Summary for B1 | 31 |
| 3. Inclinometer Telescoping Settlement Summary for B2 | 35 |
| 4. Inclinometer Telescoping Settlement Summary for C1 | 39 |
| 5. Inclinometer Telescoping Settlement Summary for C2 | 42 |
| 6. Lateral Earth Pressure Values, Predicted and Measured | 45 |
| 7. Summary of Settlement Data | 47 |
| 8. Comparison of Estimated Settlement Values to Actual Settlement Values | 49 |

LIST OF FIGURES

| Figure | Page |
|--|------|
| 1. Embankment Design Cross Section, A2 | 11 |
| 2. Embankment Design Cross Section, B1 | 13 |
| 3. Embankment Design Cross Section, B2 | 14 |
| 4. Embankment Design Cross Section, C1 | 16 |
| 5. Embankment Design Cross Section, C2 | 17 |

CHAPTER 1

INTRODUCTION

The bump at the end of the bridge is a problem experienced by almost anyone who has traveled over a highway bridge. It is caused by differential settlement between the bridge deck and the approach slab, and the poor transition between the two is evidence of the problem. In addition to the annoyance caused to motorists, this bump can increase maintenance costs and result in expensive repairs to the roadway.

Research Project Description

This research is part of an ongoing project that is being conducted to determine how different types of approach embankments perform with respect to settlement. The project is located on US Highway 177 at the Salt Fork of the Arkansas River in Noble County approximately 8 miles south of Ponca City, Oklahoma. The project involves the construction of three bridges. The three bridges are labeled A, B, and C, with A being the southernmost bridge and C being the northernmost bridge. In addition, each bridge has two approach embankments labeled 1 and 2, with 1 being the south embankment and 2 being the north embankment (the south and north embankments of bridge A are referred to as A1 and A2, respectively). The south embankment of bridge A (A1) is approximately twice as high as the other five embankments so it is not

considered in the backfill comparisons, although it was partially instrumented. The instrumentation data for this embankment are presented in Appendix B1. Four of the six approach embankments constructed for the bridges are experimental embankments, while one serves as the control to represent a typical approach embankment. The control embankment, north of bridge A, is constructed of unclassified borrow material and represents a typical approach embankment in Oklahoma. The experimental embankments were each constructed with a different type of backfill. The embankment south of bridge B is a geotextile reinforced backfill. North of bridge B, the embankment was constructed with controlled low strength material, which is a mixture of portland cement, fly ash, sand, and water. Both approach embankment backfills for bridge C were constructed using granular material. The south embankment was dynamically compacted, while the north embankment was flooded and vibrated. Instruments were installed in the bridge approach embankments and abutment walls during construction to monitor settlement, lateral movement, lateral earth pressures, and groundwater levels. Drawings showing the layout of the various instruments are included in Appendix A.

Purpose of Thesis

The purpose of this thesis is to present the instrumentation data from the approach embankments. A literature review was completed to determine what others have done to reduce the problem of approach embankment settlement.

Construction of the embankments was completed in June, 1995, and instrumentation data were gathered at three to four week intervals until June, 1996. Since that time, data have been gathered approximately every eight weeks. The data were evaluated and compared with predicted values for settlement and lateral earth pressure. The predicted values were estimated using conventional methods.

The surface deposits at the project site are alluvium consisting of sand, clay, gravel, and silt. The foundation soils consist mostly of sand and silt, with little cohesive material. The bedrock is shale with a few limestone lenses. A complete description of the site geology, all soils tests performed at the project site, and a presentation of the boring logs are given by Benson (2); Schwidder (12) also gives a detailed description of the site geology. The type of soil for each of the embankments is uniform across the site. Therefore, it is possible to compare the performance of the experimental approach embankments and relate the performance to the construction type and material for the embankment. Comparisons were made between the performance of the different embankments and the best alternatives for bridge approach embankment construction were chosen.

CHAPTER 2

LITERATURE REVIEW

The bump at the end of the bridge has plagued highway agencies for many years. Achieving a smooth transition from the approach embankment to the bridge deck is a common problem which has no simple solution. The bump is caused by differential settlement between the bridge abutment wall and the approach embankment. Generally, the approach embankment moves vertically downward with respect to the abutment wall resulting in a number of problems. The bump causes discomfort to motorists, unnecessary wear and tear to vehicles, and can be dangerous (4). In addition to these problems, it can result in expensive roadway repairs, such as patching or mudjacking (3). Repairs take time as well as money and often cause one or more lanes of traffic to be closed for a period of time. Shutting down traffic lanes always has the potential for causing dangerous and costly accidents. Finally, the bridge structure is typically not designed for the type of impact loading that can result from an uneven roadway.

The first step in solving a problem is attempting to determine the source of the problem. Settlement of the approach embankment has a variety of possible causes. The two major causes of settlement are subsidence of the foundation material under the approach embankment and settlement within the

fill mass (6). According to the Colorado Department of Highways (1), bridge approach settlement can be attributed to one or more of the following factors:

- time dependent consolidation of the embankment foundation,
- time dependent consolidation of the approach embankment,
- poor compaction of the abutment backfill caused by restricted access of standard compaction equipment,
- erosion of the soil at the abutment face, and
- poor drainage of the embankment and abutment backfill.

In 1985, the University of Oklahoma (OU) began a study investigating approach embankment settlement in conjunction with the Oklahoma Department of Transportation (ODOT). Through an extensive survey and literature review, OU found approach embankment settlement is a problem in Oklahoma as well as in many other states (11). Better approach embankment settlement prediction methods were needed so in 1987, OU began a study of 758 bridge approaches in Oklahoma. Information relating to construction, maintenance, and materials for these approaches was collected. Of the approaches surveyed, 83% experienced settlement (10).

In 1993, OU published a statistical model for predicting bridge approach settlement. The model was based on field tests at 29 sites in Oklahoma and several equations were developed to predict settlement (9). These equations can be found in the OU report (8). The factors found to significantly affect approach settlement included age of approach, embankment height, traffic

count, foundation soil thickness, embankment soil characteristics, and foundation soil characteristics. The skewness of the approach was found to be negligible with respect to approach settlement and the embankment and foundation soil characteristics were found to have the greatest influence on approach settlement.

In 1995, OU published a computer program called FEABAS (7). The program utilized a finite element analysis procedure to predict settlement. The program predicted both the consolidation settlement of the foundation soil under an approach embankment and the settlement of the actual embankment.

When one analyzes the procedures followed for the construction of the bridge structure and the approach embankment, it becomes more apparent why the approach embankment settles with respect to the abutment wall. The foundation material for the bridge is generally subjected to substantially more analysis than the foundation material for the approach embankment. Often, the foundation material's ability to support the fill load is determined from just a few samples, while the foundation material for the bridge is analyzed extensively (13). In addition, the bridge is usually founded on spread footings, drilled shafts, or driven piles. As a result, very little or no settlement is seen with the actual structure. On the other hand, the approach embankment has problems associated with settlement within the fill, settlement of the foundation material, and the possibility that some unknowns exist with regard to the foundation material.

Precautions should be taken to reduce the settlement of the approach embankment. Four elements that must be considered when designing an approach are the embankment foundation, the backfill material, the drainage system for the embankment, and construction practices (6). Although this research project deals with varying the construction method and backfill material to reduce approach embankment settlement problems, there are other ways of reducing settlement.

When the foundation material for the approach embankment is a cause for concern, it is often because the material is a soft, compressible soil. Differential settlement often occurs between the bridge abutment and the approach embankment when the foundation material is compressible (5), and post-construction consolidation of soft foundation soils is the major cause of settlement (14). Several options are available when this is the case. First, it may be possible to remove some or all of the compressible material. This may only be practical if the problem soil is near the surface and does not extend to unreasonable depths. Another option is to preload the foundation material, which causes consolidation to occur at a faster rate. This is done with the expectation that the majority of consolidation will occur before the approach slab is paved. This generally increases earthwork costs and may require a significant amount of time to elapse before paving. When primary consolidation is the main concern, wick drains may be used to provide an exit path for water in the foundation. This generally allows primary consolidation to occur at a much

quicker rate. To reduce loading on the embankment material, a lightweight material can be used for the fill area. When large amounts of settlement are expected within the existing material, the approach can be founded on driven piles. This has been shown to be an effective alternative for providing a smooth transition between the roadway and the bridge deck. Generally, the depth of the pile decreases with increasing distance from the structure. Dynamic compaction can be used to consolidate the foundation if the foundation material is a loose, coarse grained deposit.

After the foundation material for the approach embankment has been analyzed, it is necessary to examine the backfill itself. Settlement within the fill is caused by volume change, which may be caused by consolidation, shrinking and swelling of the soil, or ice and frost action within the fill. Most state highway agencies specify that a select material be used for the approach fill. Soft clay is not a good choice because it may take years for consolidation of the material to occur. Granular materials with a high permeability and a low void ratio are preferred because compression occurs within a few months after the embankment is constructed, generally before the approach embankment is paved.

It is necessary to provide good drainage in and around the approach embankment. The backfill should be designed to remove any hydrostatic pressure from the back of the abutment wall. Erosion of the soil around and under the approach embankment can cause settlement. Surface and subsurface

drainage must be provided, and the slope under the bridge deck should be protected from erosion. As with any construction project, good quality control should be practiced during construction. Poor construction procedures or inadequate compaction of the backfill material can lead to settlement.

The above information discusses ways to reduce approach embankment settlement by considering the embankment foundation, the backfill material, the drainage system for the embankment , and construction practices. The primary focus of this research is to reduce approach embankment settlement by varying the backfill material and the construction method for five different approach embankments. This research project is unique in nature. Instead of dealing with a number of variables when attempting to reduce settlement, only the backfill material and construction are considered. By using five sites that are similar in foundation material and abutment wall height, any movement measured after construction can be attributed to one of these two variables.

CHAPTER 3

EMBANKMENT DESIGN

Backfill Design and Construction

Control Section, North of A, A2

This embankment was used as the control section for the research, and the method of construction for the embankment was determined by the contractor. The contractor was required to meet specified densities using unclassified borrow material. The material used was classified as silty sand (SM, A-2-4). Figure 1 shows the design cross section for the embankment. The control section approach embankment was 9.8 ft. thick, and the slope on the back of the fill was 1V:5H. Compaction was achieved using a Case 1150C tracked front end loader. The loader was passed over 1 ft. thick lifts with a full bucket. The loader passed over each lift twice, once parallel to the abutment wall and once perpendicular to the abutment wall. Within 2 ft. of the abutment wall and wingwalls, compaction was achieved using a walk behind pad vibrator.

Geotextile Reinforced Wall, South of B, B1

This embankment was composed of eight layers of nonwoven geotextile and granular backfill laid perpendicular to the wall. The embankment was designed to be a self supporting structure that should not come into contact with the abutment wall.




Figure 1: Embankment Design Cross Section, A2

Figure 2 shows the design cross section for the embankment. The approach embankment was 9.0 ft. thick. The backfill for the embankment was granular backfill and was classified as poorly graded sand (SP, A-1-b). Overlapping seams were used for the geotextile with a minimum overlap of 2 ft. and the minimum rollback for the geotextile at the face of the abutment wall was 3 ft. At loose lift, the layers were 12 in. thick. When the geotextile was laid, the poorly graded sand was placed on top of the geotextile, watered, and compacted. After compaction, the layers were 9 in. thick with 10 in. of soil at the rollback. During construction, a honeycomb cardboard structure was placed against the abutment wall and the wingwalls to keep the embankment from touching the wall. When the backfill was complete, the cardboard was flooded and collapsed. The average relative density for the eight lifts was 25.8%.

Controlled Low Strength Backfill, North of B, B2

This embankment was constructed using a controlled low strength material which had a design compressive strength of 300 psi. Figure 3 shows the design cross section for the embankment. The approach embankment was 9.0 ft. thick, and the slope on the back of the fill area was 1V:1H. Like the geotextile reinforced wall, the backfill was designed to be self supporting, although nothing was used to keep the controlled low strength material from coming into contact with the face of the abutment wall during construction.




Figure 2: Embankment Design Cross Section, B1




Figure 3: Embankment Design Cross Section, B2

The construction of this approach was relatively simple. After the fill area was cleared, the material was simply poured into the fill area. The total volume of controlled low strength material used for this construction was 207 cubic yards.

Dynamically Compacted Granular Backfill, South of C, C1

This embankment was constructed using poorly graded sand (SP, A-1-b). Figure 4 shows the design cross section for the embankment. The approach embankment was 8.6 ft. thick, and the slope on the back of the fill was 1V:5H. The embankment was constructed in four 2 ft. thick lifts. After the lifts were placed, they were sprayed with water and compacted. Compaction was achieved using a 4 ft. concrete cube dropped from a height of 8 ft. The area within 2 ft. of the abutment wall and wingwalls was compacted using a walk behind pad vibrator. Movement of the abutment wall and the wingwalls during construction was a concern because of the type of compaction used for this embankment. A transit was used during construction to monitor movement. The abutment wall moved 0.01 ft. north (away from the backfill), the west wingwall moved 0.01 ft. west, and the east wingwall moved 0.02 ft. east.

Flooded and Vibrated Granular Material, North of C, C2

This embankment was constructed using granular material that was classified as poorly graded sand (SP, A-1-b). Figure 5 shows the design cross




Figure 4: Embankment Design Cross Section, C1




Figure 5: Embankment Design Cross Section, C2

section for the embankment. The approach embankment was 8.6 ft. thick, and the slope on the back of the fill was 1V:5H. The embankment was constructed in two lifts that were each 4 ft. thick. Each lift was placed, spread with a front end loader, and flooded. A hand held concrete vibrator was used to densify the material. It was inserted into the lift at 1 ft. spacing over the backfill both parallel and perpendicular to the abutment wall.

Backfill Drainage

The drainage system for each approach embankment is essentially the same. A perforated PVC pipe was placed along the inside base of the abutment wall and covered with granular material to allow for drainage of the embankment. Trial sections B1, C1, and C2 used granular material in the approach embankment, so no filter sand was necessary around the drain. For A2 and B2, the perforated pipe was covered with coarse pipe underdrain material, then covered with filter sand. The perforated pipe was connected to a solid PVC pipe which ran through the base of the east wingwall and beneath the bridge. This pipe transports water from the backfill to an exit point underneath the bridge.

Instrumentation

Approach embankments for each bridge were instrumented in the same way. The instrumentation at each approach embankment consisted of three inclinometer casings (one in the abutment wall and two in the approach

embankment), one open tube piezometer, two amplified liquid settlement gages, and three total pressure cells on the back surface of the abutment wall. A grid of sixteen surface settlement points was also set in the surface of the pavement to monitor total surface movement.

The inclinometer casings were used to measure lateral movement and settlement of the backfill. Lateral movement was measured by lowering an inclinometer into the casing and measuring the tilt of the casing with respect to the vertical plane. The readings were recorded and temporarily stored in the DataMate Manager, and the data were analyzed using DigiPro software. By using the inclinometer, it was possible to detect lateral movement trends of the backfill and the abutment wall.

The inclinometer casings in the approach embankment were equipped with three telescoping couplings to determine settlement. One inclinometer casing was installed on the pavement centerline 9 ft. from the back of the abutment wall. The second was installed 10.0 ft. west of the centerline and 9.0 ft. from the back of the abutment wall. The third inclinometer without telescoping couplings was installed in the centerline of the abutment wall.

The inclinometer casings installed in the backfill each had three telescoping joints. The location of the casings and the telescoping couplings can be seen in Appendix A. The bottom of the casing was fixed in the shale with grout and was used as a reference point to measure settlement. The remaining joints were installed by attaching the joint to the bottom casing using two rivets,

one on each side of the joint. The top of the joint was attached to the upper casing using only one rivet. In theory, one rivet is not strong enough to hold the upper portion of the joint to the upper casing when settlement begins, and a shear failure of the upper rivet will occur. Thus, settlement would be determined by measuring the relative difference between the top three telescoping joints and the bottom fixed joint. A special hook was used to measure the depth to each coupling from the top of the casing. The hook was attached to a measuring tape. The hook was lowered into the casing and pulled back up. As it was pulled up, it would catch on the bottom edge of the upper casing in the telescoping coupling. The depth to each joint was recorded, and settlement within three vertical portions of the backfill was determined.

The three layers of interest under the approach embankment are the backfill, embankment, and foundation. Plots of settlement under the approach embankment according to the inclinometer telescoping coupling readings are given in Appendix C. Graph No. 1 shows the settlement of the backfill, embankment, and foundation combined. Graph No. 2 shows the settlement of the embankment and the foundation combined, and graph No. 3 shows the settlement of the foundation. The depth to each of the four couplings was recorded at the time of construction and taken as the reference value. The difference between the reading to any coupling at a given time and the reference reading was taken as the settlement for that layer. The settlement of the three layers of interest was determined in the following manner:

$\Delta H = \text{settlement}$

$\Delta H_{\text{foundation}} = \Delta(R4-R3)$

$\Delta H_{\text{embankment}} = \Delta(R4-R2) - \Delta H_{\text{foundation}}$

$\Delta H_{\text{backfill}} = \Delta(R4-R1) - \Delta H_{\text{embankment}} - \Delta H_{\text{foundation}}$

where:

R1 = depth to first telescoping coupling

R2 = depth to second telescoping coupling

R3 = depth to third telescoping coupling

R4 = depth to fourth telescoping coupling

$\Delta(R4-R1)$ = settlement of backfill plus embankment plus foundation

$\Delta(R4-R2)$ = settlement of embankment plus foundation

$\Delta(R4-R3)$ = settlement of foundation

By using the inclinometer casings with telescoping couplings, it was possible to isolate the location of settlement. This was important in determining which backfill had the least amount of settlement.

The open tube piezometer was used to measure groundwater levels. This was done to determine if there was any correlation between measured settlement and changes in groundwater depth. The piezometer was installed in the backfill 12.0 ft. from the back of the abutment wall on the centerline, and the bottom tip of the piezometer was 3.0 - 6.0 ft. above the shale.

The amplified liquid settlement gages were also used to measure settlement. They were both installed 2 ft. below the base of the abutment wall and 6 ft. from the back of the abutment wall. One was placed on the centerline, and the other was placed 10 ft. west of the centerline.

The total pressure cells were installed on the back of the abutment wall to measure the lateral earth pressures against the wall. They were spaced 3 ft. apart on the centerline of the wall and were mounted flush with the wall surface.

The surface settlement points were installed in a grid configuration with 5 ft. spacing. They covered the area from the west wingwall to the centerline and extended 20 ft. back from the abutment wall. The layout of the sixteen surface settlement points for each embankment is given in Appendix A.

The above dimensions for the instrument locations are approximate; the exact dimensions for each embankment are shown on the as-built drawings in Appendix A. Embankment A1 is lacking both the west of centerline inclinometer and the west of centerline amplified liquid settlement gage.

CHAPTER 4

DATA PRESENTATION

The instruments in each backfill were read on a periodic basis. The instrumentation data are included in Appendix B. The graphs for lateral earth pressure, lateral earth movement, settlement, and groundwater levels are included in Appendix C.

North of A, A2

Total Pressure Cells

The top total pressure cell shows 1.3 psi exerted on the back of the abutment wall. The plot for the top cell has two distinct peaks. The peaks occur in the summer months, while the valleys occur in the winter months. The data appear to be approaching another peak. The increase in pressure during the summer months is likely due to expansion of the bridge deck. When the deck expands, it pushes on the wall and causes an increase in pressure on the back of the abutment wall. The opposite is true in the winter months. The bridge deck shrinks with the decrease in temperature which decreases the pressure on the back of the wall.

The middle total pressure cell has a pressure of 1.6 psi. The data show the same trend as the top total pressure cell, but the difference between the low and the high values of the middle cell is not nearly as great as the difference

between the low and high values of the top cell. The contraction and expansion characteristics of the bridge deck cause the same decrease and increase in pressure on the middle of the wall. The effect is not as great because the middle cell is farther away from the bridge deck.

The bottom total pressure cell is experiencing a constant decreasing trend in pressure exerted on the wall. The pressure on the bottom of the wall rose immediately after construction, but has since decreased steadily. The pressure has gone from a high value of 2.2 psi to only 0.3 psi. The bottom cell is far enough away from the bridge deck that the contraction and expansion characteristics of the bridge deck do not appear to have any effect on the pressure.

The expectation for the active lateral earth pressure distribution would be increasing pressure with depth. The pressure increases from the top cell to the middle cell, then decreases to a low value at the bottom cell. The low value is not likely due to reader error because the bottom cell has shown a consistent decrease in pressure since August, 1995. As shown in Figure 1, granular backfill was placed in the area immediately behind the abutment wall. Arching of the granular material in front of the bottom cell could be contributing to the low pressure value.

Lateral Earth Movement

Lateral movement of the backfill and the abutment wall was measured using an inclinometer. Both the centerline and offset inclinometer casings are fixed in the shale. The anticipated direction of movement is south, toward the abutment wall. This is the case for the centerline, offset, and abutment wall inclinometer casings for this embankment. The magnitudes of movement are small. The top of the centerline casing has moved 0.3 in., the top of the offset casing has moved 0.4 in., and the top of the abutment wall casing has moved 0.12 in, all relative to the bottom of the casing.

In the direction parallel to the face of the abutment wall, the centerline and offset inclinometer casings have moved east toward the centerline of the roadway. The centerline casing has moved 0.06 in. at the top of the casing. The offset casing has moved 0.12 in. at the top of the casing. The casing in the abutment wall has moved west 0.05 in. toward the wingwall.

Amplified Liquid Settlement Gages

The centerline amplified liquid settlement gage data plot exhibits the expected trend. The settlement occurred within the first ten months after construction and has leveled off. The centerline amplified liquid settlement gage shows that 0.332 ft. of settlement have occurred since construction of the approach embankment.

The offset liquid settlement gage data plot shows the same trend as the centerline liquid settlement gage. The settlement for the offset is 0.247 ft. The amplified liquid settlement gages indicate settlement below the backfill, i.e., settlement of the embankment and foundation strata.

Inclinometer Telescoping Couplings

The following table summarizes the settlement for each individual stratum according to the centerline and offset inclinometer telescoping coupling readings.

Table 1: Inclinometer Telescoping Coupling Settlement Summary for A2

| ΔH (ft) | Centerline | Offset |
|-----------------------------------|-------------------|---------------|
| Δ (R4-R1) | 0.080 | 0.155 |
| Δ (R4-R2) | 0.075 | 0.080 |
| Δ (R4-R3) | 0.074 | 0.085 |
| $\Delta H_{\text{backfill}}$ | 0.005 | 0.075 |
| $\Delta H_{\text{embankment}}$ | 0.001 | -0.005 |
| $\Delta H_{\text{foundation}}$ | 0.074 | 0.085 |

The centerline backfill settlement is 0.005 ft. The centerline embankment settlement is 0.001 ft. The centerline foundation settlement is 0.074 ft. All three curves show an initial increase in settlement after construction was complete. Since October, 1995, the settlement values have remained essentially constant.

The offset backfill has exhibited 0.075 ft. of settlement since construction. The settlement for graph No. 1 is leveling off. The offset embankment has settled -0.005 ft. Graph No. 2 showed a sudden increase in settlement in October, 1995, which could be attributed to rivet shear in the second telescoping

coupling. The offset foundation has exhibited 0.085 ft of settlement. The settlement plot shows significant variation in the readings for the foundation settlement.

Surface Settlement Points

The surface settlement point data were evaluated for both wheel paths of the average vehicle. The wheel path closest to centerline is composed of reading points 4, 8, 12, and 16. The offset wheel path is composed of reading points 2, 6, 10, and 14. The centerline wheel path has settled 0.03 ft. at a location 5 ft. behind the abutment wall, and 0.061 ft. at a location 20 ft. behind the abutment wall. The plot for this wheel path indicates a slight dip at reading point 8 and a significant dip at reading point 16. This means that the approach embankment is settling more with increasing distance from the abutment wall.

The offset wheel path has settled 0.058 ft. at a location 5 ft. behind the abutment wall and 0.043 ft. at a distance 20 ft. behind the abutment wall. The plot shows that a depression has developed at reading point 14, and a bump at the end of the bridge is beginning to develop for this approach.

South of B, B1

Total Pressure Cells

The top total pressure cell shows 0.2 psi exerted on the back of the wall. The total pressure versus time plot shows two distinct peaks in pressure. These

peaks occur in the summer, which can be attributed to expansion of the bridge deck with the increase in temperature. This expansion causes the pressure on the back of the wall to increase, as explained earlier.

The middle total pressure cell shows 0.5 psi on the back of the abutment wall. Shortly after construction, the pressure reached 2.4 psi, but it decreased and has remained at 0.5 psi since that time. The middle cell shows no variation of pressure with temperature change.

According to the bottom total pressure cell, the total pressure on the bottom of the wall is 1.7 psi. There are fluctuations in the plot, but the pressure on the bottom of the wall has shown a general downward trend since the pressure peaked at 8.8 psi shortly after construction.

On May 2, 1996, the cardboard that was placed against the abutment wall for construction purposes was flooded and collapsed. This caused an initial increase in pressure of 0.1 psi on the top cell and 0.2 psi on the middle cell. These values are such small increases that the change is not significant. There was an immediate decrease in pressure on the bottom cell of 1.8 psi. This indicates that the cardboard structure collapsed as planned.

This embankment shows an increase in lateral earth pressure with depth. The increase in pressure from the top to the middle cell is slight, especially in the summer months when the pressure in the top cell can increase to 0.5 psi. The backfill for this embankment was designed to be self supporting. In theory, the backfill should never come in contact with the abutment wall. Since the

backfill is in contact with the abutment wall, it is necessary to identify possible reasons for the problem. The geotextile fabric in the embankment could be creeping, which would put the backfill into contact with the wall. Also, the density of the sand within the backfill could be insufficient. The average relative densities for the eight layers was only 25.8%, which correlates to a loose material. This indicates that even though the required standard Proctor-based densities were met, the relative densities should have been higher. The densities were specified using the standard Proctor test which is not a good test for cohesionless soils.

Lateral Earth Movement

The centerline inclinometer casing shows movement toward the bridge (north), which is the expected direction of movement. The centerline casing has moved 0.25 in. at the top of the casing. The offset casing has exhibited movement both toward and away from the abutment wall. The plot of lateral displacement is variable, but the magnitude of movement is less than 0.07 in. The inclinometer casing in the abutment wall indicates that the abutment wall is moving south toward the backfill. The indication from the casing in the abutment wall may be misleading. The bottom of the casing in the abutment wall is not fixed. The casing could actually be moving toward the bridge but be tilted toward the backfill at the top of the casing. The casing would tilt toward the backfill if it began moving toward the bridge because the bridge deck would

prohibit the top of the casing from moving toward the bridge. The abutment wall casing has moved 0.08 in. at the top of the casing.

All three of the casings show westward movement in the direction parallel to the wall. The magnitudes of movement are very small. The centerline casing has moved 0.015 in., the offset casing has moved 0.25 in., and the cumulative movement of the abutment wall is zero.

Amplified Liquid Settlement Gages

The centerline amplified liquid settlement gage data plot shows 0.264 ft. of settlement. The settlement increased rapidly after construction then began leveling off in February, 1996.

The offset amplified liquid settlement gage data plot shows a settlement of 0.214 ft. The plot of settlement versus time shows a downward trend, and settlement appears to be continuing under the offset gage.

Inclinometer Telescoping Couplings

The following table summarizes the settlement for each individual stratum according to the centerline and offset inclinometer telescoping coupling readings.

Table 2: Inclinator Telescoping Coupling Settlement Summary for B1

| ΔH (ft) | Centerline | Offset |
|--------------------------------|------------|--------|
| $\Delta (R4-R1)$ | 0.057 | 0.126 |
| $\Delta (R4-R2)$ | 0.018 | 0.028 |
| $\Delta (R4-R3)$ | 0.016 | 0.016 |
| $\Delta H_{\text{backfill}}$ | 0.039 | 0.098 |
| $\Delta H_{\text{embankment}}$ | 0.002 | 0.012 |
| $\Delta H_{\text{foundation}}$ | 0.016 | 0.016 |

The centerline backfill has experienced 0.039 ft. of settlement. The centerline embankment has settled 0.002 ft. since construction, and the centerline foundation has settled 0.016 ft. since construction. All three centerline plots showed higher settlement values during the period of July, 1995, to May, 1996. Since May, 1996, the settlement readings have been consistently lower. This could be attributed to reader error since different people read the depths on different dates.

The offset backfill has settled 0.098 ft. There was a sudden increase to this value in May, 1996, and it has remained at this value since that time. The offset embankment has settled 0.012 ft., and appears to be remaining constant. The offset foundation has settled 0.016 ft., and is also remaining constant. Both the embankment and foundation settlements have exhibited a very gradual increase over time and appear to have leveled off.

The foundation layer shows the same amount of settlement (0.016 ft.) for both the centerline and the offset inclinometer. Also, the embankment layer has settled very little according to both inclinometer readings. The majority of settlement appears to be in the backfill, which again indicates that the densities

required for the backfill were not as high as they should have been. Elastic settlement of the sand in the backfill could be contributing to the backfill settlement.

Surface Settlement Points

As with embankment A2, the surface settlement data were evaluated for both of the wheel paths. The wheel path closest to centerline is composed of reading points 4, 8, 12, and 16. The offset wheel path is composed of reading points 2, 6, 10, and 14. The centerline wheel path has settled 0.053 ft. at a distance of 5 ft. behind the abutment wall, and has settled 0.022 ft. at a distance of 20 ft. behind the wall. It has significantly more settlement near the abutment wall.

The offset wheel path has settled 0.058 ft. at a distance of 5 ft. behind the wall, and has settled 0.048 ft. at a distance of 20 ft. behind the wall. This wheel path has settled uniformly, and while it has a little more settlement near the abutment wall (0.01 ft.), it is not as significant as the differential settlement for the centerline wheel path.

The bump at the end of the bridge has started to develop at this approach. This indicates that although the required densities were achieved during construction of this embankment, the required densities were not great enough to eliminate a bump at the transition between the bridge approach and deck.

North of B, B2

Total Pressure Cells

There are 0.4 psi of pressure exerted on the back of the abutment wall at the top cell. There was an initial peak in the pressure at the top cell shortly after construction, but the value has remained constant at 0.4 psi since March, 1996. The initial peak could be a result of the hydrostatic pressure of the wet controlled low strength material shortly after construction.

The middle total pressure cell measures 0.1 psi of pressure on the back of the abutment wall. The pressure on the middle cell reached a peak of 2.8 psi shortly after construction but has stayed below 0.5 psi since May, 1995. The plot has small peak values of 0.5 psi in the summer months. The peaks could be due to thermal expansion of the bridge deck or the backfill itself during summer months, but if this were the case, the same trend would be exhibited in the top pressure cell.

The pressure on the bottom total pressure cell is 0.9 psi. The pressure has increased from an average value of 0.7 psi before May, 1996, to recent values in the 0.8 - 1.0 psi range. The sand covering the lower cell, as shown in Figure 3, could be putting pressure on the lower cell.

Like the geotextile reinforced embankment, this backfill was designed to be self supporting. Nothing was placed between the controlled low strength material and the abutment wall during construction so the material is in contact

with the wall. The pressure is higher than expected. This could be attributed to movement of the controlled low strength material toward the abutment wall as the pressure is fairly uniform (less than 1 psi) along the face of the abutment wall.

Lateral Earth Movement

The data from the centerline inclinometer show the casing has moved 0.2 in. toward the bridge at the top of the casing. At a depth of 5 ft., the movement toward the bridge reduces to 0.00 in. The larger indication of movement at the top of the casing is inconsistent with the rest of the data, so 0.00 in. is a better assessment of actual movement. The offset inclinometer data show 0.06 in. of movement toward the bridge at the top of the casing. The abutment wall casing has moved 0.02 in. toward the bridge at the top of the casing. The middle section of this casing has moved 0.06 in. toward the backfill. This is probably due to an error in the reference data set because the subsequent data sets show the movement toward the backfill.

In a direction parallel to the abutment wall, the centerline casing has moved 0.01 in. east. The offset casing has moved 0.03 in. west toward the wingwall. The data for the abutment wall in this direction also indicate that the initial data set is incorrect. The data show that the top of the casing has moved east 0.15 in. If the reference and the June data sets were ignored, movement would only be 0.02 in. west.

Amplified Liquid Settlement Gages

The centerline amplified liquid settlement gage shows a settlement of 0.348 ft. The settlement showed an increase following construction and has since leveled off.

The offset amplified liquid settlement gage has 0.143 ft. of settlement. Although there are some variations in the plot, it has shown a general increase in settlement since construction. Settlement is still occurring according to the offset amplified liquid settlement gage data.

Inclinometer Telescoping Couplings

The following table summarizes the settlement for each individual stratum according to the centerline and offset inclinometer telescoping coupling readings.

Table 3: Inclinometer Telescoping Coupling Settlement Summary for B2

| ΔH (ft) | Centerline | Offset |
|--------------------------------|------------|--------|
| Δ (R4-R1) | -0.080 | 0.028 |
| Δ (R4-R2) | 0.050 | 0.090 |
| Δ (R4-R3) | 0.050 | 0.040 |
| $\Delta H_{\text{backfill}}$ | -0.130 | -0.062 |
| $\Delta H_{\text{embankment}}$ | 0.000 | 0.050 |
| $\Delta H_{\text{foundation}}$ | 0.050 | 0.040 |

The centerline backfill has consistently shown upward movement since construction. This is difficult to explain as there is no plausible reason for upward movement. The indication of upward movement could be due to

inconsistent installation of the inclinometer casing. The entire tube may have been pushed down further than it should have been during construction which would have altered the bottom reading. The embankment settlement also has some negative settlement values, but the average settlement is 0.000 ft. The foundation settlement is 0.050 ft.

The offset backfill settlement is -0.062 ft. As before, the negative value is difficult to explain. The embankment settlement is 0.050 ft., and the foundation settlement is 0.040 ft. Both the embankment and the foundation settlement values are questionable because, over time, the plots show upward movement of the embankment.

Surface Settlement Points

The surface settlement data for the two vehicle wheel paths were evaluated. The wheel path closest to centerline is composed of reading points 4, 8, 12, and 16. The offset wheel path is composed of reading points 2, 6, 10, and 14. The centerline wheel path has had 0.036 ft. of settlement at a distance of 5 ft. behind the abutment wall, and 0.013 ft. of settlement at a distance of 20 ft. behind the wall. The most settlement has occurred at reading points 4 and 12, 5 ft. and 15 ft. behind the wall, respectively. This means that there is a small dip at each of these points.

The offset wheel path has had 0.030 ft. of settlement 5 ft. behind the abutment wall, and 0.041 ft. of settlement 20 ft. behind the wall. The settlement

for this wheel path is more uniform than the settlement for the centerline wheel path. The change in surface elevation increases with distance from the abutment wall.

South of C, C1

Total Pressure Cells

The pressure on the top cell peaked after construction and immediately decreased to a value of 0.1 psi. It has remained at 0.1 psi since that time.

The pressure on the middle cell is 1.8 psi. The plot shows two definite peaks in total pressure on the middle cell. One peak is in July, 1995, and the other is in October, 1996.

The pressure on the bottom cell is 2.4 psi. The plot for the bottom total pressure cell also shows peaks in July, 1995, and October, 1996. The variations in pressure on the middle and bottom cell are probably due to seasonal temperature variations. Expansion of the bridge deck in the summer months causes more pressure on the back of the wall. The lack of cyclic behavior in the top cell suggests that the soil is not as dense near the top cell as it is near the middle and bottom cells. The soil around the top cell could be arching which would result in less pressure on the top cell.

Lateral Earth Movement

The top of the centerline casing has moved 0.12 in. toward the bridge. The offset casing has moved 0.12 in. toward the bridge. The abutment wall casing has moved 0.20 in. away from the bridge. This could indicate that the abutment wall has moved toward the bridge but is tilted into the backfill at the top of the wall because of the bridge deck, as explained earlier.

In a direction parallel to the abutment wall, the centerline casing has shown small movements in both the east and the west direction. It has moved 0.15 in. west at the top of the casing. The offset casing has moved 0.06 in. east at the top of the casing. The abutment wall casing has moved west 0.25 in.

Amplified Liquid Settlement Gages

The centerline settlement gage stopped functioning properly in May, 1996. Prior to that time, 0.364 ft. of settlement had occurred, and settlement appeared to be continuing.

The offset settlement gage shows that 0.343 ft. of settlement have occurred. The plot looks like it is approaching a constant value, but a small amount of additional settlement will likely occur before it does.

Inclinometer Telescoping Couplings

The following table summarizes the settlement for each individual stratum according to the centerline and offset inclinometer telescoping coupling readings.

Table 4: Inclinometer Telescoping Coupling Settlement Summary for C1

| ΔH (ft) | Centerline | Offset |
|--------------------------------|------------|--------|
| Δ (R4-R1) | 0.083 | 0.265 |
| Δ (R4-R2) | 0.055 | 0.050 |
| Δ (R4-R3) | 0.050 | 0.085 |
| $\Delta H_{\text{backfill}}$ | 0.028 | 0.215 |
| $\Delta H_{\text{embankment}}$ | 0.005 | -0.035 |
| $\Delta H_{\text{foundation}}$ | 0.050 | 0.085 |

According to the centerline inclinometer telescoping coupling readings, the backfill stratum has settled 0.028 ft. The embankment has settled 0.005 ft. The foundation has settled 0.050 ft.

According to the offset telescoping coupling readings, the backfill has settled 0.215 ft. The embankment has settled -0.035 ft. The foundation has settled 0.085 ft. Again, the negative value for the embankment settlement raises questions about the reliability of the inclinometer data. For both the centerline and the offset inclinometer readings, the foundation has exhibited a large amount of settlement, and the embankment has exhibited little settlement. However, the large difference between the centerline and offset values for settlement of the backfill is questionable.

Surface Settlement Points

The wheel path closest to centerline consists of reading points 4, 8, 12, and 16. At a distance of 5 ft. behind the abutment wall, 0.027 ft. of settlement has occurred, and 0.012 ft. of settlement has occurred 20 ft. behind the abutment wall. Initially, there was a dip in the pavement at reading point 12, and the pavement was flat between points 8 and 4. Now, the dip extends from point 12 to point 8 before coming back up to point 4. Point 8 has settled 0.044 ft. which is the largest amount of settlement for this wheel path.

The offset wheel path consists of reading points 2, 6, 10, and 14. At a point 5 ft. behind the abutment wall, 0.039 ft. of settlement has occurred. At a point 20 ft. behind the abutment wall, 0.027 ft. of settlement has occurred.

North of C, C2

Total Pressure Cells

The top total pressure cell had an initial peak in pressure of 0.6 psi. Then pressure decreased to 0.1 psi, where it remained constant until October, 1996. It then began increasing and recently reached a value of 0.3 psi.

The middle total pressure cell has shown a steady increase in pressure since construction. The total pressure is 1.6 psi. The pressure appears to be approaching a constant value.

The bottom cell has also been increasing steadily since construction and has reached a value of 3.4 psi. It also appears to be reaching a constant value.

Of the five embankments, C2 is the most consistent with expectations in terms of pressure distribution. The wall has a nearly linear pressure distribution from the top cell to the bottom cell.

Lateral Earth Movement

The centerline inclinometer casing has moved 0.15 in. toward the bridge, The offset inclinometer casing has moved 0.10 in. toward the bridge. The abutment wall casing has moved 0.08 in. toward the bridge.

In a direction parallel to the abutment wall, the centerline casing has moved 0.03 in. east. The top of the offset casing has moved 0.01 in. west. The abutment wall casing has moved 0.25 in. west.

Amplified Liquid Settlement Gages

The gages both had questionable readings in February, 1997. The readings could be the result of insufficient flow in the system.

Settlement for the centerline amplified liquid settlement gage is 0.200 ft. The settlement is approaching a constant value.

Settlement for the offset gage is 0.071 ft. The plot for the offset gage is variable.

Inclinometer Telescoping Couplings

The following table summarizes the settlement for each individual stratum according to the centerline and offset inclinometer telescoping coupling readings.

Table 5: Inclinometer Telescoping Coupling Settlement Summary for C2

| ΔH (ft) | Centerline | Offset |
|--------------------------------|------------|--------|
| $\Delta (R4-R1)$ | 0.045 | 0.315 |
| $\Delta (R4-R2)$ | 0.038 | 0.035 |
| $\Delta (R4-R3)$ | 0.026 | 0.040 |
| $\Delta H_{\text{backfill}}$ | 0.007 | 0.280 |
| $\Delta H_{\text{embankment}}$ | 0.012 | -0.005 |
| $\Delta H_{\text{foundation}}$ | 0.026 | 0.040 |

According to the centerline telescoping coupling, the backfill has settled 0.007 ft. The settlement seems to have reached a constant value since the total settlement value ($\Delta (R4-R1)$) has remained at 0.045 ft. since May, 1996. The embankment has settled 0.012 ft., which is also a constant value. The foundation has settled 0.026 ft. The plot for the foundation settlement has not leveled off, and some additional settlement may occur.

The offset inclinometer telescoping coupling indicates that the backfill has settled 0.280 ft. The settlement was gradually decreasing after construction but experienced a significant increase in May, 1996. This could indicate that the rivet in the first telescoping coupling sheared in May, 1996. The embankment settlement has been gradually increasing since construction, and settlement appears to have stopped at -0.005 ft. The foundation settlement has also been

decreasing since construction and it seems to have stopped at 0.040 ft. The settlement indicated by the offset inclinometer readings is significantly greater than the settlement indicated by the centerline inclinometer readings. There is also a negative value of settlement for the embankment indicated by the offset inclinometer which suggests that these readings are unreliable.

Surface Settlement Points

The wheel path closest to centerline contains reading points 4, 8, 12, and 16. For this wheel path, 0.033 ft. of settlement has occurred at a point 5 ft. behind the abutment wall, and 0.041 ft. of settlement has occurred at a point 20 ft. behind the abutment wall. A slight bump is developing at reading point 12.

The offset wheel path contains reading points 2, 6, 10, and 14. At a point 5 ft. behind the abutment wall, 0.053 ft. of settlement has occurred. At a point 20 ft. behind the abutment wall, 0.049 ft. of settlement has occurred. Settlement is uniform along this wheel path.

CHAPTER 5

DISCUSSION OF RESULTS

Performance

Total Pressure Cells

The pressure on the back of the abutment walls was measured at three heights using total pressure cells. The theoretical lateral earth pressure values were predicted for both active and at rest conditions by Benson (2). The active lateral earth pressures were calculated using the Rankine formula:

$$\sigma_a = K_a * \gamma * H$$

σ_a = active lateral earth pressure

K_a = Rankine active earth pressure coefficient = $\tan^2(45-\phi/2)$

ϕ = angle of internal friction

γ = dry density

H = depth of interest

At rest earth pressures were calculated using the Jaky at rest coefficient

$K_o = 1 - \sin\phi$, where $\sigma_o = K_o * \gamma * H$. Table 6 gives a comparison between the theoretical values of earth pressure estimated by Benson and the actual measured values.

Table 6: Lateral Earth Pressure Values, Predicted and Measured

| | A2 | B1 | B2 | C1 | C2 |
|----------------------------------|------------------|------------------|------------------|------------------|-----------|
| H₁, ft. | 2.19 | 1.86 | 1.55 | 0.96 | 0.96 |
| σ_a, psi | 0.4 | 0.5 | * | 0.1 | 0.1 |
| σ_o, psi | 0.6 | 0.8 | * | 0.2 | 0.2 |
| σ_{measured}, psi | 1.3 ^a | 0.2 ^a | 0.5 | 0.1 | 0.3 |
| H₂, ft. | 5.19 | 4.86 | 4.55 | 3.96 | 3.96 |
| σ_a, psi | 0.8 | 1.4 | * | 0.5 | 0.5 |
| σ_o, psi | 1.4 | 2.0 | * | 0.6 | 0.9 |
| σ_{measured}, psi | 1.6 ^a | 1.5 | 0.1 ^a | 1.8 ^a | 1.6 |
| H₃, ft. | 7.66 | 7.86 | 7.55 | 6.96 | 6.96 |
| σ_a, psi | 1.3 | 2.2 | * | 0.9 | 0.9 |
| σ_o, psi | 2.0 | 3.2 | * | 1.5 | 1.6 |
| σ_{measured}, psi | 0.3 | 1.7 | 0.9 | 2.4 ^a | 3.4 |

H₁=depth to top cell, H₂=depth to middle cell, and H₃=depth to bottom cell.

^a Total pressure cell data fluctuate with seasonal temperature change.

*Pressures not calculated because φ value for controlled low strength material unknown.

The measured values of lateral earth pressure do not correlate with the estimated values. The estimated active lateral earth pressures for embankment B1 are the closest to the actual measured values. The Rankine active lateral earth pressure closely approximates the actual conditions for this embankment. The Rankine active conditions and the at rest conditions underestimate the lateral earth pressure conditions for embankments C1 and C2. The measured values at A2 are also higher than the estimated values with the exception of the bottom total pressure cell. Although the pressures were higher than expected for C2, the abutment wall has the expected linear pressure distribution. Compaction efforts could have caused excess pressure to be exerted on the

back of the abutment wall C1 if the concrete cube was dropped too close to the face of the abutment wall. This should not be the case, as a walk behind pad vibrator was used within 2 ft. of the abutment wall and wingwalls. Also, the observed effect of temperature on the pressures could be causing the measured pressures to be higher than the estimated pressures.

Lateral Earth Movement

All approach embankments show the same general trend for lateral earth movement as indicated by the inclinometers. The backfill area is moving toward the bridge which is the expected direction of movement. In the direction parallel to the abutment wall, the embankments have shown small amounts of movement. There has been movement both toward the centerline of the roadway and toward the wingwall west of the roadway. The westward movement is more common and has greater magnitudes than the eastward movement. As settlement occurs, the embankment tends to spread. Since the inclinometers are installed either on the centerline or west of centerline, the movement is mostly west. The movement to the west is also influenced by the presence of spur dikes at three of the locations.

Settlement

Settlement was measured by the amplified liquid settlement gages, the inclinometer telescoping couplings, and the surface settlement points. The

following table summarizes the settlement data for the control embankment and the four experimental approach embankments.

Table 7 : Summary of Settlement Data

Amplified Liquid Settlement Gage Data, ΔH in ft.

| ΔH | A2 | B1 | B2 | C1 | C2 |
|-------------------|-------|-------|-------|-------|-------|
| Centerline | 0.332 | 0.264 | 0.348 | 0.364 | 0.200 |
| Offset | 0.247 | 0.214 | 0.143 | 0.343 | 0.071 |
| Difference | 0.085 | 0.050 | 0.205 | 0.021 | 0.129 |

Inclinometer Data, ΔH in ft.

| ΔH | A2 | B1 | B2 | C1 | C2 |
|-------------------|--------|-------|--------|--------|--------|
| Centerline | | | | | |
| Backfill | 0.005 | 0.039 | -0.130 | 0.028 | 0.007 |
| Embankment | 0.001 | 0.002 | 0.000 | 0.005 | 0.012 |
| Foundation | 0.074 | 0.016 | 0.050 | 0.050 | 0.026 |
| Offset | | | | | |
| Backfill | 0.075 | 0.098 | -0.062 | 0.215 | 0.280 |
| Embankment | -0.005 | 0.012 | 0.050 | -0.035 | -0.005 |
| Foundation | 0.085 | 0.016 | 0.040 | 0.085 | 0.040 |

The amplified liquid settlement gages indicate that settlement was greater under the centerline of the approach embankments than under the offset. This is true in all cases. Embankment C2 had the least settlement for both the centerline and the offset. The centerline settlement was 0.200 ft., and the offset settlement was 0.071 ft. Embankment C1 settled the most, with 0.364 ft. of centerline settlement and 0.343 ft. of offset settlement. Although C1 had the most settlement, it had the lowest differential settlement, 0.021 ft., between the centerline and the offset of any of the five embankments. C2 had a large

differential settlement of 0.129 ft., second only to B2, which had a differential settlement of 0.205 ft.

The amplified liquid settlement gage data are more reliable than the settlement data obtained from the inclinometer telescoping couplings. The data from the inclinometer telescoping couplings show upward movement of the approach embankment in some cases, which is not a likely occurrence. One reason for data error is reader variability. The depth to the various telescoping couplings in the inclinometer casing was not read by the same person each time data were recorded, which may have caused some mistakes in the measurements. In addition, differences of a hundredth of a foot could be easily misread by simply reading the measuring tape at an angle instead of level. Also, to accurately measure settlement, the top rivet in the telescoping coupling must shear. This appears to have happened in only two cases, the second telescoping coupling of A2 and the first telescoping coupling of C2. Conversely, the amplified liquid settlement gage data were gathered using calibrated instruments which are considered more reliable. The decision to measure settlement using the inclinometer telescoping couplings was a good idea in theory, but it is highly variable and is not a good backup system for determining settlement.

Even though the settlement data from the inclinometer telescoping couplings are questionable, trends can be detected. In all cases, the total settlement for the centerline inclinometer was less than the settlement for the

offset inclinometer. For both the centerline and the offset inclinometer, B2 showed upward movement of the backfill. Although this is unlikely, it is probable that very little or no settlement occurred within the backfill of this embankment.

The surface settlement data give a good indication of whether or not a bump has started to develop at the end of the bridge. At embankments A2 and B1, the bump has started to develop, and there has been traffic on the road for less than one year.

Table 8 compares the values of settlement estimated by Schwidder (12) to the actual values of settlement according to the amplified liquid settlement gages for each approach embankment .

Table 8: Comparison of Estimated Settlement Values to Actual Settlement Values

| ΔH , ft. | A2 | B1 | B2 | C1 | C2 |
|-------------------------|-------|-------|-------|-------|-------|
| Actual Values | | | | | |
| Centerline | 0.332 | 0.264 | 0.348 | 0.364 | 0.200 |
| Offset | 0.247 | 0.214 | 0.143 | 0.343 | 0.071 |
| Estimated Values | 0.250 | 0.187 | 0.203 | 0.179 | 0.143 |

The estimated values of settlement are lower than the actual values of settlement according to the centerline amplified liquid settlement gages in all cases. The estimated value for A2 is the same as the offset value. The estimated value for B1 is close to the offset value. The estimated settlements give reasonable indications of the actual settlement, based on the material properties of the approach embankment assumed at the time.

Groundwater Levels

The plots of groundwater table elevation versus time (Appendix C) showed the same trend for all of the embankments. The groundwater table rose approximately 8 ft. above normal levels in July, 1995, during the record rainfalls of that summer. The levels then returned to and have remained at normal levels. The variations in the groundwater level do not appear to have any effect on either settlement or lateral earth pressure. If groundwater had a noticeable effect on the lateral earth pressure, it would indicate that the drainage systems for the approach embankments were not functioning properly and there was water in the backfill.

Conclusions

In terms of settlement, C2 appears to be performing the best. Even though settlement values are higher than predicted, it has the least settlement of any of the approach embankments. It has not developed a bump at the end of the bridge, and settlement is uniform along the centerline and the offset wheel path. The only real concern is the large amount of differential settlement (0.120 ft.) between the centerline and the offset, which is not an extremely high value, but it is the largest of any of the embankments. C2 also shows the expected trend in terms of lateral earth pressure. The lateral earth pressures are higher than expected, but the distribution has the expected linear increase with depth.

The lateral earth pressure values are the closest to the predicted values for B1. Embankment B1 is performing the second best in terms of settlement, but a bump is beginning to develop at this embankment. A bump is also beginning to develop at A2.

B2 is performing well with respect to settlement. The surface settlement point data show that at a distance of 5 ft. behind the abutment wall, there are 0.036 ft. of settlement at the wheel path closest to centerline and 0.030 ft. of settlement at the offset wheel path. No bump has started to develop at this approach embankment. In addition, the controlled low strength material is exerting very little pressure on the back of the abutment wall. The settlement according to the settlement gages is high, second only to C1. A greater amount of settlement is expected with this type of embankment construction because of the weight of material. The controlled low strength material exerts more weight on the foundation material than either the compacted granular backfill or unclassified borrow. The embankment has experienced little lateral movement.

Embankment C1 has the highest amount of settlement for both centerline and offset according to the amplified liquid settlement gage data. Although it has the greatest amount of settlement, it does not yet have a significant bump at the abutment wall. C1 is exerting less pressure on the abutment wall than C2, which can be directly related to the construction method because C1 and C2 are constructed of the same backfill material.

The least expensive embankment construction was A2. The total cost for A2 was \$1500. The most expensive was B1 at \$25,000. The remaining embankments cost in the range of \$14,500 - \$16,000. Although A2 was by far the least expensive construction, it poses the conventional construction problems related to compaction requirements. The unclassified borrow material used for this embankment is generally not as good as the material used in the other options, and A2 has not performed as well as some of the other approach embankments. Therefore, the added expense of embankment B2, C1, or C2 may be justified.

Data still need to be gathered for at least one more year in order to obtain real information from this study. Continued observation over several years is desirable to determine the long-term performance of the embankments, because as the embankments get older, a bump is more likely to develop. Traffic has been on the road for less than one year, and any problems with the construction methods or materials may not have yet been uncovered.

Little research has been done on this subject to date. The potential benefit of the knowledge gained from this study is a good incentive for the continued monitoring of this project. With continued observation, this project could serve as an important reference for highway agencies.

REFERENCES

1. Ardani, A., Bridge Approach Settlement, Report No. CDOH-DTP-R-87-06, Colorado Department of Highways, 1987.
2. Benson, John B., Construction of Experimental Approach Embankments at Salt Fork River Bridges on US 177 and Their Initial Performance, Oklahoma State University, 1995.
3. Chini, S. Abdol, Wolde-Tinsae, Amde M., and Aggour, M. Sherif, "Drainage and Backfill Provisions for Approaches to Bridges", Transportation Research Record, Vol. 1425, 1993.
4. Grover, Raymond A., "Movements of Bridge Approaches and Settlement of Approach Pavements in Ohio", Transportation Research Record, Vol. 178, 1978.
5. Holmberg, Soren, "Bridge Approaches on Soft Clay Supported by Embankment Piles," Geotechnical Engineering, Vol. 10 (1), June, 1979.
6. Hopkins, T.C., Long-Term Movements of Highway Bridge Approach Embankments and Pavements, Report No. UKTRP-85-12, Transportation Research Cabinet, 1985.
7. Laguros, J., Zaman, M., Chen, H., and Rahman, M., FEABAS - A User-Friendly Software for Prediction of Bridge Approach Settlement, Study 2188, ORA 125-6074, Oklahoma Department of Transportation, Oklahoma City, 1995.
8. Laguros, J., Boyd, D., Zaman, M., and Jha, R., Statistical Models for Identification of Problematic Bridge Sites and Estimation of Approach Settlements, Study 2188, ORA 125-064, Oklahoma Department of Transportation, Oklahoma City, 1993.
9. Laguros, J., and Zaman, M., Evaluation of Causes of Excessive Settlements of Pavements Behind Bridge Abutments and their Remedies - Phase III, Study 2163, ORA 157-293, Oklahoma Department of Transportation, Oklahoma City, 1990.


10. Laguros, J., Zaman, M., and Mahmood, I., Evaluation of Causes of Excessive Settlements of Pavements Behind Bridge Abutments and their Remedies - Phase II, Study 86-04-2, ORA 157-293, Oklahoma Department of Transportation, Oklahoma City, 1990.
11. Laguros, J., Boyd, D., Zaman, M., and Mahmood, I., Evaluation of Causes of Excessive Settlements of Pavements Behind Bridge Abutments and their Remedies - Phase I, Study 84-12-2, Oklahoma Department of Transportation, Oklahoma City, 1986.
12. Schwidder, Arthur J., Estimation of Stress and Deformation Parameters at Salt Fork River Bridges on US 177, Oklahoma State University, 1994.
13. Stewart, Carl F., Highway Structure Approaches, Report No. FHWA/CA/SD-85-05, Federal Highway Administration, 1985.
14. Wahls, Harvey E., "Design and Construction of Bridge Approaches", National Cooperative Highway Research Program Synthesis of Highway Practice, Vol. 159, 1990.

APPENDIX A

As-Built Instrument Locations


APPENDIX A1

A1 Instrument Locations




⊕ CROSS SECTION, SOUTH ABUTMENT WALL, BRIDGE A, AS-BUILT CONDITIONS

SCALE
0 FEET 5



BACK OF WALL SECTION, SOUTH ABUTMENT
WALL, BRIDGE A, AS-BUILT CONDITIONS




PLAN SECTION, SOUTH ABUTMENT WALL,
BRIDGE A, AS-BUILT CONDITIONS

Surface Settlement Point Locations, South Abutment Wall, Bridge A

APPENDIX A2


A2 Instrument Locations




Q CROSS SECTION, NORTH ABUTMENT WALL, BRIDGE A, AS-BUILT CONDITIONS

SCALE
0 FEET 5


ELEV.



BACK OF WALL SECTION, NORTH ABUTMENT
WALL, BRIDGE A, AS-BUILT CONDITIONS




PLAN SECTION, NORTH ABUTMENT WALL,
BRIDGE A, AS-BUILT CONDITIONS




APPENDIX A3


B1 Instrument Locations



Q CROSS SECTION, SOUTH ABUTMENT WALL,
BRIDGE B, AS-BUILT CONDITIONS




BACK OF WALL SECTION, SOUTH ABUTMENT
WALL, BRIDGE B, AS-BUILT CONDITIONS




PLAN SECTION, SOUTH ABUTMENT WALL,
BRIDGE B, AS-BUILT CONDITIONS

Surface Settlement Point Locations, South Abutment Wall, Bridge B


APPENDIX A4
B2 Instrument Locations




Q CROSS SECTION, NORTH ABUTMENT WALL,
BRIDGE B, AS-BUILT CONDITIONS



BACK OF WALL SECTION, NORTH ABUTMENT
WALL, BRIDGE B, AS-BUILT CONDITIONS




PLAN SECTION, NORTH ABUTMENT WALL,
BRIDGE B, AS-BUILT CONDITIONS




APPENDIX A5


C1 Instrument Locations



Q CROSS SECTION, SOUTH ABUTMENT WALL,
BRIDGE C, AS-BUILT CONDITIONS



BACK OF WALL SECTION, SOUTH ABUTMENT
WALL, BRIDGE C, AS-BUILT CONDITIONS




PLAN SECTION, SOUTH ABUTMENT WALL,
BRIDGE C, AS-BUILT CONDITIONS

BURIED CONDUIT FOR
INSTRUMENT TUBING

2-AMPLIFIED LIQUID SETTLEMENT
GUAGES W/ SETTLEMENT PLATES.


2" PVC TUBE
BLOCK OUT




Surface Settlement Point Locations, South Abutment Wall, Bridge C


APPENDIX A6

C2 Instrument Locations




**Q CROSS SECTION, NORTH ABUTMENT WALL,
BRIDGE C, AS-BUILT CONDITIONS**





PLAN SECTION, NORTH ABUTMENT WALL,
BRIDGE C, AS-BUILT CONDITIONS



Surface Settlement Point Locations, North Abutment Wall, Bridge C

APPENDIX B

Instrumentation Data

APPENDIX B1

A1 Instrumentation Data

ODOT US177 Approach Embankment Evaluation

Bridge A, South Abutment Wall (Unclassified Borrow)

Total Pressure Cells:

| | Tubing Length | Date Installed | Test Pressures | | |
|-------------------|---------------|----------------|----------------|--------|---------|
| | | | 5 psi | 50 psi | 100 psi |
| Top - SN 44196 | 34' | 5/4/95 | 4.56 | 49.50 | 99.63 |
| Middle - SN 44203 | 37' | 5/4/95 | 4.90 | 50.03 | 100.03 |
| Bottom - SN 44210 | 40' | 5/4/95 | 4.40 | 49.49 | 99.33 |

| Date | Time | TPC Readings (psi) | | | | | | Remarks |
|----------|----------|--------------------|--------------|---------------|-----------------|---------------|-----------------|---|
| | | Top w/flow | Top w/o flow | Middle w/flow | Middle w/o flow | Bottom w/flow | Bottom w/o flow | |
| 5/5/95 | | 0.0 | 0.0 | 0.3 | 0.0 | 0.2 | 0.0 | Initial readings by WCC, no backfill |
| 6/19/95 | AM | 0.7 | 0.4 | 0.4 | 0.2 | 0.9 | 0.7 | No backfill, drain cov. mat'l over bottom TPC |
| 7/7/95 | 10:25 AM | 0.9 | 0.6 | 0.5 | 0.3 | 1.0 | 0.7 | No backfill, drain cov. mat'l over bottom TPC |
| 7/14/95 | 9:40 AM | 1.0 | 0.5 | 0.5 | 0.2 | 0.7 | 0.1 | No backfill, drain cov. mat'l over bottom TPC |
| 7/26/95 | 1:30 PM | 0.6 | 0.3 | 2.3 | 2.1 | 2.7 | 2.5 | Backfill placed |
| 8/9/95 | 11:35 AM | 0.1 | 0.0 | 2.0 | 1.2 | 2.0 | 1.2 | |
| 9/1/95 | 11:35 AM | 0.3 | 0.1 | 2.8 | 2.6 | 2.7 | 2.5 | Equip. parked adj. to wall for several weeks |
| 9/20/95 | 2:25 PM | 0.1 | 0.0 | 2.9 | 2.7 | 2.7 | 2.5 | |
| 10/11/95 | 2:15 PM | 0.1 | 0.0 | 1.8 | 1.7 | 2.5 | 2.3 | |
| 11/3/95 | 8:50 AM | 0.1 | 0.0 | 2.6 | 2.4 | 2.3 | 2.1 | |
| 11/22/95 | 9:00 AM | 0.1 | 0.0 | 1.9 | 1.7 | 2.3 | 2.1 | |
| 12/20/95 | 10:00 AM | 0.0 | 0.0 | 1.8 | 1.7 | 2.0 | 1.8 | |
| 1/11/96 | 9:00 AM | 0.1 | 0.0 | 1.3 | 1.2 | 2.0 | 1.9 | |
| 2/8/96 | 1:00 PM | 0.1 | 0.0 | 1.3 | 1.1 | 2.0 | 1.9 | |
| 2/29/96 | 1:00 PM | 0.0 | 0.0 | 3.1 | 2.9 | 2.7 | 2.5 | |
| 3/28/96 | 12:30 PM | 0.0 | 0.0 | 3.1 | 3.0 | 2.8 | 2.7 | |
| 4/23/96 | 10:00 AM | 0.1 | 0.0 | 3.9 | 3.8 | 3.4 | 3.3 | |
| 5/21/96 | 8:00 AM | 1.3 | 1.0 | 4.8 | 4.6 | 3.9 | 3.8 | |
| 6/11/96 | 2:00 PM | 0.7 | 0.4 | 4.5 | * | 4.1 | 4.0 | Highway opened to traffic |
| 8/6/96 | 2:00 PM | 1.3 | 1.0 | 5.3 | * | 4.3 | 4.2 | *Cell won't hold pressure for no flow |
| 10/31/96 | 1:25 PM | 0.5 | 0.2 | 4.8 | 4.7 | 2.5 | 2.1 | |
| 12/16/96 | 11:35 AM | 0.2 | 0.1 | 3.8 | 3.6 | 2.2 | 2.1 | |
| 2/27/97 | 11:50 AM | 0.2 | 0.1 | 3.6 | 3.3 | 2.8 | 2.6 | |

ODOT US177 Approach Embankment Evaluation

Bridge A, South Abutment Wall (Unclassified Borrow)

Amplified Liquid Settlement Gages:

| | Tubing Length | Date Installed | As Built Elevation | |
|-----------------------|------------------|-------------------|-------------------------|-------------------------|
| Centerline - SN 44224 | 40' | 5/4/95 | Top of Plate 919.55' | Top of Fluid 930.72' |
| Initial Head = 11.17' | | | | |

Calibration for: Centerline

$$\text{Head(ft)} = \frac{\text{Reading} - (-3.415 \text{ psi})}{8.425 \text{ psi / ft}}$$

| ALSG Readings, Heads, & ΔH | | | | | |
|----------------------------|----------|----------------|------------------|----------|---|
| Date | Time | Reading psi | CL Head ft | ΔH ft | Remarks |
| 5/5/95 | | 90.7 | 11.171 | - | Initial readings by WCC, no backfill, reference reading (datum) |
| 6/19/95 | AM | 90.6 | 11.159 | -0.012 | No backfill |
| 7/7/95 | 10:25 AM | 90.7 | 11.171 | 0.000 | No backfill |
| 7/14/95 | 9:40 AM | 90.8 | 11.183 | 0.012 | No backfill |
| 7/26/95 | 1:30 PM | 91.4 | 11.254 | 0.083 | Backfill placed |
| 8/9/95 | 11:35 AM | 91.6 | 11.278 | 0.107 | |
| 9/1/95 | 11:35 AM | 91.6 | 11.278 | 0.107 | Equip. parked over backfill |
| 9/20/95 | 1:25 PM | 91.6 | 11.277 | 0.106 | |
| 10/11/95 | 2:15 PM | 92.0 | 11.325 | 0.154 | |
| 11/3/95 | 8:50 AM | 92.0 | 11.325 | 0.154 | |
| 11/22/95 | 9:00 AM | 92.1 | 11.337 | 0.166 | |
| 12/20/95 | 10:00 AM | 92.4 | 11.373 | 0.202 | |
| 1/11/96 | 9:00 AM | 91.6 | 11.278 | 0.107 | |
| 2/8/96 | 1:00 PM | 92.0 | 11.325 | 0.154 | |
| 2/29/96 | 1:00 PM | 92.0 | 11.325 | 0.154 | |
| 3/28/96 | 12:30 PM | 91.4 | 11.254 | 0.083 | |
| 4/23/96 | 9:50 AM | 91.9 | 11.313 | 0.142 | |
| 5/21/96 | 8:10 AM | 91.8 | 11.301 | 0.130 | |
| 6/11/96 | 2:00 PM | 92.2 | 11.349 | 0.178 | Highway opened to traffic |
| 8/6/96 | 1:00 PM | 91.8 | 11.301 | 0.130 | |
| 10/31/96 | 1:25 PM | 91.3 | 11.242 | 0.071 | |
| 12/16/96 | 11:35 AM | 92.5 | 11.385 | 0.214 | |
| 2/27/97 | 11:50 AM | 92.5 | 11.385 | 0.214 | |

ODOT US177 Approach Embankment Evaluation

Bridge A, South Abutment Wall (Unclassified Borrow)

Inclinometer Telescoping Couplings - Centerline: Installed 7/25/95

Casing Elevation 933.50' → 931.94'
(top=2.60' above GS) As Built After Paving

GS Elevation 930.92' Pavement Elevation 932.46'

Reference Coupling 54.08' → 876.84' Bottom of Casing 56.5'
Depth Elevation

| 06 | Date | Time | Readings, Changes, & ΔH Values | | | | | | | | | | | | | | |
|----|----------|----------|--------------------------------|--------|-------|-----------------|--------|-------|-----------------|--------|--------|-----------------|--------|--------|------------------|-------|-------|
| | | | Level 1 (Top) | | | Level 2 | | | Level 3 | | | Level 4 | | | Level 5 (Bottom) | | |
| | | | Reading R5 - R1 | ΔH | | Reading R5 - R2 | ΔH | | Reading R5 - R3 | ΔH | | Reading R5 - R4 | ΔH | | Reading R5 | ΔR5 | ΔH |
| | | | R1, ft | ft | ft | R2, ft | ft | ft | R3, ft | ft | ft | R4, ft | ft | ft | R5, ft | ft | ft |
| | 7/26/95 | 1:30 PM | 9.125 | 47.555 | - | 13.140 | 43.540 | - | 23.650 | 33.030 | - | 34.160 | 22.520 | - | 56.680 | - | - |
| | 8/9/95 | 11:35 AM | 9.125 | 47.550 | 0.005 | 13.140 | 43.535 | 0.005 | 23.645 | 33.030 | 0.000 | 34.150 | 22.525 | -0.005 | 56.675 | 0.005 | 0.005 |
| | 9/1/95 | 11:35 AM | 9.125 | 47.538 | 0.017 | 13.140 | 43.523 | 0.017 | 23.640 | 33.023 | 0.007 | 34.147 | 22.516 | 0.004 | 56.663 | 0.017 | 0.017 |
| | 9/20/95 | 1:25 PM | 9.120 | 47.545 | 0.010 | 13.137 | 43.528 | 0.012 | 23.640 | 33.025 | 0.005 | 34.147 | 22.518 | 0.002 | 56.665 | 0.015 | 0.015 |
| | 10/11/95 | 2:15 PM | 9.125 | 47.535 | 0.020 | 13.140 | 43.520 | 0.020 | 23.640 | 33.020 | 0.010 | 34.145 | 22.515 | 0.005 | 56.660 | 0.020 | 0.020 |
| | 11/3/95 | 8:50 AM | 9.115 | 47.550 | 0.005 | 13.130 | 43.535 | 0.005 | 23.633 | 33.032 | -0.002 | 34.137 | 22.528 | -0.008 | 56.665 | 0.015 | 0.015 |
| | 11/22/95 | 9:00 AM | 9.115 | 47.538 | 0.017 | 13.130 | 43.523 | 0.017 | 23.630 | 33.023 | 0.007 | - | - | - | 56.653 | 0.027 | 0.027 |
| | 12/20/95 | | 9.110 | 47.535 | 0.020 | 13.120 | 43.525 | 0.015 | 23.625 | 33.020 | 0.010 | 34.237 | 22.408 | 0.112 | 56.645 | 0.035 | 0.035 |
| | 1/11/96 | 9:00 AM | 9.110 | 47.535 | 0.020 | 13.120 | 43.525 | 0.015 | 23.623 | 33.022 | 0.008 | 34.133 | 22.512 | 0.008 | 56.645 | 0.035 | 0.035 |
| | 2/8/96 | 1:00 PM | 9.110 | 47.525 | 0.030 | 13.123 | 43.512 | 0.028 | 23.623 | 33.012 | 0.018 | 34.133 | 22.502 | 0.018 | 56.635 | 0.045 | 0.045 |
| | 2/29/96 | 1:00 PM | 9.109 | 47.531 | 0.024 | 13.120 | 43.520 | 0.020 | 23.624 | 33.016 | 0.014 | 34.130 | 22.510 | 0.010 | 56.640 | 0.040 | 0.040 |
| | 3/28/96 | 12:50 PM | 9.110 | 47.527 | 0.028 | 13.120 | 43.517 | 0.023 | 23.620 | 33.017 | 0.013 | 34.133 | 22.504 | 0.016 | 56.637 | 0.043 | 0.043 |
| | 4/23/96 | 9:50 AM | 9.110 | 47.525 | 0.030 | 13.123 | 43.512 | 0.028 | 23.625 | 33.010 | 0.020 | 34.133 | 22.502 | 0.018 | 56.635 | 0.045 | 0.045 |
| | 5/21/96 | 8:10 AM | 9.110 | 47.500 | 0.055 | 13.115 | 43.495 | 0.045 | 23.615 | 32.995 | 0.035 | 34.120 | 22.490 | 0.030 | 56.610 | 0.070 | 0.070 |
| | 6/11/96 | 2:00 PM | 9.110 | 47.500 | 0.055 | 13.120 | 43.490 | 0.050 | 23.619 | 32.991 | 0.039 | 34.108 | 22.502 | 0.018 | 56.610 | 0.070 | 0.070 |
| | 8/8/96 | 2:00 PM | 9.110 | 47.487 | 0.068 | 13.120 | 43.477 | 0.063 | 23.623 | 32.974 | 0.056 | 34.117 | 22.480 | 0.040 | 56.597 | 0.083 | 0.083 |
| | 10/31/96 | 1:25 PM | 9.105 | 47.480 | 0.075 | 13.110 | 43.475 | 0.065 | 23.616 | 32.969 | 0.061 | 34.105 | 22.480 | 0.040 | 56.585 | 0.095 | 0.095 |
| | 12/16/96 | 11:35 AM | 9.100 | 47.493 | 0.062 | 13.107 | 43.486 | 0.054 | 23.615 | 32.978 | 0.052 | 34.100 | 22.493 | 0.027 | 56.593 | 0.087 | 0.087 |
| | 2/27/97 | 11:50 AM | 9.103 | 47.482 | 0.073 | 13.105 | 43.480 | 0.060 | 23.610 | 32.975 | 0.055 | 34.100 | 22.485 | 0.035 | 56.585 | 0.095 | 0.095 |

ODOT US177 Approach Embankment Evaluation

Bridge A, South Abutment Wall (Unclassified Borrow)

Piezometer:

Standpipe Elevation 932.93' (As Built) → 931.93' (After Paving)
 *As Built ► (Top=2.05 ft above GS)

GS Elevation 930.92' (Top of Subgrade) Pavement Elevation 932.46' (Top of Pavement)

Tip Elevation 888.92' Tip Depth 42.0'

Groundwater Depth = Piezometer Reading + 0.53' (0.53' = Diff. between standpipe and pavement)
 (Below Top of Pavement)

Groundwater Elevation = Standpipe Elevation (931.93') - Piezometer Reading

| Piezometer Data | | | | | Remarks |
|-----------------|----------|---------|----------|----------|--|
| Date | Time | Reading | GW Depth | GW Elev. | |
| | | ft | ft | ft | |
| 7/25/95 | PM | - | - | - | Installed piezometer |
| 7/26/95 | 1:30 PM | 37.93 | 35.88 | 897.62 | Initial reading by OSU |
| 8/9/95 | 11:35 AM | 33.63 | 31.58 | 901.92 | |
| 9/1/95 | 11:35 AM | 38.78 | 36.73 | 896.77 | |
| 9/20/95 | 1:25 PM | 40.18 | 38.13 | 895.37 | |
| 10/11/95 | 2:15 PM | 40.64 | 38.59 | 894.91 | |
| 11/3/95 | 8:50 AM | 41.08 | 39.03 | 894.47 | |
| 11/22/95 | 9:00 AM | 41.30 | 39.25 | 894.25 | |
| 12/20/95 | | 41.20 | 39.15 | 894.35 | Surveyed elevations established |
| 1/11/96 | 9:00 AM | 41.12 | 39.07 | 894.43 | |
| 2/8/96 | 1:00 PM | 41.17 | 39.12 | 894.38 | |
| 2/29/96 | 1:00 PM | 41.48 | 39.43 | 894.07 | |
| 3/28/96 | 12:50 PM | 41.42 | 39.37 | 894.13 | |
| 4/23/96 | 10:00 AM | 41.60 | 39.55 | 893.95 | |
| 5/21/96 | 8:10 AM | 40.88 | 41.41 | 891.05 | Use new standpipe elev., changed reference for depth |
| 6/11/96 | 2:00 PM | 40.17 | 40.70 | 891.76 | Highway opened to traffic |
| 8/6/96 | 1:00 PM | 40.12 | 40.65 | 891.81 | |
| 10/31/96 | 1:25 PM | 39.51 | 40.04 | 892.42 | |
| 12/16/96 | 11:35 AM | 38.85 | 39.38 | 893.09 | |
| 2/27/97 | 11:50 AM | 36.69 | 37.22 | 895.24 | |

ODOT US177 Approach Embankment Evaluation

Bridge A, South Abutment Wall (Unclassified Borrow), Surface Settlement Points

| Date | 6/12/96 | | 8/6/96 | | 10/31/96 | | 2/28/97 | |
|------|---------|-----------|---------|-----------|----------|-----------|---------|-----------|
| | Reading | Elevation | Reading | Elevation | Reading | Elevation | Reading | Elevation |
| BM | W E | 934.30 | W E | 934.30 | W E | 934.30 | W E | 934.30 |
| BS | 2.5 | - | 2.570 | - | 3.418 | - | 3.138 | - |
| HI | 936.80 | - | 936.87 | - | 937.72 | - | 937.438 | - |
| FS 1 | 4.80 | 932.00 | 4.882 | 931.988 | 5.754 | 931.964 | 5.480 | 931.958 |
| 2 | 4.69 | 932.11 | 4.787 | 932.083 | 5.644 | 932.074 | 5.366 | 932.072 |
| 3 | 4.61 | 932.19 | 4.695 | 932.175 | 5.548 | 932.170 | 5.273 | 932.165 |
| 4 | 4.52 | 932.28 | 4.604 | 932.266 | 5.455 | 932.263 | 5.183 | 932.255 |
| 5 | 4.80 | 932.00 | 4.874 | 931.996 | 5.748 | 931.970 | 5.473 | 931.965 |
| 6 | 4.69 | 932.11 | 4.783 | 932.087 | 5.639 | 932.079 | 5.364 | 932.074 |
| 7 | 4.61 | 932.19 | 4.690 | 932.180 | 5.542 | 932.176 | 5.278 | 932.160 |
| 8 | 4.53 | 932.27 | 4.614 | 932.256 | 5.469 | 932.249 | 5.200 | 932.238 |
| 9 | 4.79 | 932.01 | 4.866 | 932.004 | 5.739 | 931.979 | 5.463 | 931.975 |
| 10 | 4.68 | 932.12 | 4.775 | 932.095 | 5.632 | 932.086 | 5.356 | 932.082 |
| 11 | 4.59 | 932.21 | 4.674 | 932.196 | 5.529 | 932.189 | 5.254 | 932.184 |
| 12 | 4.52 | 932.28 | 4.615 | 932.255 | 5.466 | 932.252 | 5.195 | 932.243 |
| 13 | 4.80 | 932.00 | 4.879 | 931.991 | 5.750 | 931.968 | 5.463 | 931.975 |
| 14 | 4.68 | 932.12 | 4.784 | 932.086 | 5.638 | 932.080 | 5.364 | 932.074 |
| 15 | 4.58 | 932.22 | 4.675 | 932.195 | 5.530 | 932.188 | 5.258 | 932.180 |
| 16 | 4.50 | 932.30 | 4.588 | 932.282 | 5.445 | 932.273 | 5.173 | 932.265 |

*Settlement Reading Point is missing.

APPENDIX B2

A2 Instrumentation Data

ODOT US177 Approach Embankment Evaluation

Bridge A, North Abutment Wall (Control Section-Unclassified Borrow)

Total Pressure Cells:

| | Tubing Length | Date Installed | Test Pressures | | |
|-------------------|---------------|----------------|----------------|--------|---------|
| | | | 5 psi | 50 psi | 100 psi |
| Top - SN 44201 | 34' | 4/25/95 | 5.10 | 50.18 | 100.50 |
| Middle - SN 44207 | 37' | 4/25/95 | 5.37 | 50.41 | 100.51 |
| Bottom - SN 44213 | 40' | 4/25/95 | 5.34 | 50.41 | 100.47 |

| Date | Time | TPC Readings (psi) | | | | | | Remarks |
|----------|----------|--------------------|--------------|---------------|-----------------|---------------|-----------------|---|
| | | Top w/flow | Top w/o flow | Middle w/flow | Middle w/o flow | Bottom w/flow | Bottom w/o flow | |
| 4/25/95 | PM | 0.0 | - | 0.0 | - | 0.0 | - | No Backfill T=40 degrees C |
| 4/27/95 | AM | 0.0 | - | 0.0 | - | 0.1 | - | No Backfill T=50 degrees C |
| 4/27/95 | 5:35 PM | 0.0 | - | 0.0 | - | 0.0 | - | No Backfill T=60 degrees C |
| 4/28/95 | 8:50 AM | 0.0 | - | 0.0 | - | 0.0 | - | T=50 degrees C |
| 4/28/95 | 3:30 PM | 0.1 | 0.0 | 0.7 | 0.4 | 1.3 | 1.5 | T=60 degrees C |
| 5/1/95 | AM | 0.1 | 0.0 | 0.4 | 0.0 | 0.8 | 0.7 | |
| 5/10/95 | AM | 0.2 | 0.1 | 1.7 | 1.6 | 1.3 | 1.2 | Unclassified Borrow Backfill Complete |
| 5/15/95 | AM | 0.4 | 0.2 | 1.3 | 1.2 | 1.2 | 1.1 | |
| 5/19/95 | AM | 0.3 | 0.1 | 1.5 | 1.4 | 1.3 | 1.2 | |
| 5/31/95 | PM | 0.2 | 0.0 | 1.6 | 1.5 | 1.5 | 1.4 | |
| 6/19/95 | AM | 1.0 | 0.9 | 1.7 | 1.7 | 2.1 | 2.0 | W. side of approach used for access to bridge |
| 6/28/95 | PM | 0.9 | 0.8 | 1.9 | 1.8 | 2.1 | 2.0 | |
| 7/7/95 | 10:50 AM | 1.3 | 1.3 | 2.0 | 1.9 | 2.2 | 2.1 | |
| 7/14/95 | 10:05 AM | 1.6 | 1.5 | 2.1 | 2.0 | 2.2 | 2.1 | |
| 7/26/95 | 12:40 PM | 1.3 | 1.2 | 2.2 | 2.1 | 2.1 | 2.0 | |
| 8/9/95 | 7:35 AM | 1.3 | 1.2 | 2.1 | 2.0 | 1.9 | 1.8 | |
| 9/1/95 | 7:45 AM | 1.6 | 1.5 | 2.3 | 2.2 | 2.2 | 2.1 | |
| 9/20/95 | 2:25 PM | 1.0 | 0.9 | 2.2 | 2.1 | 2.0 | 1.9 | T = 21 degrees C |
| 10/11/95 | 3:15 PM | 1.5 | 1.4 | 1.6 | 1.5 | 1.8 | 1.7 | T = 34 degrees C |
| 11/3/95 | 9:45 AM | 0.7 | 0.5 | 2.2 | 2.1 | 1.9 | 1.8 | |
| 11/22/95 | 10:00 AM | 0.7 | 0.6 | 1.8 | 1.8 | 1.8 | 1.7 | |
| 12/20/95 | 10:30 AM | 0.5 | 0.4 | 1.6 | 1.5 | 1.5 | 1.4 | |
| 1/11/96 | 10:00 AM | 0.6 | 0.5 | 1.4 | 1.3 | 1.5 | 1.4 | |
| 2/8/96 | 2:00 PM | 1.1 | 1.0 | 1.1 | 1.0 | 1.4 | 1.3 | |
| 2/29/96 | 2:00 PM | 1.1 | 1.0 | 2.0 | 1.9 | 1.5 | 1.4 | |
| 3/28/96 | 1:00 PM | 1.1 | 1.0 | 1.8 | 1.7 | 1.5 | 1.4 | |
| 4/23/96 | 9:00 AM | 1.1 | 1.0 | 2.1 | 2.0 | 1.5 | 1.4 | |
| 5/21/96 | 8:30 AM | 1.9 | 1.8 | 2.3 | 2.2 | 1.8 | 1.7 | |
| 6/11/96 | 1:00 PM | 2.1 | 2.0 | 1.6 | 1.5 | 1.4 | 1.3 | Highway Opened to Traffic |
| 8/6/96 | 2:00 PM | 2.4 | 2.3 | 1.9 | 1.8 | 1.1 | 1.0 | |
| 10/31/96 | 12:45 PM | 1.6 | 1.4 | 2.0 | 1.9 | 0.6 | 0.5 | |
| 12/16/96 | 11:00 AM | 1.1 | 1.0 | 1.8 | 1.7 | 0.4 | 0.3 | |
| 2/27/97 | 11:10 AM | 1.3 | 1.2 | 1.6 | 1.5 | 0.3 | 0.2 | |

ODOT US177 Approach Embankment Evaluation

Bridge A, North Abutment Wall (Control Section-Unclassified Borrow)

Amplified Liquid Settlement Gages:

| | Tubing Length | Date Installed | As Built Elevation | |
|-----------------------|---------------|----------------|-----------------------|--------------|
| | | | Top of Plate | Top of Fluid |
| Centerline - SN 44217 | 40' | 4/28/95 | 914.21' | 925.10' |
| | | | Initial Head = 10.89' | |
| Offset - SN 44223 | 30' | 4/28/95 | 914.12' | 925.11' |
| | | | Initial Head = 10.99' | |

Calibration for: Centerline

$$\text{Head(ft)} = \frac{\text{Reading} - (-5.24 \text{ psi})}{8.44 \text{ psi / ft}}$$

Offset

$$\text{Head(ft)} = \frac{\text{Reading} - (-2.08 \text{ psi})}{8.50 \text{ psi / ft}}$$

ALSG Readings, Heads, & ΔH

| Date | Time | CL | | | OFS | | | Remarks |
|----------|----------|----------------|------------|----------|----------------|------------|----------|-------------------------------|
| | | Reading psi | Head ft | ΔH ft | Reading psi | Head ft | ΔH ft | |
| 4/28/95 | 7:45 AM | 87.6 | 11.000 | - | 91.5 | 11.009 | - | Reference Reading (Datum) |
| 4/28/95 | 11:10 AM | 87.2 | 10.953 | -0.047 | 91.5 | 11.009 | 0.000 | |
| 4/28/95 | 3:15 PM | 87.7 | 11.012 | 0.012 | 91.5 | 11.009 | 0.000 | |
| 5/1/95 | 8:25 AM | 87.6 | 11.000 | 0.000 | 91.4 | 10.998 | -0.011 | |
| 5/10/95 | AM | 87.7 | 11.012 | 0.012 | 91.7 | 11.033 | 0.024 | Unc. Borrow Backfill complete |
| 5/12/95 | AM | 88.2 | 11.071 | 0.071 | 91.5 | 11.009 | 0.000 | |
| 5/19/95 | AM | 87.9 | 11.036 | 0.036 | 91.4 | 10.998 | -0.011 | |
| 5/31/95 | PM | 88.5 | 11.107 | 0.107 | 91.6 | 11.021 | 0.012 | |
| 6/19/95 | AM | 88.7 | 11.130 | 0.130 | 92.1 | 11.080 | 0.071 | |
| 6/28/95 | PM | 88.9 | 11.154 | 0.154 | 92.1 | 11.080 | 0.071 | |
| 7/7/95 | 10:50 AM | 88.8 | 11.142 | 0.142 | 91.8 | 11.045 | 0.036 | |
| 7/14/95 | 10:05 AM | 88.2 | 11.071 | 0.071 | 91.7 | 11.033 | 0.024 | |
| 7/26/95 | 12:40 PM | 89.0 | 11.166 | 0.166 | 92.0 | 11.068 | 0.059 | |
| 8/9/95 | 7:35 AM | 88.5 | 11.107 | 0.107 | 91.7 | 11.033 | 0.024 | |
| 9/1/95 | 7:45 AM | 88.8 | 11.142 | 0.142 | 91.9 | 11.056 | 0.047 | |
| 9/20/95 | 2:25 PM | 89.1 | 11.178 | 0.178 | 92.2 | 11.092 | 0.083 | T = 21 degrees C |
| 10/11/95 | 3:15 PM | 89.5 | 11.225 | 0.225 | 94.4 | 11.351 | 0.342 | |
| 11/3/95 | 9:45 AM | 89.4 | 11.213 | 0.213 | 92.5 | 11.127 | 0.118 | |
| 11/22/95 | 10:00 AM | 89.6 | 11.237 | 0.237 | 92.8 | 11.162 | 0.153 | |
| 12/20/95 | 10:30 AM | 89.9 | 11.273 | 0.273 | 93.0 | 11.186 | 0.177 | |
| 1/11/96 | 10:00 AM | 90.3 | 11.320 | 0.320 | 93.1 | 11.198 | 0.189 | |
| 2/8/96 | 2:00 PM | 90.6 | 11.355 | 0.355 | 93.1 | 11.198 | 0.189 | |
| 2/29/96 | 2:00 PM | 90.0 | 11.284 | 0.284 | 93.0 | 11.186 | 0.177 | |
| 3/28/96 | 1:00 PM | 90.1 | 11.296 | 0.296 | 93.1 | 11.198 | 0.189 | |
| 4/23/96 | 9:00 AM | 90.0 | 11.284 | 0.284 | 93.2 | 11.209 | 0.200 | |
| 5/21/96 | 8:30 AM | 89.8 | 11.261 | 0.261 | 93.0 | 11.186 | 0.177 | |
| 6/11/96 | 1:00 PM | 90.0 | 11.284 | 0.284 | 93.1 | 11.198 | 0.189 | Highway Opened to Traffic |
| 8/6/96 | 2:00 PM | 89.8 | 11.261 | 0.261 | 92.8 | 11.162 | 0.153 | |
| 10/31/96 | 12:45 PM | 89.5 | 11.225 | 0.225 | 92.7 | 11.151 | 0.142 | |
| 12/16/96 | 11:00 AM | 90.2 | 11.308 | 0.308 | 93.5 | 11.245 | 0.236 | |
| 2/27/97 | 11:10 AM | 90.4 | 11.332 | 0.332 | 93.6 | 11.256 | 0.247 | |

ODOT US177 Approach Embankment Evaluation

Bridge A, North Abutment Wall (Control Section-Unclassified Borrow)

Inclinometer Telescoping Couplings - Centerline: Installed 5/16/95

Casing Elevation 927.41' → 926.64'
(top=1.83' above GS) As Built After Paving

GS Elevation 925.58' Pavement Elevation 926.99'

Reference Coupling 53.74' → 871.84' Bottom of Casing 55.34'
Depth Elevation

| Readings, Changes, & ΔH Values | | | | | | | | | | | | | | |
|--------------------------------|----------|-----------------|--------|----------|-----------------|--------|----------|-----------------|--------|----------|------------------|-------|----------|---------------------------|
| Date | Time | Level 1 (Top) | | | Level 2 | | | Level 3 | | | Level 4 (Bottom) | | | Remarks |
| | | Reading R4 - R1 | | ΔH ft | Reading R4 - R2 | | ΔH ft | Reading R4 - R3 | | ΔH ft | Reading ΔR4 | | ΔH ft | |
| | | R1, ft | ft | | R2, ft | ft | | R3, ft | ft | | R4, ft | ft | | |
| 6/1/95 | PM | 4.113 | 51.407 | - | 9.634 | 45.886 | - | 20.124 | 35.396 | - | 55.520 | - | - | Omit this Data set |
| 6/19/95 | PM | 4.103 | 51.469 | 0.000 | 9.634 | 45.938 | 0.000 | 20.134 | 35.438 | 0.000 | 55.572 | 0.000 | 0.000 | Reference Reading (Datum) |
| 6/28/95 | PM | 4.115 | 51.375 | 0.094 | 9.630 | 45.860 | 0.078 | 20.125 | 35.365 | 0.073 | 55.490 | 0.082 | 0.082 | |
| 7/7/95 | 10:50 AM | 4.110 | 51.460 | 0.009 | 9.635 | 45.935 | 0.003 | 20.125 | 35.445 | -0.007 | 55.570 | 0.002 | 0.002 | |
| 7/14/95 | 9:40 AM | 4.110 | 51.380 | 0.089 | 9.640 | 45.850 | 0.088 | 20.130 | 35.360 | 0.078 | 55.490 | 0.082 | 0.082 | |
| 7/26/95 | 12:40 PM | 4.105 | 51.455 | 0.015 | 9.633 | 45.927 | 0.011 | 20.125 | 35.435 | 0.003 | 55.560 | 0.012 | 0.012 | |
| 8/9/95 | 7:55 AM | 4.110 | 51.450 | 0.019 | 9.635 | 45.925 | 0.013 | 20.125 | 35.435 | 0.003 | 55.560 | 0.012 | 0.012 | |
| 9/1/95 | 7:45 AM | 4.105 | 51.245 | 0.224 | 9.640 | 45.710 | 0.228 | 20.230 | 35.120 | 0.318 | 55.350 | 0.222 | 0.222 | |
| 9/20/95 | 2:25 PM | 4.100 | 51.370 | 0.099 | 10.060 | 45.410 | 0.528 | 20.127 | 35.343 | 0.095 | 55.470 | 0.102 | 0.102 | |
| 10/11/95 | 3:15 PM | 4.105 | 51.445 | 0.024 | 9.637 | 45.913 | 0.025 | 20.130 | 35.420 | 0.018 | 55.550 | 0.022 | 0.022 | |
| 11/3/95 | 9:45 AM | 4.097 | 51.448 | 0.021 | 9.625 | 45.920 | 0.018 | 20.120 | 35.425 | 0.013 | 55.545 | 0.027 | 0.027 | |
| 11/22/95 | 10:00 AM | 4.100 | 51.370 | 0.099 | 9.625 | 45.845 | 0.093 | 20.125 | 33.345 | 0.093 | 55.470 | 0.102 | 0.102 | |
| 12/20/95 | 10:30 AM | 4.100 | 51.370 | 0.099 | 9.620 | 45.850 | 0.088 | 20.120 | 35.350 | 0.088 | 55.470 | 0.102 | 0.102 | |
| 1/11/96 | 10:00 AM | 4.095 | 51.372 | 0.097 | 9.627 | 45.840 | 0.098 | 20.117 | 35.350 | 0.088 | 55.467 | 0.105 | 0.105 | |
| 2/8/96 | 2:00 PM | 4.100 | 51.367 | 0.102 | 9.630 | 45.837 | 0.101 | 20.120 | 35.347 | 0.091 | 55.467 | 0.105 | 0.105 | |
| 2/29/96 | 2:00 PM | 4.094 | 51.446 | 0.023 | 9.629 | 45.911 | 0.027 | 20.119 | 35.421 | 0.017 | 55.540 | 0.032 | 0.032 | |
| 3/28/96 | 1:00 PM | 4.100 | 51.365 | 0.104 | 9.627 | 45.838 | 0.100 | 20.120 | 35.345 | 0.093 | 55.465 | 0.107 | 0.107 | |
| 4/23/96 | 10:30 AM | 4.095 | 51.365 | 0.104 | 9.625 | 45.835 | 0.103 | 20.113 | 35.347 | 0.091 | 55.460 | 0.112 | 0.112 | |
| 5/21/96 | 8:30 AM | 4.385 | 51.360 | 0.109 | 9.913 | 45.832 | 0.106 | 20.410 | 35.335 | 0.103 | 55.745 | 0.117 | 0.117 | |
| 6/11/96 | 1:00 PM | 4.393 | 51.417 | 0.052 | 9.910 | 45.900 | 0.038 | 20.408 | 35.402 | 0.036 | 55.810 | 0.052 | 0.052 | |
| 8/6/96 | 2:00 PM | 4.394 | 51.416 | 0.053 | 9.915 | 45.895 | 0.043 | 20.407 | 35.403 | 0.035 | 55.810 | 0.052 | 0.052 | |
| 10/31/96 | 12:45 PM | 4.385 | 51.345 | 0.124 | 9.903 | 45.827 | 0.111 | 20.400 | 35.330 | 0.108 | 55.730 | 0.132 | 0.132 | |
| 12/16/96 | 11:00 AM | 4.385 | 51.420 | 0.049 | 9.905 | 45.900 | 0.038 | 20.403 | 35.402 | 0.036 | 55.805 | 0.057 | 0.057 | |
| 2/27/97 | 11:10 AM | 4.390 | 51.410 | 0.059 | 9.903 | 45.897 | 0.041 | 20.403 | 35.397 | 0.041 | 55.800 | 0.062 | 0.062 | |

ODOT US177 Approach Embankment Evaluation

Bridge A, North Abutment Wall (Control Section-Unclassified Borrow)

Inclinometer Telescoping Couplings - Offset: Installed 5/18/95

Casing Elevation 927.54' → 926.52'
(top=1.95' above GS) As Built After Paving

GS Elevation 925.59' Pavement Elevation 926.69'

Reference Coupling 53.65' → 871.94' Bottom of Casing 55.22'
Depth Elevation

| Readings, Changes, & ΔH Values | | | | | | | | | | | | | | |
|--------------------------------|----------|-------------------|---------------|----------|-------------------|---------------|----------|-------------------|---------------|----------|-------------------|-----------|----------|---|
| Date | Time | Level 1 (Top) | | | Level 2 | | | Level 3 | | | Level 4 (Bottom) | | | Remarks |
| | | Reading R1, ft | R4 - R1 ft | ΔH ft | Reading R2, ft | R4 - R2 ft | ΔH ft | Reading R3, ft | R4 - R3 ft | ΔH ft | Reading R4, ft | ΔR4 ft | ΔH ft | |
| 6/1/95 | PM | 5.103 | 50.437 | - | 10.582 | 44.958 | - | 21.051 | 34.489 | - | 55.540 | - | - | Omit this Data set Reference Reading (Datum) |
| 6/19/95 | PM | 5.103 | 50.500 | 0.000 | 10.582 | 45.021 | 0.000 | 21.051 | 34.552 | 0.000 | 55.603 | 0.000 | 0.000 | |
| 6/28/95 | PM | 5.100 | 50.495 | 0.005 | 10.580 | 45.015 | 0.006 | 21.050 | 34.545 | 0.007 | 55.595 | 0.008 | 0.008 | |
| 7/7/95 | 10:50 AM | 5.105 | 50.495 | 0.005 | 10.585 | 45.015 | 0.006 | 21.050 | 34.550 | 0.002 | 55.600 | 0.003 | 0.003 | |
| 7/14/95 | 9:40 AM | 5.100 | 50.500 | 0.000 | 10.580 | 45.020 | 0.001 | 21.050 | 34.550 | 0.002 | 55.600 | 0.003 | 0.003 | |
| 7/26/95 | 12:40 PM | 5.105 | 50.490 | 0.010 | 10.583 | 45.012 | 0.009 | 21.050 | 34.545 | 0.007 | 55.595 | 0.008 | 0.008 | |
| 8/9/95 | 7:55 AM | 5.105 | 50.490 | 0.010 | 10.580 | 45.015 | 0.006 | 21.050 | 34.545 | 0.007 | 55.595 | 0.008 | 0.008 | |
| 9/1/95 | 7:45 AM | 5.105 | 50.490 | 0.010 | 10.583 | 45.012 | 0.009 | 21.047 | 34.548 | 0.004 | 55.595 | 0.008 | 0.008 | |
| 9/20/95 | 2:25 PM | 5.103 | 50.420 | 0.080 | 10.577 | 44.946 | 0.075 | 21.045 | 34.478 | 0.074 | 55.523 | 0.080 | 0.080 | |
| 10/11/95 | 3:15 PM | 5.107 | 50.483 | 0.017 | 10.580 | 45.010 | 0.011 | 21.047 | 34.543 | 0.009 | 55.590 | 0.013 | 0.013 | |
| 11/3/95 | 9:45 AM | 5.095 | 50.488 | 0.012 | 10.573 | 45.010 | 0.011 | 21.040 | 34.543 | 0.009 | 55.583 | 0.020 | 0.020 | |
| 11/22/95 | 10:00 AM | 5.095 | 50.428 | 0.072 | 10.567 | 44.956 | 0.065 | 21.040 | 34.483 | 0.069 | 55.523 | 0.080 | 0.080 | |
| 12/20/95 | 10:30 AM | 5.125 | 50.485 | 0.015 | 10.595 | 45.015 | 0.006 | 21.065 | 34.545 | 0.007 | 55.610 | 0.007 | -0.007 | |
| 1/11/96 | 10:00 AM | 5.095 | 50.428 | 0.072 | 10.563 | 44.960 | 0.061 | 21.033 | 34.490 | 0.062 | 55.523 | 0.080 | 0.080 | |
| 2/8/96 | 2:00 PM | 5.095 | 50.428 | 0.072 | 10.567 | 44.956 | 0.065 | 21.035 | 34.488 | 0.064 | 55.523 | 0.080 | 0.080 | |
| 2/29/96 | 2:00 PM | 5.095 | 50.425 | 0.075 | 10.563 | 44.957 | 0.064 | 21.030 | 34.490 | 0.062 | 55.520 | 0.083 | 0.083 | |
| 3/28/96 | 1:00 PM | 5.093 | 50.427 | 0.073 | 10.565 | 44.955 | 0.066 | 21.033 | 34.487 | 0.065 | 55.520 | 0.083 | 0.083 | |
| 4/23/96 | 10:30 AM | 5.093 | 50.422 | 0.078 | 10.565 | 44.950 | 0.071 | 21.137 | 34.378 | 0.174 | 55.515 | 0.088 | 0.088 | |
| 5/21/96 | 8:30 AM | 5.245 | 50.405 | 0.095 | 10.700 | 44.950 | 0.071 | 21.165 | 34.485 | 0.067 | 55.650 | 0.113 | 0.113 | |
| 6/11/96 | 1:00 PM | 5.254 | 50.288 | 0.212 | 10.600 | 44.942 | 0.079 | 21.064 | 34.478 | 0.074 | 55.542 | 0.221 | 0.221 | |
| 8/6/96 | 2:00 PM | 5.267 | 50.283 | 0.217 | 10.607 | 44.943 | 0.078 | 21.075 | 34.475 | 0.077 | 55.550 | 0.213 | 0.213 | |
| 10/31/96 | 12:45 PM | 5.250 | 50.345 | 0.155 | 10.588 | 45.007 | 0.014 | 21.056 | 34.539 | 0.013 | 55.595 | 0.168 | 0.168 | |
| 12/16/96 | 11:00 AM | 5.250 | 50.340 | 0.160 | 10.585 | 45.005 | 0.016 | 21.053 | 34.537 | 0.015 | 55.590 | 0.173 | 0.173 | |
| 2/27/97 | 11:10 AM | 5.250 | 50.345 | 0.155 | 10.585 | 45.010 | 0.011 | 21.050 | 34.545 | 0.007 | 55.595 | 0.168 | 0.168 | |

ODOT US177 Approach Embankment Evaluation

Bridge A, North Abutment Wall (Control Section-Unclassified Borrow)

Piezometer:

Standpipe Elevation 928.10' → 926.65'
 *As Built (Top=2.44 ft above GS) (As Built) (After Paving)

GS Elevation 925.66' Pavement Elevation 926.99'
 (Top of Subgrade) (Top of Pavement)

Tip Elevation 880.66' Tip Depth 45.0'

Groundwater Depth = Piezometer Reading + 0.34'
 (Below Top of Pavement)

Groundwater Elevation = Standpipe Elevation (926.65') - Piezometer Reading

| Piezometer Data | | | | | Remarks |
|-----------------|----------|---------|----------|----------|--|
| Date | Time | Reading | GW Depth | GW Elev. | |
| | | ft | ft | ft | |
| 5/17/95 | PM | - | - | - | Installed piezometer |
| 5/23/95 | AM | 33.50 | 31.06 | 894.60 | Initial reading by OSU |
| 5/31/95 | AM | 31.65 | 29.21 | 896.45 | |
| 6/19/95 | PM | 29.60 | 27.16 | 898.50 | |
| 6/28/95 | PM | 30.55 | 28.11 | 897.55 | |
| 7/7/95 | 10:25 AM | 30.38 | 27.94 | 897.72 | |
| 7/14/95 | 9:40 AM | 31.39 | 28.95 | 896.71 | |
| 7/26/95 | 12:40 PM | 31.90 | 29.46 | 896.20 | |
| 8/9/95 | 7:55 AM | 27.90 | 25.46 | 900.20 | |
| 9/1/95 | 7:45 AM | 31.80 | 29.36 | 896.30 | |
| 9/20/95 | 2:25 PM | 33.41 | 30.97 | 894.69 | |
| 10/11/95 | 3:15 PM | 33.96 | 31.52 | 894.14 | |
| 11/3/95 | 9:45 AM | 34.52 | 32.08 | 893.58 | |
| 11/22/95 | 10:00 AM | 34.72 | 32.28 | 893.38 | |
| 12/20/95 | 10:30 AM | 34.96 | 32.52 | 893.14 | |
| 1/11/96 | 10:00 AM | 35.09 | 32.65 | 893.01 | |
| 2/8/96 | 2:00 PM | 35.33 | 32.89 | 892.77 | |
| 2/29/96 | 2:00 PM | 35.47 | 33.03 | 892.64 | |
| 3/28/96 | 1:00 PM | 35.57 | 33.13 | 892.53 | |
| 4/23/96 | 10:30 AM | 35.73 | 33.29 | 892.37 | |
| 5/21/96 | 8:30 AM | 34.51 | 34.85 | 892.14 | Use new standpipe elev., changed reference for depth |
| 6/11/96 | 1:00 PM | 33.95 | 34.29 | 892.70 | Highway opened to traffic |
| 8/6/96 | 2:00 PM | 33.47 | 33.81 | 893.18 | |
| 10/31/96 | 12:45 PM | 33.18 | 33.52 | 893.48 | |
| 12/16/96 | 11:00 AM | 32.75 | 33.09 | 893.90 | |
| 2/27/97 | 11:10 AM | 32.49 | 32.83 | 894.17 | |

ODOT US177 Approach Embankment Evaluation

Bridge A, North Abutment Wall (Control Section-Unclassified Borrow), Surface Settlement Points

| Date | 6/12/96 | | | 8/6/96 | | | 10/31/96 | | | 2/27/97 | | |
|------|---------|---------------|--|---------|---------------|--|----------|---------------|--|---------|---------------|--|
| | Reading | Elevation | | Reading | Elevation | | Reading | Elevation | | Reading | Elevation | |
| BM | | W E 929.06 | | | W E 929.06 | | | W E 929.06 | | | W E 929.06 | |
| BS | 2.42 | - | | 2.730 | - | | 3.448 | - | | 3.252 | - | |
| HI | 931.48 | - | | 931.79 | - | | 932.51 | - | | 932.312 | - | |
| FS 1 | 4.80 | 926.68 | | 5.110 | 926.680 | | 5.842 | 926.666 | | 5.650 | 926.662 | |
| 2 | 4.67 | 926.81 | | 5.024 | 926.766 | | 5.746 | 926.762 | | 5.560 | 926.752 | |
| 3 | 4.55 | 926.93 | | 4.889 | 926.901 | | 5.613 | 926.895 | | 5.422 | 926.890 | |
| 4 | 4.46 | 927.02 | | 4.787 | 927.003 | | 5.512 | 926.996 | | 5.322 | 926.990 | |
| 5 | 4.81 | 926.67 | | 5.127 | 926.663 | | 5.860 | 926.648 | | 5.665 | 926.647 | |
| 6 | 4.70 | 926.78 | | 5.053 | 926.737 | | 5.778 | 926.730 | | 5.590 | 926.722 | |
| 7 | 4.59 | 926.89 | | 4.923 | 926.867 | | 5.644 | 926.864 | | 5.452 | 926.860 | |
| 8 | 4.50 | 926.98 | | 4.835 | 926.955 | | 5.556 | 926.952 | | 5.364 | 926.948 | |
| 9 | 4.83 | 926.65 | | 5.147 | 926.643 | | 5.878 | 926.630 | | 5.702 | 926.610 | |
| 10 | 4.72 | 926.76 | | 5.058 | 926.732 | | 5.785 | 926.723 | | 5.590 | 926.722 | |
| 11 | 4.60 | 926.88 | | 4.930 | 926.860 | | 5.655 | 926.853 | | 5.464 | 926.848 | |
| 12 | 4.50 | 926.98 | | 4.820 | 926.970 | | 5.543 | 926.965 | | 5.354 | 926.958 | |
| 13 | 4.85 | 926.63 | | 4.162 | 927.628 | | 5.887 | 926.621 | | 5.715 | 926.597 | |
| 14 | 4.73 | 926.75 | | 5.073 | 926.717 | | 5.796 | 926.712 | | 5.605 | 926.707 | |
| 15 | 4.62 | 926.86 | | 4.947 | 926.843 | | 5.670 | 926.838 | | 5.480 | 926.832 | |
| 16 | 4.50 | 926.98 | | 4.823 | 926.967 | | 5.543 | 926.965 | | 5.393 | 926.919 | |

APPENDIX B3

B1 Instrumentation Data

ODOT US177 Approach Embankment Evaluation

Bridge B, South Abutment Wall (Geotextile Reinforced Wall)

Total Pressure Cells:

| | Tubing Length | Date Installed | Test Pressures | | |
|-------------------|---------------|----------------|----------------|--------|---------|
| | | | 5 psi | 50 psi | 100 psi |
| Top - SN 44197 | 34' | 4/25/95 | 4.95 | 49.93 | 99.94 |
| Middle - SN 44202 | 37' | 4/25/95 | 5.06 | 50.22 | 100.29 |
| Bottom - SN 44212 | 40' | 4/25/95 | 5.43 | 50.50 | 100.52 |

| Date | Time | TPC Readings (psi) | | | | | | Remarks |
|----------|----------|--------------------|--------------|---------------|-----------------|---------------|-----------------|---|
| | | Top w/flow | Top w/o flow | Middle w/flow | Middle w/o flow | Bottom w/flow | Bottom w/o flow | |
| 5/5/95 | 10:00 AM | 0.1 | 0.0 | 0.1 | 0.0 | 0.5 | 0.3 | Initial Readings by WCC, T = 60 degrees C |
| 5/23/95 | 2:00 PM | 0.3 | 0.2 | 0.4 | 0.3 | 2.1 | 2.0 | During plcmt. of 4th lift, b/fill above lower TPC |
| 5/31/95 | PM | 0.5 | 0.4 | 1.8 | 1.7 | 4.5 | 4.4 | After compaction of G R. wall (i.e. 8 lifts) |
| 6/19/95 | AM | 0.9 | 0.8 | 2.0 | 1.9 | 6.9 | 6.8 | |
| 6/28/95 | PM | 0.7 | 0.6 | 1.6 | 1.4 | 6.5 | 6.4 | |
| 7/7/95 | 11:45 AM | 0.7 | 0.6 | 1.8 | 1.7 | 7.0 | 6.9 | |
| 7/14/95 | 11:10 AM | 0.8 | 0.6 | 2.1 | 2.0 | 7.8 | 7.7 | |
| 7/26/95 | 10:45 AM | 1.0 | 0.9 | 2.4 | 2.2 | 8.8 | 8.7 | |
| 8/9/95 | 8:40 AM | 0.7 | 0.6 | 1.9 | 1.7 | 6.3 | 6.2 | |
| 9/1/95 | 8:30 AM | 0.5 | 0.4 | 1.9 | 1.8 | 7.5 | 7.4 | |
| 9/20/95 | 3:35 PM | 0.6 | 0.5 | 1.5 | 1.3 | 7.5 | 7.4 | T = 21 degrees C |
| 10/11/95 | 3:55 PM | 0.4 | 0.3 | 0.9 | 0.7 | 6.4 | 6.4 | T = 32 degrees C |
| 11/3/95 | 11:00 AM | 0.4 | 0.3 | 1.1 | 1.0 | 8.4 | 8.3 | |
| 11/22/95 | 11:00 AM | 0.3 | 0.1 | 0.6 | 0.5 | 6.1 | 6.0 | |
| 12/20/95 | 11:30 AM | 0.2 | 0.1 | 0.4 | 0.3 | 5.9 | 5.8 | |
| 1/11/96 | 12:00 PM | 0.1 | 0.0 | 0.3 | 0.2 | 4.1 | 4.0 | |
| 2/8/96 | 3:00 PM | 0.1 | 0.0 | 0.1 | 0.0 | 3.6 | 3.5 | |
| 2/29/96 | 3:00 PM | 0.4 | 0.3 | 0.6 | 0.5 | 6.5 | 6.4 | |
| 3/28/96 | 2:00 PM | 0.2 | 0.1 | 0.4 | 0.3 | 5.6 | 5.5 | |
| 4/23/96 | 11:30 AM | 0.4 | 0.3 | 0.7 | 0.6 | 5.8 | 5.7 | |
| 5/2/96 | 8:10 AM | 0.4 | 0.2 | 0.4 | 0.3 | 5.4 | 5.3 | Before Flooding of Cardboard |
| 5/2/96 | 10:00 AM | 0.5 | 0.4 | 0.6 | 0.5 | 3.6 | 3.5 | After Flooding of Cardboard |
| 5/21/96 | 9:00 AM | 0.3 | 0.2 | 0.6 | 0.5 | 4.2 | 4.1 | |
| 6/11/96 | 12:30 PM | 0.5 | 0.3 | 0.6 | 0.5 | 3.4 | 3.3 | Highway Opened to Traffic |
| 8/6/96 | AM | 0.4 | 0.2 | 0.6 | 0.4 | 4.4 | 4.2 | |
| 10/31/96 | 10:50 AM | 0.3 | 0.1 | 0.6 | 0.5 | 4.1 | 4.0 | |
| 12/16/96 | 10:20 AM | 0.2 | 0.0 | 0.5 | 0.4 | 2.6 | 2.5 | |
| 2/27/97 | 10:40 AM | 0.2 | 0.0 | 0.5 | 0.4 | 1.7 | 1.6 | |

ODOT US177 Approach Embankment Evaluation

Bridge B, South Abutment Wall (Geotextile Reinforced Wall)

Amplified Liquid Settlement Gages:

| | Tubing Length | Date Installed | As Built Elevation | |
|-----------------------|---------------|----------------|-----------------------|--------------|
| | | | Top of Plate | Top of Fluid |
| Centerline - SN 44215 | 40' | 4/25/95 | 912.95' | 923.49' |
| | | | Initial Head = 10.54' | |
| Offset - SN 44220 | 30' | 4/25/95 | 912.94' | 923.49' |
| 10' wide | | | Initial Head = 10.55' | |

Calibration for: Centerline

Offset

$$\text{Head(ft)} = \frac{\text{Reading} - (-2.49 \text{ psi})}{8.33 \text{ psi / ft}}$$

$$\text{Head(ft)} = \frac{\text{Reading} - (-3.44 \text{ psi})}{8.40 \text{ psi / ft}}$$

| ALSG Readings, Heads, & ΔH | | | | | | | | Remarks |
|----------------------------|----------|----------------|------------------|----------|----------------|-------------------|----------|---|
| Date | Time | Reading psi | CL Head ft | ΔH ft | Reading psi | OFS Head ft | ΔH ft | |
| 5/4/95 | 11:20 AM | 85.6 | 10.575 | - | 86.0 | 10.648 | - | Initial Readings by WCC, T = 65 degrees C |
| 5/23/95 | 2:00 PM | 86.0 | 10.623 | 0.048 | 86.4 | 10.695 | 0.047 | During picmt. of 4th lift, b/fill above lower TPC After compaction of G.R. wall (i.e. 8 lifts) |
| 5/31/95 | PM | 86.4 | 10.671 | 0.096 | 86.6 | 10.719 | 0.071 | |
| 6/19/95 | AM | 86.7 | 10.707 | 0.132 | 86.7 | 10.731 | 0.083 | |
| 6/28/95 | PM | 86.7 | 10.707 | 0.132 | 86.8 | 10.743 | 0.095 | |
| 7/7/95 | 11:45 AM | 86.6 | 10.695 | 0.120 | 86.6 | 10.719 | 0.071 | |
| 7/14/95 | 11:10 AM | 86.5 | 10.683 | 0.108 | 86.4 | 10.695 | 0.047 | |
| 7/26/95 | 10:45 AM | 86.5 | 10.683 | 0.108 | 86.5 | 10.707 | 0.059 | |
| 8/9/95 | 8:40 AM | 86.4 | 10.671 | 0.096 | 86.4 | 10.695 | 0.047 | |
| 9/1/95 | 8:30 AM | 86.3 | 10.569 | 0.006 | 86.3 | 10.683 | 0.035 | |
| 9/20/95 | 3:35 PM | 86.7 | 10.707 | 0.132 | 86.5 | 10.707 | 0.059 | |
| 10/11/95 | 3:55 PM | 87.1 | 10.755 | 0.180 | 87.0 | 10.767 | 0.119 | |
| 11/3/95 | 11:00 AM | 86.8 | 10.719 | 0.144 | 86.7 | 10.731 | 0.083 | |
| 11/22/95 | 11:00 AM | 87.3 | 10.779 | 0.204 | 87.1 | 10.779 | 0.131 | |
| 12/20/95 | 11:30 AM | 87.3 | 10.779 | 0.204 | 87.2 | 10.790 | 0.142 | |
| 1/11/96 | 12:00 PM | 87.6 | 10.815 | 0.240 | 87.6 | 10.838 | 0.190 | |
| 2/8/96 | 3:00 PM | 88.0 | 10.863 | 0.288 | 87.7 | 10.850 | 0.202 | |
| 2/29/96 | 3:00 PM | 87.9 | 10.851 | 0.276 | 87.0 | 10.767 | 0.119 | |
| 3/28/96 | 2:00 PM | 87.7 | 10.827 | 0.252 | 87.4 | 10.814 | 0.166 | |
| 4/23/96 | 11:00 AM | 87.8 | 10.839 | 0.264 | 86.9 | 10.757 | 0.109 | |
| 5/21/96 | 9:00 AM | 87.2 | 10.767 | 0.192 | 86.5 | 10.707 | 0.059 | |
| 6/11/96 | 12:30 PM | 87.6 | 10.815 | 0.240 | 87.2 | 10.790 | 0.142 | Highway opened to traffic |
| 8/6/96 | PM | 87.0 | 10.743 | 0.168 | 86.9 | 10.757 | 0.109 | |
| 10/31/96 | 10:50 AM | 87.0 | 10.743 | 0.168 | 87.1 | 10.779 | 0.131 | |
| 12/16/96 | 10:20 AM | 87.8 | 10.839 | 0.264 | 87.7 | 10.850 | 0.202 | |
| 2/27/97 | 10:40 AM | 87.8 | 10.839 | 0.264 | 87.8 | 10.862 | 0.214 | |

ODOT US177 Approach Embankment Evaluation

Bridge B, South Abutment Wall (Geotextile Reinforced Wall)

Inclinometer Telescoping Couplings - Centerline: Installed 6/3/95

Casing Elevation 925.15' → 924.66'
(top=2.0' above GS) As Built After Paving

GS Elevation 923.15' Pavement Elevation 924.98'

Reference Coupling 51.23' → 871.92' Bottom of Casing 53.22'
Depth Elevation

| Readings, Changes, & ΔH Values | | | | | | | | | | | | | | |
|--------------------------------|----------|-----------------|--------|----------|-----------------|--------|----------|-----------------|--------|----------|-------------------|-----------|----------|--------------------------------|
| Date | Time | Level 1 (Top) | | | Level 2 | | | Level 3 | | | Level 4 (Bottom) | | | Remarks |
| | | Reading R4 - R1 | | ΔH ft | Reading R4 - R2 | | ΔH ft | Reading R4 - R3 | | ΔH ft | Reading R4, ft | ΔR4 ft | ΔH ft | |
| | | R1, ft | ft | | R2, ft | ft | | R3, ft | ft | | | | | |
| 6/6/95 | PM | 10.874 | 42.354 | - | 15.874 | 37.354 | - | 20.874 | 32.354 | - | 53.228 | - | - | Omit this Data set |
| 6/19/95 | AM | 10.874 | 42.427 | 0.000 | 15.900 | 37.401 | 0.000 | 20.895 | 32.406 | 0.000 | 53.301 | 0.000 | 0.000 | Reference Reading (Datum) |
| 6/28/95 | PM | 10.880 | 42.390 | 0.037 | 15.870 | 37.400 | 0.001 | 20.865 | 32.405 | 0.001 | 53.270 | 0.031 | 0.031 | |
| 7/7/95 | 11:45 AM | 10.880 | 42.390 | 0.037 | 15.875 | 37.395 | 0.006 | 20.870 | 32.400 | 0.006 | 53.270 | 0.031 | 0.031 | |
| 7/14/95 | 11:10 AM | 10.885 | 42.390 | 0.037 | 15.880 | 37.395 | 0.006 | 20.870 | 32.405 | 0.001 | 53.275 | 0.026 | 0.026 | |
| 7/26/95 | 10:45 AM | 10.880 | 42.335 | 0.092 | 15.870 | 37.345 | 0.056 | 20.865 | 32.350 | 0.056 | 53.215 | 0.086 | 0.086 | |
| 8/9/95 | 8:40 AM | 10.883 | 42.392 | 0.035 | 15.875 | 37.400 | 0.001 | 20.870 | 32.405 | 0.001 | 53.275 | 0.026 | 0.026 | |
| 9/1/95 | 8:30 AM | 10.883 | 42.390 | 0.037 | 15.873 | 37.400 | 0.001 | 20.867 | 32.406 | 0.000 | 53.273 | 0.028 | 0.028 | |
| 9/20/95 | 3:35 PM | 10.880 | 42.327 | 0.100 | 15.870 | 37.337 | 0.064 | 20.863 | 32.344 | 0.062 | 53.207 | 0.094 | 0.094 | |
| 10/11/95 | 3:55 PM | 10.883 | 42.384 | 0.043 | 15.873 | 37.394 | 0.007 | 20.865 | 32.402 | 0.004 | 53.267 | 0.034 | 0.034 | |
| 11/3/95 | 11:00 AM | 10.870 | 42.335 | 0.092 | 15.865 | 37.340 | 0.061 | 20.855 | 32.350 | 0.056 | 53.205 | 0.096 | 0.096 | |
| 11/22/95 | 11:00 AM | 10.870 | 42.387 | 0.040 | 15.865 | 37.392 | 0.009 | 20.857 | 32.400 | 0.006 | 53.257 | 0.044 | 0.044 | |
| 12/20/95 | 11:30 AM | 10.865 | 42.390 | 0.037 | 15.857 | 37.398 | 0.003 | 20.855 | 32.400 | 0.006 | 53.255 | 0.046 | 0.046 | |
| 1/11/96 | 12:00 PM | 10.865 | 42.338 | 0.089 | 15.860 | 37.343 | 0.058 | 20.853 | 32.350 | 0.056 | 53.203 | 0.098 | 0.098 | |
| 2/8/96 | 3:00 PM | 10.865 | 42.332 | 0.095 | 15.857 | 37.340 | 0.061 | 20.853 | 32.344 | 0.062 | 53.197 | 0.104 | 0.104 | |
| 2/29/96 | 3:00 PM | 10.868 | 42.337 | 0.090 | 15.855 | 37.350 | 0.051 | 20.855 | 32.350 | 0.056 | 53.205 | 0.096 | 0.096 | |
| 3/28/96 | 2:00 PM | 10.870 | 42.330 | 0.097 | 15.857 | 37.343 | 0.058 | 20.853 | 32.347 | 0.059 | 53.200 | 0.101 | 0.101 | (-0.03) for diff. b/w cutoff |
| 4/23/96 | 11:30 AM | 10.863 | 42.384 | 0.043 | 15.855 | 37.392 | 0.009 | 20.850 | 32.397 | 0.009 | 53.247 | 0.054 | 0.054 | length and ext. |
| 5/21/96 | 9:00 AM | 10.900 | 42.325 | 0.102 | 15.893 | 37.332 | 0.069 | - | - | - | 53.225 | 0.106 | 0.106 | New reference (top) using ext. |
| 6/11/96 | 12:30 PM | 10.905 | 42.375 | 0.052 | 15.895 | 37.385 | 0.016 | 20.887 | 32.393 | 0.013 | 53.280 | 0.051 | 0.051 | Highway opened to traffic |
| 8/6/96 | AM | 10.908 | 42.37 | 0.055 | 15.897 | 37.383 | 0.018 | 20.890 | 32.390 | 0.016 | 53.280 | 0.051 | 0.051 | |
| 10/31/96 | 10:50 AM | 10.905 | 42.370 | 0.057 | 15.895 | 37.380 | 0.021 | 20.890 | 32.385 | 0.021 | 53.275 | 0.056 | 0.056 | |
| 12/16/96 | 10:20 AM | 10.905 | 42.370 | 0.057 | 15.893 | 37.382 | 0.019 | 20.885 | 32.390 | 0.016 | 53.275 | 0.056 | 0.056 | |
| 2/27/97 | 10:40 AM | 10.920 | 42.370 | 0.057 | 15.907 | 37.383 | 0.018 | 20.900 | 32.390 | 0.016 | 53.290 | 0.041 | 0.041 | |

ODOT US177 Approach Embankment Evaluation

Bridge B, South Abutment Wall (Geotextile Reinforced Wall)

Inclinometer Telescoping Couplings - Offset: Installed 6/5/95

Casing Elevation 925.08' → 924.53'
(top=2.0' above GS) As Built After Paving

GS Elevation 923.08' Pavement Elevation 924.98'

Reference Coupling 51.29' → 871.79' Bottom of Casing 53.25'
Depth Elevation

| Readings, Changes, & ΔH Values | | | | | | | | | | | | | | |
|--------------------------------|----------|----------------|------------|--------|----------------|------------|--------|----------------|------------|--------|------------------|--------|--------|--|
| Date | Time | Level 1 (Top) | | | Level 2 | | | Level 3 | | | Level 4 (Bottom) | | | Remarks |
| | | Reading R1, ft | R4 - R1 ft | ΔH ft | Reading R2, ft | R4 - R2 ft | ΔH ft | Reading R3, ft | R4 - R3 ft | ΔH ft | Reading R4, ft | ΔR4 ft | ΔH ft | |
| 6/6/95 | PM | 10.884 | 42.406 | - | 15.895 | 37.395 | - | 20.884 | 32.406 | - | 53.290 | - | - | Omit this Data set Reference Reading (Datum) |
| 6/19/95 | AM | 10.884 | 42.396 | 0.000 | 15.874 | 37.406 | 0.000 | 20.874 | 32.406 | 0.000 | 53.280 | 0.000 | 0.000 | |
| 6/28/95 | PM | 10.995 | 42.405 | -0.009 | 15.975 | 37.425 | -0.019 | 20.960 | 32.440 | -0.034 | 53.400 | 0.120 | -0.120 | (?) data |
| 7/7/95 | 11:45 AM | 10.875 | 42.420 | -0.024 | 15.900 | 37.395 | 0.011 | 20.890 | 32.405 | 0.001 | 53.295 | 0.015 | -0.195 | |
| 7/14/95 | 11:10 AM | 10.880 | 42.600 | -0.204 | 15.967 | 37.513 | -0.107 | 20.958 | 32.522 | -0.116 | 53.480 | 0.200 | -0.200 | |
| 7/26/95 | 10:45 AM | 10.880 | 42.375 | 0.021 | 15.900 | 37.355 | 0.051 | 20.890 | 32.365 | 0.041 | 53.255 | 0.025 | 0.025 | |
| 8/9/95 | 8:40 AM | 10.883 | 42.422 | -0.026 | 15.903 | 37.402 | 0.004 | 20.895 | 32.410 | -0.004 | 53.305 | 0.025 | -0.025 | |
| 9/1/95 | 8:30 AM | 10.885 | 42.415 | -0.019 | 15.905 | 37.395 | 0.011 | 20.893 | 32.407 | -0.001 | 53.300 | 0.020 | -0.020 | |
| 9/20/95 | 3:35 PM | 10.877 | 42.413 | -0.017 | 15.900 | 37.390 | 0.016 | 20.890 | 32.400 | 0.006 | 53.290 | 0.010 | -0.010 | |
| 10/11/95 | 3:55 PM | 10.880 | 42.420 | -0.024 | 15.905 | 37.395 | 0.011 | 20.893 | 32.407 | -0.001 | 53.300 | 0.020 | -0.020 | |
| 11/3/95 | 11:00 AM | 10.873 | 42.412 | -0.016 | 15.895 | 37.390 | 0.016 | 20.883 | 32.402 | 0.004 | 53.285 | 0.005 | -0.005 | |
| 11/22/95 | 11:00 AM | 10.867 | 42.418 | -0.022 | 15.893 | 37.392 | 0.014 | 20.833 | 32.452 | -0.046 | 53.285 | 0.005 | -0.005 | |
| 12/20/95 | 11:30 AM | 10.860 | 42.420 | -0.024 | 15.885 | 37.395 | 0.011 | 20.877 | 32.403 | 0.003 | 53.280 | 0.000 | 0.000 | (-0.10) for diff. b/w cutoff length and ext. New reference (top) using ext. Highway opened to traffic |
| 1/11/96 | 12:00 PM | 10.863 | 42.417 | -0.021 | 15.885 | 37.395 | 0.011 | 20.875 | 32.405 | 0.001 | 53.280 | 0.000 | 0.000 | |
| 2/8/96 | 3:00 PM | 10.860 | 42.415 | -0.019 | 15.880 | 37.395 | 0.011 | 20.875 | 32.400 | 0.006 | 53.275 | 0.005 | 0.005 | |
| 2/29/96 | 3:00 PM | 10.865 | 42.417 | -0.021 | 15.887 | 37.395 | 0.011 | 20.879 | 32.403 | 0.003 | 53.282 | 0.002 | -0.002 | |
| 3/28/96 | 2:00 PM | 10.865 | 42.415 | -0.019 | 15.890 | 37.390 | 0.016 | 20.877 | 32.403 | 0.003 | 53.280 | 0.000 | 0.000 | |
| 4/23/96 | 11:00 AM | 10.870 | 42.367 | 0.029 | 15.890 | 37.347 | 0.059 | 20.880 | 32.357 | 0.049 | 53.237 | 0.006 | -0.006 | |
| 5/21/96 | 9:00 AM | 10.970 | 42.217 | 0.179 | 15.857 | 37.330 | 0.076 | - | - | - | 53.187 | 0.193 | 0.193 | |
| 6/11/96 | 12:30 PM | 10.977 | 42.265 | 0.131 | 15.864 | 37.378 | 0.028 | 20.852 | 32.390 | 0.016 | 53.242 | 0.138 | 0.138 | |
| 8/6/96 | AM | 10.982 | 42.270 | 0.126 | 15.872 | 37.380 | 0.026 | 20.863 | 32.389 | 0.017 | 53.252 | 0.128 | 0.128 | |
| 10/31/96 | 10:50 AM | 10.970 | 42.272 | 0.124 | 15.864 | 37.378 | 0.028 | 20.852 | 32.390 | 0.016 | 53.242 | 0.138 | 0.138 | |
| 12/16/96 | 10:20 AM | 10.967 | 42.228 | 0.168 | 15.857 | 37.338 | 0.068 | 20.847 | 32.348 | 0.058 | 53.195 | 0.085 | 0.085 | |
| 2/27/97 | 10:40 AM | 10.963 | 42.270 | 0.126 | 15.855 | 37.378 | 0.028 | 20.843 | 32.390 | 0.016 | 53.233 | 0.147 | 0.147 | |

ODOT US177 Approach Embankment Evaluation

Bridge B, South Abutment Wall (Geotextile Reinforced Wall)

Piezometer:

| | | | | |
|----------------------------|-------------------------------|-------------------|---------------------------|----------------|
| Standpipe Elevation | | 925.13' | 924.66' | |
| *As Built ▶ | (Top=1.90 ft above GS) | (As Built) | (After Paving) | |
| GS Elevation | | 923.23' | Pavement Elevation | 924.98' |
| (Top of Subgrade) | | | (Top of Pavement) | |
| Tip Elevation | | 878.23' | Tip Depth | 45.0' |

Groundwater Depth = Piezometer Reading - 0.32'
(Below Top of Pavement)

Groundwater Elevation = Standpipe Elevation (924.66') - Piezometer Reading

| Piezometer Data | | | | | Remarks |
|-----------------|----------|---------|----------|----------|--|
| Date | Time | Reading | GW Depth | GW Elev. | |
| | | ft | ft | ft | |
| 6/3/95 | PM | - | - | - | Installed piezometer |
| 6/5/95 | AM | 23.60 | 21.70 | 901.53 | Initial reading by OSU |
| 6/19/95 | AM | 26.55 | 24.65 | 898.58 | |
| 6/28/95 | AM | 26.74 | 24.84 | 898.39 | |
| 7/7/95 | 11:30 AM | 26.60 | 24.70 | 898.53 | |
| 7/14/95 | 9:40 AM | 26.89 | 24.99 | 898.24 | |
| 7/26/95 | 10:45 AM | 27.55 | 25.65 | 897.58 | |
| 8/9/95 | 8:40 AM | 24.30 | 22.40 | 900.83 | |
| 9/1/95 | 8:30 AM | 26.65 | 24.75 | 898.48 | |
| 9/20/95 | 3:35 PM | 28.11 | 26.21 | 897.02 | |
| 10/11/95 | 3:55 PM | 28.85 | 26.95 | 896.29 | |
| 11/3/95 | 11:00 AM | 29.54 | 27.64 | 895.59 | |
| 11/22/95 | 11:00 AM | 29.92 | 28.02 | 895.21 | |
| 12/20/95 | 11:30 AM | 30.40 | 28.50 | 894.73 | |
| 1/11/96 | 12:00 PM | 30.63 | 28.73 | 894.50 | |
| 2/8/96 | 3:00 PM | 30.97 | 29.07 | 894.16 | |
| 2/29/96 | 3:00 PM | 31.17 | 29.27 | 893.96 | |
| 3/28/96 | 2:00 PM | 31.39 | 29.49 | 893.74 | |
| 4/23/96 | 11:30 AM | 34.61 | 32.71 | 890.52 | |
| 5/21/96 | 9:00 AM | 31.31 | 30.99 | 893.35 | Use new standpipe elev., changed reference for depth |
| 6/11/96 | 12:30 PM | 31.11 | 30.79 | 893.55 | Highway opened to traffic |
| 8/6/96 | AM | 31.05 | 30.73 | 893.61 | |
| 10/31/96 | 10:50 AM | 30.58 | 30.26 | 894.08 | |
| 12/16/96 | 10:20 AM | 30.06 | 29.74 | 894.60 | |
| 2/27/97 | 10:40 AM | 31.70 | 31.38 | 892.96 | |

ODOT US177 Approach Embankment Evaluation

Bridge B, South Abutment Wall (Geotextile Reinforced Wall), Surface Settlement Points

| Date | 6/12/96 | | | 8/6/96 | | | 10/31/96 | | | 2/28/97 | | |
|------|---------|---------------|--|---------|---------------|--|----------|----------------------|--|---------|---------------|------------|
| | Reading | Elevation | | Reading | Elevation | | Reading | Elevation | | Reading | Elevation | |
| BM | | W 927.16 E | | | W 927.16 E | | | W 927.16 E 927.17 | | | W 927.16 E | |
| BS | 2.42 | - | | 2.878 | - | | 3.215 | - | | 3.138 | - | |
| HI | 929.58 | - | | 930.038 | - | | 930.38 | - | | 930.298 | - | |
| FS 1 | 4.73 | 924.85 | | 5.198 | 924.840 | | 5.560 | 924.815 | | 5.487 | 924.811 | |
| 2 | 4.65 | 924.93 | | 5.145 | 924.893 | | 5.488 | 924.887 | | 5.416 | 924.882 | |
| 3 | 4.57 | 925.01 | | 5.048 | 924.990 | | 5.395 | 924.980 | | 5.324 | 924.974 | |
| 4 | 4.47 | 925.11 | | 4.944 | 925.094 | | 5.283 | 925.092 | | 5.210 | 925.088 | |
| 5 | 4.78 | 924.80 | | 5.240 | 924.798 | | 5.600 | 924.775 | | 5.527 | 924.771 | |
| 6 | 4.68 | 924.90 | | 5.180 | 924.858 | | 5.520 | 924.855 | | 5.447 | 924.851 | |
| 7 | 4.58 | 925.00 | | 5.063 | 924.975 | | 5.408 | 924.967 | | 5.337 | 924.961 | |
| 8 | 4.51 | 925.07 | | 4.992 | 925.046 | | 5.330 | 925.045 | | 5.257 | 925.041 | |
| 9 | 4.78 | 924.80 | | 5.262 | 924.776 | | 5.608 | 924.767 | | 5.537 | 924.761 | |
| 10 | 4.69 | 924.89 | | 5.196 | 924.842 | | 5.536 | 924.839 | | 5.464 | 924.834 | |
| 11 | 4.58 | 925.00 | | 5.074 | 924.964 | | 5.420 | 924.955 | | 5.348 | 924.950 | |
| 12 | 4.54 | 925.04 | | 5.047 | 924.991 | | 5.381 | 924.994 | | 5.309 | 924.989 | |
| 13 | 4.77 | 924.81 | | 5.245 | 924.793 | | 5.606 | 924.769 | | 5.531 | 924.767 | |
| 14 | 4.70 | 924.88 | | 5.208 | 924.830 | | 5.547 | 924.828 | | 5.476 | 924.822 | |
| 15 | 4.60 | 924.98 | | 5.097 | 924.941 | | 5.442 | 924.933 | | 5.368 | 924.930 | |
| 16 | 4.55 | 925.03 | | 5.025 | 925.013 | | 5.368 | 925.007 | | 5.321 | 924.977 | *2/27/1997 |

*Settlement Reading Point is missing.

APPENDIX B4

B2 Instrumentation Data

ODOT US177 Approach Embankment Evaluation

Bridge B, North Abutment Wall (Controlled Low Strength Backfill)

Total Pressure Cells:

| | Tubing Length | Date Installed | Test Pressures | | |
|-------------------|---------------|----------------|----------------|--------|---------|
| | | | 5 psi | 50 psi | 100 psi |
| Top - SN 44198 | 34' | 4/27/95 | 4.95 | 49.96 | 100.00 |
| Middle - SN 44204 | 37' | 4/27/95 | 5.14 | 49.90 | 100.02 |
| Bottom - SN 44208 | 40' | 4/27/95 | 4.60 | 50.20 | 100.42 |

| Date | Time | TPC Readings (psi) | | | | | | Remarks |
|----------|----------|--------------------|--------------|---------------|-----------------|---------------|-----------------|--------------------------------------|
| | | Top w/flow | Top w/o flow | Middle w/flow | Middle w/o flow | Bottom w/flow | Bottom w/o flow | |
| 5/5/95 | | 0.3 | 0 | 0.1 | 0 | 0.1 | 0 | Initial Readings by WCC, no backfill |
| 5/12/95 | 1:30 PM | 0.0 | 0 | 0.9 | 0.8 | 1.7 | 1.5 | After placement of ~ 1/2 CLSB |
| 5/12/95 | 4:00 PM | 1.4 | 1.0 | 2.8 | 2.7 | 2.4 | 2.2 | After placement of all CLSB |
| 5/16/95 | 9:20 AM | 0.5 | 0.2 | 0.4 | 0.3 | 2 | 1.8 | 4 days after CLSB pour |
| 5/31/95 | AM | 0.4 | 0.2 | 0.5 | 0.5 | 1.7 | 1.6 | |
| 6/16/95 | PM | 0.5 | 0.2 | 0.3 | 0.2 | 0.7 | 0.6 | |
| 6/28/95 | PM | 0.3 | 0.0 | 0.4 | 0.2 | 0.6 | 0.4 | |
| 7/7/95 | 12:35 PM | 0.6 | 0.3 | 0.4 | 0.2 | 0.5 | 0.4 | |
| 7/14/95 | 1:25 PM | 0.7 | 0.4 | 0.1 | 0.0 | 0.4 | 0.3 | |
| 7/26/95 | 10:00 AM | 0.6 | 0.3 | 0.1 | 0.0 | 0.5 | 0.3 | |
| 8/9/95 | 9:15 AM | 0.4 | 0.1 | 0.1 | 0.0 | 0.5 | 0.3 | |
| 9/1/95 | 9:10 AM | 0.5 | 0.1 | 0.5 | 0.3 | 0.4 | 0.2 | |
| 9/22/95 | 12:10 PM | 0.3 | 0.0 | 0.3 | 0.2 | 0.7 | 0.5 | T = 13 degrees C |
| 10/12/95 | 2:35 PM | 0.4 | 0.0 | 0.0 | 0.0 | 0.7 | 0.6 | |
| 11/3/95 | 1:20 PM | 0.5 | 0.1 | 0.3 | 0.2 | 0.9 | 0.8 | |
| 11/22/95 | 12:00 PM | 0.5 | 0.1 | 0.1 | 0.0 | 0.8 | 0.7 | |
| 12/20/95 | 12:00 PM | 0.5 | 0.0 | 0.0 | 0.0 | 0.7 | 0.5 | |
| 1/11/96 | 2:00 PM | 0.4 | 0.2 | 0.1 | 0.0 | 0.5 | 0.4 | |
| 2/8/96 | 4:00 PM | 0.2 | 0.0 | 0.0 | 0.0 | 0.4 | 0.3 | |
| 2/29/96 | 4:00 PM | 0.4 | 0.3 | 0.1 | 0.0 | 0.7 | 0.6 | |
| 3/28/96 | 2:15 PM | 0.4 | 0.3 | 0.1 | 0.0 | 0.7 | 0.6 | |
| 4/23/96 | 12:00 PM | 0.4 | 0.1 | 0.3 | 0.2 | 0.6 | 0.5 | |
| 5/21/96 | 9:30 AM | 0.1 | 0.0 | 0.2 | 0.1 | 0.6 | 0.5 | |
| 6/11/96 | 11:30 AM | 0.3 | 0.1 | 0.4 | 0.3 | 1.1 | 1.0 | Highway Opened to Traffic |
| 8/6/96 | AM | 0.4 | 0.0 | 0.5 | 0.4 | 1.0 | 0.8 | |
| 10/31/96 | 10:15 AM | 0.4 | 0.0 | 0.3 | 0.2 | 1.1 | 1.0 | |
| 12/16/96 | 9:50 AM | 0.5 | 0.1 | 0.1 | 0.0 | 1.0 | 0.9 | |
| 2/27/97 | 9:50 AM | 0.5 | 0.0 | 0.1 | 0.0 | 0.8 | 0.7 | |

ODOT US177 Approach Embankment Evaluation

Bridge B, North Abutment Wall (Controlled Low Strength Backfill)

Amplified Liquid Settlement Gages:

| | Tubing Length | Date Installed | As Built Elevation | |
|-----------------------|---------------|----------------|-----------------------|--------------|
| | | | Top of Plate | Top of Fluid |
| Centerline - SN 44216 | 40' | 4/28/95 | 911.14' | 921.73' |
| | | | Initial Head = 10.59' | |
| Offset - SN 44219 | 30' | 4/28/95 | 911.15' | 921.67' |
| 10' wide | | | Initial Head = 10.52' | |

Calibration for: Centerline

Offset

$$\text{Head(ft)} = \frac{\text{Reading} - (-4.33 \text{ psi})}{8.35 \text{ psi / ft}}$$


$$\text{Head(ft)} = \frac{\text{Reading} - (-6.445 \text{ psi})}{8.395 \text{ psi / ft}}$$

| ALSG Readings, Heads, & ΔH | | | | | | | | Remarks |
|----------------------------|----------|----------------|------------------|----------|----------------|-------------------|----------|--|
| Date | Time | Reading psi | CL Head ft | ΔH ft | Reading psi | OFS Head ft | ΔH ft | |
| 5/5/95 | | 84.4 | 10.626 | - | 84.4 | 10.821 | - | Initial Readings by WCC, no backfill (datum) |
| 5/12/95 | 1:30 PM | 85.2 | 10.722 | 0.096 | 84.3 | 10.809 | -0.012 | After placement of ~ 1/2 CLSB |
| 5/12/95 | 4:00 PM | 85.4 | 10.746 | 0.120 | 84.3 | 10.809 | -0.012 | After placement of all CLSB |
| 5/16/95 | 9:20 AM | 85.5 | 10.758 | 0.132 | 84.3 | 10.809 | -0.012 | 4 days after CLSB pour |
| 5/31/95 | AM | 85.6 | 10.770 | 0.144 | 84.4 | 10.821 | 0.000 | |
| 6/16/95 | PM | 85.6 | 10.770 | 0.144 | 84.5 | 10.833 | 0.012 | |
| 6/28/95 | PM | 85.6 | 10.770 | 0.144 | 84.5 | 10.833 | 0.012 | |
| 7/7/95 | 12:35 PM | 85.5 | 10.758 | 0.032 | 84.5 | 10.833 | 0.012 | |
| 7/14/95 | 1:25 PM | 85.7 | 10.782 | 0.156 | 84.5 | 10.833 | 0.012 | |
| 7/26/95 | 10:00 AM | 85.7 | 10.782 | 0.156 | 84.5 | 10.833 | 0.012 | |
| 8/9/95 | 9:15 AM | 86.0 | 10.818 | 0.192 | 84.5 | 10.833 | 0.012 | |
| 9/1/95 | 9:10 AM | 85.9 | 10.806 | 0.180 | 84.4 | 10.821 | 0.000 | |
| 9/22/95 | 12:10 PM | 86.2 | 10.842 | 0.216 | 84.6 | 10.845 | 0.024 | |
| 10/12/95 | 2:35 PM | 84.0 | 10.578 | 0.048 | 84.4 | 10.821 | 0.000 | |
| 11/3/95 | 1:20 PM | 86.0 | 10.818 | 0.192 | 84.8 | 10.869 | 0.048 | |
| 11/22/95 | 12:00 PM | 86.5 | 10.878 | 0.252 | 85.0 | 10.893 | 0.072 | |
| 12/20/95 | 12:00 PM | 86.6 | 10.890 | 0.264 | 85.2 | 10.917 | 0.096 | |
| 1/11/96 | 2:00 PM | 87.0 | 10.938 | 0.312 | 85.4 | 10.940 | 0.199 | |
| 2/8/96 | 4:00 PM | 86.9 | 10.926 | 0.300 | 85.3 | 10.929 | 0.108 | |
| 2/29/96 | 4:00 PM | 86.7 | 10.902 | 0.276 | 85.2 | 10.917 | 0.096 | |
| 3/28/96 | 2:15 PM | 86.8 | 10.914 | 0.288 | 85.1 | 10.905 | 0.084 | |
| 4/23/96 | 12:00 PM | 87.1 | 10.950 | 0.324 | 85.0 | 10.893 | 0.072 | |
| 5/21/96 | 9:30 AM | 86.2 | 10.842 | 0.216 | 84.6 | 10.845 | 0.024 | |
| 6/11/96 | 11:30 AM | 86.9 | 10.926 | 0.300 | 85.2 | 10.917 | 0.096 | Highway opened to traffic |
| 8/6/96 | AM | 86.2 | 10.842 | 0.216 | 84.7 | 10.857 | 0.036 | |
| 10/31/96 | 10:15 AM | 86.4 | 10.866 | 0.240 | 84.6 | 10.845 | 0.024 | |
| 12/16/96 | 9:50 AM | 87.2 | 10.962 | 0.336 | 85.5 | 10.952 | 0.131 | |
| 2/27/97 | 9:50 AM | 87.3 | 10.974 | 0.348 | 85.6 | 10.964 | 0.143 | |

ODOT US177 Approach Embankment Evaluation

Bridge B, North Abutment Wall (Controlled Low Strength Backfill)

Inclinometer Telescoping Couplings - Centerline: Installed 5/22/95



| Date | Time | Readings, Changes, & ΔH Values | | | | | | | | | | | | Remarks |
|----------|----------|--------------------------------|------------|--------|----------------|------------|--------|----------------|------------|--------|------------------|--------|--------|---|
| | | Level 1 (Top) | | | Level 2 | | | Level 3 | | | Level 4 (Bottom) | | | |
| | | Reading R1, ft | R4 - R1 ft | ΔH ft | Reading R2, ft | R4 - R2 ft | ΔH ft | Reading R3, ft | R4 - R3 ft | ΔH ft | Reading R4, ft | ΔR4 ft | ΔH ft | |
| 6/1/95 | PM | 10.863 | 40.052 | 0.000 | 15.780 | 35.135 | 0.000 | 20.822 | 30.093 | 0.000 | 50.915 | 0.000 | | Reference Reading (Datum) Omit this Data set |
| 6/16/95 | AM | 10.874 | 40.802 | - | 15.895 | 35.781 | - | 20.936 | 30.740 | - | 51.676 | - | - | |
| 6/28/95 | AM | 10.870 | 40.055 | -0.003 | 15.885 | 35.040 | 0.095 | 20.825 | 30.100 | -0.007 | 50.925 | 0.010 | -0.010 | |
| 7/7/95 | 12:35 PM | 11.270 | 40.030 | 0.022 | 16.215 | 35.085 | 0.050 | 21.260 | 30.040 | 0.053 | 51.300 | 0.385 | -0.385 | |
| 7/14/95 | 1:25 PM | 10.770 | 40.170 | -0.118 | 15.785 | 35.155 | -0.020 | 20.850 | 30.090 | 0.003 | 50.940 | 0.025 | -0.025 | |
| 7/26/95 | 10:00 AM | 10.770 | 40.155 | -0.103 | 15.780 | 35.145 | -0.010 | 20.830 | 30.095 | -0.002 | 50.925 | 0.010 | -0.010 | |
| 8/9/95 | 9:15 AM | 10.765 | 40.160 | -0.108 | 15.780 | 35.145 | -0.010 | 20.830 | 30.095 | -0.002 | 50.925 | 0.010 | -0.010 | |
| 9/1/95 | 9:10 AM | 10.767 | 40.160 | -0.108 | 15.785 | 35.142 | -0.007 | 20.835 | 30.092 | 0.001 | 50.927 | 0.012 | -0.012 | |
| 9/22/95 | 12:10 PM | 10.762 | 40.095 | -0.043 | 15.780 | 35.077 | 0.058 | 20.825 | 30.032 | 0.061 | 50.857 | 0.058 | 0.058 | |
| 10/12/95 | 2:35 PM | 10.767 | 40.100 | -0.048 | 15.783 | 35.084 | 0.051 | 20.833 | 30.034 | 0.059 | 50.867 | 0.048 | 0.048 | |
| 11/3/95 | 1:20 PM | 10.755 | 40.160 | -0.108 | 15.770 | 35.145 | -0.010 | 20.820 | 30.095 | -0.002 | 50.915 | 0.000 | 0.000 | |
| 11/22/95 | 12:00 PM | 10.753 | 40.097 | -0.045 | 15.775 | 35.075 | 0.060 | 20.823 | 30.027 | 0.066 | 50.850 | 0.065 | 0.065 | |
| 12/20/95 | 12:00 PM | 10.750 | 40.160 | -0.108 | 15.770 | 35.140 | -0.005 | 20.817 | 30.093 | 0.000 | 50.910 | 0.005 | 0.005 | |
| 1/11/96 | 2:00 PM | 10.747 | 40.166 | -0.114 | 15.767 | 35.146 | -0.011 | 20.817 | 30.096 | -0.003 | 50.913 | 0.002 | 0.002 | |
| 2/8/96 | 4:00 PM | 10.747 | 40.106 | -0.054 | 15.763 | 35.090 | 0.045 | 20.813 | 30.040 | 0.053 | 50.853 | 0.062 | 0.062 | |
| 2/29/96 | 4:00 PM | 10.749 | 40.164 | -0.112 | 15.764 | 35.149 | -0.014 | 20.813 | 30.100 | -0.007 | 50.913 | 0.002 | 0.002 | |
| 3/28/96 | 2:15 PM | 10.750 | 40.160 | -0.108 | 15.765 | 35.145 | -0.010 | 20.815 | 30.095 | -0.002 | 50.910 | 0.005 | 0.005 | (-0.04) for diff. b/w cutoff length and ext. |
| 4/23/96 | 12:00 PM | 10.750 | 40.100 | -0.048 | 15.767 | 35.083 | 0.052 | 20.815 | 30.035 | 0.058 | 50.850 | 0.065 | 0.065 | |
| 5/21/96 | 9:30 AM | 10.825 | 40.100 | -0.048 | 15.840 | 35.085 | 0.050 | 20.890 | 30.035 | 0.058 | 50.925 | 0.030 | -0.030 | New reference (top) using ext. |
| 6/11/96 | 11:30 AM | 10.800 | 39.988 | 0.064 | 15.798 | 34.990 | 0.145 | 20.851 | 29.937 | 0.156 | 50.788 | 0.167 | 0.167 | Highway opened to traffic |
| 8/6/96 | AM | 10.803 | 40.14 | -0.085 | 15.803 | 35.137 | -0.002 | 20.850 | 30.090 | 0.003 | 50.940 | 0.015 | 0.015 | |
| 10/31/96 | 10:15 AM | 10.798 | 40.142 | -0.090 | 15.795 | 35.145 | -0.010 | 20.848 | 30.092 | 0.001 | 50.940 | 0.015 | 0.015 | |
| 12/16/96 | 9:50 AM | 10.790 | 40.150 | -0.098 | 15.793 | 35.147 | -0.012 | 20.843 | 30.097 | -0.004 | 50.940 | 0.015 | 0.015 | |
| 2/27/97 | 9:50 AM | 10.790 | 40.090 | -0.038 | 15.795 | 35.085 | 0.050 | 20.845 | 30.035 | 0.058 | 50.880 | 0.075 | 0.075 | |

ODOT US177 Approach Embankment Evaluation

Bridge B, North Abutment Wall (Controlled Low Strength Backfill)

Inclinometer Telescoping Couplings - Offset: Installed 5/24/95

Casing Elevation 923.84' → 922.56'
(top=2.0' above GS) As Built After Paving

GS Elevation 921.84' Pavement Elevation 923.19'

Reference Coupling 49.05' → 872.79' Bottom of Casing 51.17'
Depth Elevation

| Readings, Changes, & ΔH Values | | | | | | | | | | | | | | |
|--------------------------------|----------|-------------------|---------------|----------|-------------------|---------------|----------|-------------------|---------------|----------|-------------------|-----------|----------|---|
| Date | Time | Level 1 (Top) | | | Level 2 | | | Level 3 | | | Level 4 (Bottom) | | | Remarks |
| | | Reading R1, ft | R4 - R1 ft | ΔH ft | Reading R2, ft | R4 - R2 ft | ΔH ft | Reading R3, ft | R4 - R3 ft | ΔH ft | Reading R4, ft | ΔR4 ft | ΔH ft | |
| 6/1/95 | PM | 10.593 | 40.458 | - | 15.624 | 35.427 | - | 20.478 | 30.573 | - | 51.051 | - | - | Omit this Data set Reference Reading (Datum) |
| 6/16/95 | AM | 10.488 | 40.521 | 0.000 | 15.530 | 35.479 | 0.000 | 20.488 | 30.521 | 0.000 | 51.009 | 0.000 | 0.000 | |
| 6/28/95 | PM | 10.490 | 40.520 | 0.001 | 15.525 | 35.485 | -0.006 | 20.480 | 30.530 | -0.009 | 51.010 | 0.001 | -0.001 | |
| 7/7/95 | 12:35 PM | 10.490 | 40.510 | 0.011 | 15.525 | 35.475 | 0.004 | 20.480 | 30.520 | 0.001 | 51.000 | 0.009 | 0.009 | |
| 7/14/95 | 1:25 PM | 10.495 | 40.565 | -0.044 | 15.525 | 35.535 | -0.056 | 20.490 | 30.570 | -0.049 | 51.060 | 0.051 | -0.051 | |
| 7/26/95 | 10:00 AM | 10.490 | 40.565 | -0.044 | 15.630 | 35.425 | 0.054 | 20.480 | 30.575 | -0.054 | 51.055 | 0.046 | -0.046 | |
| 8/9/95 | 9:15 AM | 10.490 | 40.520 | 0.001 | 15.527 | 35.483 | -0.004 | 20.490 | 30.520 | 0.001 | 51.010 | 0.001 | -0.001 | |
| 9/1/95 | 9:10 AM | 10.490 | 40.520 | 0.001 | 15.530 | 35.480 | -0.001 | 20.485 | 30.525 | -0.004 | 51.010 | 0.001 | -0.001 | |
| 9/22/95 | 12:10 PM | 10.485 | 40.515 | 0.006 | 15.520 | 35.480 | -0.001 | 20.480 | 30.520 | 0.001 | 51.000 | 0.009 | 0.009 | |
| 10/12/95 | 2:35 PM | 10.487 | 40.568 | -0.047 | 15.523 | 35.532 | -0.053 | 20.485 | 30.570 | -0.049 | 51.055 | 0.046 | -0.046 | |
| 11/3/95 | 1:20 PM | 10.480 | 40.570 | -0.049 | 15.517 | 35.533 | -0.054 | 20.475 | 30.575 | -0.054 | 51.050 | 0.041 | -0.041 | |
| 11/22/95 | 12:00 PM | 10.480 | 40.520 | 0.001 | 15.513 | 35.487 | -0.008 | 20.487 | 30.513 | 0.008 | 51.000 | 0.009 | 0.009 | |
| 12/20/95 | 12:00 PM | 10.475 | 40.570 | -0.049 | 15.505 | 35.540 | -0.061 | 20.467 | 30.578 | -0.057 | 51.045 | 0.036 | -0.036 | |
| 1/11/96 | 2:00 PM | 10.470 | 40.527 | -0.006 | 15.610 | 35.387 | 0.092 | 20.465 | 30.532 | -0.011 | 50.997 | 0.012 | 0.012 | |
| 2/8/96 | 4:00 PM | 10.487 | 40.570 | -0.049 | 15.520 | 35.537 | -0.058 | 20.480 | 30.577 | -0.056 | 51.057 | 0.048 | -0.048 | |
| 2/29/96 | 4:00 PM | 10.483 | 40.516 | 0.005 | 15.505 | 35.494 | -0.015 | 20.465 | 30.534 | -0.013 | 50.999 | 0.010 | 0.010 | |
| 3/28/96 | 2:15 PM | 10.473 | 40.517 | 0.004 | 15.510 | 35.480 | -0.001 | 20.469 | 30.521 | 0.000 | 50.990 | 0.019 | 0.019 | |
| 4/23/96 | 12:00 PM | 10.475 | 40.515 | 0.006 | 15.507 | 35.483 | -0.004 | 20.573 | 30.417 | 0.104 | 50.990 | 0.019 | 0.019 | |
| 5/21/96 | 9:30 AM | 10.525 | 40.315 | 0.206 | 15.380 | 35.460 | 0.019 | 20.355 | 30.485 | 0.036 | 50.840 | 0.219 | 0.219 | |
| 6/11/96 | 11:30 AM | 10.531 | 40.237 | 0.284 | 15.490 | 35.278 | 0.201 | 20.196 | 30.572 | -0.051 | 50.768 | 0.291 | 0.291 | |
| 8/6/96 | AM | 10.533 | 40.24 | 0.284 | 15.393 | 35.377 | 0.102 | 20.205 | 30.565 | -0.044 | 50.770 | 0.289 | 0.289 | |
| 10/31/96 | 10:15 AM | 10.637 | 40.105 | 0.416 | 15.491 | 35.251 | 0.228 | 20.306 | 30.436 | 0.085 | 50.742 | 0.317 | 0.317 | |
| 12/16/96 | 9:50 AM | 10.520 | 40.247 | 0.274 | 15.380 | 35.387 | 0.092 | 20.195 | 30.572 | -0.051 | 50.767 | 0.292 | 0.292 | |
| 2/27/97 | 9:50 AM | 10.525 | 40.250 | 0.271 | 15.385 | 35.390 | 0.089 | 20.195 | 30.580 | -0.059 | 50.775 | 0.284 | 0.284 | |

ODOT US177 Approach Embankment Evaluation

Bridge B, North Abutment Wall (Controlled Low Strength Backfill)

Piezometer:

Standpipe Elevation 924.55' → 922.88'
 *As Built ► (Top=2.72 ft above GS) (As Built) (After Paving)

GS Elevation 921.83' Pavement Elevation 923.19'
 (Top of Subgrade) (Top of Pavement)

Tip Elevation 875.83' Tip Depth 46.0'

Groundwater Depth = Piezometer Reading - 0.31'
 (Below Top of Pavement)

Groundwater Elevation = Standpipe Elevation (922.88') - Piezometer Reading

| Date | Time | Piezometer Data | | | Remarks |
|----------|----------|-----------------|-------------------|-------------------|--|
| | | Reading ft | GW Depth ft | GW Elev. ft | |
| 5/24/95 | PM | - | - | - | Installed piezometer |
| 6/1/95 | PM | 29.13 | 26.41 | 895.42 | Initial reading by OSU |
| 6/2/95 | PM | 29.00 | 26.28 | 895.55 | |
| 6/16/95 | AM | 26.15 | 23.43 | 898.40 | |
| 6/28/95 | AM | 25.62 | 22.90 | 898.93 | |
| 7/7/95 | 12:35 PM | 25.48 | 22.76 | 899.07 | |
| 7/14/95 | 1:25 PM | 25.50 | 22.78 | 899.05 | |
| 7/26/95 | 10:00 AM | 26.00 | 23.28 | 898.55 | |
| 8/9/95 | 9:15 AM | 23.40 | 20.68 | 901.15 | |
| 9/1/95 | 9:10 AM | 23.96 | 21.24 | 900.59 | |
| 9/22/95 | 12:10 PM | 26.20 | 23.48 | 898.35 | |
| 10/12/95 | 2:35 PM | 26.93 | 24.21 | 897.62 | |
| 11/3/95 | 1:20 PM | 27.63 | 24.91 | 896.92 | |
| 11/22/95 | 12:00 PM | 28.12 | 25.40 | 896.43 | |
| 12/20/95 | 12:00 PM | 28.69 | 25.97 | 895.86 | |
| 1/11/96 | 2:00 PM | 29.01 | 26.29 | 895.54 | |
| 2/8/96 | 4:00 PM | 29.40 | 26.68 | 895.15 | |
| 2/29/96 | 4:00 PM | 29.61 | 26.89 | 894.94 | |
| 3/28/96 | 2:15 PM | 29.88 | 27.16 | 894.67 | |
| 4/23/96 | 12:00 PM | 30.12 | 27.40 | 894.43 | |
| 5/21/96 | 9:30 AM | 28.66 | 28.35 | 894.22 | Use new standpipe elev., changed reference for depth |
| 6/11/96 | 11:30 AM | 28.63 | 28.32 | 894.25 | Highway opened to traffic |
| 8/6/96 | AM | 28.76 | 28.45 | 894.12 | |
| 10/31/96 | 10:15 AM | 28.33 | 28.02 | 894.55 | |
| 12/16/96 | 9:50 AM | 27.77 | 27.46 | 895.11 | |
| 2/27/97 | 9:50 AM | 28.00 | 27.69 | 894.88 | |

ODOT US177 Approach Embankment Evaluation

Bridge B, North Abutment Wall (Controlled Low Strength Backfill), Surface Settlement Points

| Date | 6/12/96 | | | 8/6/96 | | | 10/31/96 | | | 2/28/97 | | |
|------|---------|---------------|--------|---------|---------------|--|----------|----------------------|--|---------|---------------|------------|
| | Reading | Elevation | | Reading | Elevation | | Reading | Elevation | | Reading | Elevation | |
| BM | | W 925.26 E | | | W 925.26 E | | | W 925.26 E 925.26 | | | W 925.26 E | |
| BS | 0.75 | - | | 2.734 | - | | 3.238 | - | | 3.114 | - | |
| HI | 926.01 | - | | 927.994 | - | | 928.498 | - | | 928.374 | - | |
| FS | 1 | 3.05 | 922.96 | 5.033 | 922.961 | | 5.554 | 922.944 | | 5.428 | 922.946 | |
| | 2 | 2.97 | 923.04 | 4.982 | 923.012 | | 5.487 | 923.011 | | 5.364 | 923.01 | |
| | 3 | 2.89 | 923.12 | 4.888 | 923.106 | | 5.397 | 923.101 | | 5.273 | 923.101 | |
| | 4 | 2.82 | 923.19 | 4.814 | 923.180 | | 5.322 | 923.176 | | 5.220 | 923.154 | *2/27/1997 |
| | 5 | 3.12 | 922.89 | 5.089 | 922.905 | | 5.606 | 922.892 | | 5.483 | 922.891 | |
| | 6 | 3.03 | 922.98 | 5.045 | 922.949 | | 5.554 | 922.944 | | 5.430 | 922.944 | |
| | 7 | 2.94 | 923.07 | 4.933 | 923.061 | | 5.444 | 923.054 | | 5.322 | 923.052 | |
| | 8 | 2.88 | 923.13 | 4.882 | 923.112 | | 5.390 | 923.108 | | 5.267 | 923.107 | |
| | 9 | 3.14 | 922.87 | 5.126 | 922.868 | | 5.642 | 922.856 | | 5.518 | 922.856 | |
| | 10 | 3.05 | 922.96 | 5.062 | 922.932 | | 5.569 | 922.929 | | 5.446 | 922.928 | |
| | 11 | 2.96 | 923.05 | 4.963 | 923.031 | | 5.472 | 923.026 | | 5.349 | 923.025 | |
| | 12 | 2.89 | 923.12 | 4.895 | 923.099 | | 5.400 | 923.098 | | 5.293 | 923.081 | *2/27/1997 |
| | 13 | 3.14 | 922.87 | 5.132 | 922.862 | | 5.643 | 922.855 | | 5.520 | 922.854 | |
| | 14 | 3.06 | 922.95 | 5.074 | 922.920 | | 5.585 | 922.913 | | 5.465 | 922.909 | |
| | 15 | 2.98 | 923.03 | 4.977 | 923.017 | | 5.485 | 923.013 | | 5.363 | 923.011 | |
| | 16 | 2.90 | 923.11 | 4.892 | 923.102 | | 5.398 | 923.100 | | 5.277 | 923.097 | |

*Settlement Reading Point is missing.

APPENDIX B5

C1 Instrumentation Data

ODOT US177 Approach Embankment Evaluation

Bridge C, South Abutment Wall (Dynamic Compaction of Granular Backfill)

Total Pressure Cells:

| | Tubing Length | Date Installed | Test Pressures | | |
|-------------------|---------------|----------------|----------------|--------|---------|
| | | | 5 psi | 50 psi | 100 psi |
| Top - SN 44199 | 34' | 5/1/95 | 4.62 | 49.64 | 99.55 |
| Middle - SN 44206 | 37' | 5/1/95 | 5.00 | 50.00 | 100.10 |
| Bottom - SN 44209 | 40' | 5/1/95 | 4.90 | 49.90 | 100.04 |

| Date | Time | TPC Readings (psi) | | | | | | Remarks |
|----------|----------|--------------------|--------------|---------------|-----------------|---------------|-----------------|--|
| | | Top w/flow | Top w/o flow | Middle w/flow | Middle w/o flow | Bottom w/flow | Bottom w/o flow | |
| 5/5/95 | | 0.0 | 0.0 | 0.1 | 0.0 | 0.1 | 0.0 | Initial Readings by WCC, no backfill |
| 5/15/95 | AM | 0.0 | 0.0 | 0.0 | 0.0 | 0.5 | 0.4 | After placing 1st lift, before dyn. compaction |
| 5/15/95 | 1:00 PM | 0.0 | 0.0 | 0.0 | 0.0 | 0.8 | - | After 1st lift compaction (2 ft) |
| 5/15/95 | 3:00 PM | 0.0 | 0.0 | 0.8 | 0.7 | 1.4 | 1.3 | After 2nd lift compaction (4 ft) |
| 5/17/95 | 11:40 AM | 0.0 | 0.0 | 1.6 | 1.4 | 1.9 | 1.8 | After 3rd lift compaction (6 ft) |
| 5/17/95 | PM | 0.5 | 0.4 | 2.6 | 2.5 | 2.6 | 2.5 | After 4th lift compaction (8 ft) |
| 5/19/95 | AM | 0.9 | 0.8 | 2.7 | 2.6 | 2.7 | 2.6 | |
| 5/31/95 | AM | 0.2 | 0.1 | 1.7 | 1.6 | 2.7 | 2.6 | |
| 6/16/95 | AM | 0.3 | 0.1 | 1.9 | 1.8 | 2.5 | 2.4 | |
| 6/28/95 | AM | 0.1 | 0.0 | 2.0 | 1.9 | 2.7 | 2.6 | |
| 7/7/95 | 2:20 PM | 0.4 | 0.2 | 1.6 | 1.5 | 2.7 | 2.6 | |
| 7/14/95 | 2:15 PM | 0.4 | 0.3 | 2.2 | 2.1 | 2.9 | 2.8 | |
| 7/26/95 | 9:25 PM | 0.1 | 0.0 | 2.7 | 2.6 | 3.2 | 3.1 | |
| 8/9/95 | 10:00 AM | 0.1 | 0.0 | 2.0 | 1.9 | 2.8 | 2.7 | |
| 9/1/95 | 9:55 AM | 0.1 | 0.0 | 2.8 | 2.7 | 3.0 | 3.0 | |
| 9/22/95 | 1:40 PM | 0.1 | 0.0 | 1.9 | 1.8 | 3.0 | 2.9 | T = 15 degrees C |
| 10/12/95 | 3:05 PM | 0.4 | 0.3 | 0.8 | 0.7 | 2.2 | 2.1 | |
| 11/3/95 | 2:05 PM | 0.1 | 0.0 | 1.5 | 1.3 | 2.8 | 2.7 | |
| 11/22/95 | 2:00 PM | 0.1 | 0.0 | 0.6 | 0.5 | 2.2 | 2.1 | |
| 12/20/95 | 1:30 PM | 0.1 | 0.0 | 1.0 | 0.8 | 2.5 | 2.4 | |
| 1/11/96 | 3:00 PM | 0.1 | 0.0 | 0.3 | 0.2 | 2.0 | 1.9 | |
| 2/8/96 | 5:00 PM | 0.1 | 0.0 | 0.3 | 0.1 | 1.2 | 1.1 | |
| 2/29/96 | 4:00 PM | 0.2 | 0.1 | 1.7 | 1.6 | 1.5 | 1.4 | |
| 3/28/96 | 3:00 PM | 0.0 | 0.0 | 1.3 | 1.2 | 1.4 | 1.4 | |
| 4/23/96 | 1:15 PM | 0.1 | 0.0 | 1.5 | 1.4 | 1.6 | 1.5 | |
| 5/21/96 | 10:00 AM | 0.1 | 0.0 | 1.9 | 1.8 | 2.2 | 2.1 | |
| 6/11/96 | 10:30 AM | 0.1 | 0.0 | 1.4 | 1.3 | 2.4 | 2.3 | Highway Opened to Traffic |
| 8/6/96 | 9:30 AM | 0.0 | 0.0 | 1.5 | 1.4 | 2.7 | 2.6 | |
| 10/31/96 | 8:30 AM | 0.2 | 0.1 | 2.2 | 2.1 | 3.2 | 3.1 | |
| 12/16/96 | 9:00 AM | 0.1 | 0.0 | 2.0 | 1.8 | 3.0 | 2.9 | |
| 2/27/97 | 9:05 AM | 0.2 | 0.1 | 1.8 | 1.6 | 2.4 | 2.3 | |

ODOT US177 Approach Embankment Evaluation

Bridge C, South Abutment Wall (Dynamic Compaction of Granular Backfill)

Amplified Liquid Settlement Gages:

As Built Elevation

| | Tubing Length Installed | Date | Top of Plate | Top of Fluid |
|-----------------------|-------------------------|--------|-----------------------|--------------|
| Centerline - SN 44214 | 40' | 5/1/95 | 909.91' | 920.85' |
| | | | Initial Head = 10.94' | |
| Offset - SN 44218 | 30' | 5/1/95 | 909.88' | 920.86' |
| 10' wide | | | Initial Head = 10.98' | |

Calibration for: Centerline

Offset

| | | | |
|----------|------------------------|----------|-----------------------|
| Head(ft) | Reading - (-3.855 psi) | Head(ft) | Reading - (-3.30 psi) |
| | 8.505 psi / ft | | 8.18 psi / ft |

| ALSG Readings, Heads, & ΔH | | | | | | | | Remarks |
|----------------------------|----------|----------------|------------|----------|----------------|------------|----------|--|
| Date | Time | CL | | | OFS | | | |
| | | Reading psi | Head ft | ΔH ft | Reading psi | Head ft | ΔH ft | |
| 5/5/95 | | 90.2 | 11.059 | - | 86.6 | 10.990 | - | Initial Readings by WCC, no backfill |
| 5/15/95 | AM | 90.2 | 11.059 | 0.000 | 86.5 | 10.978 | -0.012 | After placing 1st lift, before dyn. compaction |
| 5/15/95 | 1:00 PM | 89.8 | 11.012 | -0.047 | 86.5 | 10.978 | -0.012 | After 1st lift compaction (2 ft) |
| 5/15/95 | 3:00 PM | 90.9 | 11.141 | 0.082 | 86.9 | 11.027 | 0.037 | After 2nd lift compaction (4 ft) |
| 5/17/95 | 11:40 AM | 91.3 | 11.188 | 0.129 | 86.8 | 11.015 | 0.025 | After 3rd lift compaction (6 ft) |
| 5/17/95 | PM | 91.3 | 11.188 | 0.129 | 86.8 | 11.015 | 0.025 | After 4th lift compaction (8 ft) |
| 5/19/95 | AM | 91.0 | 11.153 | 0.094 | 86.7 | 11.002 | 0.012 | |
| 5/31/95 | AM | 92.0 | 11.270 | 0.211 | 87.4 | 11.088 | 0.098 | Prob w/cCL SG, won't hold pressure at 0.1, |
| 6/16/95 | AM | 91.1 | 11.165 | 0.106 | 87.4 | 11.088 | 0.098 | used 0.2 reading |
| 6/28/95 | AM | 91.2 | 11.176 | 0.117 | 87.6 | 11.112 | 0.122 | Used interpolation to get CL reading at 0.1 |
| 7/7/95 | 2:20 PM | 91.0 | 11.153 | 0.094 | 87.5 | 11.100 | 0.110 | Used interpolation to get CL reading at 0.1 |
| 7/14/95 | 2:15 PM | 91.0 | 11.153 | 0.094 | 87.3 | 11.076 | 0.186 | Used interpolation to get CL reading at 0.1 |
| 7/26/95 | 9:25 PM | 91.0 | 11.153 | 0.094 | 87.4 | 11.088 | 0.098 | Problem with CL SG has stopped |
| 8/9/95 | 10:00 AM | 91.2 | 11.176 | 0.117 | 87.5 | 11.100 | 0.110 | |
| 9/1/95 | 9:55 AM | 91.0 | 11.153 | 0.094 | 87.6 | 11.112 | 0.122 | |
| 9/22/95 | 1:40 PM | 91.3 | 11.188 | 0.129 | 87.8 | 11.137 | 0.147 | |
| 10/12/95 | 3:05 PM | 91.7 | 11.235 | 0.176 | 88.0 | 11.161 | 0.171 | |
| 11/3/95 | 2:05 PM | 91.8 | 11.247 | 0.188 | 87.9 | 11.149 | 0.159 | |
| 11/22/95 | 2:00 PM | 92.2 | 11.294 | 0.235 | 88.3 | 11.198 | 0.208 | |
| 12/20/95 | 1:30 PM | 92.3 | 11.306 | 0.247 | 88.6 | 11.235 | 0.245 | |
| 1/11/96 | 3:00 PM | 92.7 | 11.353 | 0.294 | 88.9 | 11.271 | 0.281 | |
| 2/8/96 | 5:00 PM | 92.7 | 11.353 | 0.294 | 88.9 | 11.271 | 0.281 | |
| 2/29/96 | 4:00 PM | 92.8 | 11.364 | 0.305 | 88.9 | 11.271 | 0.281 | |
| 3/28/96 | 3:00 PM | 92.5 | 11.329 | 0.270 | 88.6 | 11.234 | 0.244 | |
| 4/23/96 | 1:15 PM | 93.3 | 11.423 | 0.364 | 88.9 | 11.271 | 0.281 | CL SG - high volume of air bubbles in line |
| 5/21/96 | 10:00 AM | 76.5 | - | - | 88.4 | 11.210 | 0.220 | CL ALSG has stopped functioning properly. |
| 6/11/96 | 10:30 AM | 70.7 | - | - | 88.7 | 11.247 | 0.257 | Gage will be read but no data reduction carried out. |
| 8/6/96 | 9:30 AM | 62.4 | - | - | 88.0 | 11.161 | 0.171 | |
| 10/31/96 | 8:30 AM | 54.9 | - | - | 88.2 | 11.186 | 0.196 | |
| 12/16/96 | 9:00 AM | 63.3 | - | - | 89.1 | 11.296 | 0.306 | |
| 2/27/97 | 9:05 AM | 56.5 | - | - | 89.4 | 11.333 | 0.343 | |

ODOT US177 Approach Embankment Evaluation

Bridge C, South Abutment Wall (Dynamic Compaction of Granular Backfill)

Inclinometer Telescoping Couplings - Centerline: Installed 5/25/95

Casing Elevation 922.49' → 921.21'
(top=2.04' above GS) As Built After Paving

GS Elevation 920.45' Pavement Elevation 921.65'

Reference Coupling 54.99' → 865.46' Bottom of Casing 57.11'
Depth Elevation

| Readings, Changes, & ΔH Values | | | | | | | | | | | | | | |
|--------------------------------|----------|-----------------|--------|----------|-----------------|--------|----------|-----------------|--------|----------|-------------------|-----------|----------|--------------------------------|
| Date | Time | Level 1 (Top) | | | Level 2 | | | Level 3 | | | Level 4 (Bottom) | | | Remarks |
| | | Reading R4 - R1 | | ΔH ft | Reading R4 - R2 | | ΔH ft | Reading R4 - R3 | | ΔH ft | Reading R4, ft | ΔR4 ft | ΔH ft | |
| | | R1, ft | ft | | R2, ft | ft | | R3, ft | ft | | | | | |
| 6/2/95 | AM | 10.874 | 46.156 | - | 16.061 | 40.969 | - | 20.863 | 36.167 | - | 57.030 | - | - | Omit this data set |
| 6/16/95 | PM | 10.884 | 46.104 | - | 15.968 | 41.020 | - | 20.863 | 36.125 | - | 56.988 | - | - | Omit this data set |
| 6/28/95 | AM | 10.885 | 46.150 | 0.000 | 15.960 | 41.075 | 0.000 | 20.860 | 36.175 | 0.000 | 57.035 | 0.000 | 0.000 | Reference Reading(Datum) |
| 7/7/95 | 2:20 PM | 10.885 | 46.155 | -0.005 | 15.970 | 41.070 | 0.005 | 20.860 | 36.180 | -0.005 | 57.040 | 0.005 | -0.005 | |
| 7/14/95 | 2:15 PM | 10.890 | 46.150 | 0.000 | 15.970 | 41.070 | 0.005 | 20.865 | 36.175 | 0.000 | 57.040 | 0.005 | -0.005 | |
| 7/26/95 | 9:25 PM | 10.890 | 46.150 | 0.000 | 15.967 | 41.073 | 0.002 | 20.865 | 36.175 | 0.000 | 57.040 | 0.005 | -0.005 | |
| 8/9/95 | 10:00 AM | 10.890 | 46.105 | 0.045 | 15.970 | 41.025 | 0.050 | 20.867 | 36.128 | 0.047 | 56.995 | 0.040 | 0.040 | |
| 9/1/95 | 9:55 AM | 10.887 | 46.158 | -0.008 | 15.970 | 41.075 | 0.000 | 20.867 | 36.178 | -0.003 | 57.045 | 0.010 | -0.010 | |
| 9/22/95 | 1:40 PM | 10.880 | 46.105 | 0.045 | 15.960 | 41.025 | 0.050 | 20.855 | 36.130 | 0.045 | 56.985 | 0.050 | 0.050 | |
| 10/12/95 | 3:05 PM | 10.880 | 46.157 | -0.007 | 15.960 | 41.077 | 0.002 | 20.857 | 36.180 | -0.005 | 57.037 | 0.002 | -0.002 | |
| 11/3/95 | 2:05 PM | 10.980 | 46.050 | 0.100 | 15.953 | 41.077 | 0.002 | 20.850 | 36.180 | -0.005 | 57.030 | 0.005 | 0.005 | |
| 11/22/95 | 1:00 PM | 10.875 | 46.108 | 0.042 | 15.955 | 41.028 | 0.047 | 20.850 | 36.133 | 0.042 | 56.983 | 0.052 | 0.052 | |
| 12/20/95 | 1:30 PM | 10.870 | 46.155 | -0.005 | 15.947 | 41.078 | -0.003 | 20.845 | 36.180 | -0.005 | 57.025 | 0.010 | 0.010 | |
| 1/11/96 | 3:00 PM | 10.867 | 46.108 | 0.042 | 15.943 | 41.032 | 0.043 | 20.843 | 36.132 | 0.043 | 56.975 | 0.060 | 0.060 | |
| 2/8/96 | 5:00 PM | 10.870 | 46.105 | 0.045 | 15.943 | 41.032 | 0.043 | 20.840 | 36.135 | 0.040 | 56.975 | 0.060 | 0.060 | |
| 2/29/96 | 4:00 PM | 10.871 | 46.102 | 0.048 | 15.945 | 41.028 | 0.047 | 20.843 | 36.130 | 0.045 | 56.973 | 0.062 | 0.062 | |
| 3/28/96 | 3:00 PM | 10.870 | 46.109 | 0.041 | 15.945 | 41.034 | 0.041 | 20.843 | 36.136 | 0.039 | 56.979 | 0.056 | 0.056 | (+0.16) for diff. b/w cutoff |
| 4/23/96 | 1:15 PM | 10.875 | 46.105 | 0.045 | 15.943 | 41.037 | 0.038 | 20.847 | 36.133 | 0.042 | 56.980 | 0.055 | 0.055 | length and ext. |
| 5/21/96 | 10:00 AM | 10.720 | 46.093 | 0.057 | 15.787 | 41.026 | 0.049 | 20.685 | 36.128 | 0.047 | 56.813 | 0.062 | 0.062 | New reference (top) using ext. |
| 6/11/96 | 10:30 AM | 10.722 | 46.061 | 0.089 | 15.728 | 41.055 | 0.020 | 20.612 | 36.171 | 0.004 | 56.783 | 0.092 | 0.092 | Highway opened to traffic |
| 8/6/96 | 9:30 AM | 10.728 | 46.012 | 0.138 | 15.725 | 41.015 | 0.060 | 20.618 | 36.122 | 0.053 | 56.740 | 0.135 | 0.135 | |
| 10/31/96 | 8:30 AM | 10.715 | 46.020 | 0.130 | 15.717 | 41.018 | 0.057 | 20.613 | 36.122 | 0.053 | 56.735 | 0.140 | 0.140 | |
| 12/16/96 | 9:00 AM | 10.740 | 46.070 | 0.080 | 15.740 | 41.070 | 0.005 | 20.637 | 36.173 | 0.002 | 56.810 | 0.065 | 0.065 | |
| 2/27/97 | 9:05 AM | 10.715 | 46.067 | 0.083 | 15.710 | 41.072 | 0.003 | 20.605 | 36.177 | -0.002 | 56.782 | 0.093 | 0.093 | |

ODOT US177 Approach Embankment Evaluation

Bridge C, South Abutment Wall (Dynamic Compaction of Granular Backfill)

Inclinometer Telescoping Couplings - Offset: Installed 5/30/95

Casing Elevation 922.61' → 921.37'
(top=2.05' above GS) As Built After Paving

GS Elevation 920.56' Pavement Elevation 921.65'

Reference Coupling 56.11' → 864.45' Bottom of Casing 58.17'
Depth Elevation

| Date | Time | Readings, Changes, & ΔH Values | | | | | | | | | | | | Remarks |
|----------|----------|--------------------------------|------------|-------|----------------|------------|-------|----------------|------------|-------|------------------|--------|-------|---|
| | | Level 1 (Top) | | | Level 2 | | | Level 3 | | | Level 4 (Bottom) | | | |
| | | Reading R1, ft | R4 - R1 ft | ΔH ft | Reading R2, ft | R4 - R2 ft | ΔH ft | Reading R3, ft | R4 - R3 ft | ΔH ft | Reading R4, ft | ΔR4 ft | ΔH ft | |
| 6/2/95 | AM | 10.874 | 47.281 | - | 15.874 | 42.281 | - | 20.988 | 37.167 | - | 58.155 | - | - | Omit this Data set Reference Reading (Datum) |
| 6/16/95 | PM | 10.884 | 47.240 | 0.000 | 15.884 | 42.240 | 0.000 | 20.894 | 37.230 | 0.000 | 58.124 | 0.000 | 0.000 | |
| 6/28/95 | AM | 10.885 | 47.230 | 0.010 | 15.875 | 42.240 | 0.000 | 20.890 | 37.225 | 0.005 | 58.115 | 0.009 | 0.009 | |
| 7/7/95 | 2:20 PM | 10.890 | 47.230 | 0.010 | 15.880 | 42.240 | 0.000 | 20.895 | 37.225 | 0.005 | 58.120 | 0.004 | 0.004 | |
| 7/14/95 | 2:15 PM | 10.890 | 47.225 | 0.015 | 15.885 | 42.230 | 0.010 | 20.895 | 37.220 | 0.010 | 58.115 | 0.009 | 0.009 | |
| 7/26/95 | 9:25 AM | 10.890 | 47.230 | 0.010 | 15.885 | 42.234 | 0.006 | 20.897 | 37.223 | 0.007 | 58.120 | 0.004 | 0.004 | |
| 8/9/95 | 10:00 AM | 10.890 | 47.165 | 0.075 | 15.885 | 42.170 | 0.070 | 20.895 | 37.160 | 0.070 | 58.055 | 0.069 | 0.069 | |
| 9/1/95 | 9:55 AM | 10.895 | 47.225 | 0.015 | 15.885 | 42.235 | 0.005 | 20.900 | 37.220 | 0.010 | 58.120 | 0.004 | 0.004 | |
| 9/22/95 | 1:40 PM | 10.885 | 47.160 | 0.080 | 15.880 | 42.165 | 0.075 | 20.890 | 37.155 | 0.075 | 58.045 | 0.079 | 0.079 | |
| 10/12/95 | 3:05 PM | 10.885 | 47.202 | 0.038 | 15.857 | 42.230 | 0.010 | 20.870 | 37.217 | 0.013 | 58.087 | 0.037 | 0.037 | |
| 11/3/95 | 2:05 PM | 10.880 | 47.140 | 0.100 | 15.850 | 42.170 | 0.070 | 20.863 | 37.157 | 0.073 | 58.020 | 0.194 | 0.194 | |
| 11/22/95 | 2:30 PM | 10.880 | 47.140 | 0.100 | 15.953 | 42.067 | 0.173 | 20.865 | 37.155 | 0.075 | 58.020 | 0.104 | 0.104 | |
| 12/20/95 | 1:30 PM | 10.875 | 47.135 | 0.105 | 15.840 | 42.170 | 0.070 | 20.855 | 37.155 | 0.075 | 58.010 | 0.114 | 0.114 | |
| 1/11/96 | 3:00 PM | 10.870 | 47.145 | 0.095 | 15.843 | 42.172 | 0.068 | 20.855 | 37.160 | 0.070 | 58.015 | 0.109 | 0.109 | |
| 2/8/96 | 5:00 PM | 10.873 | 47.200 | 0.040 | 15.845 | 42.228 | 0.012 | 20.855 | 37.218 | 0.012 | 58.073 | 0.051 | 0.051 | |
| 2/29/96 | 4:00 PM | 10.975 | 47.103 | 0.137 | 15.842 | 42.236 | 0.004 | 20.859 | 37.219 | 0.011 | 58.078 | 0.046 | 0.046 | |
| 3/28/96 | 3:00 PM | 10.877 | 47.200 | 0.040 | 15.849 | 42.228 | 0.012 | 20.860 | 37.217 | 0.013 | 58.077 | 0.047 | 0.047 | (-0.02) for diff. b/w cutoff |
| 4/23/96 | 1:15 PM | 10.880 | 47.195 | 0.045 | 15.847 | 42.228 | 0.012 | 20.860 | 37.215 | 0.015 | 58.075 | 0.049 | 0.049 | length and ext. |
| 5/21/96 | 10:00 AM | 10.885 | 46.952 | 0.288 | 15.675 | 42.162 | 0.078 | 20.683 | 37.154 | 0.076 | 57.837 | 0.307 | 0.307 | New reference (top) using ext. |
| 6/11/96 | 10:30 AM | 10.891 | 47.007 | 0.233 | 15.675 | 42.223 | 0.017 | 20.690 | 37.208 | 0.022 | 57.898 | 0.246 | 0.246 | Highway opened to traffic |
| 8/6/96 | 9:30 AM | 10.897 | 47.003 | 0.237 | 15.682 | 42.218 | 0.022 | 20.797 | 37.103 | 0.127 | 57.900 | 0.244 | 0.244 | |
| 10/31/96 | 8:30 AM | 10.888 | 46.945 | 0.295 | 15.673 | 42.160 | 0.080 | 20.688 | 37.145 | 0.085 | 57.833 | 0.311 | 0.311 | |
| 12/16/96 | 9:00 AM | 10.885 | 46.945 | 0.295 | 15.673 | 42.157 | 0.083 | 20.787 | 37.043 | 0.187 | 57.830 | 0.314 | 0.314 | |
| 2/27/97 | 9:05 AM | 10.910 | 47.010 | 0.230 | 15.693 | 42.227 | 0.013 | 20.707 | 37.213 | 0.017 | 57.920 | 0.224 | 0.224 | |

ODOT US177 Approach Embankment Evaluation

Bridge C, South Abutment Wall (Dynamic Compaction of Granular Backfill)

Piezometer:

| | | | |
|-----------------------------------|------------|---|---|
| Standpipe Elevation | 922.89' | → | 921.28' |
| *As Built (Top=2.35 ft above GS) | (As Built) | | (After Paving) |
| GS Elevation (Top of Subgrade) | 920.54' | | Pavement Elevation (Top of Pavement) |
| | | | 921.65' |
| Tip Elevation | 870.54' | | Tip Depth |
| | | | 50.0' |

Groundwater Depth = Piezometer Reading - 0.37'
(Below Top of Pavement)

Groundwater Elevation = Standpipe Elevation (921.28') - Piezometer Reading

| Piezometer Data | | | | | Remarks |
|-----------------|----------|---------|----------|----------|--|
| Date | Time | Reading | GW Depth | GW Elev. | |
| | | ft | ft | ft | |
| 5/25/95 | PM | - | - | - | Installed piezometer |
| 6/2/95 | AM | 23.95 | 21.60 | 898.94 | Initial reading by OSU |
| 6/16/95 | PM | 19.00 | 16.65 | 903.89 | |
| 6/28/95 | AM | 19.88 | 17.53 | 903.01 | |
| 7/7/95 | 2:20 PM | 19.40 | 17.05 | 903.49 | |
| 7/14/95 | 2:15 PM | 19.84 | 17.49 | 903.05 | |
| 7/26/95 | 9:25 AM | 20.00 | 17.65 | 902.89 | |
| 8/9/95 | 10:00 AM | 17.30 | 14.95 | 905.59 | |
| 9/1/95 | 9:55 AM | 19.38 | 17.03 | 903.51 | |
| 9/22/95 | 1:40 PM | 19.65 | 17.30 | 903.24 | |
| 10/12/95 | 3:05 PM | 20.30 | 17.95 | 902.59 | |
| 11/3/95 | 2:05 PM | 20.99 | 18.64 | 901.90 | |
| 11/22/95 | 2:30 PM | 21.45 | 19.10 | 901.44 | |
| 12/20/95 | 1:30 PM | 22.00 | 19.65 | 900.89 | |
| 1/11/96 | 3:00 PM | 22.40 | 20.05 | 900.49 | |
| 2/8/96 | 5:00 PM | 22.90 | 20.55 | 899.99 | |
| 2/29/96 | 4:00 PM | 23.19 | 20.84 | 899.70 | |
| 3/28/96 | 3:00 PM | 23.61 | 21.26 | 899.28 | |
| 4/23/96 | 1:15 PM | 23.77 | 21.42 | 899.12 | |
| 5/21/96 | 10:00 AM | 22.87 | 22.50 | 898.41 | Use new standpipe elev., changed reference for depth |
| 6/11/96 | 10:30 AM | 23.21 | 22.84 | 898.07 | Highway opened to traffic |
| 8/6/96 | 9:30 AM | 23.96 | 23.59 | 897.32 | |
| 10/31/96 | 8:30 AM | 23.96 | 23.59 | 897.32 | |
| 12/16/96 | 9:00 AM | 22.89 | 22.52 | 898.40 | |
| 2/27/97 | 9:05 AM | 22.18 | 21.81 | 899.11 | |

ODOT US177 Approach Embankment Evaluation

Bridge C, South Abutment Wall (Dynamic Compaction of Granular Backfill), Surface Settlement Points

| Date | 6/12/96 | | 8/6/96 | | 10/31/96 | | 2/28/97 | |
|------|----------------------|-----------|---------------|-----------|----------------------|-----------|---------------|--------------------|
| | Reading | Elevation | Reading | Elevation | Reading | Elevation | Reading | Elevation |
| BM | W 924.65 E 923.46 | | W 924.65 E | | W 924.65 E 923.46 | | W 924.65 E | |
| BS | 2.26 | - | 3.044 | - | 3.145 | - | 3.243 | - |
| HI | 925.72 | - | 927.694 | - | 927.795 | - | 927.893 | - |
| FS 1 | 3.65 | 922.07 | 5.623 | 922.071 | 5.755 | 922.040 | 5.848 | 922.045 |
| 2 | 3.81 | 921.91 | 5.798 | 921.896 | 5.911 | 921.884 | 6.010 | 921.883 |
| 3 | 4.00 | 921.72 | 5.983 | 921.711 | 6.102 | 921.693 | 6.198 | 921.695 |
| 4 | 4.18 | 921.54 | 6.162 | 921.532 | 6.266 | 921.529 | 6.365 | 921.528 |
| 5 | 3.63 | 922.09 | 5.602 | 922.092 | 5.726 | 922.069 | 5.823 | 922.070 |
| 6 | 3.79 | 921.93 | 5.785 | 921.909 | 5.898 | 921.897 | 5.997 | 921.896 |
| 7 | 4.00 | 921.72 | 5.982 | 921.712 | 6.096 | 921.699 | 6.195 | 921.698 |
| 8 | 4.18 | 921.54 | 6.173 | 921.521 | 6.281 | 921.514 | 6.387 | 921.496 *2/27/1997 |
| 9 | 3.63 | 922.09 | 5.605 | 922.089 | 5.734 | 922.061 | 5.832 | 922.061 |
| 10 | 3.79 | 921.93 | 5.788 | 921.906 | 5.895 | 921.900 | 5.998 | 921.895 |
| 11 | 4.00 | 921.72 | 5.985 | 921.709 | 6.100 | 921.695 | 6.200 | 921.693 |
| 12 | 4.20 | 921.52 | 6.192 | 921.502 | 6.304 | 921.491 | 6.404 | 921.489 |
| 13 | 3.64 | 922.08 | - | | 5.734 | 922.061 | 5.843 | 922.050 |
| 14 | 3.78 | 921.94 | 5.778 | 921.916 | 5.887 | 921.908 | 5.992 | 921.901 |
| 15 | 3.97 | 921.75 | 5.950 | 921.744 | 6.067 | 921.728 | 6.169 | 921.724 |
| 16 | 4.12 | 921.60 | 6.110 | 921.584 | 6.219 | 921.576 | 6.320 | 921.573 |

*Settlement Reading Point is missing.

APPENDIX B6

C2 Instrumentation Data

ODOT US177 Approach Embankment Evaluation

Bridge C, North Abutment Wall (Flooding and Vibration of Granular Backfill)

Total Pressure Cells:

| | Tubing Length | Date Installed | Test Pressures | | |
|-------------------|---------------|----------------|----------------|--------|---------|
| | | | 5 psi | 50 psi | 100 psi |
| Top - SN 44200 | 34' | 5/2/95 | 5.11 | 50.05 | 100.20 |
| Middle - SN 44205 | 37' | 5/2/95 | 4.92 | 50.00 | 100.05 |
| Bottom - SN 44211 | 40' | 5/2/95 | 5.40 | 50.46 | 100.59 |

| Date | Time | TPC Readings (psi) | | | | | | Remarks |
|----------|----------|--------------------|--------------|---------------|-----------------|---------------|-----------------|---|
| | | Top w/flow | Top w/o flow | Middle w/flow | Middle w/o flow | Bottom w/flow | Bottom w/o flow | |
| 5/5/95 | | 0.0 | 0.0 | 0.0 | 0.0 | 0.5 | 0.3 | Initial readings by WCC, drain cov. mat'l over bottom TPC |
| 5/12/95 | AM | 0.2 | 0.0 | 0.1 | 0.0 | 0.7 | 0.0 | After 1st flood.& vib. of 1st lift, b/fill below mid.TPC |
| 5/12/95 | AM | 0.0 | 0.0 | 0.0 | 0.0 | 0.9 | 0.1 | After 2nd flood.& vib. of 1st lift, b/fill below mid.TPC |
| 5/16/95 | 9:00 AM | 0.6 | 0.4 | 0.7 | 0.5 | 1.5 | 0.9 | After placing 2nd lift, b/fill to top, flood. & vib. underway |
| 5/17/95 | 10:00 AM | 0.2 | 0.1 | 0.4 | 0.2 | 2.0 | 1.4 | After flooding and vibrating complete |
| 5/19/95 | AM | 0.4 | 0.3 | 0.9 | 0.7 | 2.1 | 1.6 | |
| 5/31/95 | AM | 0.3 | 0.2 | 0.3 | 0.2 | 2.0 | 1.8 | |
| 6/16/95 | AM | 0.3 | 0.2 | 0.3 | 0.2 | 2.0 | 1.8 | |
| 6/28/95 | AM | 0.2 | 0.0 | 0.3 | 0.1 | 2.1 | 1.9 | |
| 7/7/95 | 3:05 PM | 0.1 | 0.0 | 0.0 | 0.0 | 1.5 | 1.1 | Top and middle TPC readings are "??" |
| 7/14/95 | 3:00 PM | 0.1 | 0.0 | 0.1 | 0.0 | 1.8 | 1.2 | Top and middle TPC readings are "??" |
| 7/26/95 | 8:35 AM | 0.1 | 0.0 | 1.2 | 1.0 | 2.3 | 1.6 | |
| 8/9/95 | 10:45 AM | 0.1 | 0.0 | 0.9 | 0.7 | 2.0 | 1.6 | |
| 9/1/95 | 10:40 AM | 0.1 | 0.1 | 1.4 | 1.3 | 2.3 | 1.8 | |
| 9/22/95 | 3:10 PM | 0.1 | 0.0 | 0.8 | 0.7 | 2.4 | 2.2 | |
| 10/12/95 | 3:45 PM | 0.0 | 0.0 | 0.3 | 0.1 | 1.7 | 1.5 | |
| 11/3/95 | 2:50 PM | 0.3 | 0.0 | 1.5 | 1.4 | 3.1 | 2.7 | |
| 11/22/95 | 1:00 PM | 0.1 | 0.0 | 0.9 | 0.8 | 2.7 | 2.6 | |
| 12/20/95 | 2:00 PM | 0.0 | 0.0 | 1.0 | 0.9 | 2.7 | 2.5 | |
| 1/11/96 | 4:00 PM | 0.1 | 0.1 | 0.4 | 0.3 | 1.7 | 1.6 | |
| 2/8/96 | 5:00 PM | 0.0 | 0.0 | 0.2 | 0.1 | 1.5 | 1.3 | |
| 2/29/96 | 4:00 PM | 0.1 | 0.0 | 1.5 | 1.4 | 3.3 | 3.2 | |
| 3/28/96 | 3:30 PM | 0.1 | 0.0 | 1.3 | 1.2 | 3.0 | 2.9 | |
| 4/23/96 | 12:35 PM | 0.1 | 0.0 | 1.3 | 1.2 | 3.2 | 3.1 | |
| 5/21/96 | 10:00 AM | 0.0 | 0.0 | 1.5 | 1.3 | 2.7 | 2.5 | |
| 6/11/96 | 8:45 AM | 0.1 | 0.0 | 1.5 | 1.4 | 2.4 | 2.2 | Highway Opened to Traffic |
| 8/6/96 | 8:45 AM | 0.1 | 0.0 | 1.5 | 1.4 | 2.8 | 2.6 | |
| 10/31/96 | 8:15 AM | 0.2 | 0.1 | 1.6 | 1.5 | 3.4 | 3.2 | |
| 12/16/96 | 8:15 AM | 0.2 | 0.1 | 1.7 | 1.6 | 3.6 | 3.4 | |
| 2/27/97 | 8:05 AM | 0.3 | 0.2 | 1.6 | 1.5 | 3.3 | 3.1 | |

ODOT US177 Approach Embankment Evaluation

Bridge C, North Abutment Wall (Flooding and Vibration of Granular Backfill)

Amplified Liquid Settlement Gages:

As Built Elevation

| | Tubing Length | Date Installed | Top of Plate | Top of Fluid |
|-----------------------|---------------|----------------|-----------------------|--------------|
| Centerline - SN 44221 | 40' | 5/2/95 | 909.91' | 920.88' |
| | | | Initial Head = 10.97' | |
| Offset - SN 44222 | 30' | 5/2/95 | 909.87' | 920.90' |
| 10' wide | | | Initial Head = 11.03' | |

Calibration for: Centerline

Offset

$$\text{Head(ft)} = \frac{\text{Reading} - (-4.405 \text{ psi})}{8.455 \text{ psi / ft}}$$

$$\text{Head(ft)} = \frac{\text{Reading} - (-3.50 \text{ psi})}{8.48 \text{ psi / ft}}$$

| ALSG Readings, Heads, & ΔH | | | | | | | | Remarks |
|----------------------------|----------|----------------|------------|----------|----------------|------------|----------|---|
| Date | Time | CL | | | OFS | | | |
| | | Reading psi | Head ft | ΔH ft | Reading psi | Head ft | ΔH ft | |
| 5/5/95 | | 90.2 | 11.147 | | 90.3 | 11.061 | | Initial readings by WCC, drain cov. mat'l over bottom TI |
| 5/12/95 | AM | 90.0 | 11.123 | 0.000 | 90.0 | 11.026 | 0.000 | After 1st flooding & vib. of 1st lift on 5/11 |
| 5/12/95 | AM | 90.5 | 11.182 | 0.059 | 91.1 | 11.156 | 0.130 | After 2nd flooding & vib. of 1st lift on 5/12 |
| 5/16/95 | 9:00 AM | 90.3 | 11.158 | 0.035 | 89.2 | 10.932 | -0.094 | After placing 2nd lift, b'fill to top, flood. & vib. underway |
| 5/17/95 | 10:00 AM | 89.8 | 11.099 | -0.024 | 90.1 | 11.038 | 0.012 | After flooding and vibrating complete |
| 5/19/95 | AM | 90.3 | 11.158 | 0.035 | 90.2 | 11.050 | 0.024 | |
| 5/31/95 | AM | 90.8 | 11.218 | 0.095 | 89.8 | 11.002 | -0.024 | |
| 6/16/95 | AM | 90.4 | 11.170 | 0.047 | 89.0 | 10.908 | -0.118 | |
| 6/28/95 | AM | 90.8 | 11.218 | 0.095 | 90.0 | 11.026 | 0.000 | |
| 7/7/95 | 3:05 PM | 90.8 | 11.218 | 0.095 | 89.8 | 11.002 | -0.024 | |
| 7/14/95 | 3:00 PM | 90.8 | 11.218 | 0.095 | 89.9 | 11.014 | -0.012 | |
| 7/26/95 | 8:35 AM | 90.5 | 11.182 | 0.059 | 89.8 | 11.002 | -0.024 | |
| 8/9/95 | 10:45 AM | 90.7 | 11.206 | 0.083 | 89.8 | 11.002 | -0.024 | |
| 9/1/95 | 10:40 AM | 90.8 | 11.218 | 0.095 | 89.9 | 11.014 | -0.012 | |
| 9/22/95 | 3:10 PM | 91.0 | 11.241 | 0.118 | 89.8 | 11.002 | -0.024 | |
| 10/12/95 | 3:45 PM | 91.1 | 11.253 | 0.130 | 89.6 | 10.979 | -0.047 | |
| 11/3/95 | 2:50 PM | 91.1 | 11.253 | 0.130 | 90.2 | 11.050 | 0.024 | |
| 11/22/95 | 1:00 PM | 91.3 | 11.277 | 0.154 | 90.8 | 11.120 | 0.094 | |
| 12/20/95 | 2:00 PM | 91.5 | 11.300 | 0.177 | 90.5 | 11.085 | 0.059 | |
| 1/11/96 | 4:00 PM | 91.8 | 11.336 | 0.213 | 90.9 | 11.132 | 0.106 | |
| 2/8/96 | 5:00 PM | 91.7 | 11.324 | 0.201 | 90.8 | 11.120 | 0.094 | |
| 2/29/96 | 5:00 PM | 91.8 | 11.378 | 0.255 | 90.3 | 11.061 | 0.035 | |
| 3/28/96 | 3:30 PM | 91.6 | 11.312 | 0.189 | 89.9 | 11.014 | -0.012 | |
| 4/23/96 | 12:35 PM | - | - | - | 90.3 | 11.061 | 0.035 | Misread - not on plot |
| 5/2/96 | 9:00 AM | 91.5 | 11.300 | 0.177 | 90.4 | 11.073 | 0.047 | |
| 5/21/96 | 10:00 AM | 91.5 | 11.300 | 0.177 | 90.2 | 11.050 | 0.024 | |
| 6/11/96 | 8:45 AM | 91.6 | 11.312 | 0.189 | 90.4 | 11.073 | 0.047 | Highway opened to traffic |
| 8/6/96 | 8:45 AM | 91.1 | 11.253 | 0.130 | 89.8 | 11.002 | -0.024 | |
| 10/31/96 | 8:15 AM | 91.7 | 11.324 | 0.201 | 90.6 | 11.097 | 0.071 | |
| 12/16/96 | 8:15 AM | 92.3 | 11.395 | 0.272 | 91.1 | 11.156 | 0.130 | |
| 2/27/97 | 8:05 AM | 72.2 | 9.060 | -2.063 | 58.3 | 7.288 | -3.738 | (?) Readings, not enough flow? |

ODOT US177 Approach Embankment Evaluation

Bridge C, North Abutment Wall (Flooding and Vibration of Granular Backfill)

Inclinometer Telescoping Couplings - Centerline: Installed 6/1/95

| | | | |
|--|---------------------|--------------------|-------------------------|
| Casing Elevation (top=1.91' above GS) | 922.38' As Built | → | 921.35' After Paving |
| GS Elevation | 920.47' | Pavement Elevation | 921.68' |
| Reference Coupling Depth | 55.27' | → | 865.20' Elevation |
| | | Bottom of Casing | 57.22' |

| Readings, Changes, & ΔH Values | | | | | | | | | | | | | | |
|--------------------------------|----------|-------------------|---------------|----------|-------------------|---------------|----------|-------------------|---------------|----------|-------------------|-----------|----------|--------------------------|
| Date | Time | Level 1 (Top) | | | Level 2 | | | Level 3 | | | Level 4 (Bottom) | | | Remarks |
| | | Reading R1, ft | R4 - R1 ft | ΔH ft | Reading R2, ft | R4 - R2 ft | ΔH ft | Reading R3, ft | R4 - R3 ft | ΔH ft | Reading R4, ft | ΔR4 ft | ΔH ft | |
| 6/5/95 | AM | 10.853 | 46.323 | - | 15.843 | 41.333 | - | 20.853 | 36.323 | - | 57.176 | - | - | Omit this data set |
| 6/16/95 | AM | 10.858 | 46.328 | 0.000 | 15.843 | 41.343 | 0.000 | 20.853 | 36.333 | 0.000 | 57.186 | 0.000 | 0.000 | Reference Reading(Datum) |
| 6/28/95 | AM | 10.860 | 46.315 | 0.013 | 15.845 | 41.330 | 0.013 | 20.850 | 36.325 | 0.008 | 57.175 | 0.011 | 0.011 | |
| 7/7/95 | 3:05 PM | 10.860 | 46.315 | 0.013 | 15.845 | 41.330 | 0.013 | 20.855 | 36.320 | 0.013 | 57.175 | 0.011 | 0.011 | |
| 7/14/95 | 3:00 PM | 10.865 | 46.315 | 0.013 | 15.845 | 41.335 | 0.008 | 20.850 | 36.330 | 0.003 | 57.180 | 0.006 | 0.006 | |
| 7/26/95 | 8:35 AM | 10.865 | 46.315 | 0.013 | 15.850 | 41.330 | 0.013 | 20.855 | 36.325 | 0.008 | 57.180 | 0.006 | 0.006 | |
| 8/9/95 | 10:45 AM | 10.865 | 46.315 | 0.013 | 15.850 | 41.330 | 0.013 | 20.853 | 36.327 | 0.006 | 57.180 | 0.006 | 0.006 | |
| 9/1/95 | 10:40 AM | 10.865 | 46.312 | 0.016 | 15.850 | 41.327 | 0.016 | 20.853 | 36.324 | 0.009 | 57.177 | 0.009 | 0.009 | |
| 9/22/95 | 3:10 PM | 10.860 | 46.307 | 0.021 | 15.845 | 41.322 | 0.021 | 20.845 | 36.322 | 0.011 | 57.167 | 0.019 | 0.019 | |
| 10/12/95 | 3:45 PM | 10.860 | 46.267 | 0.061 | 15.845 | 41.282 | 0.061 | 20.847 | 36.280 | 0.053 | 57.127 | 0.059 | 0.059 | |
| 11/3/95 | 2:50 PM | 10.853 | 46.310 | 0.018 | 15.943 | 41.220 | 0.123 | 20.837 | 36.326 | 0.007 | 57.163 | 0.023 | 0.023 | |
| 11/22/95 | 1:00 PM | 10.850 | 46.307 | 0.021 | 15.837 | 41.320 | 0.023 | 20.840 | 36.137 | 0.016 | 57.157 | 0.029 | 0.029 | |
| 12/20/95 | 2:00 PM | 10.845 | 46.408 | -0.080 | 15.827 | 41.426 | -0.083 | 20.925 | 36.328 | 0.005 | 57.253 | 0.067 | -0.067 | |
| 1/11/96 | 4:00 PM | 10.845 | 46.265 | 0.063 | 15.827 | 41.283 | 0.060 | 20.830 | 36.280 | 0.053 | 57.110 | 0.076 | 0.076 | |
| 2/8/96 | 5:00 PM | 10.843 | 46.307 | 0.021 | 15.825 | 41.325 | 0.018 | 20.827 | 36.323 | 0.010 | 57.150 | 0.036 | 0.036 | |
| 2/29/96 | 5:00 PM | 10.845 | 46.302 | 0.026 | 15.825 | 41.322 | 0.021 | 20.828 | 36.319 | 0.014 | 57.147 | 0.039 | 0.039 | |
| 3/28/96 | 3:30 PM | 10.845 | 46.300 | 0.028 | 15.825 | 41.320 | 0.023 | 20.825 | 36.320 | 0.013 | 57.145 | 0.041 | 0.041 | |
| 4/23/96 | 12:35 PM | 10.849 | 46.258 | 0.070 | 15.827 | 41.280 | 0.063 | 20.830 | 36.277 | 0.056 | 57.107 | 0.079 | 0.079 | |
| 5/21/96 | 10:00 AM | 10.850 | 43.290 | 0.038 | 15.830 | 41.310 | 0.033 | 20.830 | 36.310 | 0.023 | 57.140 | 0.046 | 0.046 | |
| 6/11/96 | 8:45 AM | 10.852 | 46.288 | 0.040 | 15.830 | 41.310 | 0.033 | 20.830 | 36.310 | 0.023 | 57.140 | 0.046 | 0.046 | |
| 8/6/96 | 8:45 AM | 10.858 | 46.282 | 0.046 | 15.835 | 41.305 | 0.038 | 20.830 | 36.310 | 0.023 | 57.140 | 0.046 | 0.046 | |
| 10/31/96 | 8:15 AM | 10.850 | 46.280 | 0.048 | 15.828 | 41.302 | 0.041 | 20.825 | 36.305 | 0.028 | 57.130 | 0.056 | 0.056 | |
| 12/16/96 | 8:15 AM | 10.847 | 46.283 | 0.045 | 15.825 | 41.305 | 0.038 | 20.823 | 36.307 | 0.026 | 57.130 | 0.056 | 0.056 | |
| 2/27/97 | 8:05 AM | 10.840 | 46.285 | 0.043 | 15.820 | 41.305 | 0.038 | 20.813 | 36.312 | 0.021 | 57.125 | 0.061 | 0.061 | |

ODOT US177 Approach Embankment Evaluation

Bridge C, North Abutment Wall (Flooding and Vibration of Granular Backfill)

Inclinometer Telescoping Couplings - Offset: Installed 6/2/95

Casing Elevation 922.65'
(top=2.04' above GS) As Built → After Paving

GS Elevation 920.61' Pavement Elevation

Reference Coupling 55.23' Depth → 865.38' Elevation Bottom of Casing 57.17'

| Date | Time | Readings, Changes, & ΔH Values | | | | | | | | | | | Remarks | |
|----------|----------|--------------------------------|---------------|----------|-------------------|---------------|----------|-------------------|---------------|----------|-------------------|-----------|---------|---|
| | | Level 1 (Top) | | | Level 2 | | | Level 3 | | | Level 4 (Bottom) | | | |
| | | Reading R1, ft | R4 - R1 ft | ΔH ft | Reading R2, ft | R4 - R2 ft | ΔH ft | Reading R3, ft | R4 - R3 ft | ΔH ft | Reading R4, ft | ΔR4 ft | | ΔH ft |
| 6/5/95 | AM | 10.884 | 46.385 | 0.000 | 15.884 | 41.385 | 0.000 | 20.905 | 36.364 | 0.000 | 57.269 | 0.000 | 0.000 | Reference Reading (Datum) Omit this Data set |
| 6/16/95 | AM | 10.884 | 46.323 | - | 15.884 | 41.323 | - | 20.915 | 36.292 | - | 57.207 | - | - | |
| 6/28/95 | AM | 10.911 | 46.389 | -0.004 | 15.915 | 41.385 | 0.000 | 20.940 | 36.360 | 0.004 | 57.300 | 0.031 | -0.031 | |
| 7/7/95 | 3:05 PM | 10.890 | 46.380 | 0.005 | 15.885 | 41.385 | 0.000 | 20.915 | 36.355 | 0.009 | 57.270 | 0.001 | -0.001 | |
| 7/14/95 | 3:00 PM | 10.890 | 46.380 | 0.005 | 15.895 | 41.375 | 0.010 | 20.920 | 36.350 | 0.014 | 57.270 | 0.001 | -0.001 | |
| 7/26/95 | 8:35 AM | 10.885 | 46.385 | 0.000 | 15.890 | 41.380 | 0.005 | 20.915 | 36.355 | 0.009 | 57.270 | 0.001 | -0.001 | |
| 8/9/95 | 10:45 AM | 10.890 | 46.380 | 0.005 | 15.890 | 41.380 | 0.005 | 20.915 | 36.355 | 0.009 | 57.270 | 0.001 | -0.001 | |
| 9/1/95 | 10:40 AM | 10.927 | 46.396 | -0.011 | 15.933 | 41.390 | -0.005 | 20.960 | 36.363 | 0.001 | 57.323 | 0.054 | -0.054 | |
| 9/22/95 | 3:10 PM | 10.877 | 46.323 | 0.062 | 15.885 | 41.315 | 0.070 | 20.910 | 36.290 | 0.074 | 57.200 | 0.069 | 0.069 | |
| 10/12/95 | 3:45 PM | 10.890 | 46.370 | 0.015 | 15.893 | 41.367 | 0.018 | 20.910 | 36.350 | 0.014 | 57.260 | 0.009 | 0.009 | |
| 11/3/95 | 2:50 PM | 10.875 | 46.395 | -0.010 | 15.880 | 41.390 | -0.005 | 20.920 | 36.450 | -0.086 | 57.270 | 0.001 | -0.001 | |
| 11/22/95 | 1:00 PM | 10.870 | 46.323 | 0.062 | 15.875 | 41.318 | 0.067 | 20.903 | 36.290 | 0.074 | 57.193 | 0.076 | 0.076 | |
| 12/20/95 | 2:00 PM | 10.865 | 46.415 | -0.030 | 15.870 | 41.410 | -0.025 | 20.900 | 36.380 | -0.016 | 57.280 | 0.011 | -0.011 | |
| 1/11/96 | 4:00 PM | 10.865 | 46.380 | 0.005 | 15.870 | 41.375 | 0.010 | 20.895 | 36.350 | 0.014 | 57.245 | 0.024 | 0.024 | |
| 2/8/96 | 5:00 PM | 10.865 | 46.378 | 0.007 | 15.870 | 41.373 | 0.012 | 20.895 | 36.348 | 0.016 | 57.243 | 0.026 | 0.026 | |
| 2/29/96 | 5:00 PM | 10.869 | 46.376 | 0.009 | 15.870 | 41.375 | 0.010 | 20.899 | 36.346 | 0.018 | 57.245 | 0.024 | 0.024 | |
| 3/28/96 | 3:30 PM | 10.867 | 46.313 | 0.072 | 15.870 | 41.310 | 0.075 | 20.899 | 36.281 | 0.083 | 57.180 | 0.089 | 0.089 | |
| 4/23/96 | 12:35 PM | 10.870 | 46.310 | 0.075 | 15.873 | 41.307 | 0.078 | 20.900 | 36.280 | 0.084 | 57.180 | 0.089 | 0.089 | |
| 5/21/96 | 10:00 AM | 10.880 | 46.097 | 0.288 | 15.615 | 41.362 | 0.023 | 20.640 | 36.337 | 0.027 | 56.977 | 0.292 | 0.292 | ----- New reference (top) using ext Highway opened to traffic |
| 6/11/96 | 8:45 AM | 10.890 | 46.010 | 0.375 | 15.602 | 41.298 | 0.087 | 20.628 | 36.272 | 0.092 | 56.900 | 0.369 | 0.369 | |
| 8/6/96 | 8:45 AM | 10.898 | 46.080 | 0.377 | 15.613 | 41.365 | 0.020 | 20.740 | 36.238 | 0.126 | 56.978 | 0.291 | 0.291 | |
| 10/31/96 | 8:15 AM | 10.917 | 46.068 | 0.317 | 15.635 | 41.350 | 0.035 | 20.660 | 36.325 | 0.039 | 56.985 | 0.284 | 0.284 | |
| 12/16/96 | 8:15 AM | 10.885 | 46.070 | 0.315 | 15.605 | 41.350 | 0.035 | 20.630 | 36.325 | 0.039 | 56.955 | 0.314 | 0.314 | |
| 2/27/97 | 8:05 AM | 10.890 | 46.070 | 0.315 | 15.605 | 41.355 | 0.030 | 20.630 | 36.330 | 0.034 | 56.960 | 0.309 | 0.309 | |

ODOT US177 Approach Embankment Evaluation

Bridge C, North Abutment Wall (Flooding and Vibration of Granular Backfill)

Piezometer:

| | | | | |
|--|---------|--------------------|---------|----------------|
| Standpipe Elevation | | 923.12' | → | 921.31' |
| *As Built ► (Top=2.63 ft above GS) | | (As Built) | | (After Paving) |
| GS Elevation | 920.49' | Pavement Elevation | 921.68' | |
| (Top of Subgrade) | | (Top of Pavement) | | |
| Tip Elevation | 875.49' | Tip Depth | 45.0' | |
| Groundwater Depth = Piezometer Reading - 0.37' | | | | |
| (Below Top of Pavement) | | | | |

Groundwater Elevation = Standpipe Elevation (921.31) - Piezometer Reading

| Piezometer Data | | | | | Remarks |
|-----------------|----------|---------|----------|----------|--|
| Date | Time | Reading | GW Depth | GW Elev. | |
| | | ft | ft | ft | |
| 6/1/95 | PM | - | - | - | Installed piezometer |
| 6/16/95 | AM | 19.05 | 16.42 | 904.07 | |
| 6/28/95 | AM | 19.44 | 16.81 | 903.68 | |
| 7/7/95 | 3:05 PM | 18.94 | 16.31 | 904.18 | |
| 7/14/95 | 3:00 PM | 19.36 | 16.73 | 903.76 | |
| 7/26/95 | 8:35 AM | 19.60 | 16.97 | 903.52 | |
| 8/9/95 | 10:45 AM | 17.40 | 14.77 | 905.72 | |
| 9/1/95 | 10:40 AM | 18.98 | 16.35 | 904.14 | |
| 9/22/95 | 3:10 PM | 19.24 | 16.61 | 903.88 | |
| 10/12/95 | 3:45 PM | 19.85 | 17.22 | 903.27 | |
| 11/3/95 | 2:50 PM | 20.47 | 17.84 | 902.65 | |
| 11/22/95 | 1:00 PM | 20.87 | 18.24 | 902.25 | |
| 12/20/95 | 2:00 PM | 21.35 | 18.72 | 901.77 | |
| 1/11/96 | 4:00 PM | 21.73 | 19.10 | 901.39 | |
| 2/8/96 | 5:00 PM | 22.19 | 19.56 | 900.93 | |
| 2/29/96 | 5:00 PM | 22.60 | 19.97 | 900.52 | |
| 3/28/96 | 3:30 PM | 22.89 | 20.26 | 900.23 | |
| 4/23/96 | 12:35 PM | 23.10 | 20.47 | 900.02 | |
| 5/21/96 | 10:00 AM | 21.79 | 21.42 | 899.52 | Use new standpipe elev., changed reference for depth |
| 6/11/96 | 8:45 AM | 22.17 | 21.80 | 899.14 | Highway opened to traffic |
| 8/6/96 | 8:45 AM | 23.02 | 22.65 | 898.29 | |
| 10/31/96 | 8:15 AM | 23.14 | 22.77 | 898.17 | |
| 12/16/96 | 8:15 AM | 21.94 | 21.57 | 899.37 | |
| 2/27/97 | 8:05 AM | 21.02 | 20.65 | 900.29 | |

ODOT US177 Approach Embankment Evaluation

Bridge C, North Abutment Wall (Flooding and Vibration of Granular Backfill), Surface Settlement Points

| Date | 6/12/96 | | 8/6/96 | | 10/31/96 | | 2/28/97 | |
|------|----------------------|-----------|----------------------|-----------|----------------------|-----------|---------------|--------------------|
| | Reading | Elevation | Reading | Elevation | Reading | Elevation | Reading | Elevation |
| BM | W 924.78 E 923.56 | | W 924.78 E 923.56 | | W 924.78 E 923.56 | | W 924.78 E | |
| BS | 2.18 | - | 2.70 | - | 2.78 | - | 2.537 | - |
| HI | 925.74 | - | 927.48 | - | 927.56 | - | 927.317 | - |
| FS 1 | 3.60 | 922.14 | 5.340 | 922.140 | 5.435 | 922.125 | 5.197 | 922.120 |
| 2 | 3.74 | 922.00 | 5.520 | 921.960 | 5.605 | 921.955 | 5.370 | 921.947 |
| 3 | 3.88 | 921.86 | 5.650 | 921.830 | 5.735 | 921.825 | 5.500 | 921.817 |
| 4 | 4.05 | 921.69 | 5.810 | 921.670 | 5.895 | 921.665 | 5.680 | 921.657 |
| 5 | 3.64 | 922.10 | 5.385 | 922.095 | 5.475 | 922.085 | 5.265 | 922.052 *2/27/1997 |
| 6 | 3.79 | 921.95 | 5.565 | 921.915 | 5.655 | 921.905 | 5.418 | 921.899 |
| 7 | 3.93 | 921.81 | 5.685 | 921.795 | 5.770 | 921.790 | 5.560 | 921.757 *2/27/1997 |
| 8 | 4.13 | 921.61 | 5.890 | 921.590 | 5.963 | 921.577 | 5.747 | 921.570 |
| 9 | 3.69 | 922.05 | 5.442 | 922.038 | 5.535 | 922.025 | 5.318 | 921.999 *2/27/1997 |
| 10 | 3.84 | 921.90 | 5.605 | 921.875 | 5.695 | 921.865 | 5.462 | 921.855 |
| 11 | 3.97 | 921.77 | 5.730 | 921.750 | 5.825 | 921.735 | 5.587 | 921.730 |
| 12 | 4.14 | 921.60 | 5.890 | 921.590 | 5.975 | 921.585 | 5.745 | 921.572 |
| 13 | 3.73 | 922.01 | 5.484 | 921.996 | 5.575 | 921.985 | 5.360 | 921.957 *2/27/1997 |
| 14 | 3.88 | 921.86 | 5.646 | 921.834 | 5.740 | 921.820 | 5.506 | 921.811 |
| 15 | 4.01 | 921.73 | 5.767 | 921.713 | 5.867 | 921.693 | 5.627 | 921.690 |
| 16 | 4.15 | 921.59 | 5.915 | 921.565 | 6.000 | 921.560 | 5.768 | 921.549 |


*Settlement Reading Point is missing.

APPENDIX C

Instrumentation Data Plots





APPENDIX C1

A1 Instrumentation Data Plots




Total Pressure Cell Data (Time Plot) South Abutment Wall, Bridge A



Settlement from Amplified Liquid Settlement Gages, South Abutment Wall, Bridge A





Settlement from Inclinator Telescoping Couplings (Time Plot) Centerline, South Abutment Wall, Bridge A





Groundwater Table Elevation (Time Plot) South Abutment Wall, Bridge A



Surface Settlement Point Data, South Abutment Wall, Bridge A




Lateral Displacement, Centerline





Lateral Displacement, Abutment Wall

APPENDIX C2




A2 Instrumentation Data Plots




Total Pressure Cell Data (Time Plot) North Abutment Wall, Bridge A




Settlement from Amplified Liquid Settlement Gages, North Abutment Wall, Bridge A





Settlement from Inclinator Telescoping Couplings (Time Plot) Centerline, North Abutment Wall, Bridge A





Settlement from Inclinometer Telescoping Couplings (Time Plot) Offset, North Abutment Wall, Bridge A





Groundwater Table Elevation (Time Plot) North Abutment Wall, Bridge A





Surface Settlement Point Data, North Abutment Wall, Bridge A



Lateral Displacement, Centerline




Lateral Displacement, Offset




Lateral Displacement, Abutment Wall

APPENDIX C3


B1 Instrumentation Data Plots






Total Pressure Cell Data (Time Plot) South Abutment Wall, Bridge B




Settlement from Amplified Liquid Settlement Gages, South Abutment Wall, Bridge B





Settlement from Inclinator Telescoping Couplings, Centerline, South Abutment Wall, Bridge B





Settlement from Inclinator Telescoping Couplings, Offset, South Abutment Wall, Bridge B





Groundwater Table Elevation (Time Plot) South Abutment Wall, Bridge B





Surface Settlement Point Data, South Abutment Wall, Bridge B



Lateral Displacement, Centerline




Lateral Displacement, Offset





Lateral Displacement, Abutment Wall

APPENDIX C4


B2 Instrumentation Data Plots




Total Pressure Cell Data (Time Plot) North Abutment Wall, Bridge B




Settlement from Amplified Liquid Settlement Gages, North Abutment Wall, Bridge B





Settlement from Inclinator Telescoping Couplings (Time Plot) Centerline, North Abutment Wall, Bridge B





Settlement from Inclinator Telescoping Couplings (Time Plot) Offset, North Abutment Wall, Bridge B





Groundwater Table Elevation (Time Plot) North Abutment Wall, Bridge B





Surface Settlement Point Data, North Abutment Wall, Bridge B



Lateral Displacement, Centerline




Lateral Displacement, Offset




Lateral Displacement, Abutment Wall

APPENDIX C5


C1 Instrumentation Data Plots




Total Pressure Cell Data (Time Plot) South Abutment Wall, Bridge C





Settlement from Inclinometer Telescoping Couplings (Time Plot) Centerline, South Abutment Wall, Bridge C





Settlement from Inclinometer Telescoping Couplings (Time Plot) Offset, South Abutment Wall, Bridge C





Groundwater Table Elevation (Time Plot) South Abutment Wall, Bridge C





Surface Settlement Point Data, South Abutment Wall, Bridge C



Lateral Displacement, Centerline




Lateral Displacement, Offset




Lateral Displacement, Abutment Wall

APPENDIX C6


C2 Instrumentation Data Plots




Total Pressure Cell Data (Time Plot) North Abutment Wall, Bridge C





Settlement from Inclinator Telescoping Couplings (Time Plot) Centerline, North Abutment Wall, Bridge C





Settlement from Inclinator Telescoping Couplings (Time Plot) Offset, North Abutment Wall, Bridge C





Groundwater Table Elevation (Time Plot) North Abutment Wall, Bridge C





Surface Settlement Point Data, North Abutment Wall, Bridge C



Lateral Displacement, Centerline



Lateral Displacement, Offset



Lateral Displacement, Abutment Wall