

SELECTION OF OPTIMAL COMBINATIONS OF PRECAST,
PRESTRESSED CONCRETE COMPONENTS FOR
SYSTEMS BUILDING CONSTRUCTION
BY LINEAR PROGRAMMING

By

HILARY ISU AGHA

Bachelor of Science
California State University at San Jose
San Jose, California
1966

Master of Engineering
Brigham Young University
Provo, Utah
1974

Submitted to the Faculty of the Graduate College
of the Oklahoma State University
in partial fulfillment of the requirements
for the Degree of
DOCTOR OF PHILOSOPHY
May, 1977

Thesis
1977D
A2665
cop. 2



SELECTION OF OPTIMAL COMBINATIONS OF PRECAST,
PRESTRESSED CONCRETE COMPONENTS FOR
SYSTEMS BUILDING CONSTRUCTION
BY LINEAR PROGRAMMING

Thesis Approved:

Robert L. James

Thesis Adviser

Gerald D. Abulander

Mitchell O. Locks

Phillip L. Marke

Norman V. Durbin

Dean of the Graduate College

To my wife, Nonyelum, for her encouragement and patience throughout the writing of this treatise, and to my late parents, Agha and Ugo, who gave me the right orientation in life.

ACKNOWLEDGMENTS

The author wishes to express his sincere gratitude and appreciation to all the people who made this study and the documentation of this dissertation possible.

Dr. Robert L. Janes, who served as thesis adviser and chairman of the Graduate Committee was most helpful in directing this research and providing very valuable advice and guidance throughout the writing of this dissertation. He also recommended the author to the precast concrete company that supplied the data for testing the linear programming models developed in this treatise.

The author is also greatly indebted to the following members of his Graduate Committee for their helpful suggestions and personal involvement throughout the preparation of this study: Professor Phillip G. Manke, Civil Engineering faculty, whose encouragement and advice proved indispensable to the successful completion of the author's career in this institution, and this study; Professor Mitchell O. Locks, Management Science faculty, who once accompanied the author on a trip for data collection, and who provided necessary advice and guidance during the linear programming formulation and the computerized solution to the models developed in this dissertation; Professor Garold D. Oberlender, Civil Engineering faculty, who reviewed the engineering data used in testing the models, and whose sound understanding of both the Structural Engineering and Construction problems associated with the models' formulation proved a great asset to the author.

Mr. William A. Maples, Executive Director, American Concrete Institute, and Mrs. Nancy R. Ady, Research Librarian, Portland Cement Association, were very cooperative in locating publications on the development and current status of precast, prestressed concrete construction and concrete systems buildings.

The author thanks in a very special way the Vice President, Engineering, and the entire management of the Precast Concrete Systems Building Company which made readily available to the author all data necessary for the verification of the models developed in this treatise.

The author is also very grateful to Dr. J. V. Parcher, Professor and Head, School of Civil Engineering, for approving the financial aid from the Oklahoma State University Development Foundation, which made the typing of this dissertation possible.

TABLE OF CONTENTS

Chapter	Page
I. INTRODUCTION	1
II. THE DEVELOPMENT OF PRECAST, PRESTRESSED CONCRETE CONSTRUCTION	11
Introduction	11
Some Early Examples of Precast Concrete Construction	11
The Development of Precast, Prestressed Concrete Construction	12
The Systems Building Approach to Precast, Prestressed Concrete Construction	14
Development of Concrete Systems Buildings	15
Operation Breakthrough	16
Evaluation of European Systems	17
The Advantages of Precast, Prestressed Concrete Construction	18
Some Historic and Current Problems Associated with Precast, Prestressed Concrete Construction	19
Lack of Uniformity among Design Codes	20
Conflicting Highway Requirements on the Weight and Dimensions of Precast Members	21
Some Economic Considerations in the Planning of a Concrete Systems Building Enterprise	22
III. APPLICATIONS OF LINEAR PROGRAMMING TO CIVIL ENGINEERING PROBLEMS	25
The Attitude of the Construction Industry to Mathematical Models	31
Linear Programming Applications in Construction Management	33
IV. MODEL FORMULATION	36
Introduction	36
Formulation of Decision Variables	38
A Mathematical Statement of the Linear Programming Model	41

Chapter	Page
V. MODEL VALIDATION	44
Functional Groups and Precast Concrete Components . . .	44
Decision Variables Representation	46
Row Names Representation	49
Decision Variable Coefficient Computation	51
General Requirements for Decision Variable Coefficients	55
Computation of Conversion Factors for Truck Loads at First Location	60
The Need for Solving the Problem by Many ILP Models . .	63
Computerized Solution to the Linear Programming Models	63
VI. SELECTION AND RANKING OF OPTIMAL COMBINATIONS	66
Optimal Concrete Components Recommended for Concrete Systems Buildings Development	67
The Problems Associated with the Solution	75
The Advantages of the LP Solution	75
VII. SUMMARY, CONCLUSIONS, AND RECOMMENDATIONS	77
Summary	77
Conclusions	78
Recommendations	79
BIBLIOGRAPHY	80
APPENDIX A - DATA AS ORIGINALLY COLLECTED FROM THE PROGRESSIVE CONCRETE COMPANY	92
APPENDIX B - TABLES OF QUANTITIES FOR THE CONSTRAINT EQUATIONS . .	94
APPENDIX C - TABLES OF QUANTITIES FOR THE COMPUTATION OF CONVERSION FACTORS AND TRUCK LOADS FOR THE SECOND AND THIRD LOCATIONS	106
APPENDIX D - A TYPICAL COMPUTER PROGRAM EXPLAINED AND LISTED . . .	113

LIST OF TABLES

Table	Page
I. Functional Groups and Their Precast Concrete Components . .	39
II. Functional Groups and Their Precast Concrete Components . .	45
III. Building Alternatives and Their Relevant Precast Concrete Components	47
IV. Relationship Between the Location, L, and the Distance in Miles of a Building Alternative	48
V. Row Names and the Resources They Represent	50
VI. Prestressing Steel Requirements (psi)	54
VII. Summary of Computation of Conversion Factors for the First Location	61
VIII. Summary of Conversion Factors and Converted Truck Loads for the First, Second, and Third Locations	62
IX. Summary of Selections and Their Precast Concrete Components	74
X. Precast Concrete Components and the Resources Needed for Their Production and Erection	93
XI. Reinforcing Steel Requirements (RB 2)	95
XII. Wire Mesh Type I Requirements (WM 3)	96
XIII. Wire Mesh Type II Requirements (WM 4)	97
XIV. Wire Mesh Type III Requirements (WM 5)	98
XV. Concrete Type I Requirements (CN 6)	99
XVI. Concrete Type II Requirements (CN 7)	100
XVII. Concrete Type III Requirements (CN 8)	101
XVIII. Plant Labor Requirements (PL 9)	102

Table	Page
XIX. *Erection Labor Requirements for Precast and Prestressed Members (EL 10)	103
XX. *Erection Labor Requirements for Block Wall (ELB 11)	104
XXI. Highway Weight Limit Requirements--First Location (WLR 12)	105
XXII. Increase in Transportation Cost Up to the Second Location, Above That of the First Location	107
XXIII. Increase in Transportation Cost Up to the Third Location, Above That of the First Location	108
XXIV. Summary of Computation of Conversion Factors for the Second Location	109
XXV. Summary of Computation of Conversion Factors for the Third Location	110
XXVI. Computation of Converted Truck Loads for the Second Location	111
XXVII. Computation of Converted Truck Loads for the Third Location	112

LIST OF FIGURES

Figure	Page
1. Typical Prestressing Operation	2
2. Gripping Devices for Prestressing Steel Tendons (1)	4
3. Precast Concrete Components	5
4. Transportation Cost of Different Precast Concrete Components for the First 75 Miles from the Precasting Plant	57
5. Transportation Cost of Different Precast Concrete Components for the First 150 Miles from the Precasting Plant	58
6. Transportation Cost of Different Precast Concrete Components for the First 225 Miles from the Precasting Plant	59
7. Rate of Consumption of a Typical Resource by Functional Groups	64
8. Selection of the Three Most Optimal Combinations for the First Story Height at Three Locations	68
9. Selection of the Three Most Optimal Combinations up to the Second Story Height at Two Locations	69
10. Selection of the Three Most Optimal Combinations up to the Second Story Height at the Second Location	70
11. Selection of the Three Most Optimal Combinations up to the Third Story Height at Three Locations	71
12. Selection of the Three Most Optimal Combinations up to the Fourth Story Height at Three Locations	72
13. Selection of the Three Most Optimal Combinations up to the Fifth Story at Three Locations	73
14. MPSX360 Control Language Source Program	115
15. A Typical MPSX360 Input Data Format	118


CHAPTER I

INTRODUCTION


Prestressing, as applied to concrete structures, means the intentional creation of predetermined permanent stresses and internal moments in the concrete structure, so that internal stresses and moments resulting from service loads are confined within certain limits. Prestressed concrete is a concrete structure which has been subjected to prestressing before service loads act upon it. If the prestressed concrete structure is made at a place other than its final location in service, it is a precast, prestressed concrete structure.

In precast, prestressed concrete construction operations, steel cables (prestressing steel tendons) are stretched under large tension between two supports (bulk heads). Fresh concrete mix is then poured over these stretched prestressing steel tendons, and allowed to harden. In the process, the concrete is bonded to the steel tendons. When the steel tendons are cut they contract, thus subjecting the concrete to large compressive stresses. Figure 1(a) is a double tee which has been formed between two bulk heads. After the prestressing steel tendons are cut, Figure 1(b), the contraction of the tendons produces a bowing effect in the double tee. This effect induces compressive stresses in the bottom fibers of the concrete and tensile stresses in the top fibers.

There are many ways of anchoring the steel tendons to the bulk



(a) Double Tee Cast Between Two Bulk Heads



CAMBER DUE TO PRESTRESSING

(b) Double Tee After Prestressing
Steel Tendons Have Been Cut

Figure 1. Typical Prestressing Operation

heads. Figure 2(a) and (b) show two possible ways of doing this (1).¹ Figure 2(a) is a split cone wedge made from a tapered conical pin. Another grip made from a conical pin on which a flat surface has been machined and serrated, is shown in Figure 2(b).

Precast concrete construction often requires that concrete components be transported long distances. Therefore, it is economically desirable to make the components as light as possible. This can be achieved principally in two ways. First, by using high strength concrete to ensure small sections of components. Second, concrete aggregates (gravel, broken stones, pieces of non-reactive solid materials) weighing around 100 lb per cubic foot (light weight aggregates), should be used in precast concrete work. Many factors influence the strength of concrete mixes. The ratio of water to cement (water cement ratio), the type of aggregate used in the mix, and the temperature and moisture conditions (curing conditions) of the concrete structure especially during the first two weeks of the life of the precast concrete structure, all influence the strength of the concrete. The higher the density of the aggregate, the greater the weight per cubic yard of the hardened concrete. Because of the many factors which influence the properties of concrete mixes, there are many types of concrete.

Many different geometrical shapes, requiring different forms (steel forms, wooden forms, forms made of plastic materials) have been developed for precast, prestressed concrete construction. Double tees, flat slabs, el-beams, rectangular beams, concrete blocks to be used principally in the walls of buildings, core wall boxes and core wall panels for interior walls, stair landings and stair frames, are among such shapes. Some of these shapes are shown in Figure 3.




Figure 2. Gripping Devices for
Prestressing Steel
Tendons (1)







Figure 3. Precast Concrete Components




Core Wall Panel



Precast Stairs



Flat Slab Stair Landing



Core Box

Figure 3. Continued

This treatise addresses the problem of selecting precast concrete components in such a way as to minimize the cost of a completed building.

During the planning stages of a precast concrete systems manufacturing enterprise, the selection of appropriate geometrical shapes and sizes of precast structural concrete members to manufacture is always a difficult decision. Once the choice of shapes and sizes are made and the proper forms purchased, it may take years before the replacement of the steel forms can be economically justified. In the late 1960's elaborate research projects were initiated by the United States Department of Housing and Urban Development (HUD) and the Illinois Institute of Technology Research Institute (IITRI) to determine structurally feasible geometrical shapes and modules which were economical and well fitted to the North American construction industry and labor practices.

If the research teams could have agreed on any one geometrical shape or module as the most economical, the uncertainties associated with the planning of concrete formwork for a precast concrete systems building (2) company would have been greatly minimized. However, the conclusions of the research teams regarding the economics of certain geometrical shapes or modules were contradictory.

Due to the experience in the precast concrete construction industry in both the United States and in Europe, one would anticipate the type of contradictions alluded to above. The research projects were executed under different organizations and management personnel. Also they were located in different areas of the United States. Location, environment, and the management of construction resources within the precast concrete plant can make a given geometrical shape or module

more economical than another.

Thus, there exists a need for a method of analysis by the top management of a precast concrete systems building company, for the selection of economic combinations of geometric sections for new pre-casting plants. Such analysis should include a quantitative planning and decision model which establishes the relative economics of structurally feasible combinations of components or modules that make up precast concrete systems buildings. Additionally, such a model must contain specific provisions for the environmental constraints which are endemic to both the precast concrete plant and the marketing area in which the prospective precast concrete systems building company intends to operate.

Research at Oklahoma State University to develop such a quantitative planning and decision model by use of linear programming (LP)(3) has been completed. The LP model selects the economical and yet structurally feasible combinations of precast concrete components for precast concrete systems buildings. The model is a valuable aid to objective planning and selection of geometrical shapes (concrete forms) at a new plant location for a precast concrete systems building company. The model can also be used when steel forms replacement is to be considered.

The three phases of precast concrete systems building construction treated in this paper are plant operations, transportation of precast concrete components to the construction site, and the erection of the components at the building site. Structurally feasible combinations of precast concrete components which make up a building, formed the linear programming model. The effects which change in story height

and the distance of a building from the precast concrete plant could have on the selection of economical combinations were also investigated. The precast concrete components that consistently formed the most economical combinations were recommended for precast concrete systems buildings development.

Chapter II presents a brief account of the development of concrete systems building construction. Chapter III is a review of literature on the applications of linear programming in Civil Engineering practice.

Chapter IV is on the formulation of the linear programming model developed in the investigation, while Chapter V addresses the problem of applying the model to the operations of an existing precast concrete systems building company, the Progressive Concrete Company (PCC). The real name of this company is disguised in this treatise.

The results of the various LP runs are presented in Chapter VI.

Chapter VII contains the summary and conclusions made from the research and recommendations for further research.

The references used in the dissertation are listed under "Bibliography".

The Appendix presents the data from the PCC, tables of quantities used in the models, as well as a brief description of a typical computer program. The description of the computer program is facilitated by the use of a listing of the typical program.

NOTES

¹Numbers in parentheses refer to the Bibliography.

CHAPTER II

THE DEVELOPMENT OF PRECAST, PRESTRESSED CONCRETE CONSTRUCTION

Introduction

Initially precast concrete was used by engineers who were interested in building design and construction with limited knowledge of designing, forming, bracing, shoring and scaffolding, and placing concrete. Since precast concrete units could be inspected and tested for defective sections at the time of handling and erection, many engineers preferred to design structures in precast concrete. Other engineers reasoned that the problems and costs associated with forming, shoring, and placing cast-in-place concrete were excessive and that precast concrete construction was justified on the grounds of convenience in construction and cost.

Some Early Examples of Precast

Concrete Construction

In 1900 (4, 5), a stable was built in Brooklyn, with precast concrete roof slabs 17 x 14 feet and two inches thick. The same precast slabs were used for partitions, cross walls, vents and manure pits.

In 1905 one of the early industrial applications of precast concrete in buildings was initiated in this country. During that year, a

four-story building of complete precast reinforced concrete floor-and-roof system was constructed for the Textile Machine Works in Reading, Pa. By 1910 precast concrete was being used nation-wide in the construction of industrial buildings. The Unit Construction Co., St. Louis, Mo., constructed a large number of buildings completely built of precast units using a system called "Unit Structural Concrete Method," later named the "Unit System." The "Unit System" construction technique required that the connections between precast columns and girders be grouted to develop some continuity and rigidity. Conselman, the engineer and designer responsible for the development of the "Unit System," obtained more than 51 patents for the "Unit System," from 1910 to 1916. In 1911, a five story building was constructed for the National Lead Co., St. Louis, Mo., using the "Unit System." The five story building was completely precast, with design floor loadings of 500 lb per square foot. The interior and exterior columns, wall slabs, thin-shell channel-section floor slabs, and beams of this five story building were all made of precast concrete.

The Development of Precast, Prestressed Concrete Construction

The first prestressed concrete structures to be constructed in the United States were also precast structures. About 1886, P. H. Jackson, an engineer of San Francisco, California, obtained patents for tightening steel tie rods in artificial stones and precast concrete arch sections used as floors of buildings or side walls over excavations. In 1888, C.E.W. Doebling of Germany independently secured a patent for concrete reinforced with metal that had tensile stress applied to it

before the slab was loaded (1).

In 1925, R. E. Dill of Alexandria, Nebraska, applied for a patent to produce precast, prestressed concrete members such as posts and slabs. Dill used a high tensile steel coated with a plastic substance to prevent bond (6). The steel was tensioned after the concrete had set, and was anchored to the concrete by means of nuts.

E. Freyssinet of France is credited with modern development of prestressed concrete. In 1928, Freyssinet used the first high-strength steel wires for prestressing. However, despite Freyssinet's ingenious development, it was still necessary to devise reliable and economical methods of tensioning and anchoring the steel wires before prestressed concrete construction could become popular.

From 1928 through 1940 adequate tensioning and anchoring techniques were invented. One of the engineers who made significant contributions in this area was E. Hoyer of Germany, by developing the Hoyer system. The Hoyer system consisted of stretching wires between two buttresses several hundred feet apart, constructing special forms to separate the units, placing the concrete, and cutting the wires after the concrete had hardened (1). In 1939, Freyssinet developed end anchorages and double acting jacks for tensioning wires. The Magnel system, developed in 1940 by Professor G. Magnel of Belgium, used two wires stretched one at a time and anchored with a simple metal wedge at each end.

Linear prestressing was initiated in the United States in 1949 with the construction of the Philadelphia Walnut Lane Bridge. Prior to 1949, circular prestressing of storage tanks was commonly used. Between 1935 and 1963, the Preload Company built about one thousand

prestressed concrete tanks in the United States and other parts of the world (1).

By 1950, the use of prestressed concrete construction became common practice. Although there was only one precast, prestressed concrete plant in this country in 1950, there were 34 such plants in 1954. According to a survey by the Prestressed Concrete Institute (1), 229 plants were operating in this country by 1961. Some of these plants made both prestressed concrete components, and precast concrete blocks as well.

The Systems Building Approach to Precast, Prestressed Concrete Construction

The past ten years have shown an increased interest by governmental agencies and engineering institutions to improve the quality and economy of concrete construction by methods of mass production of precast, prestressed concrete buildings.

There was an acute shortage of residential houses in the United States in the 1960's. A report by Module Communities, Inc. (7) showed two-thirds of the population in the United States in 1968 was concentrated in the 228 metropolitan areas and that the total United States population would grow from 200 million in 1960 to 260 million by 1985. Thus, 20 million households would need residences by 1985. Consequently, President Johnson's message to the United States Congress in 1968 called for a new direction in the housing program. In his message to Congress, President Johnson emphasized the need to start and rehabilitate an average of 2.6 million private housing units per annum over the next 10 years. Records of the housing construction industry

in the United States at that time showed the industry had not supplied over 1.5 million housing units per year during the preceding ten years. Thus, a new and faster approach to building construction was urgently needed.

The housing shortage in the United States in 1968 was similar to that of Europe after World War II. Post World War Europe experienced a severe housing shortage, especially for low-income groups.

The European countries' investigation of alternative methods of construction showed precast prestressed concrete systems buildings construction to reduce the cost of materials and labor. In addition, savings in time of construction due to mass production of structural elements was also determined. Thus, United States government agencies and institutions interested in industrialized concrete buildings had to carry out a thorough review of the European experience before developing or even approving most of the systems buildings in use in the United States today.

Development of Concrete

Systems Buildings

Since 1946, the Federal Housing Administration (FHA) which is now part of the United States Department of Housing and Urban Development (HUD) has been involved in the evaluation and acceptance of manufactured and prefabricated housing. The FHA issued Structural Engineering Bulletins (SEB's) since there were no codes guiding this type of construction practice.

Three building systems developed in the North American continent since the 1960's have overcome the many constraints of residential

construction. They provide aesthetically and functionally flexible buildings which are also economically feasible.

Habitat '67, developed in Canada is described by Fuller (8) as "... an exciting architectural utilization of prefabricated modules for residential construction; an escape from the typical staid cracker-box type of system."

Another system developed at approximately the same time was by H. B. Zachry Company of San Antonio, Texas. This was a box module system. A crash program was required involving the use of a checkerboard pattern of modules for the 21 story, 500 room Hilton Palacio del Rio. Construction had to be completed in nine months so the hotel could be ready for occupancy by April, 1968 for the opening of the Hemisfair. The first module was cast on August 15, 1967, while the final module was in place on December 20 of the same year.

The third system's building was developed by the Illinois Institute of Technology Research Institute (IITRI), through a demonstration grant awarded in 1967 by HUD (9). This study included an extensive survey of industrialized building methods used throughout the world. The system selected was a three dimensional open-top, concrete box module similar in concept to the H. B. Zachry System. A ten-story building with 78 apartments was modeled and several box unit models were tested.

Operation Breakthrough

On May 8, 1969, the United States Department of Housing and Urban Development announced a very comprehensive program to encourage industrialized housing concepts in the United States (8). The program,

"Operation Breakthrough" (10, 11), was a total development program to resolve a multitude of problems associated with mass production of quality housing. It was to use modern design technology and contemporary approaches to financing, marketing, land use and management. The major objective of the program was to show that producers of housing in volume could realize economies of scale.

Operation breakthrough consisted of the three main phases listed below:

Phase I: Design phase which required that a precast concrete systems building met all the structural design criteria as specified by HUD.

Phase II: Construction of a structurally sound system. All the construction problems associated with the system were identified and resolved where possible.

Phase III: Private systems building companies were authorized by HUD to produce the systems buildings which had met the requirements of Phase I and Phase II.

Evaluation of European Systems

Realizing the great potential of the United States housing market, some European systems developers soon formed affiliations in this country. In January, 1968, the Cebus System was submitted to HUD, through the sponsorship of Laurel Concrete Products, Inc., Maryland. The Cebus System was designed by Tadjar and Cohen, based on a June 1966 French document "Joint Directives for the Acceptance of Building Systems with Large and Heavy Panels," by Cahiers du Centre Scientifique et Technique du Batiment. On May 29, 1968, HUD issued Structural Engineering Bulletin (SEB) No. 455 to accept the Cebus System.

Other European Systems which were studied by HUD are listed below (12, 13):

1. Balency (Thamesmead Project)
2. Bison (Concrete Limited)
3. Camus (Camus, Gt. Britain, Limited)
4. Coignet (Construction Edmond Coignet)
5. Laing (John Laing Construction Co.)
6. Tracoba (Industrialized Building Systems)
7. Wates (Wates Limited)

The Advantages of Precast, Prestressed Concrete Construction

The development of precast, prestressed concrete construction as a major segment of the construction industry since the 1950's has occurred due to its many advantages (14). One primary advantage is the reduction in formwork costs. Depending on geometrical configuration, size, material, labor, and the number of reuses, the cost of concrete forms vary from 33-1/3% to 60% of the total cost of each cubic yard of reinforced concrete in place. In most precast, prestressed concrete operations, forms can be used many times, thus drastically reducing formwork cost per use. Construction site labor costs can also be very much reduced by precast construction. Fuller (8) notes that construction labor could be reduced by 30 to 50% through the systems building approach. Other advantages of precast, prestressed concrete construction are listed below:

- (1) The use of high tensile strength steel and high compressive strength concrete permits the use of smaller sections and less steel and concrete in prestressed components. Smaller sections also provide smaller dead loads (1).
- (2) The use of high strength materials and the consequent reduction in dead load further extends the scope of use of

precast, prestressed concrete components by making longer spans possible and by substantially increasing the load carrying capacity of members.

- (3) Precasting operations are usually conducted at ground level. This ensures close supervision of placing of concrete so that better quality control is provided.
- (4) In many precast, prestressed concrete plants, precasting operations are accomplished in an enclosure. In such plants, the interruption of production due to bad weather is reduced.
- (5) Reduction in labor costs is one of the major advantages of precast, prestressed concrete construction. Due to mechanization, less labor is required to build precast, prestressed concrete structures than cast-in-place reinforced concrete structures. Fuller (8) noted that in most European countries the construction site labor force can be reduced at least 50% and that box-type building systems in the U.S.S.R. showed a reduction as high as 80%.
- (6) In the construction industry, reduction in time usually results in reduction of costs. A fast construction procedure provides at least three advantages:
 - (i) Banks and other financial institutions show more interest for financial support for a construction project using such a procedure.
 - (ii) Early completion of a facility to allow early use of it for rental property, a hotel or a restaurant could result in early recovery of a substantial part of the invested capital.
 - (iii) Early completion of a project financed by borrowed money would normally reduce the interest costs. The literature on precast, prestressed concrete construction is replete with accounts of its savings in construction time (14, 15, 16, 17, 18, 19, 20, 21).

Some Historic and Current Problems Associated with Precast, Prestressed Concrete Construction

The availability of adequate lifting and transportation equipment was one of the problems associated with early precast concrete construction. Although the use of fewer heavier precast components reduces

handling and erection labor, a precast component may not be heavier than the capacity of the largest available lifting and transportation equipment. Since heavy and economical equipments were not always available, the sizes of precast components were often limited.

Precast, prestressed concrete structures generally require extra design effort and a higher level of competency in structural design than ordinary reinforced concrete structures. Connections for precast, prestressed concrete structures require very careful design. In addition, every phase of the precast, prestressed concrete construction process must be programmed into a coordinated sequence of activities.

Lack of Uniformity among Design Codes

The absence of appropriate building codes and design standards has also retarded the progress of precast, prestressed concrete construction. Building codes differ from one political subdivision to another. For example, on the issue of live load requirements, D'Arcy (22) noted that in Oak Brook, Illinois, the code requirement for live load was 50 lbs per square foot which could be reduced for large supporting members down to 35 lbs per square foot. In the geographically close cities of Milwaukee and Chicago, a design for a superimposed live load of 75 lbs per square foot was required. Thus in a 90 mile radius, the specified design load in one area requires over twice the amount in another area for identical forms of loading. This lack of uniformity in live load design requirements forces the manufacturer of precast concrete components to assume the strictest code requirements within his marketing area. The assumption of the strictest code requirements tends to escalate the cost of precast

concrete components and thereby reduce their popularity among contractors and builders.

Conflicting Highway Requirements on the Weight and Dimensions of Precast Members

The transportation of precast concrete components to erection sites is subject to many regulations regarding the use of the highway. Stringent transportation regulations tend to limit the sizes of precast concrete components and consequently the ability of a manufacturer to service an optimum marketing area. Various states have differing limitations on the widths of loads which can be allowed on the highway. A manufacturer of precast components in any one state may be confronted with different restrictions in adjoining states within his marketing area. Shipping widths as large as eight feet are generally permitted in all state and interstate highways. However, this eight feet upper limit can be extended up to 10 feet, 12 feet and even up to 14 feet in some states or among cities within the same state.

Most states allow lengths as large as 55 feet without special permit while others require that any length larger than 55 feet have special permit and escorts front and back and to limit travel to certain times of the day. Other states require only a simple permit for lengths larger than 70 feet.

Other limitations usually imposed on the transportation of precast concrete components are load limits and height limits. Although the general load limit is 20 tons to 22 tons, some states allow loads as large as 100 tons. A gross height (including height of truck and load) of 13 feet 6 inches can be transported without permit in some states

while others place a maximum limit at 12 feet.

The lack of uniformity among codes makes the standardization of precast concrete components difficult. Standardization can increase the scope of application of precast concrete components and even enhance the expansion of the marketing area of a components manufacturer. Standardization can also reduce the cost of concrete forms. In an Engineering News Record (ENR) report (14), it was noted that if form manufacturers could follow a single pattern for any particular item for all customers, the cost of forms would decrease by 20%. Limiting the sizes of components increases the number of pieces required to construct a structure. Handling and erection labor, the number of joints and the quantity of materials needed to seal the joints, as well as the design effort, all increase with increase in the number of pieces. The result is an increase in the cost of a precast concrete structure, thus making it less competitive with other methods of construction.

Transportation cost is another problem associated with precast concrete building construction. Fuller (8) counsels that transportation distances be kept to a minimum, preferably to a maximum travel of one day round trips. Travel distances longer than one day round trips result in excessive transportation costs.

Some Economic Considerations in the Planning of a Concrete Systems Building Enterprise

One of the requirements for the success of a concrete systems building company is the existence of a large market to insure a large scale of production. Reliable market data which can distinguish

between need and effective demand (23) must be accumulated before initiating a systems building enterprise. Reliable marketing information should state the number of building contracts that can be placed with the building industry. A systems building company should secure some contract agreement to insure adequate production volume for a reasonable time in the immediate future.

Concrete systems operations require high investments in manufacturing and transporting equipment. Unless a systems building company can be assured large production volume and continuity, high investments in equipment may not be economically justifiable.

Most concrete systems building companies in the United States use steel forms in their plant operations. These steel forms generally last from three and one-half to four years. Since the geometry of the forms affects both the aesthetic appeal and the manufacturing and handling problems associated with precast concrete components, it becomes an economic requirement for a concrete systems company to exercise sound judgement in the choice of forms.

Different geometrical shapes have different structural properties which affect the cost of the precast concrete components differently. Bryan (24) notes that in the United States, the double tee is being displaced by hollow core slabs for spans less than 30 feet. In selecting members for longer spans, Bryan states that for spans under 80 feet the deep double tee is preferred over the single tee.

The local construction requirements as well as the management of the construction resources within the precasting plant affect different geometrical shapes in different ways. This is why experts in the precast concrete construction industry have conflicting views on the

economics of certain geometrical shapes or modules. For instance, Fuller (8), a structural engineer for HUD-FHA, states that box-module systems have the most difficulty in sustaining long-term success. On the contrary, the Illinois Institute of Technology Research Institute (IITRI) concluded from a HUD-sponsored research project (9) that box-like modular systems were the ultimate solution to the United States housing shortage problem. A survey conducted by the ENR showed that the double tee was the United States precast concrete "... industry's bread and butter product" (14). Dr. Gifford (25) of Concrete Limited, Great Britain, who disagrees with the ENR survey (14) has this to say about double tees:

A particular point which has always intrigued the author, and on which he would welcome comments, is the complete absence of double tees from Concrete Limited's products as sold--and the virtual absence of double tees as competition--various firms have, and some still do, make these units but they in no way are serious competition; we offer the unit but even on very large contracts it has never met the grade;

Since views differ on the economics of certain geometrical shapes, the selection of concrete forms for a new concrete systems building enterprise should be made only after a thorough evaluation of the local construction and structural problems affecting the economics of all geometrical shapes which are candidates for selection.

CHAPTER III

APPLICATIONS OF LINEAR PROGRAMMING TO CIVIL ENGINEERING PROBLEMS

Linear Programming (LP) is one of the most widely used mathematical decision tools in the optimization of scarce and valuable resources. Dantzig shows that before 1947 it was unknown although Fourier may have recognized its potential in 1823 (3). Its popular acceptance as a mathematical decision tool since 1947 is due to the following factors:

1. The development of electronic computers which reduce the computational burden required of manual solution of large sets of mathematical equations.
2. The development of the simplex algorithm by Dantzig.

Since the late 1950's, the interest of Civil Engineers in linear programming has grown very rapidly. This interest has been demonstrated by the publication of numerous research papers in which linear programming has been used to solve a wide range of optimization problems in Civil Engineering practice. Structural Engineering, Engineering Mechanics, Traffic Engineering, Hydraulics and Hydrology, and to a much less degree, Construction Management, are among the areas of Civil Engineering in which many realistic optimization problems have been solved using linear programming techniques.

This chapter reviews the literature relating to the applications

of linear programming in the various areas of Civil Engineering. The inertia of the construction industry towards a popular adoption of quantitative management techniques is also discussed.

Romstad and Wang (26) and Moses (27) used linear programming to optimize the design of framed structures such as trusses, continuous beams and rigid frames. The objective of their linear programming model was to minimize the weight of the designed structure, subject to all allowable stress and displacement requirements. The computerized solution technique to the LP model is iterative. Thus, from a given solution, the solution variables are computed and used subsequently to modify the design parameters from a preceding acceptable solution to minimize the total weight of the structure. The iterations are terminated when no more significant reductions in the overall weight of the structure can be realized by additional iterations.

Reinschmidt and Norabhoompipat (28) and Farshi and Schmit (29) also studied the problem of optimizing the design of framed structures from the viewpoint of a global optimum. Farshi and Schmit demonstrated that the linear programming approach, when applied to a limited class of structures and failure modes, does offer an opportunity to obtain the global optimum design. Reinschmidt and Norabhoompipat proved that the linear programming optimization technique is a satisfactory method for seeking global optimums of structural design optimization problems.

Grierson and Gladwel (30) have presented a kinematic approach to the collapse load analysis of framed structures using linear programming. The object of the analysis was to determine the smallest load factor for which a collapse mechanism forms, subject to the following requirements:

1. The bending moments at every critical section of the structure are in equilibrium with the factored loads.
2. A sufficient number of plastic hinges have formed at the critical sections to transform the whole structure, or any part of it, into a collapse mechanism.
3. The fully plastic moment is not exceeded at any critical section of the structure. Consideration of all possible combinations of elementary mechanisms and hence, all possible collapse modes, was essential to the analysis.

Baldur (31) has demonstrated the application of an iterative method of optimizing a nonlinear multidimensional objective function subject to nonlinear inequality constraints to the design of structures. The method uses a sequence of linearized programs technique. The iterative procedure converges to the final point through a series of intermediate solutions in the feasible design hyperspace, which are least critical in regard to the linearized boundaries. Every cycle of the iterative method solves a linear programming model problem. No transformations of the original problem specifications are required, thus allowing the engineer to exercise practical and intuitive judgement on the results during any stage of the solution process.

Cohn et al. (32) treated the analysis and design of plastic frames subjected to fixed, alternative and shake down loadings, as a linear programming problem. Both static and kinematic approaches were used in the analysis.

Abdel et al. (33) and Cohn and Rafay (34) have presented a linear programming formulation of second order collapse load analysis of elastic-plastic frames. In addition to the requirements of the

analytic technique used by Grierson and Gladwel (30), the method used by Abdel (33) further includes the following:

1. The influence of axial forces on plastic moment capacities and on member flexibilities,
2. The secondary moments created through the interaction of axial forces and deformations.

The solution method is iterative and starts from an upper-bound estimate to the failure load, with the solution to the problem being either equal to or a lower-bound estimate of the true failure load.

The Cohn and Rafay (34) model also uses linear and nonlinear programming techniques in conjunction with linearized and curvilinear yield conditions, respectively.

Kalinowski and Pilkey (35) have presented a deterministic, linear programming formulation of the problem of designing for incompletely prescribed dynamic loading. The Kalinowski formulation treats both steady-state vibrations and transient systems in which the structural equations of motion are linear. The computational procedure is iterative with the analysis at each iteration being a worst disturbance analysis.

Thakkar (36) formulated the design of non-cylinder composite prestressed concrete pressure pipes as a linear programming problem. The objective of the design was to minimize the cost of the pipes, subject to transient loading and possible service load combinations.

Many problems associated with the control of traffic in street network systems and inter-state highway designs have been investigated using LP models.

Killin (37) presented a general method by which linear programming

may be applied to traffic estimation relating to interchange design. The LP model was based on a case study of the proposed interchange of the Federal Aid Interstate Route (F.A.I.) 03 with U.S. 50 near Seymour, Indiana. The desire to make a traffic movement was given a weight. The objective function expression was the linear sum of the products of these weights and the corresponding traffic volumes which make the movements. The objective function was maximized to yield the maximum traffic flow through the interchange. A lower bound was specified for the volume of traffic making any one of the possible movements.

Pinnel and Satterly (38) applied a linear programming model, the multi-copy missing model, developed by A. Charnes and W. W. Cooper, to the solution of the problem of arterial street analysis. The freeway volume was held at or below a fixed amount and thence developed the resulting optimum flow which was used to illustrate the LP formulation.

Wattleworth and Shuldiner (39) have demonstrated the application of linear programming to the assignment of traffic to routes in a network when the origins and destinations of the trips are known. An example of a network is presented on which no capacity restraint is placed on any of the links. An intersection model that permits time penalties to be assigned to individual turning maneuvers within the intersection was also presented. Charnes and Cooper (40, 41) have given a linear programming formulation of the traffic assignment problem in which capacity restraints on any set of links, in addition to the origin-destination requirements, may be satisfied.

Many papers involving the optimization of water supply systems by linear programming have also been published since the late 1960's. In 1969, Gupta (42) analysed a water pipe line system with a single

source of supply. He formulated various combinations of pipe sizes and used a linear programming model to select the combination that minimizes the cost of pipe lines, subject to the requirements that customer demand for water usage and supply pressure be satisfied. Case and White (43) solved the same problem as Gupta but made specific provisions for the head losses in both the objective function expression and in the constraint inequalities.

Gupta, et al. (44) designed an optimum water distribution system using linear programming. This later formulation differs from the earlier work of Gupta (42) in that multiple supply points were used. Also the later paper uses an analogy of electrical network theory along with an algorithm developed in the paper. A water pipe line system with two supply sources were used to illustrate the LP formulation.

Yeh and Becker (45) applied linear programming to the parameter identification problem for unsteady open channel flow. They combined the linear programming with the influence coefficient technique.

Stephenson (46) has demonstrated a method of planning complex water resources projects using the principle of decomposition of linear programs. He used the Vaal and Tugela River Basins in South Africa as illustrative examples. A linear programming model was formulated for each river basin, and links between basins were incorporated in a master program. The objectives of the LP formulations were to optimize electric power plant capacity, reservoir capacities, and a water distribution pattern. The basin programs as well as the master program were solved successively numerous times before an optimum solution was obtained.

The Attitude of the Construction Industry to Mathematical Models

The indictment of the construction industry for lack of growth in productivity is well documented in the literature (47, 48, 49, 50, 51, 52). Invariably, a concomitant of this indictment is the enumeration of suspect factors which are claimed to be partly responsible for this lack of growth in productivity. For instance, the construction industry is traditionally unenthusiastic about the use of mathematical models even where such models have been known to yield substantial managerial and financial advantages (53).

In order to determine the attitude of the construction industry for the use of mathematical models, a survey of 23 construction firms was conducted by Adrian (47). The survey revealed a widespread lack of faith in mathematical models by members of the construction industry. Although 23 construction firms is not an accurate representation of the entire construction industry, the findings shown below indicate a slow acceptance of mathematical models.

The survey revealed that models such as tables for estimation of construction quantities were the most popular among the contractors covered in the survey. In fact, over 60% of the contractors used estimating models or tables of quantities. Network models which were used by over 43% of the contractors was second in popularity to estimating tables of quantities. The survey also revealed that network models were used more as project planning tools than as method models. Linear programming was used by only two of the 23 firms interviewed in the survey.

Some of the reasons given by the contractors for this lack of faith in mathematical models were the following (47):

1. Contractors' lack of knowledge of models and their applications.
2. Contractors' belief that models were inappropriate in their application to the construction industry.
3. Contractors' fear that the cost of implementing a model would exceed its benefits.
4. Contractors' fear that the models would conflict with union work rules and industry practices.

In 1965, Robinson (54) conducted a survey of 500 (mostly small) general contractors to evaluate their attitude towards the use of the critical path method (CPM). The survey showed that these companies were, in general, not using CPM and concluded that CPM use in the industry was concentrated almost exclusively among a relatively small number of large construction firms with annual volumes of construction over \$10,000,000.

A decade after Robinson's survey, Davis (53) surveyed the top 400 U.S. construction firms to ascertain CPM use in those firms. The survey showed that not all those large companies were using network methods. The reasons given for the non-use of CPM were very similar to those already stated in Adrian's survey (47).

The author is persuaded that as contractors become more familiar with mathematical models and as the models become better adapted to the needs of the construction industry, the popularity of these models among construction contractors will grow. However, the diversity of the construction business and the great disparity in the levels of

training of construction contractors will continue to be impediments to the popular adoption of mathematical models, at least for some time.

Linear Programming Applications in Construction Management

The remainder of this chapter presents brief summaries of linear programming applications in construction management.

A linear programming (LP) formulation of the project critical path network problem has been published by Charnes and Cooper (55), using network flow principles. Specifically, the formulation starts with a project precedence diagram, having activities on arrows. The project activities constitute the decision variables and the estimated mean activities' durations are the objective function coefficients of the decision variables.

Constraint equations are established by applying Kirchoff's law at every intermediate node. This implies that the algebraic sum of the flows in and out of every intermediate node is equal to zero. A unit positive flow is considered to be incident on the first node and a unit negative flow is assumed to flow out of the last node.

A maximum value of the objective function is then obtained to yield the project network critical path.

The Charnes, Cooper LP model has been applied to the time - cost trade-off problem of a project critical path network (56, 57, 58). However, much simpler techniques for computing the critical path and the necessary project network statistics have been well documented in the literature (59, 60, 61).

The bidding problem has been formulated as a linear programming

problem by Stark (62). The objective of the formulation was to maximize the present worth of all expected future revenue accruing from payments on completed portions of a construction project, subject to the following three constraints:

1. The Bid Amount Constraint
2. The Unit Bid Constraints
3. The Rate Payment Constraints.

Upper and lower bounds were imposed on the values of the unit bid quantities. The Stark LP model has been published by Mayer et al. (63).

Ritter and Shaffer (64) treated the problem of blending natural earth deposits for granular embankment or base course in highway construction, as an LP problem. A solution to the LP model yields the quantities of each available natural earth deposit to be blended to produce the desired material at least cost to the constructor. An actual blending problem involving granular materials was used to demonstrate the use of the LP model.

A very interesting application of linear programming to the problem of planning a highway grading operation has been presented by Shaffer (65). The objective of the LP model was to determine which items of earth moving equipment in any selected contractor's equipment spread should be used on a grading operation. In addition, the LP model was to determine the combinations of equipment that should be used, when, where, and for what lengths of time the equipment should be used, in order to perform the grading operation on any project for the least total cost. Shaffer used a hypothetical, small-scale grading project to explain and demonstrate the necessary formulations. The

hypothetical problem included:

- a. The earthwork quantity
- b. Equipment combinations
- c. Available equipment times
- d. Capital restrictions
- e. Project completion time.

The extensive review of literature in this chapter shows that linear programming is a versatile optimization technique. However, it is not a cure-all for every optimization problem in Civil Engineering practice. To apply it to most practical problems, one needs to acquire a thorough understanding of the problem to be modelled as well as the techniques of LP formulation.

The next two chapters of this treatise discuss the problem of selecting precast concrete components for a precast concrete systems building company, by linear programming. Both the LP model formulation and its application to the operations of an existing precast concrete systems building company are demonstrated.

CHAPTER IV

MODEL FORMULATION

Introduction

A precast concrete systems building company, the Progressive Concrete Company (PCC), wants to select precast concrete forms to be installed at a new plant location. The company can afford to purchase only a limited number of steel forms.

The cost of a completed building is influenced very much by the geometry of the forms. Therefore, in order to remain competitive, the company needs to invest money only in those geometrical shapes which will ensure a minimum cost for a completed building.

The objective of the linear programming study is to select optimum combination(s) of steel forms which will enable the firm to satisfy the widest possible market for precast concrete systems buildings and precast concrete shapes, and which will ensure that the firm remains competitive. Since the PCC's systems buildings consist of seven major categories of precast components: floor, roof, wall, beam, center service core, stair and stair landing, there must be one form for each category. The PCC management planning problem is to select which forms in each category will produce the lowest cost building, taking into account highway load requirements, local building codes, and construction labor union contractual agreements.

In addition to taking full cognizance of all significant

construction requirements at the area of the plant location, the solution to the linear programming model must accomplish the following:

1. Select the combination(s) of precast, prestressed concrete components which are the most economical for the PCC to manufacture at the chosen plant location.
2. Verify if the increase in the story height of a building affects the selection of the most economical combination(s).
3. Since the PCC may sometimes transport its precast concrete components hundreds of miles away from their precasting plant, to establish the influence, if any, which the distance of a building from the precasting plant has on the selection of the most economical combination(s).

For purposes of applying quantitative techniques to the solution of the PCC management problem, and also accomplishing the above three objectives, it was necessary to categorize the types of precast concrete systems buildings which were candidates for selection. The bases for categorization were height (number of stories) and distance from the precasting concrete plant. Five heights were considered: 1, 2, 3, 4, or 5 stories, and three distances: up to 75 miles, 75 miles to 150 miles, 150 up to 225 miles. Since there are five story heights and three distances, there are 15 categories of buildings for which solutions were obtained.

For each of the 15 categories of buildings, a linear programming model was formulated. Linear constraint functions were formulated to represent limitations on the following: Prestressing Steel Tendons (number of lineal feet); Reinforcing Steel Bars (number of pounds); Types of Concrete (cubic yards); Concrete Blocks (number of blocks in

the building); Plant Labor (number of man hours in precasting the concrete); Erection Labor (number of man hours in erecting both the block walls and precast wall panels); Number of Truck Loads to transport the precast concrete components to the erection site. The decision variables of the LP models were derived from 48 different combinations of precast, prestressed concrete components, each combination including a type of precast concrete component from each of the seven major categories of precast components. Each LP model was solved as a cost minimization.

Results were obtained in two stages for each of the 15 building categories by formulating four different LP models for each category, or 60 LP solutions in all. For each of the 15 categories of buildings an LP was formulated in which three optimal combinations had to be selected. Subsequently, the selection of optimal combinations was limited to one selection. This was repeated two more times, thus providing a ranking (1st, 2nd and 3rd choices) of the three most optimal combinations for each of the 15 categories of buildings.

Formulation of Decision Variables

To formulate the decision variables, all precast, prestressed concrete components that constitute the systems buildings are classified into the following groups:

- Wall
- Floor
- Beam
- Center Core
- Roof
- Stair Landing
- Stair Frame.

Since each of these groups perform a definite function in the

building, they will be designated as functional groups. Table I illustrates the relationship between functional groups and precast concrete components used by the PCC.

TABLE I
FUNCTIONAL GROUPS AND THEIR PRECAST
CONCRETE COMPONENTS

Functional Group No. Name	Precast Concrete Components
1 Wall	Double Tee Wall Panel, Flat Wall Panel, Blocks and Accessories
2 Floor	Double Tee Floor Slab, Flat Floor Slab
3 Beam	L-Beam, Rectangular Beam
4 Center Core	Core Wall Panel, Core Box
5 Roof	Double Tee Roof Slab, Flat Roof Slab
6 Stair Landing	Stair Landing
7 Stair Frame	Stair Frame

A functional group must contain at least two alternative precast concrete components before those components can be relevant to the model formulation. All precast concrete components which belong to the same functional group are said to be mutually exclusive alternatives. This means that in combining the components to make up a building, one and

only one member of a functional group may belong to such a combination. Furthermore, a combination is deemed to be complete only if it incorporates one relevant precast concrete component from each functional group which has relevant components.

Table I shows that Stair Frame is the only member of the functional group named "Stair Frame". Since it is the only member of that functional group it is irrelevant to the analysis to follow. In contrast, Flat Floor Slabs and Double Tee Floor Slabs which all belong to the same functional group named "Floor" are mutually exclusive alternatives and are therefore relevant to the model development.

A building alternative is a combination of relevant precast concrete components formed with one component coming from each and every functional group possessing relevant components. In addition, a building alternative which is further identified by its story height and its distance in miles from the precasting plant of the PCC is named a decision variable.

There are five functional groups in Table I which have mutually exclusive precast concrete components. Since components can be chosen only one at a time from all five functional groups to form a combination, it follows that there are:

$$(NPC_1)(NPC_2)---(NPC_r)---(NPC_5)$$

combinations (building alternatives), where:

$$NPC_r = \text{Number of Precast Concrete components in a functional group } r.$$

$$r = 1, ---, 5.$$

Furthermore, there are:

$$(NPC_1)(NPC_2)(NPC_3)(NPC_4)(NPC_5) \cdot H \cdot L$$

decision variables, where

H = the total number of story heights studied in the investigation,

= 5.

L = the total number of building locations used in the model formulation,

= 3.

Implicit in the above formulation is the assumption that every building alternative and decision variable meet all the structural design and construction requirements at the given plant location.

A Mathematical Statement of the Linear Programming Model

A mathematical statement of the linear programming model follows presently:

$$\text{Minimize: } \sum_{j=1}^n c_j x_j$$

$$\text{Subject to: } \sum_{j=1}^n a_{ij} x_j \leq b_i, \quad i = 1, \dots, m$$

$$x_j \geq 0, \quad j = 1, \dots, n.$$

$$x_j \text{ is integer.}$$

where:

c_j = the total plant cost plus transportation and erection costs of all precast concrete components used in the decision variable j .

x_j = a decision variable j .

n = the total number of decision variables.

a_{ij} = the amount of resource i required to make all precast components in a decision variable j .

b_j = the total available quantity b , of a resource type i .

m = the total number of resources used in the model formulation.

: means \leq , $=$, \geq .

The linear sum,

$$\sum_{j=1}^n C_j X_j,$$

is called the objective function or the merit function. It is a mathematical statement of the criterion on which the decision to select a decision variable is based. The decision to select any decision variable X_j is subject to the requirements that all the inequalities and equations: $\sum_{j=1}^n C_j X_j$, the constraint functions, be satisfied. Both the merit function and the constraint functions are linear. There are m linear constraint functions used in the model. In the sequel, the words equations and inequalities will be used interchangeably unless there is need for a more specific usage.

It is significant to note that in the mathematical statement of the model, all the decision variables are constrained to take on only integer values. A linear programming model in which all decision variables must take on only integer values is named an integer linear programming (ILP) model. If some, but not all of the decision variables are integer, then the LP model is named a mixed integer linear programming (MILP) model. The LP model developed in this treatise is an ILP model.

Many managerial planning and decision problems involving choices between alternatives require that "yes-no", or "go-no-go" decisions be made regarding the alternatives. Capital budgeting, plant location,

critical path scheduling with resource constraints, are among such decision problems. The art and science of linear programming have developed the techniques for formulating such decision problems as ILP problems. The decision variables X_j of such problems are invariably subject to the requirement that:

$$X_j = \begin{cases} 1 & \text{if alternative } j \text{ is chosen} \\ 0 & \text{otherwise.} \end{cases}$$

The decision variables of the model developed in the present investigation are constrained to be "zero or one" only. Decision variables of this type are oftentimes called "zero-one" variables. Furthermore, the name "dummy" variables (66) is frequently used to emphasize the fact that these variables serve only as indicators as to whether or not particular alternatives are chosen or rejected.

CHAPTER V

MODEL VALIDATION

The model formulation presented in Chapter IV is now applied to the operations of an actual precast concrete systems building company, the Progressive Concrete Company (PCC). Since the model is being adapted to an already existing precast concrete systems building company, only those operational constraints which are relevant to the operational circumstances of the PCC are included in the formulated model.

A table of functional groups and their respective precast concrete components as they exist in the PCC is first presented. This presentation is then followed by a formulation of all distinct building alternatives.

Functional Groups and Precast Concrete Components

There are seven functional groups which are used by the PCC. Only five of the seven functional groups have at least two precast concrete components. Members of groups six and seven shown in Table II do not contain more than one precast concrete component and will not be used in the present validation analysis.

TABLE II
FUNCTIONAL GROUPS AND THEIR PRECAST
CONCRETE COMPONENTS

Functional Group		Precast Concrete Components
No.	Name	
1	Wall	Double Tee Wall Panel, Flat Wall Panel, Blocks and Accessories
2	Floor	Double Tee Floor Slab, Flat Floor Slab
3	Beam	L-Beam, Rectangular Beam
4	Center Core	Core Wall Panel, Core Box
5	Roof	Double Tee Roof Slab, Flat Roof Slab
6	Stair Landing	Stair Landing
7	Stair Frame	Stair Frame

The following symbols will be used to represent the precast concrete components which make up a building alternative

DTWP = Double Tee Wall Panel

FWP = Flat wall panel

CB = Concrete Blocks, Concrete Block Beams, and Columns which are used with block walls

DTFS = Double Tee Floor Slab

FFS = Flat Floor Slab

LB = L-Beam

RB = Rectangular Beam

CW = Central Core Wall Panel


BOX = Central Core Box
 DTRS = Double Tee Roof Slab
 FRS = Flat Roof Slab
 SL = Stair Landing
 SF = Stair Frame

There are a total of $(3)(2)(2)(2)(2) = 48$ building alternatives.

All the building alternatives and their relevant precast concrete components are presented in Table III.

Decision Variables Representation

A decision variable is a building alternative which has been identified by its story height and location. A typical notation for a decision variable is shown below.



For the decision variable X_jhL

$j = 1, 2, \dots, 48$

= The serial number shown in Table III, of the building alternative from which the decision variable was formulated.

h = Story height of the building alternative from which the decision variable was formulated.

$= 1, 2, \dots, 5.$

TABLE III
BUILDING ALTERNATIVES AND THEIR RELEVANT
PRECAST CONCRETE COMPONENTS

Building Alternative	Relevant Precast Concrete Components	Building Alternative	Relevant Precast Concrete Components
X1	DTWP, DTFS, LB, CW, DTRS	X25	DTWP, DTFS, LB, CW, FRS
X2	DTWP, DTFS, LB, BOX, DTRS	X26	DTWP, DTFS, LB, BOX, FRS
X3	DTWP, DTFS, RB, CW, DTRS	X27	DTWP, DTFS, RB, CW, FRS
X4	DTWP, DTFM, RB, BOX, DTRS	X28	DTWP, DTFS, RB, BOX, FRS
X5	DTWP, FFS, LB, CW, DTRS	X29	DTWP, FFS, LB, CW, FRS
X6	DTWP, FFS, LB, BOX, DTRS	X30	DTWP, FFS, LB, BOX, FRS
X7	DTWP, FFS, RB, CW, DTRS	X31	DTWP, FFS, RB, CW, FRS
X8	DTWP, FFS, RB, BOX, DTRS	X32	DTWP, FFS, RB, BOX, FRS
X9	FWP, DTFS, LB, CW, DTRS	X33	FWP, DTFS, LB, CW, FRS
X10	FWP, DTFS, LB, BOX, DTRS	X34	FWP, DTFS, LB, BOX, FRS
X11	FWP, DTFS, RB, CW, DTRS	X35	FWP, DTFS, RB, CW, FRS
X12	FWP, DFFS, RB, BOX, DTRS	X36	FWP, DTFS, RB, BOX, FRS
X13	FWP, FFS, LB, CW, DTRS	X37	FWP, FFS, LB, CW, FRS
X14	FWP, FFS, LB, BOX, DTRS	X38	FWP, FFS, LB, BOX, FRS
X15	FWP, FFS, RB, CW, DTRS	X39	FWP, FFS, LB, CW, FRS
X16	FWP, FFS, RB, BOX, DTRS	X40	FWP, FFS, RB, BOX, FRS
X17	CB, DTFS, LB, CW, DTRS	X41	CB, DTFS, LB, CW, FRS
X18	CB, DTFS, LB, BOX, DTRS	X42	CB, DTFS, LB, BOX, FRS
X19	CB, DTFS, RB, CW, DTRS	X43	CB, DTFS, RB, CW, FRS
X20	CB, DTFS, RB, BOX, DTRS	X44	CB, DTFS, RB, BOX, FRS
X21	CB, FFS, LB, CW, DTRS	X45	CB, FFS, LB, CW, FRS
X22	CB, FFS, LB, BOX, DTRS	X46	CB, FFS, LB, BOX, FRS
X23	CB, FFS, RB, CW, DTRS	X47	CB, FFS, RB, CW, FRS
X24	CB, FFS, RB, BOX, DTRS	X48	CB, FFS, RB, BOX, FRS

L = location of the building alternative

= 1, 2, 3.

The relationship between the location, L, of a building alternative and the distance in miles of that building alternative from the PCC's precast concrete plant is shown in Table IV.

TABLE IV

RELATIONSHIP BETWEEN THE LOCATION, L,
AND THE DISTANCE IN MILES OF A
BUILDING ALTERNATIVE

Location, L.	Distance in Miles of a Building Alternative From the PCC's Precast Concrete Plant
1	75
2	150
3	225


A decision variable designated as X4543 denotes a serial number of 45 as shown in Table III, is four stories tall, and 225 miles away from the PCC's precast concrete plant.

Since there are two precast concrete components which are used in the construction of floors, and since the floors of one story building alternatives are on grade, it follows that there are

48 x 5 x 3 - 3 x 24 decision variables,
 = 648 decision variables to be used in the model validation.

Row Names Representation

The objective function row and the constraint constant for every constraint function is given a definite name. These names denote the type of resource the constraint constants designate and also the serial numbers of the constraint rows in which the constants are represented. However, the objective function row named "COST", has no serial row number attached to it. A typical designation of a row name or a constraint constant is shown below.



In the above designation, PS denotes prestressing steel tendons with $i=1$. This implies that constraint row No.1 or constraint equation No.1 is based on prestressing steel tendons and is designated as PS1. A complete listing of all the row names used in the model are listed in Table V.

There are a total of 14 rows used in the model as shown in Table V. However, all, except the first row, the objective function row, represent the constraint equations or inequalities.

Table V could be expanded more than its present length. There should be a constraint row for every distinct resource used by the concrete company whose operational data are being used to validate

TABLE V
ROW NAMES AND THE RESOURCES
THEY REPRESENT

Row Name	Type of Resource Represented in the Row	Constraint Equation No.
COST	Objective Function	None
PS1	Prestressing Steel Tendons	1
RB2	Reinforcing Steel Bars	2
WM3	Wire Mesh Type I	3
WM4	Wire Mesh Type II	4
WM5	Wire Mesh Type III	5
CN6	Concrete Type I	6
CN7	Concrete Type II	7
CN8	Concrete Type III	8
PL9	Plant Labor	9
EL10	Erection Labor for Concrete Components other than Block Walls	10
ELB11	Erection Labor for Concrete Block Walls	11
WLR12	Weight Limit Requirement, in Truck Loads	12
CR13	Choice Requirements	13

the model. Furthermore, all other operational constraints which are known to affect the plant, transportation, and erection operations of the company, should be represented by a distinct constraint row as shown in Table V. All resources or constraints pertaining to the PCC's operations are listed in Table V.

Decision Variable Coefficient Computation

There are three types of decision variable coefficients involved in the model validation. The first type includes the objective function coefficients and the constraint function coefficients. The Weight Limit Requirement (WLR12) and the Choice Requirement (CR13) constraint function coefficients are excluded from coefficients of the first type for several reasons. Decision variable coefficients of the first type are computed by the direct summation of the amounts of the resources associated with the precast concrete components which constitute the decision variable. The coefficients of the decision variables for the Weight Limit Constraint (WLR12) belong to the second type of coefficients. The type three coefficients of decision variables pertain to the Choice Requirement (CR13) constraint. They are computed simply by assigning a value of one to each of them.

The following is a typical example of how the decision variable coefficients of the first type are computed using prestressing steel tendons, PS1 and the usual plan dimensions (108 feet by 108 feet) of the PCC's concrete systems building. The material quantities for prestressing steel tendons are now computed. The data for this and other computations of decision variable coefficients are obtained from Table X in Appendix A.

$$\begin{aligned}
 \text{Perimeter of building} &= 4 (108 \text{ feet} - 0 \text{ inch}) \\
 &= 432 \text{ feet} - 0 \text{ inch} \\
 \text{Width of DTWP} &= 8 \text{ feet} - 0 \text{ inch} \\
 \text{Perimeter Length per DTWP,} \\
 \text{allowing } 3' - 0'' \text{ for windows} &= 8 \text{ feet} - 0 \text{ inch} + 3 \text{ feet} - \\
 &\quad 0 \text{ inch} \\
 &= 11 \text{ feet} - 0 \text{ inch} \\
 \text{Therefore DTWP/story height} &= 432 \div 11 \text{ panels} \\
 &= 39.273 \text{ panels} \\
 &= 40 \text{ panels/story} \\
 \text{Story height - floor to floor} &= 12 \text{ feet, using L-Beams} \\
 &= 14 \text{ feet, using Rectangular Beams} \\
 \text{Total length of DTWP/story height} &= 40 \times 12 \text{ feet (for 12 feet wall} \\
 &\quad \text{height)} \\
 &= 480 \text{ feet} \\
 &\quad \text{or} \\
 &= 40 \times 14 \text{ feet (for 14 feet wall} \\
 &\quad \text{height)} \\
 &= 560 \text{ feet/story}
 \end{aligned}$$

Flat Wall Panel (FWP)

A similar computation for FWP is also made to obtain the total length of FWP per story height.

Hence:

$$\begin{aligned}
 \text{Total length of FWP} &= 432 \text{ feet, using L-Beams} \\
 &= 504 \text{ feet, using Rectangular Beams.}
 \end{aligned}$$

For every other constraint equation (function), a table similar to

Table VI is computed and presented in Tables XI through XXI in Appendix B. In Table VI and in the tables in Appendix B, if two quantities of a given resource are tabulated for a precast concrete component and a story height, the upper quantity stands for a 12 feet wall height, while the lower quantity represents the quantity for a 14 feet wall height. A value of zero in Table VI and in all the tables of Appendix B implies that the precast concrete component does not use prestressing steel tendons or the particular resource at the indicated floor (story height), or not at all. The units of the quantities of each type of resource are stated in each table.

The computation of the coefficient of a decision variable for the constraint equation PS1 is now illustrated, using the data from the column headed "1st Floor" in Table VI and the information in Table III. For the decision variable X1411, we establish from Table III that X14 is composed of FWP, FFS, LB, BOX, DTRS. When the lengths of prestressing steel tendons used in the precast components that constitute X14 are added the following can be obtained:

$$\begin{aligned}
 \sum_{k=1}^{kk} M_k(i,j) &= \sum_{k=1}^3 M_k(1,14) \\
 &= 388 + 0 + 2160 + 0 + 5488 \\
 &= 11536 \text{ feet, where}
 \end{aligned}$$

$M_k(i,j)$ = quantity (feet) of the material (prestressing steel tendons-PS) i , required to build the relevant precast concrete component k , in a decision variable j (=14 in this example).

kk = total number of relevant precast concrete

TABLE VI
PRESTRESSING STEEL REQUIREMENTS (PSI)

Member Description	Quantities Feet Consumed Per Floor				
	1st Floor	2nd Floor	3rd Floor	4th Floor	5th Floor
(1) Double Tee Wall Panels	4800 5600	9600 11200	14400 16800	19200 22400	24000 28000
(2) Flat Wall Panels	3888 4536	7776 9072	11664 13608	1552 18144	19440 22680
(3) Block and Block Beams	0	0	0	0	0
(4) Columns to go with Blocks	1920 2240	3840 4480	5760 6720	7680 8960	9600 11200
(5) Double Tee Floor Members	0	8232	16464	24696	32928
(6) Flat Floor Slabs	0	16464	32928	49392	65856
(7) L-Beams	2160	4320	6480	8640	10800
(8) Rectangular Beams	2160	4320	6480	8640	10800
(9) Core Wall Panels	0 0	0 0	0 0	0 0	0 0
(10) Boxes for Ser. Core	0 0	0 0	0 0	0 0	0 0
(11) Double Tee Roof Members	5488	5488	5488	5488	5488
(12) Flat Roof Slabs	13720	13720	13720	13720	13720

components in the decision variable j ,
utilizing the material i .

= 3 in this illustration.

Since $\sum_{k=1}^{kk} M_k(i, j) = 11536$, the coefficient of X_{1411} in the constraint row PS1 is 11536. This is the procedure used to compute all the coefficients of the first type both in the objective function and in the constraint equations.

General Requirements for Decision Variable Coefficients

There are two criteria which must be satisfied by every term in a constraint equation or in the objective function expression:

1. Every coefficient of a decision variable in a constraint equation must be capable of direct conversion into cost by multiplying such a coefficient by a constant numerical quantity which may be unique for each constraint equation.
2. The terms in a constraint equation or in the objective function must be dimensionally homogeneous. This criterion demands that the product of a decision variable and its coefficient for any specified constraint equation be expressed in precisely the same dimensions as the dimensions of the resource quantity on the right hand side of the constraint equation. In the case of objective function terms, each product must be numerically equal to a value of United States dollars.

The transportation of different precast concrete components along

the highway is affected differently by highway use requirements. Thus a particular truck used to transport different precast concrete components may be considered fully loaded either because of its gross weight or because of the total height of the truck and its load. Other load characteristics can also be the constraining requirements in various realistic circumstances. According to the PCC's transportation arrangements, every precast concrete component, except concrete blocks and center service core boxes, costs \$50 to transport and every truck load costs one dollar per truck load per mile. Thus a truck load of one type of precast concrete component may not cost the same amount of dollars as a truck load of a different type of precast concrete component. These cost differences are illustrated in Figures 4, 5, and 6.

In order to ensure that the decision variable coefficients in the constraint equation pertaining to truck loads (the weight limit constraint WLR12), have the same unit cost, it has been necessary to convert every coefficient in the WLR12 constraint onto the same cost basis by using a conversion factor.

At every location the conversion factor for a truck load of a particular precast concrete component is unique. It is affected by the following:

1. The distance of travel or location, since every truck load of every type of precast concrete component, except concrete blocks, costs one dollar per mile.
2. The number of pieces of precast concrete components per truck load.
3. The cost of that truck load which costs the least for a given location.




Figure 4. Transportation Cost of Different Precast Concrete Components for the First 75 Miles from the Precasting Plant




Figure 5. Transportation Cost of Different Precast Concrete Components for the First 150 Miles from the Precasting Plant




Figure 6. Transportation Cost of Different Precast Concrete Components for the First 225 Miles from the Precasting Plant

Once the conversion factor has been applied to the truck loads of every type of precast concrete component, the decision variable coefficients of the second type can then be computed.

Computation of Conversion Factors for Truck Loads at First Location

The conversion factors for a typical location are computed by establishing the total number of truck loads and the total transportation cost for each type of precast concrete component to that location. The total transportation cost is then divided by the number of truck loads to obtain the cost per truck load. This computation is made for each type of precast concrete component. The least cost per truck load is used as a basis for comparison to establish the conversion factors.

Hence, the conversion factor CF_i for a precast concrete component i at a specified location is stated mathematically as follows:

$$CF_i = \frac{CTL_i}{LCTL}, \text{ where}$$

CTL_i = the cost per truck load of precast concrete component i at a specified location.

$LCTL$ = the least cost per truck load up to the specified location.

It should be noted that $CF_i = 1$ if the cost per truck load of precast component i is the least cost per truck load at the particular location. The results of these computations for the first location are presented in Table VII. Where two values are tabulated in any one column in Table VII and Table VIII, the upper value refers to 12 feet tall wall

TABLE VII
SUMMARY OF COMPUTATION OF CONVERSION FACTORS
FOR THE FIRST LOCATION

Precast Concrete Component	Total Transportation Cost, 1st Story	Truck Loads Before Conversion for 1st Story	Cost Per Truck Load	Conversion Factor	Converted Truck Load
Double Tee Wall Panel	\$2450 \$2525	6 7	\$408.33 \$360.71	6.842 6.044	41 43
Flat Wall Panel	\$2475 \$2475	4 4	\$275.00 \$275.00	4.61	19 19
Concrete Block	\$357.98 \$417.76	6 7	\$59.63 \$59.68	1 1	6 7
Columns to go with Block	\$2150	2	\$1075	18	36
Double Tee Floor Member	\$2700	10	\$270	4.524	46
Flat Floor Slab	\$3375	19	\$177.63	2.976	57
L-Beam	\$525	3	\$175	2.932	9
Rectangular Beam	\$525	3	\$175	2.932	9
Core Wall Panel	\$500	4	\$125	2.095	9
Box	\$500	4	\$125	2.095	9
Double Tee Roof Member	\$2700	10	\$270	4.524	46
Flat Roof Slab	\$3375	19	\$177.63	2.976	57

TABLE VIII

SUMMARY OF CONVERSION FACTORS AND CONVERTED TRUCK LOADS
FOR THE FIRST, SECOND, AND THIRD LOCATIONS

Precast Concrete Component	Conversion Factors			Conversion Factors		
	1st Location	2nd Location	3rd Location	1st Location	2nd Location	3rd Location
Double- Tee Wall Panel	6.842 6.044	6.36 5.73	6.07 5.55	41 43	39 41	37 39
Flat Wall Panel	4.61 4.61	4.61 4.61	4.62 4.62	42 42	42 42	42 42
Concrete Block	1 1	1 1	1 1	6 7	6 7	6 7
Column With Block	18	15.13	13.32	36	31	27
Double- Tee Floor Member	4.52	4.54	4.57	46	46	46
Flat Floor Slab	2.98	3.32	3.56	57	64	68
L-Beam	2.93	3.29	3.53	9	10	11
Rectangu- lar Beam	2.93	3.29	3.53	9	10	11
Core Wall Panel	2.09	2.63	2.99	9	11	12
Core Service Box	2.09	2.63	2.99	9	11	12
Double Tee Roof Member	4.52	4.54	4.57	46	46	46
Flat Roof Slab	2.98	3.32	3.56	57	64	68

while the lower value is for the 14 feet tall wall. Conversion factors for all three locations are summarized in Table VIII. The data used to compute the conversion factors for the second and third locations are presented in Appendix C.

The Need for Solving the Problem by Many ILP Models

During the verification of the ILP model developed in this treatise, 648 distinct decision variables were formulated. Because of the following reasons, it was necessary to divide the model into 15 distinct models corresponding to 15 categories of buildings.

1. Each of the 15 categories of buildings corresponds to a specific story height at a specific location.
2. Construction materials used in different story heights did not vary linearly from one-story-tall buildings to five-story-tall buildings. This non-linear relationship is illustrated in Figure 8.

Computerized Solution to the Linear Programming Models

The IBM (International Business Machines) computer program package, MPSX360 (Mathematical Programming Systems Extended-360) provided the computerized solutions to the 15 LP models (67, 68). The MPSX360 program package solved each of the 15 ILP model problems in two stages. In the first stage, all the decision variables were assumed to be non-integer (continuous). The problems were then solved using the Revised Simplex Method. Many texts on linear programming by Dantzig (3),




Figure 7. Rate of Consumption of a Typical Resource by Functional Groups

Locks (66), and Zionts (69) have good illustrative problems on the Revised Simplex Method. In the second stage of the solution process, a method, the Branch and Bound algorithm, was used to obtain an integer solution from the solution of the first stage.

The Branch and Bound algorithm was introduced by Land and Doig (70). Again the texts on linear programming by Dantzig (3), Locks (66), Zionts (69), Wagner (71), have good examples on the Branch and Bound algorithm.

CHAPTER VI

SELECTION AND RANKING OF OPTIMAL COMBINATIONS

The objective of the analysis was to select the best building alternatives for each category of building. In the process, linear programming was used in such a way as to provide information on the relative desirability of different combinations, and to rank them for planning purposes.

For each of the 15 categories of buildings (combinations of specified story heights up to five story heights, plus a distance from the plant: up to 75 miles, 75-150 miles, 150-225 miles), LP models to select optimum combinations of precast concrete components which make up building alternatives (combinations of relevant precast concrete components, with one type of relevant precast concrete component from each of the seven functional groups), were solved in two stages. In the first stage, three alternatives were obtained as the best choices for that category by using a linear programming model which allowed the selection of up to three building alternatives. Since the objective of the project is to obtain optimal combinations of precast concrete components and to establish the relative desirability of the combinations, further uses were made with a model which restricted the choice to one. It was necessary to choose three optimal alternatives for each of the 15 categories of buildings because

in some cases, a feasible linear programming model allowing the choice of one building alternative could not be found.

In the "best three" runs, for each of the 12 constraint functions, the right hand side (RHS) constraint constants which set limitations on Prestressing Steel Tendons, Reinforcing Steel Bars, etc., were set at such levels as would permit up to three choices of alternatives. For the "best one" runs, the RHS constants were set so that only one alternative is feasible. Thus both the lower and upper limits for the RHS constants in the "best three" models are approximately three times as large as they are in the "best one" models. Three "best one" models were solved for each of the 15 categories of buildings, to make the further ranking of "best" (1st choice), "second best" (2nd choice) and "third best" (3rd choice). In general, it was found that only the "best" (1st choice) alternatives were relevant, and the second and third choices were insignificant.

In this chapter, the results of all the 60 computer runs are presented. First, the "best three" choices for each of the 15 categories of buildings are shown in Figures 8 through 13. Following these is Table IX which contains a summary of all the "best three" and all the "best", "second best" and "third best" building alternatives, and the precast concrete components which constitute them.

The building alternatives X1, X2, X26 were the only combinations which were members of the 1st choices for all of the 60 runs.

Optimal Concrete Components Recommended for Concrete Systems Buildings Development

It is significant to note that certain geometrical shapes are

NODE	2	NODE	1	NODE	5
FUNCTIONAL	150024.0000	FUNCTIONAL	151565.0000	FUNCTIONAL	158574.0000
ESTIMATION	INTEGER	ESTIMATION	INTEGER	ESTIMATION	INTEGER
15= X0111	1.0000	15= X0112	1.0000	15= X0113	1.0000
16= X0211	1.0000	16= X0212	1.0000	16= X0213	1.0000
17= X0311	.	17= X0312	.	17= X0313	.
18= X0411	.	18= X0412	.	18= X0413	.
19= X0911	.	19= X0912	.	19= X0913	.
20= X1011	.	20= X1012	.	20= X1013	.
21= X1111	.	21= X1112	.	21= X1113	.
22= X1211	.	22= X1212	.	22= X1213	.
23= X1711	.	23= X1712	.	23= X1713	.
24= X1811	.	24= X1812	.	24= X1813	.
25= X1911	.	25= X1912	.	25= X1913	.
26= X2011	.	26= X2012	.	26= X2013	.
27= X2511	.	27= X2512	.	27= X2513	.
28= X2611	1.0000	28= X2612	1.0000	28= X2613	1.0000
29= X2711	.	29= X2712	.	29= X2713	.
30= X2811	.	30= X2812	.	30= X2813	.
31= X3311	.	31= X3312	.	31= X3313	.
32= X3411	.	32= X3412	.	32= X3413	.
33= X3511	.	33= X3512	.	33= X3513	.
34= X3611	.	34= X3612	.	34= X3613	.
35= X4111	.	35= X4112	.	35= X4113	.
36= X4211	.	36= X4212	.	36= X4213	.
37= X4311	.	37= X4312	.	37= X4313	.
38= X4411	.	38= X4412	.	38= X4413	.

(a) First Location (b) Second Location (c) Third Location

Figure 8. Selection of the Three Most Optimal Combinations for the First Story Height at Three Locations

NODE	1	NODE	93
FUNCTIONAL	304360.0000	FUNCTIONAL	334773.0000
ESTIMATION	INTEGER	ESTIMATION	INTEGER
15= X0121	1.0000	15= X0123	.
16= X0221	1.0000	16= X0223	1.0000
17= X0321	.	17= X0323	.
18= X0421	.	18= X0423	.
19= X0521	.	19= X0523	.
20= X0621	.	20= X0623	.
21= X0721	.	21= X0723	.
22= X0821	.	22= X0823	.
23= X0921	.	23= X0923	.
24= X1021	.	24= X1023	.
25= X1121	.	25= X1123	.
26= X1221	.	26= X1223	.
27= X1321	.	27= X1323	.
28= X1421	.	28= X1423	.
29= X1521	.	29= X1523	.
30= X1621	.	30= X1623	.
31= X1721	.	31= X1723	.
32= X1821	.	32= X1823	.
33= X1921	.	33= X1923	.
34= X2021	.	34= X2023	.
35= X2121	.	35= X2123	.
36= X2221	.	36= X2223	.
37= X2321	.	37= X2323	.
38= X2421	.	38= X2423	.
39= X2521	1.0000	39= X2523	.
40= X2621	.	40= X2623	.
41= X2721	.	41= X2723	.
42= X2821	.	42= X2823	.
43= X2921	.	43= X2923	1.0000
44= X3021	.	44= X3023	1.0000
45= X3121	.	45= X3123	.
46= X3221	.	46= X3223	.
47= X3321	.	47= X3323	.
48= X3421	.	48= X3423	.
49= X3521	.	49= X3523	.
50= X3621	.	50= X3623	.
51= X3721	.	51= X3723	.
52= X3821	.	52= X3823	.
53= X3921	.	53= X3923	.
54= X4021	.	54= X4023	.
55= X4121	.	55= X4123	.
56= X4221	.	56= X4223	.
57= X4321	.	57= X4323	.
58= X4421	.	58= X4423	.
59= X4521	.	59= X4523	.
60= X4621	.	60= X4623	.
61= X4721	.	61= X4723	.
62= X4821	.	62= X4823	.

(a) First Location

(b) Third Location

Figure 9. Selection of the Three Most Optimal Combinations up to the Second Story Height at Two Locations

INTEGER NODES			
NODE	4	100	110
FUNCTIONAL	317437.0000	316777.0000	316777.0000
ESTIMATION	INTEGER	INTEGER	INTEGER
15= X0122	.	1.0000	1.0000
16= X0222	1.0000	.	1.0000
17= X0322	1.0000	1.0000	.
18= X0422	.	.	.
19= X0522	.	.	.
20= X0622	1.0000	.	.
21= X0722	.	.	.
22= X0822	.	.	.
23= X0922	.	.	.
24= X1022	.	.	.
25= X1122	.	.	.
26= X1222	.	.	.
27= X1322	.	.	.
28= X1422	.	.	.
29= X1522	.	.	.
30= X1622	.	.	.
31= X1722	.	.	.
32= X1822	.	.	.
33= X1922	.	.	.
34= X2022	.	.	.
35= X2122	.	.	.
36= X2222	.	.	.
37= X2322	.	.	.
38= X2422	.	.	.
39= X2522	.	.	.
40= X2622	.	1.0000	.
41= X2722	.	.	1.0000
42= X2822	.	.	.
43= X2922	.	.	.
44= X3022	.	.	.
45= X3122	.	.	.
46= X3222	.	.	.
47= X3322	.	.	.
48= X3422	.	.	.
49= X3522	.	.	.
50= X3622	.	.	.
51= X3722	.	.	.
52= X3822	.	.	.
53= X3922	.	.	.
54= X4022	.	.	.
55= X4122	.	.	.
56= X4222	.	.	.
57= X4322	.	.	.
58= X4422	.	.	.
59= X4522	.	.	.
60= X4622	.	.	.
61= X4722	.	.	.
62= X4822	.	.	.

Figure 10. Selection of the Three Most Optimal Combinations up to the Second Story Height at the Second Location

NODE		NODE		NODE	
1		4		1	
FUNCTIONAL		FUNCTIONAL		FUNCTIONAL	
465243.0000		480385.0000		467843.0000	
ESTIMATION		ESTIMATION		ESTIMATION	
INTEGER		INTEGER		INTEGER	
15= X0131	1.0000	15= X0132	1.0000	15= X0133	1.0000
16= X0231	.	16= X0232	1.0000	16= X0233	.
17= X0331	.	17= X0332	.	17= X0333	.
18= X0431	.	18= X0432	.	18= X0433	.
19= X0531	.	19= X0532	.	19= X0533	.
20= X0631	.	20= X0632	.	20= X0633	.
21= X0731	.	21= X0732	.	21= X0733	.
22= X0831	.	22= X0832	.	22= X0833	.
23= X0931	.	23= X0932	.	23= X0933	.
24= X1031	.	24= X1032	.	24= X1033	.
25= X1131	.	25= X1132	.	25= X1133	.
26= X1231	.	26= X1232	.	26= X1233	.
27= X1331	.	27= X1332	.	27= X1333	.
28= X1431	.	28= X1432	.	28= X1433	.
29= X1531	.	29= X1532	.	29= X1533	.
30= X1631	.	30= X1632	.	30= X1633	.
31= X1731	.	31= X1732	.	31= X1733	.
32= X1831	.	32= X1832	.	32= X1833	.
33= X1931	.	33= X1932	.	33= X1933	.
34= X2031	.	34= X2032	.	34= X2033	.
35= X2131	.	35= X2132	.	35= X2133	.
36= X2231	.	36= X2232	.	36= X2233	.
37= X2331	.	37= X2332	.	37= X2333	.
38= X2431	1.0000	38= X2432	.	38= X2433	.
39= X2531	1.0000	39= X2532	.	39= X2533	1.0000
40= X2631	.	40= X2632	.	40= X2633	1.0000
41= X2731	.	41= X2732	.	41= X2733	.
42= X2831	.	42= X2832	.	42= X2833	.
43= X2931	.	43= X2932	.	43= X2933	.
44= X3031	.	44= X3032	1.0000	44= X3033	.
45= X3131	.	45= X3132	.	45= X3133	.
46= X3231	.	46= X3232	.	46= X3233	.
47= X3331	.	47= X3332	.	47= X3333	.
48= X3431	.	48= X3432	.	48= X3433	.
49= X3531	.	49= X3532	.	49= X3533	.
50= X3631	.	50= X3632	.	50= X3633	.
51= X3731	.	51= X3732	.	51= X3733	.
52= X3831	.	52= X3832	.	52= X3833	.
53= X3931	.	53= X3932	.	53= X3933	.
54= X4031	.	54= X4032	.	54= X4033	.
55= X4131	.	55= X4132	.	55= X4133	.
56= X4231	.	56= X4232	.	56= X4233	.
57= X4331	.	57= X4332	.	57= X4333	.
58= X4431	.	58= X4432	.	58= X4433	.
59= X4531	.	59= X4532	.	59= X4533	.
60= X4631	.	60= X4632	.	60= X4633	.
61= X4731	.	61= X4732	.	61= X4733	.
62= X4831	.	62= X4832	.	62= X4833	.

(a) First Location

(b) Second Location

(c) Third Location

Figure 11. Selection of the Three Most Optimal Combinations up to the Third Story Height at Three Locations

NODE	10	NODE	14	NODE	24
FUNCTIONAL	623413.0000	FUNCTIONAL	638313.0000	FUNCTIONAL	654013.0000
ESTIMATION	INTEGER	ESTIMATION	INTEGER	ESTIMATION	INTEGER
15= X0141	1.0000	15= X0142	1.0000	15= X0143	1.0000
16= X0241	1.0000	16= X0242	1.0000	16= X0243	1.0000
17= X0341	.	17= X0342	.	17= X0343	.
18= X0441	.	18= X0442	.	18= X0443	.
19= X0541	.	19= X0542	.	19= X0543	.
20= X0641	.	20= X0642	.	20= X0643	.
21= X0741	.	21= X0742	.	21= X0743	.
22= X0841	.	22= X0842	.	22= X0843	.
23= X0941	.	23= X0942	.	23= X0943	.
24= X1041	1.0000	24= X1042	1.0000	24= X1043	1.0000
25= X1141	.	25= X1142	.	25= X1143	.
26= X1241	.	26= X1242	.	26= X1243	.
27= X1341	.	27= X1342	.	27= X1343	.
28= X1441	.	28= X1442	.	28= X1443	.
29= X1541	.	29= X1542	.	29= X1543	.
30= X1641	.	30= X1642	.	30= X1643	.
31= X1741	.	31= X1742	.	31= X1743	.
32= X1841	.	32= X1842	.	32= X1843	.
33= X1941	.	33= X1942	.	33= X1943	.
34= X2041	.	34= X2042	.	34= X2043	.
35= X2141	.	35= X2142	.	35= X2143	.
36= X2241	.	36= X2242	.	36= X2243	.
37= X2341	.	37= X2342	.	37= X2343	.
38= X2441	.	38= X2442	.	38= X2443	.
39= X2541	.	39= X2542	.	39= X2543	.
40= X2641	.	40= X2642	.	40= X2643	.
41= X2741	.	41= X2742	.	41= X2743	.
42= X2841	.	42= X2842	.	42= X2843	.
43= X2941	.	43= X2942	.	43= X2943	.
44= X3041	.	44= X3042	.	44= X3043	.
45= X3141	.	45= X3142	.	45= X3143	.
46= X3241	.	46= X3242	.	46= X3243	.
47= X3341	.	47= X3342	.	47= X3343	.
48= X3441	.	48= X3442	.	48= X3443	.
49= X3541	.	49= X3542	.	49= X3543	.
50= X3641	.	50= X3642	.	50= X3643	.
51= X3741	.	51= X3742	.	51= X3743	.
52= X3841	.	52= X3842	.	52= X3843	.
53= X3941	.	53= X3942	.	53= X3943	.
54= X4041	.	54= X4042	.	54= X4043	.
55= X4141	.	55= X4142	.	55= X4143	.
56= X4241	.	56= X4242	.	56= X4243	.
57= X4341	.	57= X4342	.	57= X4343	.
58= X4441	.	58= X4442	.	58= X4443	.
59= X4541	.	59= X4542	.	59= X4543	.
60= X4641	.	60= X4642	.	60= X4643	.
61= X4741	.	61= X4742	.	61= X4743	.
62= X4841	.	62= X4842	.	62= X4843	.

(a) First Location

(b) Second Location

(c) Third Location

Figure 12. Selection of the Three Most Optimal Combinations up to the Fourth Story Height at Three Locations

FUNCTIONAL	773414.0000	FUNCTIONAL	792093.0000	FUNCTIONAL	810714.0000
ESTIMATION	INTEGER	ESTIMATION	INTEGER	ESTIMATION	INTEGER
15= X0151	1.0000	15= X0152	1.0000	15= X0153	1.0000
16= X0251	1.0000	16= X0252	1.0000	16= X0253	1.0000
17= X0351	.	17= X0352	.	17= X0353	.
18= X0451	.	18= X0452	.	18= X0453	.
19= X0551	.	19= X0552	.	19= X0553	.
20= X0651	.	20= X0652	.	20= X0653	.
21= X0751	.	21= X0752	.	21= X0753	.
22= X0851	.	22= X0852	.	22= X0853	.
23= X0951	.	23= X0952	.	23= X0953	.
24= X1051	.	24= X1052	.	24= X1053	.
25= X1151	.	25= X1152	.	25= X1153	.
26= X1251	.	26= X1252	.	26= X1253	.
27= X1351	.	27= X1352	.	27= X1353	.
28= X1451	.	28= X1452	.	28= X1453	.
29= X1551	.	29= X1552	.	29= X1553	.
30= X1651	.	30= X1652	.	30= X1653	.
31= X1751	.	31= X1752	.	31= X1753	.
32= X1851	.	32= X1852	.	32= X1853	.
33= X1951	.	33= X1952	.	33= X1953	.
34= X2051	.	34= X2052	.	34= X2053	.
35= X2151	.	35= X2152	.	35= X2153	.
36= X2251	.	36= X2252	.	36= X2253	.
37= X2351	.	37= X2352	.	37= X2353	.
38= X2451	.	38= X2452	.	38= X2453	.
39= X2551	.	39= X2552	.	39= X2553	.
40= X2651	1.0000	40= X2652	1.0000	40= X2653	1.0000
41= X2751	.	41= X2752	.	41= X2753	.
42= X2851	.	42= X2852	.	42= X2853	.
43= X2951	.	43= X2952	.	43= X2953	.
44= X3051	.	44= X3052	.	44= X3053	.
45= X3151	.	45= X3152	.	45= X3153	.
46= X3251	.	46= X3252	.	46= X3253	.
47= X3351	.	47= X3352	.	47= X3353	.
48= X3451	.	48= X3452	.	48= X3453	.
49= X3551	.	49= X3552	.	49= X3553	.
50= X3651	.	50= X3652	.	50= X3653	.
51= X3751	.	51= X3752	.	51= X3753	.
52= X3851	.	52= X3852	.	52= X3853	.
53= X3951	.	53= X3952	.	53= X3953	.
54= X4051	.	54= X4052	.	54= X4053	.
55= X4151	.	55= X4152	.	55= X4153	.
56= X4251	.	56= X4252	.	56= X4253	.
57= X4351	.	57= X4352	.	57= X4353	.
58= X4451	.	58= X4452	.	58= X4453	.
59= X4551	.	59= X4552	.	59= X4553	.
60= X4651	.	60= X4652	.	60= X4653	.
61= X4751	.	61= X4752	.	61= X4753	.
62= X4851	.	62= X4852	.	62= X4853	.

(a) First Location

(b) Second Location

(c) Third Location

Figure 13. Selection of the Three Most Optimal Combinations
up to the Fifth Story at Three Locations

TABLE IX
SUMMARY OF SELECTIONS AND THEIR PRECAST CONCRETE COMPONENTS

Combination	No. of Times Selected as:				Precast Concrete Components in the Combination
	Member of 3 together	1st Choice	2nd Choice	3rd Choice	
X01	14	4			DTWP, DTFS, LB, CW, DTRS
X02	12	4			DTWP, DTFS, LB, BOX, DTRS
X26	10	3	2		DTWP, DTFS, LB, BOX, FRS
X25	3		6		DTWP, DTFS, LB, CW, FRS
X03			1	3	DTWP, DTFS, RB, CW, DTRS
X04				2	DTWP, DTFM, RB, BOX, DTRS
X06				3	DTWP, FFS, LB, BOX, DTRS
X09				1	FWM, DTFS, LB, CW, DTRS
X10	3		1		FWP, DTFS, LB, BOX, DTRS
X27	1				DTWP, DTFS, RB, CW, FRS
X28	1				DTWP, DTFS, RB, BOX, FRS
X29	1			1	DTWP, FFS, LB, CW, FRS
X30			1		DTWP, FFS, LB, BOX, FRS
Totals:	45	11	11	11	

associated with the 1st choice building alternatives. For instance: DTWP, DTFS, LB, CW, BOX, DTRS, and FRS, constitute the building alternatives X1, X2, and X26.

If the PCC is to operate optimally at its present location, it is recommended that the PCC should invest in the Precast concrete forms needed to make the components in X1, X2, X26. In addition, all the precast concrete components in the functional groups 6 and 7 of Table II, which are needed in all the concrete systems buildings should also be developed.

The Problems Associated with the Solution

(1) It is possible not to obtain an integer solution for a given model, e.g.:

(a) Selection of one combination for the 1st Story at all three locations.

(b) Selection of one combination for the 2nd Story at the 1st location.

(2) The verification depends on accurate historic data. This means that someone who thoroughly understands the construction requirements must be available and able to supply the needed data.

(3) It requires computerized solution.

(4) Long hours of computations must be carried out.

The Advantages of the LP Solution

(1) It gives quantitative answers which compare well with real world experiences in the construction industry (14). It should therefore be used for managerial planning and selection of precast concrete

components for systems buildings.

(2) It is very flexible with respect to environmental or local requirements. It can be expanded to reflect practically any construction requirements at the plant, the highway and the erection site, by way of constraint equations/or inequalities.

This environmental flexibility makes it capable of resolving the contradictions among the views of experts on the economics of certain geometric shapes. It does this by providing tailor-made solutions.

(3) It is capable of up-date as the need arises, by slight changes in the computed coefficients, or by addition or deletion of constraints.

(4) The use of the models as developed does not require any in-depth knowledge of computer programming.

CHAPTER VII

SUMMARY, CONCLUSIONS, AND RECOMMENDATIONS

Summary

The objective of this research was the selection of types of forms for a new plant location considering the most economical and feasible combinations of precast concrete components needed for a concrete systems building. It has shown that by use of integer linear programming, these economical and feasible combinations can be selected for a concrete systems building company and that the chosen combinations can be ranked in the order of their economic advantages. The integer linear programming model developed in the research places emphasis on the importance of environmental requirements by considering all significant requirements in the constraint equations.

The research treated precast concrete plant operations, transportation of the precast concrete components along the highway, and the erection of the components at the building site.

The feasible combinations of precast concrete components for an existing precast concrete systems building company were compared, and the most economical combinations selected for every story height and at each specified distance from the precast concrete plant to the

building site. It was then recommended that those geometric shapes which consistently formed the economical combinations should be used in the company's precast concrete systems buildings.

Conclusions

The following conclusions should be made based on the findings of this research.

1. Environmental requirements for the construction of different precast concrete components affect the economics of these components in different ways. Therefore, one should not expect different precast concrete components to possess the same economic advantages, regardless of the arrangements in the precast concrete plant, and the requirements of the marketing area in which these components are to be sold.

2. Conclusions regarding the economics of any one precast concrete component at any specified environment should not be based on the economics of such an individual piece. It should be based upon the economics of those combinations of individual precast concrete components.

The results of the integer linear programming model agree well with experiences of the concrete systems building company whose operational data were used to verify the model. Of all the candidates for selection, the double-tee featured consistently as the most economical geometric shape. Thus this method of analysis should be useful for the precast concrete industry in this country.

Recommendations

The linear programming models developed in this research can be extended to cover greater story heights than the five story heights used in the model verification. Furthermore, once the most economical and feasible combination(s) have been chosen, the lengths and other physical dimensions of the selected components can be varied to establish the variation of cost with dimensional changes.

The scope of this research can also be extended to include all the design problems and costs associated with the design of each combination of precast concrete components, which is a candidate for selection. This can be achieved by relating the LP models developed in this treatise to the LP models already published in the literature on the optimal design of multistory framed structures by linear programming.

BIBLIOGRAPHY

- (1) Lin, T. Y. Design of Prestressed Concrete Structures. 2nd ed. New York: John Wiley & Sons, Inc., 1963.
- (2) Waddell, Joseph J. "Precast Concrete: Handling and Erection." American Concrete Institute Monograph No. 8 (1974).
- (3) Dantzig, G. B. Linear Programming and Extensions. Princeton: Princeton University Press, 1963.
- (4) Peterson, J. L. "History and Development of Precast Concrete in the United States." Journal of the American Concrete Institute, Vol. 25, No. 6 (Feb., 1954), pp. 477-495.
- (5) Hubbs, Samuel. "Tilt-Up Construction in Western United States." Journal of the American Concrete Institute, Vol. 24, No. 4 (Dec., 1952), pp. 144-1-144-3.
- (6) Libby, James R. Modern Prestressed Concrete. 1st ed. New York: Van Nostrand Reinhold Company, 1971.
- 3 (7) Module Communities, Inc. "The National Housing Picture." Proposal to HUD for use of Tracoba No. 1 System, 1969, pp. 1, 2.
- 5 (8) Fuller, C. Robert. "Industrialized Construction for HUD." ACI Publication SP-48 (1975), pp. 8-33.
- (9) "Application of Component Construction to Multi-Story, Low-Income Housing." Illinois Institute of Technology Research Institute. Final report, IITRI Research No. M6171 for HUD, Vols. I, III (Jan., 1968), p. 275.
- (10) "Operation Breakthrough." U.S. Department of Housing and Urban Development, 1972, p. 26.
- (11) "Feedback-Design and Development of Housing Systems for Operation Breakthrough." Phase I. U.S. Department of Housing and Urban Development. Superintendent of Documents, U.S. Government Printing Office, Washington, D. C., 1973, pp. 3-6, 11.
- (12) "Industrialized Building--A Comparative Analysis of European Experience." U.S. Department of Housing and Urban Development. Division of International Affairs Special Report, April, 1968, pp. 5, 32, 34-40.

- (13) "Building Fabrication--the State of the Art in World Perspective." Office of International Affairs. HUD International Brief No. 14, Washington, D. C. (June, 1972), pp. 2-6.
- 4 (14) "Prestressed Concrete: A 20-Year Success Story Without an End." Engineering News Record (Sept. 28, 1972), pp. 28-33.
- 6 (15) "Oklahoma Precast Concrete Building Assembled in 13 Days." American Concrete Institute Journal, Vol. 72 (Oct., 1975), pp. 521-522.
- 7 (16) Etheridge, D. C. "Precast Concrete Jumbo Key to Rapid Fire Construction." Construction Methods, Vol. 53 (Feb., 1971), pp. 88-92.
- 8 (17) "Sewage Treatment Plants Constructed in Days with Precast Concrete." Civil Engineering, Vol. 40 (Nov., 1970), p. 86.
- 9 (18) "Switch to Precasting Cuts Job Time." Construction Methods, Vol. 52 (Oct., 1970), pp. 78-80.
- 10 (19) "Construction Time Saved by Systems Building." American Concrete Institute Journal, Vol. 68 (May, 1971), pp. 345-347.
- (20) Smith, M. L. "Precasting Boxes Cut Hotel Building Time in Half; San Antonio's Palacio del Rio." Construction Methods, Vol. 50 (Jan., 1968), pp. 58-59.
- (21) "Eleven Stories Up in Ten Weeks." Engineering, Vol. 200 (Nov. 26, 1965), p. 698.
- (22) D'Arcy, Thomas J. "Codes, Specifications, and Regulations." ACI Publication SP-48, 1975, pp. 70-75.
- (23) Davidson, Colin H. "Industrialized Construction--a Commentary." ACI Publication SP-48, 1975, pp. 2-6.
- (24) Bryan, Ross H. "Long Line Production of Building Elements in United States." Proceedings of the American Society of Civil Engineers. Journal of the Construction Division, Vol. 101, No. 1 (March, 1975), pp. 143-153.
- (25) Gifford, F. W. "U. K. Experience with Industrialized Concrete Construction." ACI Publication SP-48-3, 1975, pp. 37-62.
- (26) Romstad, Karl M. and Chu Kia Wang. "Optimum Design of Framed Structures." Proceedings of the American Society of Civil Engineers. Journal of the Structural Engineering Division, Vol. 12, No. 6273 (Dec., 1968), pp. 2817-2845.

- (27) Moses, F. "Optimum Structural Design Using Linear Programming." Proceedings of the American Society of Civil Engineers. Journal of the Structural Engineering Division, Vol. 6, No. 4163 (Dec., 1964), pp. 89-104.
- (28) Reinschmidt, K. R. and T. Norabhoompipat. "Structural Optimization by Equilibrium Linear Programming." Proceedings of the American Society of Civil Engineers. Journal of the Structural Engineering Division, Vol. 4, No. 112191 (Apr., 1975), pp. 921-938.
- (29) Farshi, Behrooz and Lucien A. Schmit, Jr. "Minimum Weight Design of Stress Limited Trusses." Proceedings of the American Society of Civil Engineers. Journal of the Structural Engineering Division, Vol. 1, No. 10259 (Jan., 1974), pp. 97-107.
- (30) Grierson, Donald E. and Graham M. L. Gladwell. "Collapse Load Analysis Using Linear Programming." Proceedings of the American Society of Civil Engineers. Journal of the Structural Engineering Division, Vol. 5, No. 8127 (May, 1971), pp. 1561-1573.
- (31) Baldur, R. "Structural Optimization by Inscribed Hyperspheres." Proceedings of the American Society of Civil Engineers. Journal of the Engineering Mechanics Division, Vol. 3, No. 8934 (June, 1972), pp. 503-518.
- (32) Cohn, M. Z. et al. "Unified Approach to Theory of Plastic Structures." Proceedings of the American Society of Civil Engineers. Journal of the Engineering Mechanics Division, Vol. 5, No. 9246 (Oct., 1972), pp. 1133-1158.
- (33) Abdel, S. B. et al. "Second Order Collapse Load Analysis; LP Approach." Proceedings of the American Society of Civil Engineers. Journal of the Structural Engineering Division, Vol. 11, No. 10128 (Nov., 1973), pp. 2215-2228.
- (34) Cohn, M. A. and T. Rafay. "Collapse Load Analysis of Frames Considering Axial Forces." Proceedings of the American Society of Civil Engineers. Journal of the Engineering Mechanics Division, Vol. 4, No. 10757 (Aug. 10, 1974), pp. 773-794.
- (35) Kalinowski, Anthony J. and Walter D. Pilkey. "Design for Incompletely Prescribed Loading." Proceedings of the American Society of Civil Engineers. Journal of the Engineering Mechanics Division, Vol. 4, No. 11474 (Aug. 17, 1975), pp. 505-510.
- (36) Thakkar, M. C. "Some Studies on Optimization in Concrete Structures." (Unpub. Ph. D. dissertation, South Gujarat University, Surat, India, 1974.)

- (37) Killin, E. L. "Highway Traffic Estimation by Linear Programming." Proceedings of the American Society of Civil Engineers. Journal of the Highway Engineering Division, Vol. 3, No. 2180 (Jan., 1959), pp. 95-98.
- (38) Pinnell, C. and G. T. Satterly, Jr. "Systems Analysis for Arterial Street Operation." Proceedings of the American Society of Civil Engineers. Journal of the Engineering Mechanics Division, Vol. 6, No. 3728 (Dec., 1963), pp. 67-95.
- (39) Wattleworth, Joseph A. and Paul W. Shuldiner. "Left-Turn Penalties in Traffic Assignment Models." Proceedings of the American Society of Civil Engineers. Journal of the Engineering Mechanics Division, Vol. 6, No. 3729 (Dec., 1963), pp. 97-126.
- (40) Charnes, A. and W. W. Cooper. "Extremal Principles for Simulating Traffic Flow Over Network of City Streets." National Academy of Sciences, Proceedings, Vol. 44, No. 2 (Feb., 1958), pp. 75-90.
- (41) Charnes, A. and W. W. Cooper. Management Models and Industrial Applications of Linear Programming. Vol. II. New York: John Wiley and Sons, 1961.
- (42) Gupta, Ishwar. "Linear Programming Analysis of a Water Supply System." American Institute of Industrial Engineers, Transactions, Vol. 1, No. 1 (March, 1969), pp. 56-61.
- (43) Case, Kenneth E. and John A. White. "Linear Programming Formulation of a Water Supply Problem." American Institute of Industrial Engineers, Transactions, Vol. 4, No. 2 (June, 1972), pp. 85-91.
- (44) Gupta, Ishwar et al. "Linear Programming Analysis of Water Supply System with Multiple Supply Points." American Institute of Industrial Engineers, Transactions, Vol. 4, No. 3 (Sept., 1972), pp. 200-204.
- (45) Yeh, W. G. and L. Becker. "Linear Programming and Channel Flow Identification." Proceedings of the American Society of Civil Engineers. Journal of the Hydraulics Division, Vol. 11, No. 10177 (Nov., 1973), pp. 2013-2021.
- (46) Stephenson, David. "Optimum Design of Complex Water Resource Projects." Proceedings of the American Society of Civil Engineers. Journal of the Hydraulics Division, Vol. 6, No. 7320 (June, 1970), pp. 1229-1246.
- (47) Adrian, J. "Modeling Construction Method Productivity." (Unpub. Ph. D. dissertation, University of Illinois at Urbana-Champaign, 1974.)

- (48) "Low Productivity: The Real Sin of High Wages." Engineering News Record (Feb. 24, 1972), pp. 18-23.
- (49) Kendrick, J. W. "Productivity Trends in the United States." A study by the National Bureau of Economic Research. Princeton: Princeton University Press, 1961, pp. 464-498.
- (50) "Pilot Study of Productivity in the Residential Building Trades." Rockville, Maryland: NAHB Research Foundation, 1972, p. 32.
- (51) "First Quarterly Cost Roundup." Engineering News Record (March 22, 1973), pp. 79-86.
- (52) "Union Philosophy Surrounds Productivity Measurement Conference." The Contractor (Nov., 1972), p. 22.
- (53) Davis, Edward W. "CPM Use in Top 400 Construction Firms." American Society of Civil Engineers. Journal of the Construction Division, Vol. 100, No. C01 (March, 1974), pp. 39-49.
- (54) Robinson, M. R. "CPM Surveyed." Building Construction, Vol. 10 (Dec., 1965), pp. 35-37.
- (55) Charnes, A. and W. W. Cooper. "A Network Interpretation and a Directed Subdual Algorithm for Critical Path Scheduling." Journal of Industrial Engineering, Vol. 13, No. 4 (1962), pp. 213-218.
- (56) Meyer, W. L. and L. R. Shaffer. "Extensions of the Critical Path Method Through the Application of Integer Programming." A report by the Department of Civil Engineering, University of Illinois at Urbana, July, 1963.
- (57) Fulkerson, D. R. "A Network Flow Computation for Project Cost Curves." Management Science, Vol. 7, No. 2 (Jan., 1961), pp. 167-179.
- (58) Ford, L. R. and D. R. Fulkerson. Flows in Networks. Princeton: Princeton University Press, 1962.
- (59) Moder, J. J. and Cecil R. Phillips. Project Management with CPM and PERT. 2nd ed. New York: Van Nostrand Reinhold Company, 1970.
- (60) Fondahl, J. W. "Can Contractors' Own Personnel Apply CPM Without Computers." The Constructor, Vol. 3 (Nov., 1961), pp. 56-60, and Vol. 4 (Dec., 1961), pp. 30-35.
- (61) Moder, J. J. "How to do CPM Scheduling Without a Computer." Engineering News Record (March 14, 1963), pp. 30-34.

- (62) Stark, Robert M. "Unbalanced Bidding Models--Theory." Proceedings of the American Society of Civil Engineers. Journal of the Construction Division, Vol. 94, No. 2 (Oct., 1968), pp. 197-209.
- (63) Mayer, Robert H., E. William Fitzgerald, and Robert M. Stark. "Unbalanced Bidding Models--Application." Newark, Delaware: Department of Civil Engineering, University of Delaware, 1967.
- (64) Ritter, J. B. and L. R. Shaffer. "Blending Natural Earth Deposits for Least Cost; Applicability of Linear Programming." Proceedings of the American Society of Civil Engineers. Journal of the Construction Division, Vol. 1, No. 2773 (March, 1961), pp. 39-61.
- (65) Shaffer, L. R. "Planning a Grading Operation for Least Total Cost." Proceedings of the American Society of Civil Engineers. Journal of the Engineering Mechanics Division, Vol. 6, No. 3734 (Dec., 1963), pp. 47-66.
- (66) Locks, Mitchell O. Practical Linear Programming with Computer Applications. 1st ed. North Hollywood, Calif.: Western Periodicals Co., 1974.
- (67) "Mathematical Programming System/360, Version 2, Linear and Separable Programming--User's Manual." IBM Technical Publications Department, GH 20-0476, August, 1974.
- (68) "Mathematical Programming System Extended (MPSX) Mixed Integer Programming (MIP) Program Description." Program No. 594-XM4. IBM Technical Publications Department, SH 20-0908-1, 1974.
- (69) Zions, Stanley. Linear and Integer Programming. Englewood Cliffs, N. J.: Prentice-Hall, Inc., 1974, pp. 87-90, 104-126, 202, 305, and 319.
- (70) Land, A. H. and A. G. Doig. "An Automatic Method of Solving Discrete Programming Problems." Econometrica, Vol. 28 (1960), pp. 497-520.
- (71) Wagner, H. M. Principles of Management Science with Applications to Executive Decisions. Englewood Cliffs, N. J.: Prentice-Hall, Inc., 1970.
- (72) Waespy, Charles Matthew. "An Application of Linear Programming to Minimum Fuel Optimal Control." (Unpub. Ph. D. dissertation, University of California, Los Angeles, 1967.)
- (73) Gomory, R. E. "Outline of an Algorithm for Integer Solutions to Linear Programs." Bulletin of American Mathematics Society, Vol. 64 (1958), pp. 275-278.

- (74) Ballas, Elgon. "An Additive Algorithm for Solving Linear Programs with Zero-One Variables." Operations Research, Vol. 13 (1965), pp. 517-546.
- (75) Glover, F. and S. Zionts. "A Note on the Additive Algorithm of Ballas." Operations Research, Vol. 13 (1965), pp. 546-549.
- (76) Glover, F. "A Multiphased-Dual Algorithm for the Zero-One Integer Programming Problem." Operations Research, Vol. 13 (1965), pp. 879-919.
- (77) Glover, F. Private communication, 1974.
- (78) Giordano, F. "A Heuristic for the Construction of Surrogate Constraints for the Solution of the Linear Zero-One Integer Problem." (Unpub. Ph. D. dissertation, University of Arkansas, 1975.)
- (79) Lewicki, B. "Building with Large Prefabricates." Institute for Building Research (Warsaw, Poland). London: Elsevier Publishing Co., 1966, pp. 9, 22, 59-70.
- (80) Bishop, D. "Large Panel Construction. Housing from the Factory." Proceedings, Cement and Concrete Assoc. Conference, London, Oct., 1962, p. 52.
- (81) Barr, A. W. C. "Systems Building and the Future." The System Builder's Year Book 1969-70. London: the National Federation of Building Trades Employers, 1969, p. 43.
- (82) "Large Panel Structures and Structural Connections in Precast Concrete." Addendum No. 1 to CP116. British Standards Institution, London, 1970.
- (83) Safir, Otto. "Precast Concrete Construction in Canada." Proceedings, Journal of the American Concrete Institute, Vol. 47 (Jan., 1960), pp. 461-467; and Vol. 22, No. 6 (Feb., 1951), pp. 160-170.
- (84) "Precast System Cuts High-Rise Erection Time by One Third." Engineering News Record (Jan., 1976), p. 16.
- (85) Leonhardt, Fritz. "To New Frontiers for Prestressed Concrete Design and Construction." Journal of the Prestressed Concrete Institute, Vol. 2 (Sept./Oct., 1974), pp. 54-69.
- (86) "Prestressing Business Up for Most in '74; Most Look for Equal or More Business in '75." Modern Concrete, Vol. 4 (Jan., 1975), pp. 40-44.
- (87) "Precast System Works Many Ways to Cut Costs." Engineering News Record (May 1, 1975), p. 20.

- (88) Adrian, J. J. Quantitative Methods in Construction Management. New York: Elsevier, 1973.
- (89) National Construction Estimator. Los Angeles: Craftsman Book Company, 1975.
- (90) Walker, Frank R. "The Building Estimator's Reference Book." Chicago: Frank R. Walker Company, 1972.
- (91) Kawal, Donald E. "A Systems Model of a Construction Firm." (Unpub. Ph. D. dissertation, Iowa State University, 1970.)
- (92) Garfinkel, Robert S. and George L. Nemhauser. Integer Programming. New York: John Wiley & Sons, 1972.
- (93) Heady, E. O. et al. "Agricultural Water Allocation, Land Use, and Policy." Proceedings of the American Society of Civil Engineers. Journal of the Hydraulics Division, Vol. 10, No. 10074 (Oct., 1973), pp. 1795-1812.
- (94) Deb, A. K. "Least Cost Design of Branched Pipe Network System." Proceedings of the American Society of Civil Engineers. Journal of the Environmental Engineering Division, Vol. 4, No. 10711 (Aug., 1974), pp. 821-835.
- (95) Downing, P. B. "Economic Analysis of Periodic Vehicle Inspection Programs." Atmospheric Environment, Vol. 7 (Dec., 1973), pp. 1237-1246.
- (96) Aguado, E. and I. Remson. "Ground Water Hydraulics in Aquifer Management." Proceedings of the American Society of Civil Engineers. Journal of the Hydraulics Division, Vol. 1, No. 10287 (Jan., 1974), pp. 103-118.
- (97) Moses, F. and S. Onoda. "Minimum Weight Design of Structures with Application to Elastic Grillage." International Institute for Numerical Methods in Engineering, Vol. 1 (1969), pp. 311-331.
- (98) Wattleworth, J. A. "Capacity Analysis Technique for Highway Junctions." Traffic Engineering, Vol. 42 (June, 1972), pp. 30-60.
- (99) Foster, B. B. "Linear Programming: A Method of Determining Least Cost Blends or Mixes in Paper Making." Tappi, Vol. 52 (Sept., 1969), pp. 1658-1660.
- (100) Chan, H. S. Y. "Foulkes Mechanism in Portal Frame Design for Alternative Loads." Journal of Applied Mechanics, Vol. 36 (March, 1969), pp. 73-75.
- (101) ReVelle, C. S. et al. "Management Model for Water Quality Control." Journal of the Water Pollution Control Federation, Vol. 39 (July, 1967), pp. 1164-1183.

- (102) Charnes, A. et al. "Critical Path Analysis Via Chance Constrained and Stochastic Programming." Operations Research, Vol. 12 (May, 1974), pp. 460-470.
- (103) "House Sections Molded in Factory." Automation, Vol. 22 (June, 1975), p. 13.
- (104) Carr, R. L. and W. L. Meyer. "Planning Construction of Repetitive Building Units." Proceedings of the American Society of Civil Engineers. Journal of the Construction Division, Vol. 3, No. 10812 (Sept., 1974), pp. 403-412.
- (105) Haith, D. A. "Optimum Control of Nitrogen Losses from Land Disposal Areas." Proceedings of the American Society of Civil Engineers. Journal of the Environmental Engineering Division, Vol. 6, No. 10200 (Dec., 1973), pp. 923-937.
- (106) Wesphal, L. C. "Optimal Scheduling of a Satellite Control Network Using Zero-One Linear Programming." Journal of Spacecraft and Rockets, Vol. 11 (Oct., 1974), pp. 731-733.
- (107) Kirshen, P. H. and D. H. Marks. "Screening Model for Storm Water Control." Proceedings of the American Society of Civil Engineers. Journal of the Environmental Engineering Division, Vol. 4, No. 10712 (Aug., 1974), pp. 807-820.
- (108) Waddel, J. J. "Precast Concrete: Handling and Erection." American Concrete Journal, Vol. 70 (Dec., 1973), pp. 821-22.
- (109) Pilarski, L. "Worldwide Construction, Switzerland, Precast Walls, Drop into Place in Six Easy Steps." Construction Methods, Vol. 56 (July, 1974), p. 71.
- (110) "Symposium on Industrialized Concrete Construction." Journal of the American Concrete Institute, Vol. 71, Supplement 15-16 (June, 1974), pp. 675-860.
- (111) "Symposium on Industrialized Concrete Construction." Journal of the American Concrete Institute, Vol. 71, Supplement 4 (Jan., 1974), pp. 500-563.
- (112) Donnelly, W. "Prestressing: A Multi-Faceted Construction Technique; Special Report." Construction Methods, Vol. 54 (Aug., 1972), pp. 73-79.
- (113) "Japanese Apartment Modules Fit in Place Like Chinese Puzzle." Construction Methods, Vol. 54 (Aug., 1972), p. 104.
- (114) Tor, A. A. "Management of Systems Building Projects: What It Means to Architects and Engineers." Architectural Research, Vol. 15 (July, 1972), pp. 141-144.

- (115) Kally, E. "Computerized Planning of the Least Cost Water Distribution Network." Water and Sewage Works, Vol. 119 (Aug. 31, 1972), pp. 121-122.
- (116) Merten, A. G. and C. H. Falkner. "Interactive Computing in Water Quality Management." Journal of the Water Pollution Control Federation, Vol. 44 (Aug., 1972), pp. 1601-1610.
- (117) "North Harvard in Boston: A Concrete Panel System Improves with Age." Architectural Research, Vol. 149 (April, 1971), pp. 120-121.
- (118) Cohn, M. Z. "Precast Concrete Panels Cut Cost of Apartment Complex." Civil Engineering, Vol. 41 (May, 1971), pp. 48-52.
- (119) "Precast Concrete: Uniframe." Plant Engineering, Vol. 24 (Sept. 17, 1970), pp. 99-102.
- (120) Grancher, R. A. "Russians are Coming: With Concrete." Pit and Quarry, Vol. 63 (March, 1971), pp. 109-113.
- (121) Wakabayashi, J. "800-Ton Precast Units Form Dry-Dock Enclosure." Construction Methods, Vol. 51 (Sept., 1969), pp. 98-102.
- (122) "Fabrication, Handling and Erection of Precast Concrete Wall Panels." Journal of the American Concrete Institute, Vol. 67 (April, 1970), pp. 310-340.
- (123) Bennett, W. B., Jr. "Future of Prestressed Concrete." Civil Engineering, Vol. 39 (July, 1969), pp. 41-43.
- (124) "Glass Factory of Large-Scale Precast Units in Amberg, Germany, is a Prototype for Glass Making Plants of the Future." Architectural Research, Vol. 146 (Sept., 1969), pp. 148-150.
- (125) Bates, A. A. "Low-Cost Housing: Is the Soviet Union's Factory-Made Housing the Answer?" Civil Engineering, Vol. 39 (Sept., 1969), pp. 44-48.
- (126) "Modular Units are Cast Flat, Fold into Rooms When Lifted by Crane." Construction Methods, Vol. 51 (Sept., 1969), pp. 112-115.
- (127) Karmeli, D. et al. "Design of Optimal Water Distribution Networks." Proceedings of the American Society of Civil Engineers. Journal of the Traffic Engineering Division, Vol. 1, No. 6130 (Oct., 1968), pp. 1-10.
- (128) Byrne, J. L. and L. G. Proll. "Initializing Geofrion's Implicit Enumeration Algorithm for the Zero-One Linear Programming Problem." Computer Journal, Vol. 12 (Nov., 1969), pp. 381-384.

- (129) Gerald, D. J. "Construction of Habitat '67." Journal of the American Concrete Institute, Vol. 65 (Oct., 1968), pp. 801-810.
- (130) "Quality Standards and Tests for Precast Concrete Wall Panels." Journal of the American Concrete Institute, Vol. 66 (April, 1969), pp. 270-275.
- (131) Drossel, M. R. "Apartment House Rises From Staked Module Deck." Construction Methods, Vol. 50 (May, 1968), pp. 60-61.
- (132) "Prestressed Concrete and Expo '67." Civil Engineering, Vol. 37 (Nov., 1967), pp. 89-90.
- (133) Gillette, R. W. "Precast Boxes Staked to Build 496-Room Hotel in Nine Months for Hemisfair." Civil Engineering, Vol. 38 (March, 1968), pp. 44-47.
- (134) Popovici, M. "Development of Precast, Reinforced, and Prestressed Concrete Elements for Industrial Single Story Buildings in Romania." Journal of the American Concrete Institute, Vol. 64 (Sept., 1967), pp. 547-556.
- (135) "International Prestressing Federation Congress, 5th, Paris, June 11." Engineer, Vol. 222 (July 1, 1966), pp. 8-10.
- (136) Lin, T. Y. "Tall Buildings in Prestressed Concrete." Architectural Research, Vol. 138 (Dec., 1965), pp. 165-170.
- (137) Birkeland, P. W. and H. W. Birkeland. "Connections in Precast Concrete Construction." Journal of the American Concrete Institute, Vol. 63 (March, 1966), pp. 345-368.
- (138) "Czechoslovak Precast Concrete Plants." Engineer, Vol. 221 (Feb. 11, 1966), pp. 260-261.
- (139) Laszlo, G. "Expanding a Prestressed Concrete Plant." Civil Engineering, Vol. 35 (April, 1965), pp. 42-44.
- (140) Hanson, J. A. "Optimum Steam Curing Procedure in Precasting Plants." Journal of the American Concrete Institute, Vol. 60 (Jan., 1963), pp. 75-100.
- (141) Armstrong, R. D. "Algorithm for Zero-One and Mixed Integer Programming." (Unpub. Ph. D. dissertation, University of Massachusetts, 1974.)
- (142) Stanley, William. "Control of River Reservoir System With Sequential Linear Programming: An Out-Line Algorithm." (Unpublished Ph. D. dissertation, University of Waterloo, Canada, 1972.)

- (143) Albert, Chris, Jr. "Application of Integer Programming to Effective Optimum Truck and Shovel Selection in Open Pit Mines." (Unpub. Ph. D. dissertation, University of Utah, 1972.)
- (144) Hughes, T. C. "A Mixed Integer Programming Approach to Planning Multiple Water Supply." (Unpub. Ph. D. dissertation, Utah State University, 1971.)
- (145) Wallace, J. R. "Linear Programming Analysis of River-Basin Analysis." (Unpub. Ph. D. dissertation, Massachusetts Institute of Technology, 1966.)
- (146) Nieswand, George H. "The Conjunctive Use of Surface and Ground Waters in the Mullica River Basin, New Jersey: A Chance Constrained Linear Programming Approach." (Unpub. Ph. D. dissertation, Rutgers University, 1970.)
- (147) Tanaka, Masaru. "A Linear Programming Model for Solid Waste Management." (Unpub. Ph. D. dissertation, North-Western University, 1970.)

APPENDIX A

DATA AS ORIGINALLY COLLECTED FROM THE
PROGRESSIVE CONCRETE COMPANY

TABLE X

PRECAST CONCRETE COMPONENTS AND THE RESOURCES NEEDED FOR THEIR PRODUCTION AND ERECTION

	Double Tee Wall Panel	Flat Wall Panel	Columns with Blocks	Double Tee Floor Slab	Flat Floor Slab	L-Beam	Rectangular Beam	Core Wall Panel	Core Box	Double Tee Roof Slab	Stair Landing	Stair Frame	Flat Roof Slab
All Costs Associated With Plant Production	\$20/lin ft	\$3/sq ft	\$10/lin ft	\$12/lin ft	\$1.85/sq ft \$14.40/lin ft	\$18/lin ft	\$15/lin ft	\$3/sq ft	\$160/lin ft of building height	\$10.50 /ft	\$2.00 /sq ft	\$15/riser riser ht. 7 1/2 in.	\$1.50 /sq ft or \$12/ft
Freight Costs	\$50/piece, \$1/mile/truck load								1 box/truck load, \$50/ box + \$1/ mi time load	\$50/piece, \$1/mile/truck load			
Labor at Plant-- Costing, Handling	4 men /150 ft /day	7 men /1500 ft /day	2 men /4 columns /day	7 men /500 ft /day	5 men /230 ft /day	4 men /100 ft /day	3 men /100 ft /day	7 men /1200 sq ft /day	5 men /box /day	6 men /400 ft /day	2 men /100 sq ft /day	11 men /piece /day	5 men /200 ft /day
Weights	570 lb/ft	70 lb/sq ft	150 lb/ft	335 lb/ft	80 lb/sq ft	525 lb/ft	450 lb/ft	60 lb/sq ft		200 lb/ft	40 lb /sq ft	400 lb /riser	60 lb/sq ft 450 lb/ft
All Costs Associated With Erec- tion	\$125/piece	\$150/piece	\$80/piece	\$50/piece	\$75/piece	\$75/piece	\$75/piece	\$200/piece	\$150 each	\$50 /piece	\$60 /piece	\$60 /piece	\$50 /piece
Erection Labor, 1st Story	6.25 man-hrs /piece	6.5 man-hrs /piece	4.0 man-hrs /piece	2.5 man-hrs /piece	2.50 man-hrs /piece	3.75 man-hrs /piece	3.5 man-hrs /piece	10.0 man-hrs /piece	7.5 man-hrs /piece	2.5 man-hrs /piece	3.0 man-hrs /piece	3.0 man-hrs /piece	2.5 man-hrs /piece
Prestress- ing Steel Tendons	10 ft /ft of panel	9 ft /ft of panel	4 ft /ft of column	6 ft /ft of slab	12 ft /ft of slab	12 ft /ft of beam	12 ft /ft of beam	X*	X	4 ft /ft of slab	X	4.17 ft /riser	10 ft /ft of slab
Reinforc- ing Bars	X	3 lb /ft of panel	11 lb /ft of column	X	X	4 lb /ft of beam	3 lb /ft of beam	2.5 lb /sq ft of panel	25 lb /box	X	2 lb /sq ft	X	X
Wire Mesh, Type I	8 sq ft /ft of L Panel	X	X	8 sq ft /ft of slab	16 sq ft /ft of slab	X	X	X	X	8 sq ft /ft	X	4 sq ft /riser	8 sq ft /ft
Wire Mesh, Type II	2 ft /ft of panel	X	X	20 ft /slab	X	X	X	X	X	20 ft/ft	X	X	X
Wire Mesh, Type III	X	X	X	X	X	X	X	X	612 sq ft /box	X	X	X	X
Concrete, Type I	X	X	X	0.103 crl yd /ft	0.198 crl yd /ft	X	X	.019 crl yd /sq ft	1126 crl yd /box	0.090 cu yd /ft	X	.09 cu yd /riser	0.148 cu yd /ft
Concrete, Type II	0.176 crl yd /ft	0.296 crl yd /ft	0.037 crl yd /ft	X	X	0.130 crl yd /ft	0.111 crl yd /ft	X	X	X	0.012 cu yd /sq ft	X	X

*X means that the precast concrete component does not consume that particular resource.

APPENDIX B

TABLES OF QUANTITIES FOR THE CONSTRAINT EQUATIONS

TABLE XI
REINFORCING STEEL REQUIREMENTS (RB2)

Member Description	Quantities (lb) Consumed				
	Up to First Story	Up to Second Story	Up to Third Story	Up to Fourth Story	Up to Fifth Story
Double Tee Wall Panels	0	0	0	0	0
Flat Wall Panels	1458 1701	2916 3402	4374 5103	5832 6804	7290 8505
Blocks	2565 2993	5130 5986	7695 8979	10260 11972	12825 14965
Columns to go with Blocks	5280 6160	10560 12320	15840 18480	21120 24640	26400 30800
Double Tee Floor Members	0	0	0	0	0
Flat Floor Slabs	0	0	0	0	0
L-Beams	720	1440	2160	2880	3600
Rectangular Beams	720	1440	2160	2880	3600
Core Wall Panels	6320 7373	12640 14745	18960 22118	25280 29490	31600 36863
Boxes for Service Core	100 100	200 200	300 300	400 400	500 500
Double Tee Roof Members	0	0	0	0	0
Flat Roof Slabs	0	0	0	0	0

TABLE XII
WIRE MESH TYPE I REQUIREMENTS
(WM 3)

Member Description	Quantities (sq ft) Consumed				
	Up to First Story	Up to Second Story	Up to Third Story	Up to Fourth Story	Up to Fifth Story
Double Tee Wall Panels	3840 4480	7680 8960	11520 11440	15360 17920	19200 22400
Flat Wall Panels	0	0	0	0	0
Blocks	0	0	0	0	0
Columns to go with Blocks	0	0	0	0	0
Double Tee Floor Members	0	10976	21952	32928	43904
Flat Floor Slabs	0	21952	43904	65856	87808
L-Beams	0	0	0	0	0
Rectangular Beams	0	0	0	0	0
Core Wall Panels	0	0	0	0	0
Boxes for Service Core	0	0	0	0	0
Double Tee Roof Members	10976	10976	10976	10976	10976
Flat Roof Slabs	10976	10976	10976	10976	10976

TABLE XIII
WIRE MESH TYPE II REQUIREMENTS
(WM 4)

Member Description	Quantities (ft) Consumed				
	Up to First Story	Up to Second Story	Up to Third Story	Up to Fourth Story	Up to Fifth Story
Double Tee Wall Panels	960 1120	1920 2240	2880 3360	3840 4480	4800 5600
Flat Wall Panels	0	0	0	0	0
Blocks	0	0	0	0	0
Columns to go with Blocks	0	0	0	0	0
Double Tee Floor Members	0	762	1524	2286	3048
Flat Floor Slabs	0	0	0	0	0
L-Beams	0	0	0	0	0
Rectangular Beams	0	0	0	0	0
Core Wall Panels	0	0	0	0	0
Boxes for Service Core	0	0	0	0	0
Double Tee Roof Members	762	762	762	762	762
Flat Roof Slabs	0	0	0	0	0

TABLE XIV
WIRE MESH TYPE III REQUIREMENTS
(WM 5)

Member Description	Quantities (sq ft) Consumed				
	Up to First Story	Up to Second Story	Up to Third Story	Up to Fourth Story	Up to Fifth Story
Double Tee Wall Panels	0	0	0	0	0
Flat Wall Panels	0	0	0	0	0
Blocks	0	0	0	0	0
Columns to go with Blocks	0	0	0	0	0
Double Tee Floor Members	0	0	0	0	0
Flat Floor Slabs	0	0	0	0	0
L-Beams	0	0	0	0	0
Rectangular Beams	0	0	0	0	0
Core Wall Panels	0	0	0	0	0
Boxes for Service Core	2448	4896	7344	9792	12240
Double Tee Roof Members	0	0	0	0	0
Flat Roof Slabs	0	0	0	0	0

TABLE XV
CONCRETE TYPE I REQUIREMENTS
(CN 6)

Member Description	Quantities (cu yd) Consumed				
	Up to First Story	Up to Second Story	Up to Third Story	Up to Fourth Story	Up to Fifth Story
Double Tee Wall Panels	0	0	0	0	0
Flat Wall Panels	0	0	0	0	0
Blocks	0	0	0	0	0
Columns to go with Blocks	0	0	0	0	0
Double Tee Floor Members	0	141	283	424	565
Flat Floor Slabs	0	272	543	815	1087
L-Beams	0	0	0	0	0
Rectangular Beams	0	0	0	0	0
Core Wall Panels	48 56	96 112	144 168	192 224	240 280
Boxes for Service Core	45 53	92 107	136 159	180 210	228 266
Double Tee Roof Members	124	124	124	124	124
Flat Roof Slabs	203	203	203	203	203

TABLE XVI
CONCRETE TYPE II REQUIREMENTS
(CN 7)

Member Description	Quantities (cu yd) Consumed				
	Up to First Story	Up to Second Story	Up to Third Story	Up to Fourth Story	Up to Fifth Story
Double Tee Wall Panels	85 99	169 197	254 296	338 395	423 494
Flat Wall Panels	144 168	288 336	432 504	576 672	720 840
Blocks	0	0	0	0	0
Columns to go with Blocks	18 21	36 42	54 63	72 84	90 105
Double Tee Floor Members	0	0	0	0	0
Flat Floor Slabs	0	0	0	0	0
L-Beams	24	48	72	96	120
Rectangular Beams	20	40	60	80	100
Core Wall Panels	0	0	0	0	0
Boxes for Service Core	0	0	0	0	0
Double Tee Roof Members	0	0	0	0	0
Flat Roof Slabs	0	0	0	0	0

TABLE XVII
CONCRETE TYPE III REQUIREMENTS
(CN 8)

Member Description	Quantities (Blocks) Consumed				
	Up to First Story	Up to Second Story	Up to Third Story	Up to Fourth Story	Up to Fifth Story
Double Tee Wall Panels	0	0	0	0	0
Flat Wall Panels	0	0	0	0	0
Blocks	3840 4480	7680 8960	11520 13440	15360 17920	19200 22400
Columns to go with Blocks	0	0	0	0	0
Double Tee Floor Members	0	0	0	0	0
Flat Floor Slabs	0	0	0	0	0
L-Beams	0	0	0	0	0
Rectangular Beams	0	0	0	0	0
Core Wall Panels	0	0	0	0	0
Boxes for Service Core	0	0	0	0	0
Double Tee Roof Members	0	0	0	0	0
Flat Roof Slabs	0	0	0	0	0

TABLE XVIII
PLANT LABOR REQUIREMENTS
(PL 9)

Member Description	Quantities (Man-hrs) Consumed				
	Up to First Story	Up to Second Story	Up to Third Story	Up to Fourth Story	Up to Fifth Story
Double Tee Wall Panels	103 120	206 240	309 360	412 480	515 600
Flat Wall Panels	146 170	292 340	436 510	584 680	726 850
Blocks	0	0	0	0	0
Columns to go with Blocks	160 187	320 374	480 561	640 748	800 935
Double Tee Floor Members	0	154	308	462	616
Flat Floor Slabs	0	275	550	825	1100
L-Beams	58	116	174	232	290
Rectangular Beams	44	88	132	176	220
Core Wall Panels	118 138	236 276	354 414	472 552	590 690
Boxes for Service Core	160 187	320 374	480 561	640 748	800 935
Double Tee Roof Members	165	165	165	165	165
Flat Roof Slabs	275	275	275	275	275

TABLE XIX

***ERECTION LABOR REQUIREMENTS FOR PRECAST
AND PRESTRESSED MEMBERS (EL 10)**

Member Description	Quantities (Man-hrs) Consumed				
	Up to First Story	Up to Second Story	Up to Third Story	Up to Fourth Story	Up to Fifth Story
Double Tee Wall Panels	250	510	780	1060	1350
Flat Wall Panels	234	478	731	993	1264
Blocks	0	0	0	0	0
Columns to go with Blocks	160	327	500	679	864
Double Tee Floor Members	0	98	200	306	416
Flat Floor Slabs	0	98	200	306	416
L-Beams	23	47	72	98	125
Rectangular Beams	21	43	66	89	114
Core Wall Panels	40	82	125	170	216
Boxes for Service Core	30	60	94	128	162
Double Tee Roof Members	98	100	102	104	106
Flat Roof Slabs	98	100	102	104	106

*Erection labor increases at the rate of two percent per increase in story height.

TABLE XX

*ERECTION LABOR REQUIREMENTS FOR BLOCK WALL
(ELB 11)

Member Description	Quantities (Man-hrs) Consumed				
	Up to First Story	Up to Second Story	Up to Third Story	Up to Fourth Story	Up to Fifth Story
Double Tee Wall Panels	0	0	0	0	0
Flat Wall Panels	0	0	0	0	0
Blocks	230 271	500 584	857 1001	1214 1418	1606 1876
Columns to go with Blocks	0	0	0	0	0
Double Tee Floor Members	0	0	0	0	0
Flat Floor Slabs	0	0	0	0	0
L-Beams	0	0	0	0	0
Rectangular Beams	0	0	0	0	0
Core Wall Panels	0	0	0	0	0
Boxes for Service Core	0	0	0	0	0
Double Tee Roof Members	0	0	0	0	0
Flat Roof Slabs	0	0	0	0	0

*Erection labor increases at the rate of 7.692% per increase in story height.

TABLE XXI

HIGHWAY WEIGHT LIMIT REQUIREMENTS--
FIRST LOCATION (WLR 12)

Member Description	Minimum Quantities (Truckloads) Needed				
	Up to First Story	Up to Second Story	Up to Third Story	Up to Fourth Story	Up to Fifth Story
Double Tee Wall Panels	41 43	84 86	126 129	168 172	210 215
Flat Wall Panels	42 42	84 84	126 126	168 168	210 210
Blocks	6 7	12 14	18 21	24 28	30 35
Columns to go with Blocks	36 36	72 72	108 108	144 144	180 180
Double Tee Floor Members	0	46	92	138	184
Flat Floor Slabs	0	57	114	171	228
L-Beams	9	18	27	36	45
Rectangular Beams	9	18	27	36	45
Core Wall Panels	9 9	18 18	27 27	36 36	45 45
Boxes for Service Core	9	18	27	36	45
Double Tee Roof Members	46	46	46	46	46
Flat Roof Slabs	57	57	57	57	57

APPENDIX C

TABLES OF QUANTITIES FOR THE COMPUTATION OF
CONVERSION FACTORS AND TRUCK LOADS FOR
THE SECOND AND THIRD LOCATIONS

TABLE XXII

INCREASE IN TRANSPORTATION COST UP TO THE SECOND LOCATION,
ABOVE THAT OF THE FIRST LOCATION

Precast Concrete Components	First Story (\$)	Second Story (\$)	Third Story (\$)	Fourth Story (\$)	Fifth Story (\$)
Double Tee Wall Panel	450 525	900 1050	1350 1575	1800 2100	2250 2625
Flat Wall Panel	675 675	1350 1350	2025 2025	2700 2700	3375 3375
Concrete Block	98.22 114.24	196.44 228.48	294.66 342.72	392.88 456.96	491.10 571.20
Columns to go with Block	150	300	450	600	750
Double Tee Floor Member	0	750	1500	2250	3000
Flat Floor Slab	0	1425	2850	4275	5700
Double Tee Roof Member	750	750	750	750	750
Flat Roof Slab	1425	1425	1425	1425	1425

TABLE XXIII

INCREASE IN TRANSPORTATION COST UP TO THE THIRD LOCATION,
ABOVE THAT OF THE FIRST LOCATION .

Precast Concrete Components	First Story (\$)	Second Story (\$)	Third Story (\$)	Fourth Story (\$)	Fifth Story (\$)
Double Tee Wall Panel	900 1050	1800 2100	2700 3150	3600 4200	4500 5250
Flat Wall Panel	1350 1350	2700 2700	4050 4050	5400 5400	6750 6750
Concrete Block	196.44 228.48	392.88 456.96	589.32 685.44	785.76 913.92	982.20 1142.40
Columns to go with Block	300	600	900	1200	1500
Double Tee Floor Member	0	1500	3000	4500	6000
Flat Floor Slab	0	2850	5700	8550	11400
Double Tee Roof Member	1500	1500	1500	1500	1500
Flat Roof Slab	2850	2850	2850	2850	2850

TABLE XXIV
SUMMARY OF COMPUTATION OF CONVERSION FACTORS
FOR THE SECOND LOCATION

Precast Concrete Components	Total Transportation Cost First Story	Truck Loads Before Conversion for First Story	Cost Per Truck Load	Conversion Factor	Converted Truck Loads
Double Tee Wall Panel	2900 / 3050	6 / 7	483.33 / 435.71	6.36 / 5.73	39 / 41
Flat Wall Panel	3150 / 3150	9 / 9	350.00 / 350.00	4.61 / 4.61	42 / 42
Concrete Block	456 / 532	6 / 7	76.00 / 76.00	1 / 1	6 / 7
Columns to go with Block	2300	2	1150	15.13	31
Double Tee Floor Member	3450	10	345	4.54	46
Flat Floor Slab	4800	19	252.63	3.32	64
L-Beam	750	3	250	3.29	10
Rectangular Beam	750	3	250	3.29	10
Core Wall Panel	800	4	200	2.63	11
Box	800	4	200	2.63	11
Double Tee Roof Member	3450	10	345	4.54	46
Flat Roof Slab	4800	19	252.63	3.32	64

TABLE XXV
SUMMARY OF COMPUTATION OF CONVERSION FACTORS
FOR THE THIRD LOCATION

Precast Concrete Components	Total Transportation Cost First Story	Truck Loads Before Conversion for First Story	Cost Per Truck Load	Conversion Factor	Converted Truck Loads
Double Tee Wall Panel	3350 / 3575	6 / 7	558.33 / 510.71	6.07 / 5.55	37 / 39
Flat Wall Panel	3825 / 3825	9 / 9	425.00 / 425.00	4.62 / 4.62	42 / 42
Concrete Block	552 / 644	6 / 7	92.00 / 92.00	1 / 1	6 / 7
Columns to go with Block	2450	2	1225	13.32	27
Double Tee Floor Member	4200	10	420	4.57	46
Flat Floor Slab	6225	19	327.63	3.56	68
L-Beam	975	3	325	3.53	11
Rectangular Beam	975	3	325	3.53	11
Core Wall Panel	1100	4	275	2.99	12
Box	1100	4	275	2.99	12
Double Tee Roof Member	4200	10	420	4.57	46
Flat Roof Slab	6225	19	327.63	3.56	68

TABLE XXVI
COMPUTATION OF CONVERTED TRUCK LOADS
FOR THE SECOND LOCATION

Precast Concrete Component	Truck Loads First Story	Truck Loads Second Story	Truck Loads Third Story	Truck Loads Fourth Story	Truck Loads Fifth Story
Double Tee Wall Panel	39 41	78 82	117 123	156 164	195 205
Flat Wall Panel	42 42	84 84	126 126	168 168	210 210
Concrete Block	6 7	12 14	18 21	24 28	30 35
Columns to go with Block	31	62	93	124	155
Double Tee Floor Member	0	46	92	138	184
Flat Floor Slab	0	64	128	192	256
L-Beam	10	20	30	40	50
Rectangular Beam	10	20	30	40	50
Core Wall Panel	11	22	33	44	55
Box	11	22	33	44	55
Double Tee Roof Member	46	46	46	46	46
Flat Roof Slab	64	64	64	64	64

TABLE XXVII
COMPUTATION OF CONVERTED TRUCK LOADS
FOR THE THIRD LOCATION

Precast Concrete Component	Truck Loads First Story	Truck Loads Second Story	Truck Loads Third Story	Truck Loads Fourth Story	Truck Loads Fifth Story
Double Tee Wall Panel	37 39	74 78	111 117	148 156	185 195
Flat Wall Panel	42 42	84 84	126 126	168 168	210 210
Concrete Block	6 7	12 14	18 21	24 28	30 35
Columns to go with Block	27	54	81	108	135
Double Tee Floor Member	0	46	92	138	184
Flat Floor Slab	0	68	136	204	272
L-Beam	11	22	33	44	55
Rectangular Beam	11	22	33	44	55
Core Wall Panel	12	24	36	48	60
Box	12	24	36	48	60
Double Tee Roof Member	46	46	46	46	46
Flat Roof Slab	68	68	68	68	68

APPENDIX D

A TYPICAL COMPUTER PROGRAM EXPLAINED AND LISTED

The IBM Program Package MPSX360

Introduction

The IBM program package, Mathematical Programming Systems Extended 360 (MPSX360), consists of three main types of input cards, namely:

1. Job Control Language (JCL) cards.
2. Control Language Source Program cards.
3. Input Data cards.

The JCL Cards

The JCL cards constitute the first set of cards and they immediately precede the Control Language Source Program cards. An example of a set of JCL cards is as follows (66):

```
//Job name      JOB (xxxxx, xxx-xx-xxxxx), 'xxx,' etc.  
// EXEC MPSX360  
//MPSX1.SYSIN DD * .
```

The first JCL card, the JOB card, is unique for a given computer installation. Typically, the JOB card contains the Job name, the account number for the particular job, and other identifying names of the job owner. The second card tells the computer to call MPSX360 while the third card calls for the control language compiler. Other additions to the above three JCL cards are possible, depending on the requirements of the computer installation.

Control Language Source Program

The Control Language Source Program consists of a number of cards as shown in Figure 14. Each card represents a definite operation. A

•MPSX-PTF17. CONTROL PROGRAM COMPILER. MPSX RELEASE 1 MOD LEVEL 6

```
0001      PROGRAM
0002      *
0003      TITLE ('SELCTN 3 MOST ECON COMBTN 5TH STORY,1ST LOCTN')
0004      *
0005      INITIALZ
0099      MOVE (XDATA,'COMBTN')
0100      MOVE(XPSNAME,'PBFILE')
0101      CONVERT('SUMMARY')
0102      BCDOUT
0103      SETUP ('RANGE','RESOURCE','BOUND','BLDGALT')
0104      PICTURE
0105      MOVE (XOBJ,'COST')
0106      MOVE (XRHS,'COMB TN1')
0107      PRIMAL
0108      SOLUTION
0109      OPTIMIX('COST',0.,0,0,1)
0205      RANGE
0206      EXIT
0207      PEND
```

Figure 14. MPSX360 Control Language Source Program

control program must be initiated by the PROGRAM statement. The PROGRAM statement is not an executable statement and it may not have a batch (67).

The TITLE statement is an executable control program statement. The expression in parentheses in the TITLE statement constitutes the page titles to the output program. More than one TITLE statement may be used. Where up to three TITLE statements are used, the first TITLE statement will provide a heading for the first output page, while the second TITLE statement will specify the TITLE heading for the second output page. However, all subsequent output pages will bear the TITLE heading specified in the third TITLE statement.

The INITIALZ macro instruction establishes "standard" processing of all demands. Where the INITIALZ macro instruction is not used as the first statement in a control program, all the functions of the control program must be provided by the user before the execution of the first procedure (68).

An area of central memory named the Communications Region (CR) controls the operations of MPSX360. The set of instructions beginning with the verb "MOVE" specifies that the name on the right be moved into the Communications Region cell which bears the name on the left. Specifically, in the MOVE statement:

```
MOVE (XDATA, 'COMBTN'),
```

the word "COMBTN" is transferred into the Communication Region cell named "XDATA."

The CONVERT statement specifies that the input data punched on 80-column cards in Binary Coded Decimal (BCD) format be read onto the problem file (PROBFILE) (66)(67)(68). The word "SUMMARY" in parentheses

after "CONVERT" makes it possible for the control program to provide statistics of both major and minor reading errors. The inclusion of "SUMMARY" is optional.

The BCDOUT statement specifies that the data in PROBFIL be converted to BCD for output, and that the data be output in the same order in which they were input.

The SETUP statement is used when some of the row constants have upper and lower limiting values (RANGE) and the decision variables are bounded (BOUND).

PICTURE creates a pictorial representation of the specified portion of the work matrix.

PRIMAL obtains an optimal feasible solution (if one exists) by solving the primal problem.

The SOLUTION instruction outputs the solution during or after optimization.

OPTIMIX appears between SOLUTION and EXIT, and controls the sequencing of the branch-and-bound iterations after an optimum solution to the unrestricted LP problem (that is an LP problem which satisfies all constraints and bounds, except the integer requirement).

If it is desired to establish the effect on the optimal solution, of varying the RHS constants and the objective function coefficients (sensitivity analysis), the RANGE statement is used.

The last two cards, EXIT and PEND, mark the end of the control program. Since the JCL program treats the whole of the control program as input data, the JCL card "/*" follows the PEND card.

A typical input data format is listed in Figure 15. The first data card contains the two words "NAME" and "COMBTN," and gives the

MPSX-PTF17. SELCTN 3 MOST ECON COMBNTN 5TH STORJ, 1ST LOCTN, MPSX-PTF17.				SELCTN 3 MOST ECON COMBNTN 5TH STORJ, 1ST LOCTN			
NAME	COMBNTN						
N CCST				X0751	COST	283341.0000	PS1
G PS1				X0751	RB2	40483.01300	WM3
G RE2				X0751	WM4	6362.00900	CN6
G WM3				X0751	CN7	594.00170	PL9
L WM4				X0751	EL10	2202.00101	WLR12
L WM5				X0751	CR13	1.00000	
G CN6				X0851	COST	284027.0000	PS1
G CN7				X0451	RB2	4100.00181	WM3
L CN8				X0851	WM4	6302.00720	WM5
G PL9				X0851	CN6	1477.00191	CN7
G EL10				X0851	PL9	3020.01610	EL10
L EL11				X0851	WLR12	594.00300	CR13
G WLR12				X0451	COST	270707.0000	PS1
G CR13				X0451	RB2	42470.01500	WM3
COLUMNS				X0451	WM4	3610.00950	CN6
INTORG	MARKER		INTORG	X0451	CN7	840.00690	PL9
X0151	COST	257935.0000	PS1	X0451	EL10	2127.03690	WLR12
X0151	RB2	35200.00200	WM3	X0451	CR13	1.00000	
X0151	WM4	8610.04300	CN6	X0151	COST	267219.0000	PS1
X0151	CN7	543.07000	PL9	X0151	RB2	6390.01560	WM3
X0151	EL10	2213.01100	WLR12	X0151	WM4	3810.04500	WM5
X0151	CR13	1.00000		X0151	CN6	917.01410	CN7
X0251	COST	256441.0000	PS1	X0151	PL9	2577.01690	EL10
X0251	RB2	4100.01200	WM3	X0151	WLR12	515.00000	CR13
X0251	WM4	8610.01400	WM5	X0151	COST	281457.0000	PS1
X0251	CN6	917.01600	CN7	X0151	RB2	44968.00300	WM3
X0251	PL9	2386.01900	EL10	X0151	WM4	3610.00000	CN6
X0251	WLR12	510.00000	CR13	X0151	CN7	540.01710	PL9
X0351	COST	267538.0000	PS1	X0151	EL10	2116.00100	WLR12
X0351	RB2	43463.00200	WM3	X0151	CR13	1.00000	
X0351	WM4	9410.00400	CN6	X0251	COST	282736.0000	PS1
X0351	CN7	594.00700	PL9	X0251	RB2	12605.00000	WM3
X0351	EL10	2232.00110	WLR12	X0251	WM4	3810.01600	WM5
X0351	CR13	1.00000		X0251	CN6	955.01800	CN7
X0451	COST	268324.0000	PS1	X0251	PL9	2746.00100	EL10
X0451	RB2	4100.01040	WM3	X0251	WLR12	515.00000	CR13
X0451	WM4	9410.00600	WM5	X0251	COST	286512.0000	PS1
X0451	CN6	955.00660	CN7	X0251	RB2	42470.00100	WM3
X0451	PL9	2536.00760	EL10	X0251	WM4	762.01400	CN6
X0451	WLR12	525.00120	CR13	X0251	CN7	840.01710	PL9
X0551	COST	273738.0000	PS1	X0251	EL10	2127.00000	WLR12
X0551	RB2	35200.00370	WM3	X0251	CR13	1.00000	
X0551	WM4	5562.00160	CN6	X0451	COST	285018.0000	PS1
X0551	CN7	543.01010	PL9	X0451	RB2	4390.01450	WM3
X0551	EL10	2213.01150	WLR12	X0451	WM4	762.00410	WM5
X0551	CR13	1.00000		X0451	CN6	1439.00614	CN7
X0651	COST	272244.0000	PS1	X0451	PL9	3081.01760	EL10
X0651	RB2	4100.00180	WM3	X0451	WLR12	559.05400	CR13
X0651	WM4	5562.00000	WM5	X0551	COST	297293.0000	PS1
X0651	CN6	1439.00000	CN7	X0551	RB2	48968.00180	WM3
X0651	PL9	2870.06900	EL10	X0551	WM4	762.01560	CN6
X0651	WLR12	594.00140	CR13	X0551	CN7	940.01061	PL9
				X0551	EL10	2116.01760	WLR12
				X0551	CR13	1.00000	

Figure 15. A Typical MPSX360 Input Data Format

MPSX-PTFL7. SELCTN 3 MOST ECON COMBNTN 5TH STORY.1ST LOCTN				MPSX-PTFL7. SELCTN 3 MOST ECON COMBNTN 5TH STORY.1ST LOCTN			
X1651	COST	298539.0000	PS1	104824.0000	X2351	CR13	1.000000
X1651	R02	12605.00000	WM3	67603.00100	X2451	COST	312628.0000
X1651	WM4	762.01016	WM5	12240.01600	X2451	R02	49865.00760
X1651	CN6	1477.00100	CN7	540.06810	X2451	WM4	3314.01650
X1651	PL9	30270.01970	EL10	2062.01760	X2451	CN6	1477.04600
X1651	WLR12	559.00000	CR13	1.000000	X2451	CN8	22400.01600
X1751	COST	291374.00000	PS1	56316.00600	X2451	EL10	1662.00760
X1751	R02	74425.00160	WM3	54680.00700	X2451	WLR12	564.01720
X1751	WM4	3610.00500	CN6	529.00760	X2551	COST	300000.00000
X1751	CN7	676.00171	CN8	19200.00600	X2551	R02	35200.02900
X1751	PL9	2461.00760	EL10	1727.00110	X2551	WM4	7848.00254
X1751	EL011	1696.00450	WLR12	530.00760	X2551	CN7	543.07150
X1751	CR13	1.000000			X2551	EL10	2213.00160
X1851	COST	289880.00000	PS1	58810.00100	X2551	CR13	1.000000
X1851	R02	43329.00810	WM3	54880.00800	X2651	COST	259036.00000
X1851	WM4	3810.00600	WM5	12240.00700	X2651	R02	4100.00415
X1851	CN6	917.00600	CN7	876.00510	X2651	WM4	7848.02640
X1851	CN8	19200.00150	PL9	2671.00710	X2651	CN6	917.01670
X1851	EL10	1673.00510	EL011	1600.00450	X2651	PL9	2496.07610
X1851	WLR12	515.00360	CR13	1.000000	X2651	WLR12	521.00360
X1951	COST	295539.00000	PS1	60416.00700	X2751	COST	270135.00000
X1951	R02	86226.00560	WM3	43924.00800	X2751	R02	40463.02600
X1951	WM4	3610.01640	CN6	564.01160	X2751	WM4	6648.01750
X1951	CN7	963.01890	CN8	22400.00100	X2751	CN7	544.01450
X1951	PL9	2626.00450	EL10	1716.01160	X2751	EL10	2202.09500
X1951	EL011	1876.05160	WLR12	535.01760	X2751	CR13	1.000000
X1951	CR13	1.000000			X2851	COST	271421.00000
X2051	COST	296625.00000	PS1	60416.00100	X2851	R02	4100.00234
X2051	R02	49865.00600	WM3	43904.00300	X2851	WM4	8643.01760
X2051	WM4	3810.00121	WM5	12240.02700	X2851	CN6	555.07610
X2051	CN6	955.00216	CN7	983.00760	X2851	PL9	2646.01930
X2051	CN8	22400.00510	PL9	2971.00760	X2851	WLR12	531.00000
X2051	EL10	1662.01910	EL011	1876.05160	X2951	COST	276135.00000
X2051	WLR12	520.00212	CR13	1.000000	X2951	R02	3520.00760
X2151	COST	307177.00000	PS1	91744.02100	X2951	WM4	4600.02910
X2151	R02	74425.02600	WM3	98784.01600	X2951	CN7	543.07290
X2151	WM4	2514.07610	CN6	1451.04150	X2951	EL10	2213.02910
X2151	CN7	676.00217	CN8	19200.00200	X3051	CR13	1.000000
X2151	PL9	2945.00120	EL10	1726.00000	X3051	COST	274441.00000
X2151	EL011	1806.05160	WLR12	574.01760	X3051	R02	4100.00300
X2151	CR13	1.000000			X3051	WM4	4800.00000
X2251	COST	305667.00000	PS1	91744.01700	X3051	CN6	1439.00300
X2251	R02	4325.06150	WM3	95784.00400	X3051	PL9	2980.00000
X2251	WM4	2514.00760	WM5	12240.06200	X3051	WLR12	565.01250
X2251	CN6	1439.00160	CN7	976.00170	X3151	COST	285936.00000
X2251	CN8	19200.01216	PL9	2155.09160	X3151	R02	40463.00000
X2251	EL10	1673.09190	EL011	1676.01910	X3151	WM4	5600.01340
X2251	WLR12	559.00760	CR13	1.000000	X3151	CN7	544.00000
X2351	COST	311342.00000	PS1	93344.00600	X3151	EL10	2202.00000
X2351	R02	86226.01760	WM3	87603.04100	X3151	CR13	1.000000
X2351	WM4	3314.01600	CN6	1491.00910	X3251	COST	287227.00000
X2351	CN7	963.01470	CN8	22400.00000	X3251	R02	4100.00320
X2351	PL9	3110.00290	EL10	1716.00210	X3251	WM4	5600.00000
X2351	EL011	1876.01101	WLR12	579.00120	X3251	CN6	1477.01000
						CN7	594.00160

Figure 15. (Continued)

.MPSX-PTF17. SELECTN 3 MOST ECON COMBNTN 5TH STORY.1ST LGCTN .MPSX-PTF17. SELECTN 3 MOST ECON COMBNTN 5TH STORY.1ST LGCTN

X3251	PL9	3130.00450	EL10	2148.01800	X4151	CR13	1.00000		
X3251	WLR12	575.00000	CR13	1.00000	X4251	COST	292477.0000	PS1	67043.00100
X3351	COST	273306.0000	PS1	76889.00000	X4251	R32	43325.06100	WM3	54680.00400
X3351	R32	42490.01000	WM3	54880.00000	X4251	WM4	3048.00460	WM5	12240.00100
X3351	WM4	3048.00700	CR6	529.00700	X4251	CN6	917.00165	CN7	876.00960
X3351	CN7	840.00175	PL9	2497.07100	X4251	CN8	19200.00460	PL9	2781.00560
X3351	EL10	2127.00115	WLR12	541.00620	X4251	EL10	1763.00182	ELB11	1606.01150
X3351	CR13	1.00000			X4251	WLR12	528.00181	CR13	1.00000
X3451	COST	271612.0000	PS1	76889.01400	X4351	COST	256136.0000	PS1	68648.00500
X3451	R32	8390.01760	WM3	54880.00400	X4351	R32	86228.00000	WM3	43934.00500
X3451	WM4	3048.00345	WM5	12240.00300	X4351	WM4	3048.00190	CN6	595.00150
X3451	CN6	917.00316	CN7	840.00670	X4351	CN7	983.00360	CN8	22400.00500
X3451	PL9	2737.00000	EL10	2073.00140	X4351	PL9	2736.00195	EL10	1716.00360
X3451	WLR12	526.00120	CR13	1.00000	X4351	ELB11	1876.00150	WLR12	546.00530
X3551	COST	284047.0000	PS1	80126.00900	X4351	CR13	1.00000		
X3551	R32	48906.01500	WM3	43934.01400	X4451	COST	299422.0000	PS1	68648.00900
X3551	WM4	3048.01060	CN6	567.01756	X4451	R32	49665.00600	WM3	43934.00500
X3551	CN7	940.00156	PL9	2651.00190	X4451	WM4	3048.00800	WM5	12240.00700
X3551	EL10	2116.00101	WLR12	541.00170	X4451	CN6	955.00446	CN7	583.00437
X3551	CR13	1.00000			X4451	CN8	22400.00610	PL9	2961.00910
X3651	COST	285333.0000	PS1	80126.00100	X4451	EL10	1662.00110	ELB11	1376.00120
X3651	R32	12605.00150	WM3	43934.00100	X4451	WLR12	531.00157	CR13	1.00000
X3651	WM4	3048.00364	WM5	12240.00200	X4551	COST	305774.0000	PS1	99976.00600
X3651	CN6	955.00316	CN7	940.00756	X4551	R32	74425.00300	WM3	58784.00100
X3651	PL9	2846.00590	EL10	2062.00500	X4551	WM4	1757.00300	CN6	1451.00300
X3651	WLR12	526.00180	CR13	1.00000	X4551	CN7	676.00700	CN8	19200.00100
X3751	COST	289109.0000	PS1	109816.0000	X4551	PL9	3055.00180	EL10	1727.00450
X3751	R32	42490.00400	WM3	98784.00300	X4551	ELB11	1836.00360	WLR12	535.00412
X3751	CN6	1451.00190	CN7	840.00700	X4551	CR13	1.00000		
X3751	PL9	2931.00000	EL10	2127.00160	X4651	COST	308260.0000	PS1	99576.00300
X3751	WLR12	505.00181	CR13	1.00000	X4651	R32	43325.01400	WM3	96734.00500
X3851	COST	287619.0000	PS1	109816.0000	X4651	WM4	1752.00490	WM5	12240.00600
X3851	R32	8390.00120	WM3	98784.00600	X4651	CN6	1439.00160	CN7	876.00760
X3851	WM4	12240.00100	CN6	1439.00750	X4651	CN8	19200.00460	PL9	2285.00550
X3851	CN7	840.00156	PL9	3191.00190	X4651	EL10	1673.01116	ELB11	1606.00300
X3851	EL10	2073.00540	WLR12	570.00123	X4651	WLR12	570.00300	CR13	1.00000
X3851	CR13	1.00000			X4751	COST	313939.0000	PS1	101576.0000
X3951	COST	295860.0000	PS1	113350.0000	X4751	R32	86228.00000	WM3	87838.00700
X3951	R32	48906.00140	WM3	87838.00500	X4751	WM4	2532.00400	CN6	491.00000
X3951	CN6	1491.00510	CN7	940.00739	X4751	CN7	983.00000	CN8	22400.00100
X3951	PL9	3135.00000	EL10	2116.00000	X4751	PL9	3220.00300	EL10	1716.00430
X3951	WLR12	585.00391	CR13	1.00000	X4751	ELB11	1476.00120	WLR12	590.00000
X4051	COST	301136.0000	PS1	113350.00100	X4751	CR13	1.00000		
X4051	R32	12605.00550	WM3	87838.01500	X4851	COST	315225.0000	PS1	101576.0000
X4051	WM4	12240.01400	CN6	1477.00145	X4851	R32	49065.00000	WM3	87838.00700
X4051	CN7	940.00160	PL9	3380.00164	X4851	WM4	2532.00640	WM5	12240.00000
X4051	EL10	2062.00120	WLR12	570.00180	X4851	CN6	1477.00510	CN7	533.01420
X4051	CR13	1.00000			X4851	CN8	22400.01230	PL9	3465.00150
X4151	COST	293971.0000	PS1	67048.00100	X4851	EL10	1662.00246	ELB11	1876.00450
X4151	R32	74429.01600	WM3	54880.00700	X4851	WLR12	575.00000	CR13	1.00000
X4151	WM4	3048.00190	CN6	929.00134	INTEND	*MARKER*		*INTEND*	
X4151	CN7	876.00000	CN8	19200.00000	COMBTN1	PS1	165000.0000	R32	10998.00000
X4151	PL9	2571.00860	EL10	1727.01560	COMBTN1	WM3	126000.0000	WM4	28998.00000
X4151	ELB11	1606.00113	WLR12	541.00111					

Figure 15. (Continued)

.MPSX-PTF17. SELCTN 3 MOST ECON COMBNTN 5TH STORY.1ST LGCTN.MPSX-PTF17.				SELCTN 3 MOST ECON COMBNTN 5TH STORY.1ST LGCTN			
COMBNTN1	WM5	34998.00000	CN6	2700.00000	UP BLDGALT	X4551	1.00000
COMBNTN1	CN7	1620.00000	CN8	69600.00000	UP BLDGALT	X4651	1.00000
COMBNTN1	PL9	6300.00000	EL10	4800.00000	UP BLDGALT	X4751	1.00000
COMBNTN1	EL11	5700.00000	WLR12	1245.00000	UP BLDGALT	X4851	1.00000
COMBNTN1	CR13	3.00000			ENDATA		
RANGES							
RESOURCE	PS1	190000.0000	RD2	152000.0000			
RESOURCE	WM3	231000.0000	CN6	1900.00000			
RESOURCE	CN7	1930.00000	PL9	4200.00000			
SCUNDS							
UP BLDGALT	X0151	1.00000					
UP BLDGALT	X0251	1.00000					
UP BLDGALT	X0351	1.00000					
UP BLDGALT	X0451	1.00000					
UP BLDGALT	X0551	1.00000					
UP BLDGALT	X0651	1.00000					
UP BLDGALT	X0751	1.00000					
UP BLDGALT	X0851	1.00000					
UP BLDGALT	X0951	1.00000					
UP BLDGALT	X1051	1.00000					
UP BLDGALT	X1151	1.00000					
UP BLDGALT	X1251	1.00000					
UP BLDGALT	X1351	1.00000					
UP BLDGALT	X1451	1.00000					
UP BLDGALT	X1551	1.00000					
UP BLDGALT	X1651	1.00000					
UP BLDGALT	X1751	1.00000					
UP BLDGALT	X1851	1.00000					
UP BLDGALT	X1951	1.00000					
UP BLDGALT	X2051	1.00000					
UP BLDGALT	X2151	1.00000					
UP BLDGALT	X2251	1.00000					
UP BLDGALT	X2351	1.00000					
UP BLDGALT	X2451	1.00000					
UP BLDGALT	X2551	1.00000					
UP BLDGALT	X2651	1.00000					
UP BLDGALT	X2751	1.00000					
UP BLDGALT	X2851	1.00000					
UP BLDGALT	X2951	1.00000					
UP BLDGALT	X3051	1.00000					
UP BLDGALT	X3151	1.00000					
UP BLDGALT	X3251	1.00000					
UP BLDGALT	X3351	1.00000					
UP BLDGALT	X3451	1.00000					
UP BLDGALT	X3551	1.00000					
UP BLDGALT	X3651	1.00000					
UP BLDGALT	X3751	1.00000					
UP BLDGALT	X3851	1.00000					
UP BLDGALT	X3951	1.00000					
UP BLDGALT	X4051	1.00000					
UP BLDGALT	X4151	1.00000					
UP BLDGALT	X4251	1.00000					
UP BLDGALT	X4351	1.00000					
UP BLDGALT	X4451	1.00000					

Figure 15. (Continued)

NAME of the data set. "COMBTN" must be the same as that used in the control program statement: MOVE (XDATA, 'COMBTN'). The JCL statement: //MPSX2.SYSIN DD * precedes the data set.

The indicator card "ROWS" is followed by the data cards which state the names of the rows and the types of constraints they are.

N means no constraint.

G means greater than or equal to (\geq).

L means less than or equal to (\leq).

If a constraint row is an equality then E is used in place of N, G, or L.

The indicator card "COLUMNS" introduces the data cards containing the coefficients of the decision variables. The words "INTORG," "MARKER," and "INTORG" precede the list of decision variables which are integer. Similarly, "INTEND," "MARKER," and "INTEND" terminate such a list. The coefficients of the decision variables are listed column by column. However, the sequence of listing the columns does not matter. Thus all the coefficients of the decision variable X0651 can be listed before those of X0151, but the sequence of the row names, e.g.,

COST

RB2

may not be altered in either X0651 or X0151.

RHS, RANGES, and BOUNDS are indicator cards. All RHS constants are given a group name COMBTN1. The group names for all RHS constants which have RANGES, and all decision variables having upper and lower BOUNDS are RESOURCE and BLDGALT, respectively. If UP is punched in the second and third columns of a data card in the BOUNDS section, it

means that the numerical quantity on that card is the upper bound value of the decision variable on that card. LO may be punched on a second card for the same decision variable and in the same columns as UP, if the decision variable has a lower bound value. Since all decision variables in Figure 15 are positive, their lower bound values are zero and do not have to be specified under the BOUNDS section.

The card, ENDDATA, indicates the end of the data set.

In all the data cards under the sections

COLUMNS

RHS

RANGES

BOUNDS

the following field specifications must be met:

Columns 5-12	Alphanumeric
Columns 15-22	Alphanumeric
Columns 25-36	Numeric
Columns 40-47	Alphanumeric
Columns 50-61	Numeric.

Under the BOUNDS section, two exceptions are made. First, columns 2-3 contain either of the two-letter indicators "UP" or "LO" to show whether it is the upper or lower bound value of the decision variable that is punched on the particular card. Second, columns 25-61 are not used.

VITA

Hilary Isu Agha

Candidate for the Degree of
Doctor of Philosophy

Thesis: SELECTION OF OPTIMAL COMBINATIONS OF PRECAST, PRESTRESSED
CONCRETE COMPONENTS FOR SYSTEMS BUILDING CONSTRUCTION BY
LINEAR PROGRAMMING

Major Field: Civil Engineering

Biographical:

Personal Data: Born in Amika, Ozizza, Afikpo, Nigeria, on July 19,
the son of Mr. and Mrs. Agha Ogudu.

Education: Received West African School Certificate, Grade I,
Calabar, in 1959; received Cambridge Higher School Certificate
in Mathematics, Physics and Chemistry, from Saint Patrick's
College, Calabar, in 1961; received the Bachelor of Science
degree in Civil Engineering from San Jose State College,
California, in 1966; received Master of Engineering degree in
Structural Engineering from Brigham Young University, Provo,
Utah, in 1974; completed requirements for the Doctor of
Philosophy degree at Oklahoma State University in May, 1977.

Professional Experience: Civil Engineer--Construction and Maintenance, American Overseas Petroleum Company, Port Harcourt, Nigeria, 1966-70; Civil Engineer--Construction and Surveying, Bowman Brothers Ltd., Enugu, Nigeria, 1970-71; Technical Instructor and Executive Civil Engineer--Roads/Bridges, East Central State Government, Nigeria, 1971-72; graduate teaching and research assistant, Brigham Young University, Provo, Utah, 1972-73; graduate teaching and research assistant, Oklahoma State University, School of Civil Engineering, 1973-74; graduate teaching assistant, Oklahoma State University, School of Civil Engineering, 1975-76; evening tutor, Oklahoma State University, College of Engineering, 1975-76.

Professional Societies and Academic Honors: Member of American Society of Civil Engineers, American Concrete Institute, Chi Epsilon; Certificate of Graduate Excellence Award by the Graduate College, Oklahoma State University.