

Final Update and Safety Briefing



Whats Going On Fox23 News Team Visit













Whats Going On Senior Design Expo







Overview



Structures

SME: Austin Bennett, Jackson Jandreau, Andrew Quinton

Electronics & Pneumatics

 SME: Jake Briles, Josh Pankratz, Michael Raymer, Brandon White

Deployment & Retraction Systems

- SME: Joey Lester, Madison Whiteley
- Safety
 - SME: Michael Raymer
- Summary
- Questions



Overview



Each section will follow a specific pattern

- Overview
 - Introduction to topics and areas covered in section
- Progress
 - Photos of progress in area
 - Stills & data from tests
- Further Actions
 - List of items to be accomplished
 - Limiting Factors
- Summary
 - Estimation of progress relative to end state
 - List of major milestones prior to delivery



Structures Overview





8020 Structural Framing, Component Support Structure, Mobility, and Exterior



Structures Full Scale Progress





Structures Paneling and Framework





Structures Doors and Floors







Structures Progress Checklist



Development Objectives

- ✓ Scale Model
 - Material Selection
 - Construction
 - ✓ Finishing
- 8020 Superstructure
 - ✓ Static Dock Frame Construction
 - ✓ Mobile Bulkhead Construction
 - ✓ Wheelbase Installation
 - ✓ Deployable Floor Construction
 - Deployable Floor Finishing
- Exterior Finishing
 - Exterior Paneling Selection
 - Paneling Finishing
 - ✓ Door Construction
 - ✓ Door Installation

Integration Objectives

- ✓ Tube Integration
 - ✓ Development of Mounting Device
 - ✓ Production of Mounting Device
 - ✓ Integration
- ✓ Winch Integration
 - ✓ Development of Mounting Device
 - ✓ Integration
- Systems Integration
 - ✓ Space Allocation and Designation
 - ✓ Substructure Construction
 - Total Systems Integration



Structures Further Action



Development Objectives

- 8020 Superstructure
 - Deployable Floor Finishing
 - Installation of locking mechanism
 - Installation of Deployment Assistance Tool
- Exterior Finishing
 - Paneling Finishing
 - Final Installation of 8020 superstructure Panels
 - Fabric patch to gaps between tubes and 8020 superstructure

Integration Objectives

- Systems Integration
 - □ Total Systems Integration
 - Mounting Vacuum Pump



Structures Task Summary



- Final Non-trivial task Vacuum Pump
 - Failure if initial pump on 9 May (recovered& repurposed air mattress pump)
 - Replacement to be ordered and shipped, same day install

Trivial Tasks – Floor & Paneling

- All parts & equipment on site
- Requires less than 8 man-hours to complete





Electronics & Pneumatics Overview





Networked Electronic Components, Pneumatic Controls, and User Interfaces



Electronics & Pneumatics Pressure Schematic Progress







Electronics & Pneumatics Electronics Schematic Progress







Electronics & Pneumatics Progress







Electronics & Pneumatics Hypercoding Progress







Electronics & Pneumatics Progress Checklist



Programmatic Objectives

- Inflation Subroutine
 - ✓ Wench Controls
 - ✓ Relay Controls
 - ✓ Compressor Controls
 - ✓ Lighting Controls
 - Overall Logic
- Deflation Subroutine
 - □ As Above in Inflation Subroutine
- Normal Operations
 - ✓ Write Configuration File
 - ✓ Create and Rename Data Files
 - ✓ Network Pi Devices Together
 - ✓ Read and Store Data (Pi0 Code)
 - ✓ GUI
 - □ Final Review of Code

Integration Objectives

- ✓ Tube Integration
 - ✓ Read Pressure in Tubes
 - ✓ Minimize Pressure Losses
 - ✓ Data Reading Tests
- ✓ Wench Integration
 - ✓ Create Relay Circuit
 - ✓ Test Operation
- ✓ Pressure Lines
 - ✓ Create Relay Circuit
 - ✓ Test Operation
- ✓ Light Systems
 - ✓ Determine Lighting System for Use
 - ✓ Write Code for Lights
 - ✓ Test Lighting



Electronics & Pneumatics Progress Checklist



Programmatic Objectives

- Inflation Subroutine
 - Overall Logic
 - Finishing of fully automated routine
- Deflation Subroutine
 As Above in Inflation Subroutine
- Normal Operations
 - □ Final Review of Code
 - Implementation of final comments, organization, and variable names

Integration Objectives ✓ COMPLETE



Electronics & Pneumatics Task Summary



Finishing Automation

- System can be fully manually deployed with existing GUI and two technicians
- Automation architecture and pseudocode exists
- Finalization of control methodology and testing
- Finalization of Graphical Data Monitoring





Inflatables, Retraction Cables, and Related Systems



Deployment & Retraction Airbeam Progress







Electronics & Pneumatics Sewing and Installation







10 May 19



Deployment & Retraction Winch Integration Progress







Deployment & Retraction Winch Progress



The Retraction System is comprised of:



- motor mounting bracket
- shaft spool
- wire loop fastener
- 7 ft of 3/16 aero wire
- swinging loop frame mount
- 12V 8RPM reversible motor
- 12V DC adapter connector



Deployment & Retraction Progress Checklist



Deployment Objectives

- ✓ Inflation Elements
 - ✓ Tube Development & Sensor Integration
 - ✓ Tube Deployment & DAQ Test
 - ✓ Development of 1/3 of Tubes
 - Construction of All Inflation Elements
- Inflation Testing
 - ✓ Extended Single Tube Testing
 - ✓ Force & Burst Pressure Testing
 - ✓ Single Pressure Line Test
 - ✓ Testing Multiple Line Deployment
 - ✓ Electronics Integration
 - ✓ Winch Controlled Deployment Test
 - Complete Systems Test

Retraction Objectives

- ✓ Retraction Elements
 - $\checkmark~$ Winch Sizing and Selection
 - ✓ Winch Torque Testing
 - ✓ Winch Mounding Mechanisms
- ✓ Retraction Testing
 - ✓ Winch Relay Circuit
 - ✓ Winch Electronics Test
 - \checkmark Winch Structural Integration
 - ✓ Winch Controlled Reaction Testing



Deployment & Retraction Progress Checklist



Deployment Objectives

□ Inflation Testing

- Complete Systems Test
 - To be completed as code is written
 - Will continue up to delivery data

Retraction Objectives COMPLETE



Deployment & Retraction Task Summary



Finishing Automation

- System can be fully manually deployed with existing GUI and two technicians
- Automation architecture and pseudocode exists
- Finalization of control methodology and testing
- Bugfixing Expected to continue until just prior to Delivery to JSC





Safety Overview





Compliance, Guidelines, and Documentation



Safety Hazard Matrix Progress



| P= Risk to Pe | ersonnel | | | | | | | |
|-------------------------------|--------------------|--|--|------------------------------------|---------------------------------|--------------------------|------|----------------------------|
| A= Risk to | Assets | Hazard | Hazard | | | | | |
| Severity Classifications | | A: Frequent | B: Probable | C: Occasional | D: Remote | E: Improbable | Code | Description |
| | | | | | | | 01 | Electrocution |
| I: Catastro | ophic | | | | | | 02 | Fire |
| II: Critical III: Moderate | | | | | | A02, P02, A07 | 03 | C02 |
| | | | | | | | 04 | Structural Failure |
| | | | | | | A04, P04, A07 | 05 | Minor Injury |
| IV: Negli | igible | | | P09 | P05 | A01, P01, P03, P06, | 06 | Thermal |
| | 8.0.0 | | | | | P07, A08 | 07 | Pressure Vessel Rupture |
| RAC: 1 | Unacce tempora | ptable – All ope ary controls are | erations shall ceas in place and peri | e immediately ι manent controls | intil the hazar are in work. | d is corrected, or until | 08 | Pressure Lines |
| RAC: 2 | Undesir tempora | a ble – All opera ary controls are | is corrected or until | 09 | Entering Confined Spaces | | | |
| RAC: 3 | Accepta | ble with contro | is authorized to | Contined Spaces | | | | |
| RAC: 4-7 | Accept a | ble with contro with adequate | Slides | | | | | |



Safety Progress Progress









Safety & Documentation Progress



System Objectives

- ✓ Initial Safety Review
 - ✓ Initial Review of JPR 1700
 - Initial Development of Hazard Matrix
- □ Final Safety Review
 - Specific & Extensive Review of JPR 1700
 - Review & Update of Hazard Matrix

Administrative Objectives

- Documentation Development
 - ✓ Itemized Checklist of Applicable JPR Regulations
 - Systematic Review of Compliance with Regulations
 - Development of Technical Memorandum & Guidelines for the Safe Deployment, Employment, & Retraction



Safety Further Actions



System Objectives

- □ Final Safety Review
 - Specific & Extensive Review of JPR 1700 – Target Date: 05/12
 - Review & Update of Hazard Matrix – Target Date: 05/12

Administrative Objectives

- Documentation Development
 - Systematic Review of Compliance with Regulations – Target Date: 05/12
 - Development of Guidelines for Safe Usage – Target Date: 05/19



Safety & Documentation Task Summary



Safety Review

- Review specific concerns today
- Convert JPR 1700 to Excel document, and review line by line for applicability and coverage
 - Itemized Checklist (?)

Documentation Finalization

 Deployment checklists will be in progress until delivery, written as automation testing progresses





Summary Gantt Chart Through 12 May



| XHAB - "Stargate" Inflatable Crew Lock | Status As of | April May | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|--|-------------------|-----------|----|-----|-----|-----|-----|---|-----|---|------|-----|----------|-----|-----|--------------|-----|------|------|---|------|----|------|----|----|----|----|----|----|----|----|---|---|---|---|---|------|------|------|------|-----|----|----|
| Oklahoma State University | Today's Date | 1 | 2 | 3 4 | 4 ! | 5 (| 5 7 | 8 | 9 | 1 | .0 1 | 1 1 | 2 1 | 3 1 | 4 1 | 15 1 | 6 1 | .7 1 | .8 1 | 9 | 20 2 | 21 | 22 2 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 |
| | Today S Date | M | τV | N | Γ | F ! | S S | M | 1 Т | V | V 1 | F | - 5 | 5 S | S I | M | τV | V 1 | F F | F | S | S | M | T | w | Т | F | S | S | М | Т | W | Т | F | S | S | М | Т | W | Т | F | S | S |
| Structures | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Wheel Base Installation | Awaiting Material | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Subsystem Structure Installation | Awaiting Material | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Deployable Floor Construction & Installation | Awaiting Material | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Tube Mounting | Awaiting Material | | | | | | | | | | | 1 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Winch Mounting | Awaiting Material | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Exterior Panelling Installation | Awaiting Material | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Door Construction & Installation | Not Started | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Electronics & Pneumatics | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Pressure Line Electronic Support | Ongoing | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Light Systems Integration | Not Started | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Winch Electronic Support | Ongoing | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Inflation Subroutine Implementation | Ongoing | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Deflation Subroutine Implementation | Ongoing | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| GUI Implementation | Not Started | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Deployment & Retraction | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Construction of all Inflatable Elements | Ongoing | | | | | | | | | | 1 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Complete Pressure System Test | Not Started | | | | | | | | | | 1 | 1 | | | • | • | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Full Deployment Test | Not Started | | | | | | | | | | | | | | | \downarrow | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Full Retraction Test | Not Started | | | | | | | | | | | 1 | 7 | | • | + | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Safety & Documentation | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Extensive JPR 1700 Review | Not Started | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Finalized Hazard Matrix | Not Started | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Systematic Review of JPR 1700 Compliance | Not Started | | | | | | | | | | | | | | • | ŧ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Usage Guidelines & Safety Documentation | Not Started | | | | | | | | | | | | | | • | ↓ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Updated 1 April 2019 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | Кеу | | | |
| | _ | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | Earl | iest | Star | t Da | ite | | |

In Progress Date Date of Completion



Summary Task Breakdown



- Final Assembly on track for completion 10 May (Today!)
- Remaining work reliant upon testing of automation routines
 - Manual routine exists, checklist & manual in development
 - Requires up to 10 man-hours to fully implement and bugfix

Full Safety Review

Completion pending development of itemized checklist



Photos and Charts





Additional Information for the Curious



Hazard Summary (1/5)



| Hazard | Cause | Effect | Categ | jory | Mitigations | | | | | |
|----------------------------|---|--|-----------|--------|--|--|--|--|--|--|
| Description | Cuuse | Lincer | Personnel | Assets | | | | | | |
| 01 Electrocution | 1. Exposed wires 2. Improper electrical setup | Damage to electrical components Injury to personnel | 4E | 4E | Careful attention during soldering, wiring, assembling. Inspection of electrical & wiring systems by one of the team's systems engineer. | | | | | |
| 02 Fire | 1. Electrical components malfunction or complete failure resulting in overheating and catching fire. | Injury or death to personnel. Damage to or loss of analog | 2E | 2E | Students, OSU & NASA personnel assess equipment prior to testing for fire mitigation. Manual temp monitoring. There will be temperature sensors in the analog. These are monitored in real-time by the operator. Circuit breakers installed appropriately. Operator has direct control to cut power immediately. Sensors installed for smoke. Fire extinguishers on standby for immediate use | | | | | |



Hazard Summary (2/5)



| Hazard | Cause | Effect | Cate | egory | Mitigations | | | |
|-----------------------------|--|--|-----------|--------|--|--|--|--|
| Description | | | Personnel | Assets | | | | |
| 03 CO2 | 1. Too many personnel in the analog for too long | 1. Headaches, dizziness, mental underperformance | 4E | NA | CO2 sensor installed and routinely checked Analog is properly ventilated, naturally, by having the dock portion open to ambient air | | | |
| 04 Structural Failure | Damage during deployment Loss of beam pressure 8020 beam failure | Damage to equipment/structure Entrapment Collapse causing injury | 3Е | 3E | Quality control throughout construction Routine inspections Redundant structures Pneumatic system continuously monitored by team's systems engineer via user interface Emergency egress effective and briefed to personnel | | | |



Hazard Summary (3/5)



| Hazard | Cause | Effect | Cate | gory | Mitigations | | | | |
|--------------------------------|---|--|-----------|--------|---|--|--|--|--|
| Description | | | Personnel | Assets | | | | | |
| 05 Minor Injuries | 1. Sharp edges Trip hazards | Fillet or cover all sharp edges Ensure power cords or analog components are not posing a risk to tripping personnel | 4D | NA | Quality control throughout construction Routine inspections Redundant pressure lines/components | | | | |
| 06 Thermal | Demonstration moved outside Facility's AC not functioning Lack of hydration | Dehydration Heat stress Heat exhaustion Heat stroke | 4E | NA | Utilize facility cooling equipment Limited time outdoors Ensure personnel's hydration | | | | |



Hazard Summary (4/5)



| Hazard | Cause | Effect | Cate | gory | Mitigations | | | |
|--|---|---|-----------|--------|--|--|--|--|
| Description | | | Personnel | Assets | | | | |
| 07 Pressure Vessel Rupture | 1. Exceeding allowable pressure limits of the tanks. | Low speed release of low pressure air Sudden loud popping sounds | 4E | 3E | Monitoring pressure sensors, while staying well below vessel pressure limits & 0.5 psig threshold. Routine inspections Redundant layers of fabric for stress development This complies JPR 1700 6.11 Pressurized Gas and Liguid Systems | | | |
| 08 Pneumatic System Lines | Exceeding allowable pressure limits of pneumatic lines. Hole puncture or tear. | 1. Low-speed blasts of air. | NA | 4E | Redundant pressure lines/components Routine inspections This complies JPR 1700 6.11 Pressurized Gas and Liquid Systems | | | |



Hazard Summary (5/5)



| Hazard | Cause | Effect | Categ | gory | Mitigations | | |
|--|--|--|-----------|--------|--|--|--|
| Description | | | Personnel | Assets | | | |
| 09 Entering Confined spaces. | Low ceiling. Minimum walking space. | Minor body impact Tripping, falling | 4C | NA | Entry procedure. Padding on exposed hard surfaces. This complies JPR 1700 6.10 Entering Confined Spaces and Controlled Areas | | |



































