# PREDICTING CONSTRUCTION COST GROWTH IN

# **ODOT'S PAVING PROJECTS USING**

# INFORMATION AVAILABLE

# AT THE BIDDING TIME

 $\mathbf{B}\mathbf{y}$ 

# **BASSAM AHMED GHULMAN**

Bachelor of Science Umm Al-Qura University Makkah, Saudi Arabia 1991

Master of Science Oklahoma State University Stillwater, Oklahoma 1997

Submitted to the Faculty of the Graduate College of the Oklahoma State University in partial fulfillment of the requirements for the Degree of DOCTOR OF PHILOSOPHY May, 2000

# PREDICTING CONSTRUCTION COST GROWTH IN ODOT'S PAVING PROJECTS USING

# INFORMATION AVAILABLE

# AT THE BIDDING TIME

Thesis Approved:

Sauld D. Oberlander Thesis Advisor
Thesis Advisor
Ol Sent K. Hughn
Dance Holyon
amlena
· ·
J. Feath Tune
4
1. James B Pourell

Dean of the Graduate College

## **ACKNOWLEDGMENTS**

I wish to express my sincere appreciation to my major advisor, Dr. Garold Oberlender, for his supervision, guidance, inspiration, and friendship. My sincere appreciation extends to my other committee members, Dr. Dana Hobson, Dr. J. Scott Turner, Dr. Robert Hughes, and Dr. William Warde for their assistance and encouragement. I would also like to thank the Department of Civil Engineering and every member in its family for their support.

More over, I wish to express my sincere gratitude to those who provided suggestions and assistance for the research: Mr. Jack Stewart, ODOT division engineer, Mr. Byron Poynter, ODOT construction engineer, and ODOT resident engineers and contractors who participated in various phases of the research.

In addition, I would like to give my special appreciation and thanks to my mother, Mrs. Seham Shukri; my brothers, Dr. Mahmoud, Dr. Hamza, and Dr. Motaz; and my wife Maha, for their contineous prayer and support during the study period.

Finally, I would like to thank God, the most gracious, most merciful, for granting me the ability to accomplish my goals and for giving me the oppurtunity to enjoy everything good in life.

# TABLE OF CONTENTS

	Page
CHAPTER I INTRODUCTION	1
Background	1
Purpose	2
Objectives	2
Assumptions	3
Scope and Limitations	3
Definitions	5
Research Methodology	6
Chapter Summaries.	10
CHAPTER II REVIEW OF LITERATURE	11
Introduction	11
Impacts of Project Changes	11
Cost and Schedule Growth During Construction	13
Preliminary Estimates for Construction Cost	13
Construction Cost Factors	13
Using Bid Data to Predict Construction Cost Overrun	
Summary	
CHAPTER III DATA COLLECTION PROCEDURES	
Introduction	

Survey Questionnaires	18
Introduction	18
Objective	19
Target Population	19
Survey Population	19
Frame	20
Frame Problems	20
Sampling Design	21
Data Collection Method	22
Questionnaires Design.	23
Pretest and Validation	26
Analysis of Response	26
Determination and Ranking of Factors	28
Collection of Project Information.	31
Introduction	31
Selection Criteria	31
Search Process	33
Project Data	33
Data Entry, Storage, and Processing	35
Data Preparation for Analysis	36
Demographics of the Projects	39
CHAPTER IV DATA ANALYSIS TECHNIQUES AND STATISTICS	43
Introduction	43

The Survey		44
Factors included in t	he Analysis	50
Principal Componen	ts Analysis	54
Factor Analysis	· · · · · · · · · · · · · · · · · · ·	58
Regression Analysis		65
CHAPTER V DATA AN	ALYSIS RESULTS	67
The Survey		67
Consistency and Mu	lticollinearity of the Data	68
Factor Groups (Princ	cipal Factors)	68
Regression Analysis	of the Cost Factors	69
The Prediction Mode	el	71
CHAPTER VI SUMMAI	RY, CONCLUSIONS, AND RECOMMENDATION	IS75
Summary	•••••••••••••••••••••••••••••••••••••••	75
Conclusions		78
Recommendations	•••••••••••••••••••••••••••••••••••••••	80
SELECTED BIBLIOGRAP	HY	83
APPENDICES	••••••	85
APPENDIX A	IRB APPROVAL FORM	86
APPENDIX B	THE QUESTIONNAIRES COVER LETTER	88
APPENDIX C	PROJECT DATA	90
APPENDIX D	THE CORRELATION MATRIX	145
APPENDIX E	SAS PROGRAM	148
APPENDIX F	SAS OUTPUT	159

# LIST OF TABLES

Page
Table 1 - A Summary of the Responses to the Questionnaires
Table 2 - Participants' Responses to Factors included in the Engineers'
Questionnaires29
Table 3 - Participants' Responses to Factors included in the Contractors'
Questionnaires30
Table 4 - The Unavailable Factors and the Reasons behind their Unavailability32
Table 5 - Responses of Engineers' Questionnaires including Severity Indices45
Table 6 - Responses of Contractors' Questionnaires including Severity Indices46
Table 7 - Factors included in the Questionnaires, their impact, and Ranking48
Table 8 - Availability of the Factors included in the Questionnaires
Table 9 - Primary List of Factors included in the Analysis
Table 10 - Variables included in the Analysis, their Symbols, Types, and Units55
Table 11 - Principal Factors Recommended by Factor Analysis & Variables included62
Table 12 - Rotated Factor-Loading Matrix for Eight Factors64
Table 13 - The Selected Factor Groups, or Principal Factors, and Variables included69
Table 14 - Regression Analysis Results on the 14 Variables70
Table 15 - Regression Analysis Results on the 4 Significant Variables71
Table 16 - Values of R.E. in Equation 5.172

Table 17 - Calculation of Principal Factors in Equation 5.1	73
Table 18 - Elements influencing Cost Growth and Factors included	79

# LIST OF FIGURES

	Page
Figure 1 - Research Steps	7
Figure 2 - The Engineers' Questionnaire	24
Figure 3 - The Contractors' Questionnaire	25
Figure 4 - A Data Entry Form for a Selected Project	37
Figure 5 - A Data Analysis Form for a Selected Project	38
Figure 6 - Distribution of Projects by Type	40
Figure 7 - Distribution of Projects by Letting Date	40
Figure 8 - Distribution of Projects by Contract Amount	41
Figure 9 - Distribution of Projects by Unit System	41
Figure 10 - Distribution of Projects by Duration	42
Figure 11 - Distribution of Projects by Cost Changes	42
Figure 12 - Blob Plot of the First Three Principal Component Scores	57
Figure 13 - Scree Plot of Eigenvalues	60
Figure 14 - Proportion and Cumulative Coverage of the Eigenvalues	61

# CHAPTER I

# INTRODUCTION

# Background

Construction cost growth can be defined as the increase in cost of a project. More precisely, it can be defined as the difference between final project cost and the initial contract amount. Change in a project cost results usually in either an overrun or an underrun. It remains one of the most important issues for all of the parties involved in a construction project. It is the goal of engineers and contractors to estimate, as accurately as possible, the actual final cost of a project because no one wants to lose profit or divert money from other projects to cover additional costs due to overrun or prevent other projects from being funded in the case of an underrun. For this research, cost growth and cost change are considered to have the same meaning.

The change in a project cost, or cost growth, occurs due to several factors, some of which are related to each other. Determining the existence and influence of each of these factors in a project may lead to better control on construction cost and assist in identifying possible solutions to avoid the expected over/underrun.

Previous studies of project changes have been directed towards identifying the factors that cause cost growth. There is a need for a study to determine the relationship

between those factors and to develop a statistical model to predict the amount of cost over/underrun in construction projects based on the relative influence of those factors.

# Purpose

The purpose of this study is to determine the factors related to cost growth in ODOT paving projects and to evaluate data from completed construction projects to study the influence of those factors. The relationship between the factors and the cost growth is observed and determined. A statistical model to predict the amount of cost overrun or underrun is developed based on those factors.

# **Objectives**

The objectives of the research are to (1) Identify the factors that may lead to cost changes, or cost growth, in ODOT paving projects. (2) Rank different factors according to their influence and impact on the cost changes. (3) Develop a numerical model, based on statistical theories and concepts, that predicts the amount of cost growth in ODOT paving projects using information available at the bidding time and based on the existence and relative importance of the factors identified in (2) above.

# Assumptions

The evaluation and analysis processes in this research are performed under several important assumptions. These assumptions are considered in order to use regression analysis and other statistical concepts and theories needed in the research to develop the mathematical model to predict the amount of cost growth. The assumptions are as follows:

- Cost factors included in the final prediction model are independent.
- No unusual values are observed during the regression analysis of cost factors.
- Values observed in different projects and included in the analysis are normally distributed.

# Scope and Limitations

To achieve the purpose and objectives of the research, information regarding the cost factors which may have an impact on the construction costs was gathered. Then, factors which have an influence on the construction cost were ranked according to their degree of influence. Data were collected from numerous completed construction projects. All information gathered in this research was collected from various estimating, design, and construction databases within ODOT. Regression analysis was performed on the data to show changes in construction costs.

The research was conducted in several phases. The first phase involved development of two questionnaires designed to get feedback regarding the cost factors

and their ranking. These questionnaires were distributed among ODOT engineers and contractors.

The second phase of the research involved analysis of data obtained from the questionnaire to identify and rank the final list of cost factors.

The third phase of the research involved the process of collecting project information related to cost data and determining the existence of any cost factor from the previously obtained list.

The fourth phase of the research involved analysis of the data collected in the third phase. In this phase, a statistical model was developed to predict the amount of cost growth for paving projects based on the information available at the bidding time.

All data collected and analyzed in this research were obtained from a single source: Oklahoma Department of Transportation (ODOT) paving projects. Therefore, the model can only be applied to ODOT paving projects. The model is also limited to projects with contract amounts less than five million dollars. It should also be noted that some cost factors are strongly related to economic conditions which may vary considerably from time to time. The variation in the economic conditions from the time of collecting the data to the time of predicting a project's cost growth may lead to inaccurate results.

# **Definitions**

"Cost Growth", "Cost Changes", and "Cost Over/Underrun" are considered, for the purpose of this research, to have the same meaning. They can be defined as the difference between the final project cost and the initial contract amount for a particular project.

"Contract" is an agreement between two or more parties to do a certain thing, which is legally enforceable. For the purpose of this research, all contracts are paving contracts.

"Owner" is the individual or organization for whom something is to be built or furnished under contract. For the purpose of this research, The Oklahoma Department of Transportation (ODOT) is the owner. It is the organization for which paving projects are to be built under contracts with paving contractors.

"Contractor" is the party who, for a stated price, supplies materials and performs construction services for the owner. For this research, it is the organization responsible for overall construction of paving projects, acting as general contractor or prime contractor.

"Project size" is to be defined as the cost in dollar amount of work involved in a project.

"Project location" is the county, one of seventy-seven counties in the State of Oklahoma, in which the project took place.

"Bid range" is the difference between the high and the low bids, in dollars.

"Money left on table", MLOT, is the difference between the low and the second low bids, in dollars.

"Contract difference" is the difference between ODOT estimate and the contract amount, in dollars.

"Bidding environment" is the number of projects let by ODOT during the month bids were opened.

"Timing of notice to proceed" is the period between contract award and notice to proceed, in calendar days.

# Research Methodology

Steps involved in the research are outlined in Figure 1. The first step focused on determining the cost factors from previous studies. Previous studies indicated important factors that had impact on the cost changes in construction projects. These factors were refined, and only factors related to paving projects were considered.

The second step involved the addition of other factors to those previously found.

Several discussion sessions and meetings were held with ODOT engineers and committee members in order to determine what other influencing factors could be added to the list.

Finalizing the list of cost factors was the focus of the third step in the research.

Factors from the previous two steps were combined to form the final list of cost factors which was used in the following steps. Wording of the factors was carefully checked to ensure simple and clear words.




Figure 1 – Research Steps

The fourth step involved developing, constructing, and distributing the questionnaires. Two questionnaires, one for ODOT engineers and the other for ODOT prequalified contractors, were developed. The engineers' questionnaire contained factors related to engineers, whereas the contractors' questionnaire contained factors related to contractors. Factors found to be related to both engineers and contractors were added in both questionnaires. The questionnaires were mailed to engineers and contrctors and a deadline was established to return the responses to ensure that responses would be received within an acceptable period of time.

Analyzing the responses to the questionnaires was performed in the fifth step.

Participants' responses were received and analyzed to evaluate those cost factors that were thought to have impact on the cost growth. According to the participants' point of view, significance of each factor was determined. In addition, simple calculations were performed on the responses to establish a severity index and a ranking for each factor contained in the questionnaires.

The sixth step involved checking the availability of information of the significant factors. After significant factors were determined, it was necessary to determine whether or not data related to those factors were available in ODOT files for the paving projects to be included in the analysis phase. Only factors with suitable available data were kept and considered as variables in the analysis procedures.

In the seventh step, files in the ODOT offices were searched to identify paving projects that met the established criteria. A total of 266 paving projects were selected for analysis in this research.

A database was designed and created in the eighth step. Tables, queries, and forms were designed and created within the database to make the process of entering and maintaining the project data easier and more convenient. Project data were stored in the database in a table format compatible with the Microsoft Excel Spreadsheet and the Statistical Analysis System (SAS) software. Therefore, no further transformation processes were needed to prepare the data for use in the analysis phase.

In the ninth step, a principal components analysis was performed on the collected data to check the collinearity among variables and the existence of outliers. Collinearity was observed among some of the variables which indicated that some variables were related to each other and therefore could not be used together as separate variables during the regression analysis. Thus, performing factor analysis on the variables was found to be necessary to group the related variables in factors that could be statistically evaluated in the regression analysis. Also, several outliers were observed and marked.

Factor analysis was performed in the tenth step. Related variables were grouped in principal factors and the number of variables was determined.

The eleventh step involved performing the multiple regression analysis. Principal factors that were determined in the factor analysis were used instead of individual variables. Categorical, non-numerical, variables were added to the principal factors forming the final set of variables used in the analysis process.

The predicting model was developed in the twelvth and last step. After a significance level was selected, several models containing different variables and having different  $R^2$  values were developed. All variables were statistically significant at the

specified significance level. The model that had the highest possible R<sup>2</sup>, highest practical significance, was selected to be the final prediction model.

# Chapter Summaries

In chapter II, the literature search of previous studies relating to construction cost, cost and schedule growth, impacts of project changes, construction cost factors, and construction cost overrun is discussed.

The data collection procedures are described in Chapter III. The surveying process including questionnaires design and development is discussed. Collecting, entering, storing, processing, and preparing project data are also described.

Demographics of the selected projects are also given to provide an overview of the projects involved in the research.

Data analysis techniques and statistics are described in Chapter IV. Analysis of the responses to the questionnaires, principal components analysis, factor analysis, and regression analysis are all discussed in this chapter.

The data analysis results are discussed in Chapter V. Implementation of the prediction model is also included.

Chapter VI provides a summary of findings, conclusions, and recommendations for further studies and research.

# CHAPTER II

# REVIEW OF LITERATURE

#### Introduction

Most of the publications related to project cost changes have been directed towards identifying the factors that cause or influence cost changes in projects that may lead to cost over/underrun. This chapter presents a summary of previous studies that have been conducted on cost changes and their impact on engineering and construction projects.

# Impacts of Project Changes

In their research study to quantify the impact that project changes have on engineering and construction project performance, Ibbs and Allen (1995) defined change as any event which results in a modification of the original scope, execution time, or cost of work. Because change may occur throughout all phases of a project, their research focused on the quantitative impact that change has on the detailed design and construction phase of projects. It was found that project change has a tremendous effect on the financial performance of a construction project. Improper change management

was exhibited in the increased incidence of negative impacts exhibited by project cost overruns, claims, and disputes.

A study by Hester, Kuprenas, and Chang (1991) found that most owners and engineers assume routine changes in the work will affect only the work in the changed area. It was proven that the effects can extend well beyond that area. It was explained that numerous other studies found that scope changes in projects were the most frequent source of changes and the most serious in terms of cost and schedule impact. When citing the impact of changes, all of the studies noted the consequential impact on the cost/schedule of the project as a whole.

Suhanic (1980) provided some quantitative estimates for the impact of changes on cost and schedules in a very limited manner. Thomas (1985) studied highway construction programs and reported on selected claims over changes and costs/schedule overruns on these same projects. It was found that project changes had a direct effect on costs and schedules of construction projects, primarily cost/schedule overruns.

Research by Zeitoun (1992) found that high cost and schedule growth occurred primarily in the last quartile of the construction phase. No specific reasons were given or addressed in the research for having high project growth in the last quartile of construction, but it was believed that project change was among the major reasons. Project cost and schedule growth were accredited to project changes. For 71 of the fixed price projects included in the research, the average cumulative cost growth was 11.5% and the median cumulative cost growth was 8.6% at the end of the fourth quarter.

# Cost and Schedule Growth during Construction

The study by Zeitoun identified several factors that are early warning signs of cost and/or schedule growth during construction. The cost growth in this study was based on the dollar amount of approved change orders during construction and did not include the cost of claims at the end of the project. The study addressed fixed price and cost reimbursable projects separately.

# Preliminary Estimates of Construction Cost

A study by Hester, Kuprenas, and Chang (1991) indicated that the estimating method and the accuracy of project cost estimates could be major reasons for having cost changes. When an inaccurate original estimate prepared for a project is used and compared with the actual cost of that project, there will be a noticeable difference, which is referred to as a cost change.

# Construction Cost Factors

A study by Charles and Andrew (1990) indicated that cost overruns in construction contracts include change orders and claims. Factors that influence the construction change order rates causing cost overruns were identified. Those factors were size of the project, the difference between the low bid and the estimate, the type of

construction, the level of competition, the quality of contract documents, the interpersonal relations within the project, and the policies of the contractor. It was discovered that a cost overrun rate of one to eleven percent is more likely to occur on larger projects than smaller ones. Contracts with an award amount less than the estimate were found more likely to have cost overrun rates above five percent.

Okpala and Aniekwu (1988) found that there are twenty variables that could cause cost overruns and delays, and seven others that could result in cost overruns without necessarily causing delay. It was discovered that high construction costs can be minimized by minimizing lapses in the management of human and material resources. Four major reasons for high construction costs were identified: (1) shortage of materials; (2) methods of financing and payment for completed works; (3) poor contract management; and (4) price fluctuation.

The research completed by Zeitoun focused on identifying factors that are known prior to the commencement of construction. The purpose was to provide early warning signs of project cost and schedule growth. Several early warning signs were identified. Those warning signs showed statistical correlation with the final project cost and schedule growth. For fixed price projects, the early warning signals were in the categories of money left on the table, number of bidders, execution format, and bid solicitation. It was mentioned that professionals in the construction industry can use these factors to effectively manage project changes and control costs. For cost reimbursable projects, the early warning signals were in the categories of primary driving factors, execution format, quality, and work distribution. Low cost and schedule growth were indicated when quality was the driving factor in the project.

Elinwa and Buba (1993) identified thirty-one factors as causing cost overruns and delays in construction projects. These factors were found to have some sort of influence on construction project cost and schedule. Of those factors, shortages and cost of materials, fluctuation in prices of materials, mode of financing and payment for completed works, poor contract management, and improper planning were found to be the major factors behind high construction costs.

# Using Bid Data to Predict Construction Cost Overrun

A study by Farbarik (1994) was undertaken in an attempt to define which, if any, of the many factors encountered before construction can be used to predict increased construction costs. The research attempted to predict construction cost overruns using bid data. The study focused on what means the owner, whether public or private, can predict the cost of planned construction and how much reliance should be placed on conventional wisdom in this planning effort. This basic problem was broken down into several smaller problems including the accuracy and quality of the construction cost estimate, determining the amount of contingency funds that should be set aside to cover the cost of the changes, and determining the fundamental causes of the changes. It was identified in the study that of the information available at the time of bid, only the level of construction spending and the type of facility being constructed were found to have any significant statistical relationship to construction contract change order rates. It was concluded that the results of the analysis of the relationship of change order rates to other variables thought to affect or to be useful in predicting change order rates in construction

contracts were disappointing. Low correlation coefficients and inconsistent results were obtained during regression and chi square analyses. The results of several attempts to improve the results through the removal of outlier data and multiple regression analysis were mixed and unsatisfactory. A conclusion was reached that, based on the data presented in the study, there are too many variables, both known and unknown, affecting construction contract changes to be able to predict those changes at the time of bid.

In a study by Rosemond (1984), a detailed analysis of 300 Navy construction contracts was performed. It was concluded that there was no direct relationship between any variable, or simple combination of variables, and the change order rate, which was defined as the percentage increase, or decrease, in contract price over the original award amount. There was no relationship found between change order rates and the number of bids, winning bid to mean bid ratio, type of facility, and unemployment levels at the time of contract. However, it was found that change order rates appeared to be higher when the low bid was at least 15% below the estimate, and that change order rates were significantly lower when the low bid was within 3% or more than 20% higher than the estimate. No significant difference in change order rates could be detected where the low bid was between 3 and 16% either higher or lower than the estimate.

# Summary

Previous research efforts have provided a foundation for this research. Most of the previous research involved considerable efforts investigating changes in construction projects and their impact on the performance and other aspects of projects. Changes in construction contracts not only lead to increased costs. Changes also lead to contract delays and affect all aspects of construction projects. Whether the amount of the changes can be predicted was a common question raised at the end of most of those studies.

Several research studies indicated that cost growth, overruns and underruns, in construction contracts include change orders. It was found that project change has a tremendous effect on the financial performance of construction projects. Factors that influence the construction change order rates causing cost overruns were identified. It was indicated that the estimating method and the accuracy of cost estimates could be major reasons for having cost changes. Size of project, difference between the low bid and the estimate, type of construction, level of competition, quality of contract documents, policies of the contractor, and others were factors that influence the construction change order rates. Several other factors and variables that could cause cost overrun were identified. Some of those factors were found to be known prior to the commencement of construction and could be used as early warning signs of project cost growth.

Several research studies were conducted in an attempt to predict the amount of construction cost increase. Factors that could be used in the prediction were determined and used. The results of the analysis of the relationship of change order rates to other variables thought to affect or to be useful in predicting change order rates were disappointing. Low correlation coefficients and inconsistent results were obtained during regression and other analyses. No direct relationships were found between any variable, or simple combination of variables, determined and used and the change order rate, which was defined as the change in contract cost over the original award amount.

#### CHAPTER III

# DATA COLLECTION PROCEDURES

#### Introduction

This research was conducted in four phases. The first phase involved surveying ODOT engineers and contractors through two different questionnaires; the second phase involved the analysis of the responses to the questionnaires sent to the participants in the survey; the third phase involved the collection of project data about cost factors obtained from analyzing the responses to the survey, and the fourth phase involved the analysis of the data and the creation of the predicting model.

This chapter describes the first three phases of the research. Chapter IV discusses phase four related to data analysis.

# **Survey Questionnaires**

# Introduction

Cost change in the form of overrun or underrun in any construction project may occur due to several factors. These factors were called cost factors. Although previous studies established some of these factors, other factors were added in this research study

after several discussions with ODOT professionals and thesis committee members. The final list of factors consists of 33 cost factors.

Determining the existence, influence and effectiveness of each of the cost factors may lead to better control on construction cost and help to avoid expected cost overruns/underruns. To achieve this goal, there was a need for conducting a survey that included all parties involved in ODOT paving projects.

# Objective.

The main objective of the survey was to identify factors that are indicators of potential cost growth in ODOT paving projects. In addition, the purpose was to obtain the participants' responses about whether or not the 33 cost factors have an impact on the cost growth and the magnitude of the impact.

# Target Population

Warde (1990) defined the target population as the population about or from which we would like to be able to draw inference. According to this definition, the target population in the research was considered to be ODOT engineers and construction contractors who deal with paving projects.

# Survey Population

The survey population was defined by Warde as the population to or from which we can draw valid statistical inference. The survey population in this research was

considered to be ODOT engineers and contractors who could be reached to be questioned in the survey.

### Frame

Lists for division engineers, construction engineers, resident engineers and prequalified contractors were provided by ODOT. They were used as the frame in the survey. Names, positions, telephone numbers, fax numbers and mailing addresses were given in each list.

#### Frame Problems

Three important points should be considered when using the previously mentioned lists as a frame in order to construct or use the frame correctly. The points are as follows:

- 1. The survey population, not the target population, should be used.
- 2. The frame must contain every element of the survey population.
- 3. The frame must contain each element once.

Since these points were slightly violated in one way or another, several problems were observed when trying to construct and use the frame. These problems were:

a. Missing Elements or Non-Coverage. This usually occurs when elements from the survey population do not appear in the frame. An example of this type of problem is resident engineers and contractors who previously worked with ODOT on projects included in the research, but their names and addresses were no longer included in the list provided by ODOT. To solve this problem, all resident engineers and contractors whose names were mentioned in any of the projects included in the research were obtained from the old lists available at ODOT. Projects with names that could not be found on any list were excluded from the study.

- b. Blanks or Foreign Elements. This problem usually occurs when some elements appear in the lists while they are not elements in the survey population. As an example, some contractors were included in the lists while they did no paving projects with ODOT. They were considered foreign elements since the study was restricted to paving projects actually completed. Questionnaires returned with any indication of this problem were excluded from the study.
- c. Duplication. This type of problem usually occurs when elements of the survey population appear more than once in the lists used as a frame. ODOT usually updates its contractors' list by adding and deleting names. Some names were found to appear more than once on the list. This problem was solved by going through the names, considering the first entry to be the only valid occurance of that element.

# Sampling Design

The basic sampling design considered in the survey was the census. All engineers and contractors appearing on the ODOT lists were included in the survey. All elements of the survey population were included in the survey in order to get representative answers for the questionnaires.

# **Data Collection Method**

Four generally accepted methods were available for the collection of data in the survey. The methods were as follows:

- Personal Interviews. This method involves collecting data by an interviewer directly from every element in the survey.
- 2. Telephone Interviews. This method involves contacting the respondents on the telephone, asking them questions and recording their answers.
- Self-administered questionnaires. This method involves collecting the data from questionnaires that were completed by respondents.
- 4. Examination of available data. In this method, the data have already been collected and available to the researcher for further analysis.

Self-administered questionnaires were used as the method of data collection in the research. Considering this method, the data were collected through the respondents' completion of the questionnaire. The self-administered method was selected based on the following considerations:

- Time. Due to the fact that other steps in the research could not be started until the participants' responses to the survey were collected and analyzed, self-administered questionnaires were found to be the most suitable method.
- Expense. Self-administered was believed to be the most economical method of conducting a survey since the only costs were printing and postage for distribution of the questionnaires.
- Bias. This was an important reason for selecting the self-administered method.

  This method was believed to have the least bias compared to the others.

# Questionnaire Design

As mentioned previously, the survey was considered as a self-adminstered questionnaire. Since two different populations were involved, ODOT engineers and contractors, two different questionnaires were designed. Cost factors were divided into three groups: factors related to ODOT engineers, contractors, and both groups. Each questionnaire contained cost factors related to the targeted group.

The engineers' questionnaire consisted of three pages. The first page was the cover letter. The objective of the project, confidentiality guarantee, deadline and brief instructions were included in this page, as shown in Appendix B. The latter two pages contained questions about 22 different cost factors and an extra field for added ones. The engineers' questionnaire is shown in Figure 2.

The contractors' questionnaire consisted also of three pages. The first page was the same cover letter. The latter two pages contained evaluation questions about 28 cost factors and an extra field for added ones. The contractors' questionnaire is shown in Figure 3.

Seventeen cost factors were common to both engineers' and contractors' questionnaires. Thus, there were 5 factors that were unique to engineers and 11 factors that were unique to contractors.

In both questionnaires, a subjective opinion was requested. Opinion questions were designed to determine how the respondents think about different cost factors.

Typal or Likert scale was the method used to obtain information from the participants. The scale used was asymetric allowing only four points or options. The labels were no impact, minor impact, moderate impact, and major impact. The

# Predicting construction cost growth in ODOT's paving projects using information available at the bidding time

Please indicate whether or not the following factors have an impact or influence on the cost growth in ODOT's paving projects. Note that marking minor, moderate or major impact for any factor means that a relationship is assumed to exist between cost growth and that factor, and the factor can be used as an indicator for cost growth, whether it is an overrun or underrun.

or underrun.	No	Minor	Moderate	Major
-	Impact	Impact	Impact	Impact
Project type	Ö	Ö	Ö	O
(Surfacing, Resurfacing or Overlay)				
2. Project size	0	0	0	0
(volume of work involved in a project)				
3. Project location	0	0	0	0
(County in which the project took place)				
4. Project duration	0	0	0	0
5. Weather	0	0	0	0
6. Method of estimating	0	0	0	0
7. Availability of construction-cost data	0	0	0	0
8. Bidding environment	0	0	0	0
9. Period between design and time of bidding	0	0	0	0
10. Time allowed to review plans for bidding	0	0	0	0
11. Number of bids	0	0	0	0
12. Bid range	0	0	0	0
(the difference between the highest and the				-
lowest bids, low-to-high bid range)				
13. Money left on table	0	0	0	0
(the difference between the lowest and the		0.4		
second lowest bids)				
14. Difference between the engineer's				
estimate and the contract amount	0	0	0	0
15. Timing of work order	0	0	0	0
16. Contractor performing the work	0	0	0	0
17. Contractor's history of cost overrun	0	0	0	0
18. Contractor's participation in several				
projects at the same time	0	0	0	0
19. Fraudulent practices by Contractors	0	0	0	0
20. Resident Engineer	0	0	0	0
21. Mode of payment for completed work	0	0	0	0
22. Contract administration	0	0	0	0
23. Other factors				
a)	0	0	0	0
b)	0	0	0	0
c)	0	0	0	0

Figure 2 - The Engineers' Questionnaire

# Predicting construction cost growth in ODOT's paving projects using information available at the bidding time

Please indicate whether or not the following factors have an impact or influence on the cost growth in ODOT's paving projects. Note that marking minor, moderate or major impact for any factor means that a relationship is assumed to exist between cost growth and that factor, and the factor can be used as an indicator for cost growth, whether it is an overrun or underrun.

an overrun or underrun.	No	Minor	Moderate	Major
	Impact	Impact	Impact	Impact
1. Project type	0	0	0	0
(Surfacing, Resurfacing or Overlay)				
2. Project size	0	0	0	0
(volume of work involved in a project)				
3. Project location	0	0	0	0
(County in which the project took place)				
4. Project duration	0	0	0	0
5. Weather	0	0	0	0
6. Bureaucracy of bidding method	0	0	0	0
7. Bidding environment	0	0	0	0
8. Period between design and time of bidding	0	0	0	0
9. Time allowed to review plans for bidding	0	0	0	0
10. Metric/English units confusion	0	0	0	0
(in plans and specifications)				
11. Government policies, restrictions, and regulations	0	0	0	0
12. Out-of-state construction firms	0	0	0	0
13. Mode of payment for completed work	0	0	0	0
14. Method of estimating	0	0	0	0
15. Availability of construction-cost data	0	0	0	0
16. Contractor's participation in several projects at the				
same time	0	0	0	0
17. Number of bids	0	0	0	0
18. Money left on table	0	0	0	0
(the difference between the lowest and the second lowest				
bids)				
19. Timing of work order	0	0	0	0
20. Resident Engineer	0	0	0	0
21. Availability of labor	0	0	0	0
22. Fluctuation in prices of materials	0	0	0	0
23. Availability of equipment	0	0	0	0
24. Contract administration	0	0	0	0
25. Interim financing	0	0	0	0
26. Control of internal cost	0	0	0	0
27. Interest rates on operating funds	0	0	0	0
28. Waste on the job site	0	0	0	0
29. Other factors				
a)	0	0	0	0
b)	0	0	0	0
c)	0	0	0	0

Figure 3 - The Contractors' Questionnaire

respondent was asked to indicate whether or not each of the given cost factors have an impact on the cost growth, and to assess the magnitude of the impact by marking one of the labels in front of that particular factor.

#### Pretest and Validation

Before distributing the questionnaires, members of the graduate committee and selected ODOT engineers reviewed and critiqued the questionnaires to ensure that participants could respond to them with no difficulties. Additional modifications to the questionnaires were made to improve them based on suggestions of the committee and ODOT personnel. Validity of the questionnaires was determined by considering the following:

- 1. Are factors that are relevant to respondents included?
- 2. Are factors presented in a clear and unambiguous way?
- 3. Are respondents willing to give the information requested in the questionnaire?

# Analysis of Responses

While conducting the survey, several items were taken into consideration to achieve the maximum possible response rate. Some of these items were as follows:

Appearance of the questionnaire. The length and appearance of the questionnaire were believed to have a major effect on the response rate; long and poor looking questionnaires result in greater non-response. Since it was recognized that ODOT

- engineers and contractors had limited time to spend in answering questions, the questionnaires were short, clear and easy to answer.
- Cover letter. A cover letter was prepared on official, formal paper and attached to each questionnaire. It contained a brief description about the research and simple instructions on how to complete and return the questionnaire. Several statements were also added to assure the participants maximum confidentiality and to indicate how important and beneficial their participation would be in order to achieve the research objectives.
- Type of mailing. Prepaid self-addressed return envelopes were attached to the questionnaires for use by respondents. This was believed to create an obligation on the part of respondents who were inclined to throw the questionnaires away. The researcher believed that self-addressed return envelopes contributed to a higher response rate.
- Confidentiality of responses. The promise to keep the respondents' answers confidential provided a sense of security. In the cover letter attached to each questionnaire, participants were assured strict confidentiality and that at no time would they be identified in the research results.
- Use of deadline. Because the researcher believed that a pre-set deadline for responses could improve the response rate, it was used and mentioned in the cover letter. Care was taken to choose a deadline to allow sufficient time for preparing, sending, receiving and responding to the questionnaires.

Of the 203 questionnaires sent by mail to participants, 159 were distributed to contractors and 44 to ODOT engineers. Table 1 is a summary of the responses.

Table 1 - A Summary of the Responses to the Questionnaires

			Received		
Participant	Sent	Mail	Fax	Total	Response Rate
Engineers	44	26	1	27	61.36%
Contractors	159	48	2	50	31.45%

# Determination and Ranking of Factors

After the participants' responses were received, a simple analysis was performed to determine the impact and extent that each factor has on the cost growth. The analysis provided a ranking for each factor with respect to other factors included in the questionnaires. This analysis provided the relative importance of the factors from the perspective of the participants.

A summary of the participants' responses to different factors included in the owners' and contractors' questionnaires is shown in Tables 2 and 3 respectively.

In the engineers' questionnaire, all 22 factors except bid range were found to have impact on cost growth. Since it was believed that there should be some sort of relationship between bid range and cost growth, it was decided to involve all 22 factors in the analysis process.

In the contractors' questionnaire, all 28 factors except contract administration were found to have impact on cost growth. Because no data were found about contract administration for paving projects in ODOT files, this factor was ignored and not included in the analysis.

Table 2 - Participants' Responses to Factors included in the Engineers' Questionnaires

Factor	No Impact	Minor Impact	Moderate Impact	Major Impact
Project type	3	11	8	5
(Surfacing, Resurfacing or Overlay)	_			
2. Project size	2	7	9	9
(volume of work involved in a project)			2000 at 1 am 100 at 100	
3. Project location	5	7	9	6
(County in which the project took place)				
4. Project duration	4	11	11	1
5. Weather	7	14	5	- 1
6. Method of estimating	8	9	6	3
7. Availability of construction-cost data	10	11	2	2
8. Bidding environment	3	4	11	7
9. Period between design and time of bidding	2	9	13	3
10. Time allowed to review plans for bidding	5	6	13	1
11. Number of bids	3	9	8	5
12. Bid range	9	8	7	1
(the difference between the highest and the				
lowest bids, low-to-high bid range)				
13. Money left on table	7	9	7	2
(the difference between the lowest and the				
second lowest bids)				
14. Difference between the engineer's				
estimate and the contract amount	10	11	3	2
15. Timing of work order	2	10	12	3
16. Contractor performing the work	5	4	10	8
17. Contractor's history of cost overrun	6	7	8	5
18. Contractor's participation in several				
projects at the same time	3	4	12	7
19. Fraudulent practices by Contractors	8	11	3	3
20. Resident Engineer	5	10	9	3.
21. Mode of payment for completed work	8	13	3	2
22. Contract administration	4	12	9	1

Table 3 – Participants' Responses to Factors included in the Contractors' Questionnaires

	No	Minor	Moderate	Мајог
Factor	Impact	Impact	Impact	Impact
1. Project type	12	14	12	8
(Surfacing, Resurfacing or Overlay)				
2. Project size	3	6	17	20
(volume of work involved in a project)				
3. Project location	3	16	13	14
(County in which the project took place)				
4. Project duration	1	15	21	10
5. Weather	0	12	15	19
6. Bureaucracy of bidding method	7	18	10	12
7. Bidding environment	9	16	14	7
8. Period between design and time of bidding	13	24	6	4
9. Time allowed to review plans for bidding	2	17	24	4
10. Metric/English units confusion	7	14	11	15
(in plans and specifications)				
11. Government policies, restrictions,	0	8	19	20
and regulations				
12. Out-of-state construction firms	14	13	16	4
13. Mode of payment for completed work	9	12	17	9
14. Method of estimating	12	26	8	0
15. Availability of construction-cost data	16	19	10	1
16. Contractor's participation in several projects				
at the same time	4	14	17	12
17. Number of bids	8	17	15	7
18. Money left on table	12	20	9	5
(the difference between the lowest and the				
second lowest bids)				
19. Timing of work order	5	11	21	10
20. Resident Engineer	3	13	18	13
21. Availability of labor	0	6	18	23
22. Fluctuation in prices of materials	2	12	20	13
23. Availability of equipment	8	19	16	4
24. Contract administration	16	15	13	3
25. Interim financing	16	22	6	2
26. Control of internal cost	10	22	11	3
27. Interest rates on operating funds	11	20	13	2
28. Waste on the job site	5	25	9	7

All factors that had impact on cost growth as obtained from participants' responses to both questionnaires were considered in the analysis process. Each factor was considered as a variable.

ODOT files were then examined to ensure information was available on each project involved in the study. Information related to 19 of the factors was found. Information on the remaining 14 factors was found to be unavailable. Table 4 shows the unavailable factors and the reasons behind the unavailability of information in the files.

## Collection of Project Information

#### Introduction

In the previous section, factors that had impact on cost growth were identified and considered as variables in projects. For each project included in the analysis, there was input for each one of the variables. If data for the variables were not available directly from ODOT files, it was obtained either by performing simple calculations on the available information or by other ways as explained in the following section.

#### Selection Criteria

Data about ODOT projects were key to the research. Prior to searching ODOT files and databases, selection criteria were established to meet the scope of the research. This research applies only to paving projects that were awarded and completed between January 1995 and December 1998 with contract amounts less than or equal to 5

Table 4 - The Unavailable Factors and the Reasons behind their Unavailability

	Related to			Impact		
Factor	Contractors	Owners	Both	Contractors	Owners	Reason for Unavailability
Method of estimating			х	Minor	Minor	Not available in ODOT's files of projects.
2. Availability of construction-cost data			x	Minor	Minor	Not available in ODOT's files of projects.
Bureaucracy of bidding method	х			Minor	N/A	General, no unique input for each project.
4. Government policies, restrictions, and regulations	х			Major	N/A	General, no unique input for each project.
Contractor's participation in several projects at the same time			x	Moderate	Moderate	Not available in ODOT's files of projects.
6. Fraudulent practices by Contractors		х		N/A	Minor	Not available at bidding time.
7. Fluctuation in prices of materials	х			Moderate	N/A	Not available at bidding time.
8. Availability of equipment	х			Minor	N/A	Not available at bidding time.
9. Mode of payment for completed work			×	Moderate	Minor	General, no unique input for each project.
10. Contract administration		74.	x	No	Minor	Not available in ODOT's files of projects.
11. Interim financing	x		<u> </u>	Minor	N/A	Not available in ODOT's files of projects.
12. Control of internal cost	x			Minor	N/A	Not available in ODOT's files of projects.
13. Interest rates on operating funds	х			Minor	N/A	Not available in ODOT's files of projects.
14. Waste on the job site	×			Minor	N/A	Not available in ODOT's files of projects.

million dollars. Only projects meeting those criteria were included in the research.

#### Search Process

After the search criteria were established, ODOT files and databases were searched. Most of the needed information related to completed paving projects was available in the files and databases of the Construction Division and Office Engineer offices at ODOT.

The search process began at the offices of the Construction Division. "Record of Payments on Contracts" files were searched. Project descriptions, surfacing, resurfacing and overlaying, award date, completion date, and contract amount were identified and recorded.

At the Office Engineer offices, "Bid Opening Reports" were searched. These reports, sometimes called Bid Tabs, were collected for the period between January 1995 and December 1998. The "Letting Date" and "Project Number" in the "Bid Tabs" files were matched with those that appeared on the "Record of Payments". By combining the information retrieved from both sources, a complete set of information was gathered for projects that met the selection criteria.

## Project Data

For each project included in the study, the following information was retrieved and gathered directly from the files:

- Project number.
- Project location.

- Project type.
- Letting date.
- Number of bids.
- Lowest bid.
- Second lowest bid.
- Highest bid.
- Engineers' estimate.
- Contract amount.
- Actual cost.
- Duration.
- Contractor.
- Existence of out-of-state contractor in the bidding process.
- Work order date.
- Number of bad weather days.
- Resident engineer.

Figures representing the following information were calculated and obtained from the previously collected data:

- Money left on table.
- Bid range.
- Contract difference.
- Cost growth.
- Bad weather days ratio.
- Bidding environment.

- Timing of work orders.
- Number of paving projects awarded to contractor.
- Number of projects in which an overrun existed.
- Ratio of that number to total number of projects.
- Average overrun for contractor.
- Average cost growth for contractor.

Information about English and metric unit systems used in preparing plans and specifications of different projects was obtained directly from ODOT engineers. The Oklahoma Department of Labor was contacted and monthly unemplyment rate figures for the specified period were provided.

# Data Entry, Storage, and Processing

Prior to data collection, it was recognized that there was a need to establish a database to make entering, storing, and processing the data easier and more flexible.

Therefore, Microsoft Access was used to design and create a database containing project data.

Several tables were first created to contain project data gathered directly from ODOT files. Queries were then designed and created to perform simple calculations on the data to calculate values for each of the projects.

Because forms were believed to be the most suitable part of a database that can be used as an input screen, two forms were created. The first form, Data Entry Form, was used as an input screen. All data and information related to a project and collected from ODOT files appear on a single sheet. After each entry is made in the form about data for

a particular project, a new sheet appears automatically to allow for another project's data input. A data entry form for a selected project is shown in Figure 4.

The second form, Data Analysis Form, contained all information on the first form plus fields for calculating values from the existing data. All project data and information that were used in the analysis processes are shown on the Data Analysis Form. A data analysis form for a selected project is shown in Figure 5.

# Data Preparation for Analysis

All project information from both forms was stored directly in a table in the database. The table was designed and created using Access. It arranged the projects data in a row and column format; each row represented a project and the columns represented data and information collected, obtained, and calculated specifically for that particular project. The table was compatible with Excel and SAS. This made the information accessible and useable during the analysis phase without any further transformations.

The entire set of 266 paving projects collected and prepared for analysis and their data are shown in Appendix C.




Figure 4 - A Data Entry Form for a Selected Project




Figure 5 - A Data Analysis Form for a Selected Project

## Demographics of the Projects

Data from 266 paving projects were collected from ODOT files. Figure 6 provides a breakdown of the projects by project type. The vast majority of the projects, 210, were resurfacing projects. The number of surfacing and overlay projects was low.

Figure 7 shows the distribution of the projects by letting date. On the horizontal axis of the chart, the numbers 1, 2, 3, and 4 represent the years 1995, 1996, 1997, and 1998 respectively. Among the 266 projects included in the analysis, more projects were let in 1995 than any other year.

Figure 8 represents the breakdown of the projects by contract amount. The contract amount was divided into 7 categories. The largest number of projects was in the \$500,001-\$1,000,000 category. The smallest number of projects was in the >\$1,000,000 category.

Figure 9 shows the breakdown of the projects by the English or metric unit system used by ODOT in preparing plans and specifications for the projects included in the research. Projects in which both English and metric unit systems were considered were more than those in which only the English system was considered.

Figure 10 represents the distribution of the collected projects by duration. The duration was divided into 7 categories. The largest number of projects was in the 60-120 day category.

Figure 11 provides a breakdown of the projects by type of cost change. The vast majority of the projects, 202, included in the research had underrun. Fifty-nine projects had a cost overrun. Only five projects were completed on budget.




Figure 6 – Distribution of Projects by Type




Figure 7 – Distribution of Projects by Letting Date (Legend: 1-1995, 2-1996, 3-1997, 4-1998)




Figure 8 – Distribution of Projects by Contract Amount




Figure 9 – Distribution of Projects by Unit System




Figure 10 - Distribution of Projects by Duration




Figure 11 - Distribution of Projects by Cost Changes

### CHAPTER IV

## DATA ANALYSIS TECHNIQUES AND STATISTICS

### Introduction

The analysis phase of the research started after participants' responses were received and project data were collected. Responses of both questionnaires were analyzed to determine the severity index of each included factor and that index was used in the ranking process. Also, the analysis of the responses was important in determining factors to be used as variables while collecting project information.

After project data related to the specified factors were collected from ODOT files, principal components analysis was performed for two main reasons: to check whether there were outliers in the data and to get a correlation matrix that gives an indication of the relationship among the included factors, or variables.

Factor analysis was then performed on the numeric portion of the data to overcome the multicollinearity problem. Factors, or project variables, were grouped into meaningful subdivisions, or principal factors. No relationship was supposed to exist among them. Principal factors to be included in the development of the prediction model were then determined.

The principal factors and the non-numeric variables were then combined and multiple regression analysis was then performed on them based on the 266 observations.

The final prediction model was then created based on the results of this analysis.

### The Survey

Questionnaires were distributed and collected as described in Chapter III.

Responses to each factor included in the questionnaires were recorded. The total number of responses to a particular factor was recorded on the same line under the selected degree of impact. For example, if 11 participants marked the factor "Project Type" to have minor impact on cost growth, 11 would be written in the field in front of project type and under minor impact.

Severity index was then calculated for every factor included in the questionnaires.

The formula used for calculating the severity index was as follows:

where:

No Impact = number of times the factor was marked to have no impact

Minor Impact = number of times the factor was marked to have minor impact

Moderate Impact = number of times the factor was marked to have moderate impact

Major Impact = number of times the factor was marked to have major impact.

Tables 5 and 6 represent responses of engineers' and contractors' questionnaires respectively. Severity index of every factor, calculated as mentioned above, is shown in the last column of the tables.

Table 5 - Responses of Engineers' Questionnaires including Severity Indices

Factor	No Impact	Minor Impact	Moderate Impact		No Answer	Severity Index
1. Project type	3	11	8	5	0	69
2. Project size	2	7	9	9	0	79
3. Project location	5	7	. 9	6	0	70
4. Project duration	4	11	11	1	0	63
5. Weather	7	14	5	1	0	54
6. Method of estimating	8	9	6	3	1	56
7. Availability of construction-cost data	10	11	2	2	2	46
8. Bidding environment	3	4	11	7	2	72
Period between design and time of bidding	2	9	13	3	0	71
Time allowed to review plans for Bidding	5	6	13	1	2	60
11. Number of bids	3	9	8	5	2	65
12. Bid range	9	8	7	1	2	50
13. Money left on table	7	9	7	2	2	54
Difference between the Engineer's estimate and the contract amount	10	11	3	2	1	49
15. Timing of work order	2	10	12	3	0	70
16. Contractor performing the work	5	4	10	8	0	75
17. Contractor's history of cost overrun	6	7	8	5	1	64
18. Contractor's participation in several	<del>                                     </del>					
projects at the same time	3	4	12	7	1	75
19. Fraudulent practices by Contractors	8	11	3	3	2	51
20. Resident Engineer	5	10	9	3	-0	64
21. Mode of payment for completed work	8	13	3	2	1	51
22. Contract administration	4	12	9	1	1	59

Table 6 - Responses of Contractors' Questionnaires including Severity Indices

Factor	No Impact	Minor Impact	Moderate Impact		No Answer	Severity Index
Project type	12	14	12	8	4	108
2. Project size	3	6	17	20	4	146
Project location	3	16	13	14	4	130
4. Project duration	1	15	21	10	3	134
5. Weather	0	12	15	19	4	145
6. Bureaucracy of bidding method	7	18	10	12	3	121
7. Bidding environment	9	16	14	7	4	111
Period between design and time of Bidding	13	24	6	4	3	95
Time allowed to review plans for Bidding	2	17	24	4	3	124
10. Metric/English units confusion	7	14	11	15	3	128
Government policies, restrictions, and regulations	0	8	19	20	3	153
12. Out-of-state construction firms	14	13	16	4	3	104
Mode of payment for completed work	9	12	17	9	3	120
14. Method of estimating	12	26	8	0	4	88
15. Availability of construction-cost data	16	19	10	1	4	88
16. Contractor's participation in several projects at the same time	4	14	17	12	3	131
17. Number of bids	8	17	15	7	3	115
18. Money left on table	12	20	9	5	4	99
19. Timing of work order	5	11	21	10	3	130
20. Resident Engineer	3	13	18	13	3	135
21. Availability of labor	0	6	18	23	3	158
22. Fluctuation in prices of materials	2	12	20	13	3	138
23. Availability of equipment	8	19	16	4	3	110
24. Contract administration	16	15	13	3	3	97
25. Interim financing	16	22	6	2	4	86
26. Control of internal cost	10	22	11	3	4	99
27. Interest rates on operating funds	11	20	13	2	4	98
28. Waste on the job site	5	25	9	7	4	110

After severity indices were calculated, the ranking process involved arranging the factors according to their severity indices, starting with the factor that had the largest severity index. Because some factors had the same severity index, the previously described ranking process alone did not assign every factor a unique rank. The severity index was considered a primary ranking. A secondary and final ranking process was performed in order to assign an advanced order in rank to the factor that had larger number of "Major Impact" marks.

The overall degree of impact of the factors was then determined. Each factor was assigned the degree of impact that received the maximum number of marks according to the questionnaires. In the engineers' questionnaire, all 22 factors, except bid range, were found to have impact on cost growth. Since it was believed that there was some sort of relationship between bid range and cost growth, the researcher decided to include all 22 factors in the analysis process.

In the contractors' questionnaire, all 28 factors, except contract administration, were found to have impact on cost growth. Because no data were found about contract administration for paving projects in ODOT files, it was decided to exclude that factor from the analysis.

All factors that had impact on cost growth, as obtained from participants' responses to both questionnaires, were included in the analysis process. Each factor was to be considered as a variable. Table 7 shows the factors included in both engineers' and contractors' questionnaires, their overall impact, and their ranking.

Table 7 - Factors included in the Questionnaires, their Impact, and Ranking

	Imp	act	Rank		
Factor	Contractors	Engineers	Contractors (1-28)	Engineers (1-22)	
Project type	Minor	Minor	19	8	
2. Project size	Major	Major	3	1	
3. Project location	Minor	Moderate	9	6	
Project duration	Moderate	Moderate	7	12	
5. Weather	Major	Minor	4	17	
6. Method of estimating	Minor	Minor	27	15	
7. Availability of construction-cost data	Minor	Minor	26	22	
Bureaucracy of bidding method	Minor	N/A	13	N/A	
Bidding environment	Minor	Moderate	16	4	
10. Period between design and time of bidding	. Minor	Moderate	25	5	
11. Time allowed to review plans for bidding	Moderate	Moderate	12	13	
12. Metric/English units confusion	Major	N/A	11	N/A	
13. Government policies, restrictions, and Regulations	Major	N/A	2	N/A	
14. Out-of-state construction firms	Moderate	N/A	20	N/A	
15. Number of bids	Minor	Minor	15	9	
16. Bid range	N/A	No	N/A	20	
17. Money left on table	Minor	Minor	21	16	
18. Difference between the Engineer's estimate and the contract amount	N/A	Minor	N/A	21	
19. Timing of work order	Moderate	Moderate	10	7	
20. Contractor performing the work	N/A	Moderate	N/A	2	
21. Contractor's history of cost overrun	N/A	Moderate	N/A	10	
22. Contractor's participation in several projects at the same time	Moderate	Moderate	8	3	
23. Fraudulent practices by Contractors	N/A	Minor	N/A	18	
24. Resident Engineer	Moderate	Minor	6	11	
25. Availability of labor	Major	N/A	1	N/A	
26. Fluctuation in prices of materials	Moderate	N/A	5	N/A	
27. Availability of equipment	Minor	N/A	18	N/A	
28. Mode of payment for completed work	Moderate	Minor	14	19	
29. Contract administration	No	Minor	24	14	
30. Interim financing	Minor	N/A	28	N/A	
31. Control of internal cost	Minor	N/A	22	N/A	
32. Interest rates on operating funds	Minor	N/A	23	N/A	
33. Waste on the job site	Minor	N/A	17	N/A	

ODOT files were then examined to ensure availability of information on each project involved in the study. Information related to 19 of the factors was found. No information was found for the remaining 14 factors. Both groups of variables are shown in Table 8. Table 4 in Chapter III represents the unavailable factors and the reasons behind the unavailability of information in the files.

Table 8 – Availability of the Factors included in the Questionnaires

Available Factors	Unavailable Factors
1.Project type	1.Method of estimating
2.Project size	2.Availability of construction-cost data
3.Project location	3.Bureacracy of bidding method
4.Project duration	4.Govmnt. policies, restrictions, and regulations 5.Contractors' participation in several projects at
5.Weather	the same time
6.Bidding environment	6.Fraudulent practices by contractors
7.Period between design and time of bidding	7.Fluctuation in prices of materials
8. Time allowed to review plans for bidding	8.Availability of equipment
9.Metric/English unit confusion	9.Mode of payment for completed work
10.Out-of-state construction firms	10.Contract administration
11.Number of bids	11.Interim financing
12.Bid range	12.Control of internal cost
13.Money left on table	13.Interest rates on operating funds
14.Difference between the engineers' estimate and the contract amount	14.Waste on the job site
15.Timing of work order	
16.Contractor performing the work	
17.Contractors' history of cost overrun	
18.Resident Engineer	
19.Availability of labor	·

# Factors Included in the Analysis

As described previously, thirty-three factors were included in the questionnaires; twenty-two factors were related to engineers and twenty-eight to contractors. Also, it was described previously and shown in Table 8 that 19 factors were identified as available factors. Information related to those factors, or variables, on each project involved in the study was found and the factors were included in the analysis as variables. Table 9 represents the primary list of factors included in the analysis. Only available factors were considered in further analysis procedures.

Since the research was restricted to paving projects, "Project type" was found to be one of the three types: surfacing, resurfacing, or overlay.

"Project size" was reprsented by the contract amount in dollars.

The data used in the research were obtained from ODOT files for paving projects throughout the state. Therefore, any of the 77 counties in the State of Oklahoma was a possible input for "Project location".

"Project duration" was represented in the analysis by the number of calendar days awarded for each project.

The number of bad weather days for a project during construction was defined as "Bad weather days". Since it was obvious that big projects with long durations would have larger numbers to represent this variable than short-duration projects, it was necessary to include "Ratio of bad weather days" calculated as "Bad weather days" divided by "Duration".

Table 9 - Primary List of Factors included in the Analysis

36% 415		Related		
No.	Factor	Engineers	Contractors	Availability
1	Project type	Х	Х	Х
2	Project size	Х	Х	Х
3	Project location	Х	Х	X
4	Project duration	Х	Х	X
5	Weather	Х	Х	Х
6	Method of estimating	Х	Х	
7	Availability of construction-cost data	Х	Х	
	Bureaucracy of bidding method		Х	
9	Bidding environment	Х	Х	Х
	Period between design and time of bidding	Х	Х	Х
	Time allowed to review plans for bidding	Х	Х	Х
	Metric/English units confusion		Х	X
	Government policies, restrictions, and regulations		Х	
14	Out-of-state construction firms		Х	Х
	Number of bids	Х	Х	Х
	Bid range	X		X
	Money left on table	X	Х	X
	Difference between the Engineer's estimate and		- //	
154	the contract amount	X		х
19	Timing of Notice to Proceed	Х	Х	X
	Contractor performing the work	X		X
	Contractor's history of cost overrun	X	ř.	X
	Contractor's participation in several projects at			
	the same time	X	Х	
	Fraudulent practices by Contractors	Х		
	Resident Engineer	Х	Х	X
	Availability of labor		Х	X
	Fluctuation in prices of materials		X	
	Availability of equipment		Х	
	Mode of payment for completed work	Х	Х	
29	Contract administration	Х	X	
	Interim financing		Х	
31	Control of internal cost		X	
32	Interest rates on operating funds		Х	
33	Waste on the job site		X	
Total	33	22	28	19

"Bidding environment" was identified as a numeral value by the number of projects let by ODOT at the same month a project was awarded.

Except for very large and unique projects, designs of most of the paving projects were prepared by the same manner by ODOT designers and engineers. No large variation was found in the information related to "period between design and time of bidding". Therefore, this factor was excluded from the analysis.

A fixed number of days was given to contractors to review plans for bidding.

Since the number was the same in all the projects, there was no variation in the data related to "Time allowed to review plans for bidding". Therefore it was excluded from the analysis.

Traditionally, the plans and specifications for ODOT Projects were prepared using the English unit system. In recent years, both English and metric systems were used. This led to the fact that "Metric/English unit confusion" was represented in the analysis by either English or English/metric.

"Out-of-State construction firms" denotes the existence of out-of-state construction firms in a project either as bidders or contractors. This factor, or variable, was represented in the analysis by either "yes" or "no".

"Number of bids" was represented by a simple number that indicates the number of bids submitted for a project.

"Bid range" was calculated as the difference between high and low bids. To avoid bias towards large projects, it was replaced with "Bid range ratio" caclulated as the bid range divided by the contract amount.

"Money left on table" was calculated as the difference between the low and the second low bids. Because it was believed that money left on table is directly related to size of the project, it was replaced with "Money left on table ratio" calculated as money left on table divided by contract amount.

"Contract difference". It was found to be greatly related to project size. Therefore,
"Contract difference" was replaced with "Contract difference ratio" which was calculated
as the difference between the engineers' estimate and the contract amount, divided by
contract amount.

Since information about "Notice To Proceed" was available for the projects included in the study, "Timing of work order" was replaced with "Timing of Notice To Proceed", calculated as the period between contract award and notice to proceed, in calendar days.

"Contractor performing the work" and "Resident engineer" were simply named "Contractor" and "Resident engineer" respectively.

"Contractors' history of cost overrun" was represented by the number of projects the contractor had with ODOT, the number of projects in which the contractor had an overrun, the ratio of the number of projects with overrun to total number of projects, average amount of overrun in all projects that had overrun, and average cost growth the contractor experienced in all projects. They were named "Number of projects", "Number of projects with overrun", "Ratio of projects with overrun", "Average overrun", and "Average cost growth" respectively.

"Availability of labor" was represented by unemployment rate figures for the State at the time of bid opening. These were simply named "Unemployment rate".

For the reasons mentioned above, factor 7 "Period between design and time of bidding" and factor 8 "Time allowed to review plans for bidding" of available factors shown in Table 8 were excluded from the analysis. Also, Factor 5 "Weather" and factor 17 "Contractors' history of cost overrun" were replaced with 2 and 5 new factors respectively. Therefore, a final list of 22 factors was included in the analysis. As mentioned previously, these factors were considered variables in the analysis phase. Of these 22 variables, 16 were numeric and 6 were nonnumeric, or categoric.

In addition to the 22 variables, "Project identification number" was added as an identifier. "Cost growth" was considered as the dependent variable in the analysis. Thus, the total list contained 24 variables.

Each variable included in the analysis was assigned a symbol rather than the variable name. The project identification number was given the symbol "id", the 22 independent variables were given symbols from x1 to x22, and the dependent variable was assigned the symbol "Y". Table 10 shows the final list of 24 variables, their symbols, types, and units.

## Principal Components Analysis

From the total list of 24 variables shown in Table 10, a principal components analysis was performed on the 16 numeric variables based on the 266 observations (projects). Principal components analysis is a variable-directed multivariate method

concerned with relationships that might exist among variables being measured. It was performed to screen the data for possible outliers. Outliers are defined as sample data points that appear to be inconsistent with a majority of the data. Their existence in the data during the analysis may cause a statistical analysis to be invalid or misleading.

Table 10 - Variables included in the Analysis, their Symbols, Types, and Units

No.	Symbol	Variable	Туре	Unit
1	x1	number of bids	numeric	numbers
2	x2	contract amount	numeric	\$
3	х3	duration	питепс	calendar days
4	х4	number of projects	numeric	numbers
5	х5	bad weather days	питегіс	calendar days
6	х6	ratio of bad weather days	numeric	ratio
7	х7	bidding environment	numeric	numbers
8	x8	timing of notice to proceed	numeric	calendar days
9	х9	number of projects with overrun	numeric	numbers
10	x10	ratio of projects with overrun	numeric	ratio
11	x11	average overrun	numeric	number (%)
12	x12	average cost growth	numeric	ratio
13	x13	unemployment rate	numeric	number (%)
14	x14	money left on table ratio	numeric	ratio
15	x15	bid range ratio	numeric	ratio
16	x16	contract difference ratio	numeric	ratio
17	x17	location	nonnumeric	-
18	x18	project type	nonnumeric	-
18	x19	contractor	nonnumeric	-
20	x20	resident engineer	nonnumeric	-
21	x21	unit system	nonnumeric	-
22	x22	existence of out-of-state firm	rionnumeric	-
23	ld	project identification number	numeric	-
24	Y	cost growth	numeric	ratio

Another reason for performing principal components analysis was to check the existence of multicollinearity among the predictor variables. Multicollinearity was checked and observed through the correlation matrix provided by SAS in the principal components procedure's output.

A procedure called PRINCOMP was used to perform the principal components analysis. The analysis was performed on the data, and a new set of data that contained values of the principal components scores was created. These new data contained all of the original data plus the principal component scores. Since 16 numeric variables were included in the analysis, 16 principal component scores were created and labeled PRIN1, PRIN2, PRIN3, ..., PRIN16. A blob-type plot of the first three principal component scores, shown in Figure 12, was created for examining the data included in the study and for checking the data for possible outliers.

An observation of the plot of the first three principal component scores shown in Figure 12 indicates no unusual data points. The points appear to fall into an elliptically shaped regions with major axes close to be parallel to the second principal component axes. The four points in the upper part and the one point in the lower left-hand corner of the plot could be outliers.

Appendix D shows a correlation matrix obtained by SAS during the analysis. It was used to check whether or not multicollinearity exists among variables included in the analysis. Several variables were found to be related. The related variables were identified and it was decided that this problem would be addressed during factor analysis.




Figure 12 – Blob Plot of the First Three Principal Component Scores

## Factor Analysis

Factor analysis is a variable-directed technique to explain the correlation structure among the measured variables. It was performed on the 16 numeric variables of the data to overcome the multicollinearity problem by deriving, creating, and developing a new set of uncorrelated variables that could be used in future analyses of the data. When that set of factors was derived, there was a need to perform a factor rotation for a clearer interpretation. An important decision that needed to be made during factor analysis was the determination of the number of factors to be considered and included in the regression analysis during the process of developing the prediction model. Minimum eigenvalue, scree plot, and variation coverage were among the methods that could be used for that purpose.

The factor analysis process began with the FACTOR procedure considering the minimum eigenvalue criterion "MINEIGEN" to determine the number of factors to be included in the factor analysis. This method selects the number of factors by obtaining the principal components of all the numeric variables included in the analysis, ranking their eigenvalues starting with the greatest, then selecting the number of eigenvalues greater than one as the number of factors to include in the factor analysis. This method produced 7 factor groups to be included in the analysis, based on the 16 numeric variables and 266 observations.

Figure 13 shows a SCREE plot of the eigenvalues produced by the FACTOR procedure. This was the second method to determine the number of factor groups to be included in the analysis. The number of factor groups recommended by the scree plot

method was determined by taking the number of eigenvalues at which the line started to deflect and considering that number as the number of factor groups. On the graph, it was shown that either 5 or 6 could be considered as the number of factor groups. Both were taken as alternatives.

Variation coverage was the last method used to determine the number of factor groups needed to represent the 16 numeric variables in the analysis. Figure 14 represents the 16 eigenvalues obtained during the analysis with their proportion and cumulative coverages. The procedure was performed to establish a percent coverage and to select the number of eigenvalues that gives at least that target percentage. Eighty percent coverage was selected, and 8 was found to be the first number of factor groups at which the cumulative variation exceeded 0.80. Therefore, 8 factor groups were selected by this method to be included in the analysis.




Figure 13 – Scree Plot of Eigenvalues

	. 1	2	3	4
Eigenvalue	2.9218	2.4849	1.8837	1.4621
Difference	0.4369	0.6012	0.4216	0.2133
Proportion	0.1826	0.1553	0.1177	0.0914
Cumulative	0.1826	0.3379	0.4556	0.5470
			•	
	. <b>5</b>	6	7	8
Eigenvalue	1.2488	1.0656	1.0273	0.9147
Difference	0.1833	0.0383	0.1126	0.1895
Proportion	0.0781	0.0666	0.0642	0.0572
Cumulative	0.6251	0.6917	0.7559	0.8131
i .				
	9	10	11	12
Eigenvalue	0.7252	0.5940	0.5494	0.4329
Difference	0.1313	0.0446	0.1165	0.1424
Proportion	0.0453	0.0371	0.0343	0.0271
Cumulative	0.8584	0.8955	0.9298	0.9569
a transfer of the second of th			·.	
	13	. 14	15	16
Eigenvalue	0.2905	0.2395	0.1130	0.0467
Difference	0.0510	0.1265	0.0663	
Proportion	0.0182	0.0150	0.0071	0.0029
Cumulative	0.9750	0.9900	0.9971	1.0000

Figure 14 – Proportion and Cumulative Coverage of the Eigenvalues

As mentioned previously, a factor rotation procedure was needed in order to keep the factors uncorrelated. Several rotation procedures were considered. The Varimax procedure was selected because this procedure is commonly used in statistical analysis and it does not require iterative calculations.

In the three methods described previously, four different numbers of factor groups were recommended, 5, 6, 7, and 8. Table 11 is a summary of different methods used to determine the number of factor groups, number of factor groups recommended by each method, and variables included in each factor group.

Table 11 - Principal Factors Recommended by Factor Analysis and Variables Included

Method	No. of Factors	Variables included
l. Default	[7]	
(MINEIGEN)	10,11,12	(ratio of projects with overrun, average overrun, average cost growth)
	4,9	(number of projects, number of projects with overrun)
	5,6,7	(bad weather days, ratio of bad weather days, bidding environment)
	2,3	(contract amount, duration)
	1,16	(number of bids, contract difference ratio)
	14,15	(MLOT ratio, bid range ratio)
	8,13	(timing of Notice To Proceed, unemployment rate)
II. Scree 1	[6]	
	10,11,12	(ratio of projects with overrun, average overrun, average cost growth)
	4,9,14	(number of projects, number of projects with overrun, MLOT ratio)
	1,15,16	(number of bids, bid range ratio, contract difference ratio)
	2,3	(contract amount, duration)
	5,6,7	(bad weather days, ratio of bad weather days, bidding environment)
	8,13	(timing of Notice To Proceed, unemployment rate)
III. Scree 2	[5]	
	4,9,10,11,12	(no. of projects, no. of projects w/ overrun, ratio of projects w/ overrun, avg overrun, avg cost growth)
,	1,3,5	(number of bids, duration, bad weather days)
	2,14,15,16	(contract amount, MLOT ratio, bid range ratio, contract difference ratio)
	6,7	(ratio of bad weather days, bidding environment)
	8,13	(timing of Notice To Proceed, unemployment rate)
IV. 80%	[8]	
(Variation Coverage)	10,11,12	(ratio of projects with overrun, average overrun, average cost growth)
	4,9	(number of projects, number of projects with overrun)
	5,6	(bad weather days, ratio of bad weather days)
	2,3	(contract amount, duration)
	1,16	(number of bids, contract difference ratio)
	14,15	(MLOT ratio, bid range ratio)
	8,13	(timing of work order, unemployment rate)
	7	(bidding environment)

After three different methods were applied in the factor analysis to determine the number of factor groups to be included in the regression analysis, a decision was required regarding which method to select. The interpretability and meaningfulness of the resultant groups were the major criteria considered in the decision process. As shown in Table 11, each method provided different factors containing different groups of variables. The minimum eigenvalue, scree plot 1, scree plot 2, and 80% coverage methods produced 7, 6, 5, and 8 factors respectively. In all the methods, the only agreement was found to be that variables x8 and x13 were grouped together. The other factor groups and the included variables were similar, but not the same. Scree plot 2 produced a grouping of variables that was somewhat different than the other 3 methods. The factor groups produced by the 80% variation coverage were found to be the most interpretable and meaningful grouping among the previously described methods. The resultant variable groups made the most theoretical and practical sense. Therefore, the 80% variation coverage was selected in the analysis.

Based on the 80% variation coverage, eight factor groups were chosen to represent the sixteen numeric variables in the regression analysis. Variables represented and contained within each factor are shown in Table 11. Table 12 shows the rotated factor-loading matrix for the eight-factor analysis. The framed numbers in each factor column represent the variables included in that particular factor. For example, numbers adjacent to x10, x11, and x12 in factor1 column are framed indicating that they are included in that factor.

Table 12 - Rotated Factor-Loading Matrix for Eight Factors

Variable	FACTOR1	FACTOR2	FACTOR3	FACTOR4
X1	0.14226	-0.05931	0.04705	0.00331
X2	0.03415	-0.03844	0.07420	0.80227
ХЗ	0.09454	-0.03504	0.01776	0.87420
X4	0.09196	0.96167	-0.03967	-0.05058
X5	0.12173	-0.04238	0.81033	0.46998
X6	0.00052	-0.01528	0.94847	-0.10891
X7	0.01842	-0.04619	-0.07778	0.03487
X8	-0.09865	0.01085	-0.20700	0.01751
Х9	0.34761	0.91430	-0.03099	
X10	0.79868	0.15830	-0.01173	0.16259
X11	0.67092	0.43564	0.08636	-0.03017
X12	0.89696	0.06085	0.05128	0.04061
X13	0.09086	-0.08751	0.30165	0.08038
X14	-0.02594	-0.06537	0.01078	-0.07814
× X15	0.12325	-0.11510	0.01265	0.04032
X16	0.00998	0.04795	-0.01077	-0.03921
Variable	FACTOR5	FACTOR6	FACTOR7	FACTOR8
X1	0.82107	-0.02518	0.10634	-0.07443
X2	1 1			
	-0.04510	-0.08800	0.00533	0.08430
	-0.04510 0.10011	-0.08800 0.03495	0.00533 0.07824	0.08430 -0.04263
X3 X4	-0.04510 0.10011 -0.09496	-0.08800 0.03495 -0.08436	0.00533 0.07824 -0.05725	-0.04263
Х3	0.10011	0.03495	0.07824	
X3 X4	0.10011	0.03495 -0.08436	0.07824 -0.05725	-0.04263 -0.00073
X3 X4 X5	0.10011 -0.09496 0.05185	0.03495 -0.08436 0.01110	0.07824 -0.05725 0.04932	-0.04263 -0.00073 -0.09610
X3 X4 X5 X6	0.10011 -0.09496 0.05185 0.03464	0.03495 -0.08436 0.01110 0.00727	0.07824 -0.05725 0.04932 0.00498	-0.04263 -0.00073 -0.09610 -0.02725
X3 X4 X5 X6 X7	0.10011 -0.09496 0.05185 0.03464 0.01681	0.03495 -0.08436 0.01110 0.00727 -0.02124	0.07824 -0.05725 0.04932 0.00498 0.02283	-0.04263 -0.00073 -0.09610 -0.02725 0.98077
X3 X4 X5 X6 X7 X8	0.10011 -0.09496 0.05185 0.03464 0.01681 0.11654	0.03495 -0.08436 0.01110 0.00727 -0.02124 -0.06769	0.07824 -0.05725 0.04932 0.00498 0.02283 0.83096	-0.04263 -0.00073 -0.09610 -0.02725 0.98077 -0.00102
X3 X4 X5 X6 X7 X8 X9	0.10011 -0.09496 0.05185 0.03464 0.01681 0.11654 -0.04596	0.03495 -0.08436 0.01110 0.00727 -0.02124 -0.06769 -0.05245	0.07824 -0.05725 0.04932 0.00498 0.02283 0.83096 -0.00522	-0.04263 -0.00073 -0.09610 -0.02725 0.98077 -0.00102 -0.04168
X3 X4 X5 X6 X7 X8 X9 X10	0.10011 -0.09496 0.05185 0.03464 0.01681 0.11654 -0.04596 0.19716	0.03495 -0.08436 0.01110 0.00727 -0.02124 -0.06769 -0.05245 0.10304	0.07824 -0.05725 0.04932 0.00498 0.02283 0.83096 -0.00522 0.08126	-0.04263 -0.00073 -0.09610 -0.02725 0.98077 -0.00102 -0.04168 0.03730
X3 X4 X5 X6 X7 X8 X9 X10	0.10011 -0.09496 0.05185 0.03464 0.01681 0.11654 -0.04596 0.19716 -0.07295	0.03495 -0.08436 0.01110 0.00727 -0.02124 -0.06769 -0.05245 0.10304 -0.06385	0.07824 -0.05725 0.04932 0.00498 0.02283 0.83096 -0.00522 0.08126 -0.06795	-0.04263 -0.00073 -0.09610 -0.02725 0.98077 -0.00102 -0.04168 0.03730 -0.14267
X3 X4 X5 X6 X7 X8 X9 X10 X11 X12	0.10011 -0.09496 0.05185 0.03464 0.01681 0.11654 -0.04596 0.19716 -0.07295 0.04922	0.03495 -0.08436 0.01110 0.00727 -0.02124 -0.06769 -0.05245 0.10304 -0.06385 -0.00789	0.07824 -0.05725 0.04932 0.00498 0.02283 0.83096 -0.00522 0.08126 -0.06795 -0.04388	-0.04263 -0.00073 -0.09610 -0.02725 0.98077 -0.00102 -0.04168 0.03730 -0.14267 0.06470
X3 X4 X5 X6 X7 X8 X9 X10 X11 X12 X13	0.10011 -0.09496 0.05185 0.03464 0.01681 0.11654 -0.04596 0.19716 -0.07295 0.04922 -0.07028	0.03495 -0.08436 0.01110 0.00727 -0.02124 -0.06769 -0.05245 0.10304 -0.06385 -0.00789	0.07824 -0.05725 0.04932 0.00498 0.02283 0.83096 -0.00522 0.08126 -0.06795 -0.04388 0.77320	-0.04263 -0.00073 -0.09610 -0.02725 0.98077 -0.00102 -0.04168 0.03730 -0.14267 0.06470 0.02915
X3 X4 X5 X6 X7 X8 X9 X10 X11 X12 X13	0.10011 -0.09496 0.05185 0.03464 0.01681 0.11654 -0.04596 0.19716 -0.07295 0.04922 -0.07028 -0.04184	0.03495 -0.08436 0.01110 0.00727 -0.02124 -0.06769 -0.05245 0.10304 -0.06385 -0.00789 0.06308	0.07824 -0.05725 0.04932 0.00498 0.02283 0.83096 -0.00522 0.08126 -0.06795 -0.04388 0.77320 -0.00962	-0.04263 -0.00073 -0.09610 -0.02725 0.98077 -0.00102 -0.04168 0.03730 -0.14267 0.06470 0.02915 0.00176

#### Regression Analysis

Once the numeric variables were grouped into 8 meaningful factor groups, these factor groups were combined with the 6 nonnumeric variables. A stepwise multivariate regression analysis was then performed on the 14 variables based on the 266 observations, or projects. An examination of the results of the regression analysis showed that of the 14 variables included in the analysis, only factor groups 1 and 7 were found to be significant at the  $\alpha$  = .10 level. In other words, factor groups 1 and 7 were found to be statistically significant predictors of cost growth. On the other hand,  $R^2$  was only 0.1078 which gave an indication that the regression was statistically significant but the relationship might not be of much practical importance.

Several attempts were made to improve the value of  $R^2$ . One of these attempts was based on reviewing the data and screening them for possible abnormal values. Eleven projects were found to have very high actual cost growth values compared with the others. It was decided to exclude them and perform the same analysis on the 255 remaining projects. A noticeable improvement resulted and the new results showed that factor groups 1, 4, 5, and variable x20 were significant at  $\alpha = .10$  level with  $R^2 = 0.3919$ . This value of  $R^2$  was the best that could be achieved through several trials and attempts.

Multiple regression analysis was then performed on the four significant variables; factor groups 1, 4, 5, and variable x20 based on the 255 observations.

Due to the fact that the variable x20, resident engineer, was a nonnumeric variable, there was a need to use dummy variables in order to be able to include it in the analysis. Because there were 44 levels (44 different resident engineers) in the variable

x20, 43 dummy variables were created, they were named d1, d2, d3, ..., d43. Each resident engineer was assigned a dummy variable. Each dummy variable takes the value of (1) with the existence of the resident engineer to whom it was assigned, and (zero) otherwise. The code used for this process is shown in the first two pages of Appendix E.

Multiple regression analysis was then performed on the data using the (REG) procedure. The parameter estimates for factor groups 1, 4, 5, and the dummy variables representing x20 were obtained and are presented in Chapter V.

Principal components analysis, factor analysis, and regression analysis were performed using the SAS system for Windows version 6.12. The SAS program and output for the analyses are shown in Appendices E and F respectively.

#### CHAPTER V

#### DATA ANALYSIS RESULTS

#### The Survey

As previously described in Chapters III and IV, responses of engineers' and contractors' questionnaires were used to obtain severity indices for each factor included in the questionnaires, reference Tables 5 and 6. The ranking process then started, and the degree of impact of each factor was determined, reference Table 7.

All 33 factors included in the questionnaires, except bid range and contract administration, were found to have impact on cost growth. Although it was found that bid range has no impact on cost growth, it was included in the analysis for the reasons specified in chapter IV.

Each factor that had an impact on cost growth was involved in the analysis and considered as a variable. Information related to 19 of the factors was found in ODOT's files on each project involved in the study, reference Table 8.

Two factors were excluded from the list of available factors shown in Table 8, and two other factors were replaced with seven new ones. Twenty-two factors were found to exist and needed to be included in the analysis as independent variables. Sixteen variables were numeric and the remaining 6 were non-numeric. The cost growth was

included in the analysis as the dependent variable. The final list of variables, their symbols, types, and units are shown in Table 10.

#### Consistency and Multicollinearity of the Data

A principal components analysis was performed on the numeric variables based on the 266 observations (projects) for two main reasons: to screen the data for possible outliers or inconsistency, and to check the existence of multicollinearity among the variables.

The analysis showed consistent data with nothing that appears to be too unusual. Very few points were found and identified as possible outliers. Multicollinearity was found to exist among some of the variables included in the analysis. Several variables were found to be related.

The problems of the outliers and the related variables were identified. They were dealt with in other phases of the analysis.

#### Factor Groups (Principal Factors)

Factor analysis was performed on the numeric variables to create a new set of uncorrelated variables that could be used in the regression analysis to develop the prediction model. The rotated factor-loading matrix shown in Chapter IV (Table 12) was used to establish the factor groups. The number of factor groups to be considered in the regression analysis representing the numeric variables in a form of independent and

uncorrelated variables was found to be eight. Table 13 represents the 8 factor groups, or principal factors, and the variables included, or represented, by each factor group.

Table 13 - The Selected Factor Groups, or Principal Factors, and Variables included

Factor Group	Va	ariables included
(Principal Factor)	Symbol	Name
1	x10	ratio of projects with overrun
	x11	average overrun
	x12	average cost growth
2	x4	number of projects
	<b>x</b> 9	number of projects with overrun
3	x5	bad weather days
	<b>x</b> 6	ratio of bad weather days
4	x2	contract amount
	<b>x</b> 3	duration
5	x1	number of bids
<u></u>	x16	contract difference ratio
6	x14	money-left-on-table ratio
	x15	bid range ratio
7	x8	timing of notice to proceed
	x13	unemployment rate
8	х7	bidding environment

Regression Analysis of the Cost Factors

The 8 principal factors resulting from the factor analysis were combined with the 6 non-numeric variables. Multiple regression analysis was then performed on the 14 variables. Table 14 gives the results of the regression analysis of those 14 variables.

Table 14 - Regression Analysis Results on the 14 Variables

Variable	F-value	P-value
Factor 1	41.17	0.0001
Factor 2	0.2	0.6538
Factor 3	. 0	0.9549
Factor 4	9.87	0.0022
Factor 5	3.05	0.0841
Factor 6	. 0	0.9486
Factor 7	1.39	0.2422
Factor 8	0.3	0.586
x17	1.2	0.2005
x18	0.44	0.643
x19	0.83	0.7579
x20	1.44	0.0956
x21	0	0.9611
x22	1.14	0.2884

As shown in Table 14, only factors 1, 4, 5, and variable x20 were found to be significant at  $\alpha = .10$  level with  $R^2$  equals 0.3919.

Multiple regression analysis was then performed on the four significant variables to obtain the parameter estimates. Since the variable x20, resident engineer, was a non-numeric variable, dummy variables were needed to include it as a variable in the analysis. Forty three dummy variables were created because of the 44 possible values of x20; they were named d1, d2, ..., d43. Table 15 gives the parameter estimates resulting from the regression analysis of the four significant variables. It should be noted that the variable x20 was replaced with the 43 previously described dummy variables; their estimates varied from -0.0380 to 0.0586 as shown in Appendix F (SAS Output).

The estimated standard error values were equal for all the regression factor groups, or principal factors, included in the analysis as variables because they were normalized and orthogonal.

Table 15 – Regression Analysis Results on the 4 Significant Variables

Variable	Parameter Estimate
Intercept	-0.0219
Factor 1	0.0161
Factor 4	0.0115
Factor 5	0.0043
x20	(-0.038 to 0.0586)

#### The Prediction Model

The multiple regression analysis that was performed on the four significant variables; factors 1, 4, 5, and the variable x20, produced the prediction model. Table 15 gives the parameter estimates for the following model:

Y = -0.0219 + R.E. + 0.0161\*F1 + 0.0115\*F4 + 0.0043\*F5 Equation 5.1 where:

Y =the predicted cost change, in \$

R. E. = number estimated according to resident engineers, as shown in Table 16

F1 = principal factor 1, calculated as shown in Table 17

F4 = principal factor 4, calculated as shown in Table 17

F5 = principal factor 5, calculated as shown in Table 17.

The predicted cost change, Y, in Equation 5.1 could be either positive or negative; the positive Y indicates a cost overrun while the negative Y indicates a cost underrun.

Table 16 - Values of R.E. in Equation 5.1

No.	Resident Engineer	R.E.	No.	Resident Engineer	RE.
1	Α	0.0447	23	V	-0.1117
2	В	0.0008	24	W	-0.0118
3	С	0.0049	25	X	0.0036
4	D	-0.0039	26	Υ	0.0147
5	E	-0.0002	27	Z	0.0424
6	F	0.0586	28	Ab	0.0279
7	G	-0.0342	29	Ac	-0.0082
8	H į	0.0270	30	Ad	-0.0087
9	I	-0.0129	31	Ae	-0.0106
10	. <b>J</b>	0.0272	32	Af	0.0408
11	K	0.0154	33	Ag	0.0275
12	<u>L</u>	0.0258	34	Ah	0.0026
13	М	-0.0013	35	Ai	0.0188
14	N	0.0534	36	Aj	-0.0048
15	0	-0.0361	37	Ak	0.0143
16	Р	0.0189	38	Al	0.0440
17	Q ·	-0.0380	39	Am	-0.0009
18	R	0.0015	40	An	0.0092
19	s	0.0348	41	Ao	0.0048
20	Т	-0.0191	42	Ap ·	0.0376
21	As	0.0000	43	Aq	0.0035
22	U	0.0318	44	Ar	-0.0066

(Note: For resident engineers other than mentioned above, R.E. = 0.0074)

Table 17 – Calculation of Principal Factors in Equation 5.1

Principal Factor	Calculated as
F1	(0.79868)(x10) + (0.67092)(x11) + (0.89696)(x12)
F4	(0.80227)(x2) + (0.87420)(x3)
F5	(0.82107)(x1) - (0.76748)(x16)

#### where:

x10 = ratio of projects with overrun

x11 = average overrun, as a number (%)

x12 = average cost growth, as a ratio

x2 = contract amount, in \$

x3 = duration, in calendar days

x1 = number of bids

x16 = contract difference ratio.

To illustrate the use of the prediction model, it was applied to four arbitrary selected paving projects. The first project had the following information:

- Number of bids (x1) = 3
- Contract amount (x2) = \$149,181.50
- Duration (x3) = 137 days
- Ratio of projects in which the contract had overrun (x10) = 0.18
- Average overrun (x11) = 2.68 %
- Average cost growth (x12) = -0.04
- Contract difference ratio (x16) = -0.0287
- Resident engineer (x20) = An.

By substituting these values in Equation 5.1, the predicted cost change (Y) was found to be \$1,377.77 which is equivalent to 0.92% of the contract amount. Actually, this project had a cost growth equivalent to 3%, which means that there is an agreement in identifying the occurrence of cost overrun.

The same thing was observed in the other three projects; they had actual cost changes equivalent to 12%, -2%, and -13%, while the predicted cost changes obtained by applying Equation 5.1 were found to be equivalent to 23%, -6%, and -30% respectively.

The difference between the actual and the predicted cost change amounts was expected. The value of R<sup>2</sup> obtained for the model from the analysis was 0.3919, which means that the relationship between the cost growth and the variables included in the model may not have any practical importance. On the other hand, the same relationship may have a statistical importance since the actual overruns were predicted as overruns and the underruns were predicted as underruns.

#### **CHAPTER VI**

#### SUMMARY, CONCLUSIONS, AND RECOMMENDATIONS

#### Summary

A change in cost remains one of the most important issues for all of the parties involved in a construction project. Changes may occur due to several factors, some of which are related to each other. The main objectives of this research were to identify the factors that lead to cost changes, determine their influence or degree of impact on the cost changes, and develop a numerical model that predicts the amount of cost growth in ODOT paving projects using information available at bidding time based on the existence and the effectiveness of any of those factors.

For this research, factors that had impact on the cost changes in construction projects from previous studies were identified. Through several discussion sessions and meetings, other factors were added to the previous findings. All the factors were then combined to form the final list of 33 cost factors that were used in the analysis.

Two questionnaires, one for ODOT engineers and the other for ODOT contractors, were developed. The objective was to obtain the participants' responses as to whether or not the 33 cost factors have an impact on the cost growth and the degree of impact. Two hundred and three questionnaires were sent by mail to participants, 44 to engineers and 159 to contractors. The response rate to the engineers' and contractors'

questionnaires was 61.36% and 31.45% respectively. A simple analysis was performed on the responses to determine the impact that each factor has on cost growth.

All factors that had impact on the cost growth as obtained from participants' responses to both questionnaires were involved in the analysis process. Each factor was considered a variable. Of the 33 factors that were found to be important, information related to 19 were obtainable in ODOT files. Information on the remaining 14 factors was not available, and therefore these factors were not included in the analysis.

Specific criteria were established for selecting the projects in order to meet the scope of this research. The criteria included ODOT paving projects costing less than \$5 million that were completed between 1995 and 1998. Two hundred sixty six projects met those criteria. For each project included in the analysis, there was input for each one of the 19 available factors (variables). Other variables were obtained by performing simple calculations on the available information in the project files. Twenty-two factors, 16 numeric and 6 nonnumeric, were found to exist and included in the analysis as variables.

Principal components analysis was performed on the 16 numeric variables to screen the data for outliers and to check the existence of multicollinearity among the predictor variables. Very few outliers were observed, and several variables were found to be related.

Factor analysis was performed on the numeric variables to overcome the multicollinearity problem by deriving, creating, and developing a new set of uncorrelated variables that could be used in the analysis. Eight factor groups (principal factors) were chosen to represent the 16 numeric variables in the final analysis which was the regression analysis. Table 12 presents the selected factor groups and variables included.

After the numeric variables were grouped into 8 meaningful groups (principal factors), they were combined with the 6 non-numeric variables. A multivariate regression analysis was then performed on the 14 variables based on the 266 observations (projects) as a first step in developing the prediction model. After several attempts were made to improve the value of  $R^2$ , factors 1, 4, 5, and variable x20 were found to be significant at  $\alpha = .10$  level with  $R^2 = 0.3919$ .

Including only significant variables, multiple regression analysis was then performed on the data to formulate the prediction model and to obtain the parameter estimates for the variables involved. Table 14 shows the regression analysis results (parameter estimates), and Equation 5.1 represents the resulting prediction model. The model was then applied to four arbitrary selected paving projects. There was an agreement in identifying the occurrence of cost changes between the actual cost changes and those obtained by the prediction model. In other words, the actual overruns were obtained (predicted) using the prediction equation as overruns and the actual underruns were obtained (predicted) as underruns. A difference was found between the actual and the predicted cost change amounts, which explained the fact that the relationship between the cost growth and the variables included in the model might have a statistical but not a practical importance.

More details about the data analysis techniques and statistics are shown in Chapter IV, while Chapter V provides extensive explanation of the data analysis results for different phases of the research.

#### Conclusions

Thirty-three factors were found to have impact on cost growth in ODOT paving projects. Of these 33 cost factors, 22 were related to ODOT engineers, 28 to contractors, and 17 to both groups. The factors and their degree of impact on cost growth were obtained from participants' responses to the questionnaires. The factors were ranked according to their impact on the cost growth; "Project size" was ranked first by the engineers and "Availability of labor" was ranked first by the contractors. Table 7 represents the 33 cost factors, their impact, and ranking.

Information related to 19 of the factors (variables) was found in ODOT files on each project involved in the study, reference Table 8. Two factors were excluded and two factors were replaced with seven new factors that were added to the list, which resulted in 22 cost factors that were included in the analysis as independent variables. Project identification number and the dependent variable (Y) were added to the list resulting in a final list of 24 variables, reference Table 10.

Principal factors 1, 4, 5, and "Resident engineer" represent 8 of the variables that were found to be significant in predicting the amount of cost growth, reference Table 14.

As shown in Table 13, "Ratio of projects with overrun", "Average overrun", and "Average cost growth", which are all related to contractors and specifically their history of cost overrun, are included in principal factor 1. On the other hand, "Contract amount" and "Duration", which are related to project size, are included in principal factor 4. Also, "Number of bids" and "Contract difference ratio", which are related to the bidding environment, are included in principal factor 5. Thus, 8 of the 22 independent and

available cost factors are predictor variables. In other words, contractor, project size, bidding environment, and resident engineer were found to have significant impact on the cost growth and are significant in predicting the cost growth in ODOT paving projects.

Also, based on the previous explaination and the P-values obtained in the analysis, reference Table 14, it can be concluded that "contractor" was found to have the most impact on cost growth followed by "project size", "bidding environment", and "resident engineer" respectively.

Table 18 presents a summary of the elements found to have an impact on cost growth and the included factors (the predictor variables).

Table 18 - Elements influencing Cost Growth and Factors included

Contractor	Project Size	Bidding Environment	Resident Engineer
ratio of projects with overrun	contract amount	number of bids	resident engineer
average overrun	duration	contract difference ratio	:
average cost growth			

The numerical prediction model that was developed based on those variables to predict the amount of cost growth in ODOT paving projects using information available at the bidding time is shown in Equation 5.1.

#### Recommendations

During this research, a variety of topics and points for further evaluation and investigation were identified. These topics include the following:

- Investigate cost growth in public projects in general.
- Include ODOT projects other than paving.
- Study cost growth and causation factors during construction.
- Conduct a study of cost growth regardless of size and contract amount.
- Consider the inflation rates during the analysis of previous projects and while developing the prediction model.
- Include personal interviews as a data collection method.
- Define more precisely each factor included in the questionnaires.
- Begin the survey with a guide (pilot) questionnaire.
- Evaluate the factors which are found to be unavailable in ODOT files at the bidding time.
- Include more paving projects in the study and applying the developed model to every project involved in the study.

These topics and areas are recommended for further research.

The research was restricted to ODOT projects which makes the findings applicable only to ODOT projects. Further research is needed to include all public projects.

The selection of projects to be involved in the research was based on several criteria. Projects needed to be paving projects at a specific time (January 1995 to

December 1998) and contract amount (less than 5 million dollars). Further research should include projects other than paving projects. Also, timing and size (contract amount) of projects should not be limited so that the finding would be widely applicable.

The research identified the factors that affect cost growth at the bidding time and their impact. Further research should consider the factors that affect the cost growth during construction.

While analyzing data and developing the prediction model, inflation and interest rates were not included. Further research should include them.

The survey used in the research was conducted through self-administered questionnaires which involved sending questionnaires and collecting the participants' responses by mail. Several telephone calls were received regarding the meaning and the wording of some factors. Therefore, it would be more appropriate in further research to consider the method of personal interviews as a data collection method.

Factors included in the questionnaires were written without detailed definitions and explanations. Statements defining and explaining factors included in the questionnaires would be helpful in understanding them; this might lead to more precise answers and better response rates in further research.

Although engineers' and contractors' questionnaires were designed through several discussion sessions with ODOT engineers and committee members, it was realized that starting the survey with a guide questionnaire would give the participants better understanding and provide the research with valuable inputs. This is also recommended for further research.

While collecting project data on the factors which were determined from participants' responses, information related to 14 cost factors was found to be unavailable in ODOT file, reference Table 8. These 14 factors were excluded from portions of the analysis. Since some of those factors were believed to be significant and may have an impact on the cost growth, further research is recommended to investigate those factors and collect information related to them to make them available in all of the analysis phases.

Since the prediction model was developed in this study including significant factors at  $\alpha = .10$  level with  $R^2 = 0.3919$ , further research is recommended to include more projects in order to improve the statistical importance of the model. Also, the model needs to be applied to a larger number of projects to check its practical importance.

#### SELECTED BIBLIOGRAPHY

- Charles, T. J., and Andrew, M. A. (1990). Predictors of cost-overrun rates. <u>Journal of construction engineering and management: ASCE</u>, <u>116</u>(3), 569-579.
- Devore, J. L. (1995). <u>Probability and statistics for engineering and the sciences</u> (4th ed.). Belmont, CA: International Thomson Publishing Inc.
- Elinwa, A. U., and Buba, S. A. (1993). Construction cost factors in Nigeria. <u>Journal of construction engineering and management:</u> ASCE, 119(4), 698-713.
- Farbarik, J. (1994). Evaluation of the efficacy of using bid data to predict construction cost overruns. Unpublished doctoral dissertation, University of Washington, Seattle.
- Hester, W. T., Kuprenas, J. A., and Chang, T. C. (1991). <u>Construction changes and change orders: their magnitude and impacts.</u> University of California, Berkeley.
- Ibbs, C. W., and Allen, W. E. (1995). Quantitative impacts of project change. University of California, Berkeley.
- Johnson, D. E. (1998). <u>Applied multivariate methods for data analysis.</u> (1st ed.). Boston, MA: Duxbury Press.
- Okpala, C. C., and Aniekwu, A. N. (1988). Causes of high costs of construction in Nigeria. <u>Journal of construction engineering and management:</u> ASCE, 114(2), 675-683.
- Rosemond, J. R. (1984). <u>Analysis of low bidding and change order rates for navy</u>
  <u>facilities construction contracts.</u> Unpublished thesis, Naval Postgraduate School,
  Monterey, California.
- Semple, C., Hartman, F. T., and Jergeas, G. (1994). Construction claims and disputes: causes and cost/time overruns. <u>Journal of construction engineering and management:</u> ASCE, 120(4), 785-795.
- Suhanic, G. (1980). Change orders impact on construction cost and schedule.

  <u>Transaction of the American Association of Cost Engineers.</u> Washington, D. C.

- Thomas, H. R. (1985). Comparative analysis of time and schedule performance on highway construction projects involving contract claims. Federal Highway Administration, Report No. FHWA-TS-85-217.
- Warde, W. D. (1990). <u>Sampling methods</u>. Statistics department, Oklahoma State University, Stillwater.
- Wiersma, W. (1995). Research methods in education: an introduction (6th ed.). Boston, MA: Allyn and Bacon.
- Zeitoun, A. A. (1992). Evaluation of cost and schedule growth trends during construction. Unpublished doctoral dissertation, Oklahoma State University, Stillwater.

#### **APPENDICES**

# APPENDIX A IRB APPROVAL FORM

### OKLAHOMA STATE UNIVERSITY INSTITUTIONAL REVIEW BOARD

IRB #: EG-00-002

October 29, 1999

Date:

	· · · · · · · · · · · · · · · · · · ·	
Proposal Title:	"PREDICTING CONSTRUCTION COST PROJECTS USING INFORMATION AV	
Principal Investigator(s):	Garold Oberlender Bassam Ghulman	
Reviewed and Processed as:	Exempt	
Approval Status F	Recommended by Reviewer(s): Approved	
Signature:		
•	C. enlan	
	Coadplon	October 29, 1999
Carol Olson, Dire	ctor of University Research Compliance	Date

Approvals are valid for one calendar year, after which time a request for continuation must be submitted. Any modification to the research project approved by the IRB must be submitted for approval with the advisor's signature. The IRB office MUST be notified in writing when a project is complete. Approved projects are subject to monitoring by the IRB. Expedited and exempt projects may be reviewed by the full Institutional Review Board.

#### APPENDIX B

#### THE QUESTIONNAIRES COVER LETTER



College of Engineering, Architecture and Technology Civil and Environmental Engineering 207Engineering South Stillwater, Oklohoma 74078-5033 405-744-5189 Fax 405-744-7554

#### Dear Participant:

The attached survey form has been prepared to identify indicators of cost growth of paving projects. It is a part of an academic research project that is being conducted by a Ph.D. candidate at Oklahoma State University, and named "Predicting Construction Cost Growth in ODOT's Paving Projects Using Information Available at the Bidding Time".

The purpose of the research is to evaluate a number of completed construction projects that had cost changes and study the existence of different causing factors. A statistical model to predict the amount of cost over/under run is to be developed. Determining the existence, influence and effectiveness of each cost factor affecting the cost growth may lead to better control on construction cost and help in looking for possible solutions to avoid the expected cost growth.

You have been selected to participate in this survey. The information you supply will be held in **strict confidence**. At no time will you be identified in the research results. The only persons who will have access to the survey forms are the researchers, who will summarize the survey forms of all respondents.

Please complete the attached questionnaire and return it through one of the following ways:

- Use the attached postage-paid self-addressed envelope, or
- Fax it to (405) 747-2211.

Thank you for taking the time to participate in our research. If you have any questions about the research, your participation or rights, please contact:

- Bassam Ghulman [Phone: (405) 744-1025, E-Mail: ghulman@okstate.edu],
- Dr. Garold D. Oberlender [Phone: (405) 744-5260, E-Mail: oberlender@aol.com], or
- Sharon Bacher, IRB Executive Secretary, Oklahoma State University, 203 Whitehurst, Stillwater, OK 74078 [Phone: (405) 744-5700].

Sincerely,

Bassam Ghulman Ph.D. Candidate in Civil Engineering



## APPENDIX C PROJECT DATA

ID Project No	Location (Co	unty) Project Type	Letting Date Numb	er of Bids
19(317)	Canadian	Resurfacing	2/22/96	3
252(241)	Noble	Resurfacing	4/20/95	2
352(242)	Noble	Resurfacing	4/20/95	2
453(133)	Nowata	Resurfacing	6/22/95	2
554(134)	Okfuskee	Surfacing	4/25/96	0
654(178)	Okfuskee	Surfacing	3/23/95	3
754(180)	Okfuskee	Overlay	3/23/95	4
8 55(877)	Oklahoma	Resurfacing	4/20/95	6
955(878)	Oklahoma	Resurfacing	4/20/95	6
1055(915)	Oklahoma	Resurfacing	1/25/96	6
11 55(919)	Oklahoma	Overlay	1/25/96	0
12 55(979)	Oklahoma	Resurfacing	4/25/96	0
13 55(980)	Oklahoma	Resurfacing	4/25/96	3
14 56(256)	Okmulgee	Resurfacing	5/25/95	3
15 56(261)	Okmulgee	Resurfacing	8/24/95	3
16 57 (359)	Osage	Overlay	3/23/95	2
17 57(362)	Osage	Resurfacing	6/22/95	2 5
18 57(369)	Osage	Overlay	3/23/95	5
1944-2(372)	Tulsa	Resurfacing	4/24/97	3
2044(292)	McClain	Resurfacing	3/23/95	5
2144(347)	McClain	Resurfacing	4/20/95	6
22 45(315)	McCurtain	Resurfacing	6/22/95	2
23 45 (324)	McCurtain	Resurfacing	6/20/96	3
2446(231)	Mcintosh	Resurfacing	1/25/96	3
2546(240)	Mcintosh	Resurfacing	7/27/95	3
26 46(234)	Mcintosh	Overlay	1/26/95	. 3
27 47(134)	Major	Overlay	3/23/95	1
2848(188)	Marshall	Resurfacing	2/23/95	4
29 49(327)	Mayes	Overlay	3/23/95	4
30.50(160)	Murray	Resurfacing	6/22/95	2
31 50(164)	Миггау	Resurfacing	4/25/96	0
32 51 (421)	Muskogee	Resurfacing	3/21/96	3
33.51(403)	Muskogee	Surfacing	10/26/95	3
34 51 (399)	Muskogee	Resurfacing	9/14/95	4
35 51 (422)	Muskogee	Resurfacing	4/25/96	2
36 51 (413)	Muskogee	Resurfacing	8/24/95	3
37:51(410)	Muskogee	Resurfacing	4/24/97	3
38 39(190)	Latimer	Resurfacing	6/20/96	1
3940-4(347)	Canadian	Resurfacing	3/21/96	4
4040-5(30)	Oklahoma	Resurfacing	2/23/95	2
41 40(402)	LeFlore	Resurfacing	10/26/95	2
4240(429)	LeFlore	Resurfacing	6/20/96	1
4341(235)	Lincoln	Resurfacing	5/25/95	2
4441(289)	Lincoln	Resurfacing	4/20/95	3
45,41(288)	Lincoln	Resurfacing	4/20/95	4
4641(311)	Lincoln	Resurfacing	4/25/96	4

ID	Lowest Bid	2nd Lowest Bid	Highest Bid	MLOT	Bid Range
1	\$149,181.50	\$152,760.10	\$209,604.40	\$3,578.60	\$60,422.90
2	\$313,700.00	\$337,400.50	\$337,400.50	\$23,700.50	\$23,700.50
3	\$565,917.65	\$605,692.50	\$605,692.50	\$39,774.85	\$39,774.85
4	\$870,893.75	\$1,028,527.00	\$1,028,527.00	\$157,633.25	\$157,633.25
5	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
6	\$342,922.15	\$388,751.00	\$405,192.83	\$45,828.85	\$62,270.68
7	\$131,001.20	\$132,796.40	\$0.00	\$1,795.20	(\$131,001.20)
8	\$425,655.00	\$458,445.00	\$957,100.00	\$32,790.00	\$531,445.00
9	\$42,375.00	\$54,260.76	\$74,462.50	\$11,885.76	\$32,087.50
10	\$136,167.34	\$151,776.73	\$334,988.90	\$15,609.39	\$198,821.56
11	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
12		\$0.00	\$0.00	\$0.00	\$0.00
	\$0.00				
13	\$549,157.00	\$552,976.00	\$653,604.00	\$3,819.00	\$104,447.00
14	\$268,726.40	\$272,872.50	\$294,519.10	\$4,146.10	\$25,792.70
15	\$216,896.40	\$232,908.20	\$264,152.40	\$16,011.80	\$47,256.00
16	\$252,520.00	\$349,475.00	\$349,475.00	\$96,955.00	\$96,955.00
17	\$703,170.00	\$1,171,630.00	\$1,171,630.00	\$468,460.00	\$468,460.00
18	\$849,444.00	\$983,494.85	\$1,076,315.00	\$134,050.85	\$226,871.00
19	\$643,280.04	\$694,021.75	\$1,033,593.45	\$50,741.71	\$390,313.41
20	\$61,863.20	\$63,015.80	\$65,861.20	\$1,152.60	\$3,998.00
21	\$207,588.25	\$209,879.90	\$313,001.25	\$2,291.65	\$105,413.00
22	\$487,762.00	\$490,003.20	\$490,003.20	\$2,241.20	\$2,241.20
23	\$494,464.00	\$495,526.80	\$532,460.00	\$1,062.80	\$37,996.00
24	\$163,662.00	\$168,224.50	\$183,043.50	\$4,562.50	\$19,381.50
25	\$255,885.00	\$256,863.00	\$307,550.00	\$978.00	\$51,665.00
26	\$129,900.00	\$144,452.50	\$148,512.00	\$14,552.50	\$18,612.00
27	\$308,292.08	\$308,292.08	\$308,292.08	\$0.00	\$0.00
28	\$118,123.35	\$127,305.50	\$143,135.65	\$9,182.15	\$25,012.30
29	\$306,246.40	\$336,277.00	\$375,527.50	\$30,030.60	\$69,281.10
30	\$486,327.65	\$677,047.50	\$677,047.50	\$190,719.85	\$190,719.85
31	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
32	\$539,665.10	\$549,567.55	\$584,925.10	\$9,902.45	\$45,260.00
33	\$169,921.00	\$181,580.00	\$230,951.15	\$11,659.00	\$61,030.15
34	\$138,112.65	\$144,356.18	\$160,483.98	\$6,243.53	\$22,371.33
35	\$255,376.00	\$276,026.00	\$276,026.00	\$20,650.00	\$20,650.00
36	\$23,163.00	\$28,313.00	\$36,054.40	\$5,150.00	\$12,891.40
37	\$222,697.23	\$274,117.92	\$322,989.32	\$51,420.69	\$100,292.09
38	\$156,761.00	\$156,761.00	\$156,761.00	\$0.00	\$0.00
39	\$3,566,952.95	\$3,575,881.49	\$4,796,198.53	\$8,928.54	\$1,229,245.58
40		\$1,623,316.80	\$1,623,316.80	\$311,126.66	\$311,126.66
41	\$318,207.50	\$371,334.00	\$371,334.00	\$53,126.50	\$53,126.50
42	\$471,757.90	\$471,757.90	\$471,757.90	\$0.00	\$0.00
43	\$122,475.20	\$125,131.30	\$125,131.30	\$2,656.10	\$2,656.10
44	\$444,213.60	\$457,217.30	\$593,360.60	\$13,003.70	\$149,147.00
45	\$668,714.32	\$761,910.00	\$866,336.00		The state of the s
46				\$93,195.68 \$28,482,42	\$197,621.68 \$62,612.87
40	\$697,812.95	\$726,295.37	\$760,425.82	\$28,482.42	\$62,612.87

ID	Engr's Estimate	Contract Amount	Contract Difference	Actual Cost	Cost Growth
1	\$153,465.50	\$149,181.50	(\$4,284.00)	\$142,750.18	-4.31%
2	\$358,613.25	\$313,700.00	(\$44,913.25)	\$297,595.12	-5.13%
3	\$446,668.75	\$565,917.65	\$119,248.90	\$565,916.55	0.00%
4	\$810,505.00	\$870,893.75	\$60,388.75	\$870,491.17	-0.05%
5	\$0.00	\$261,618.90	\$261,618.90	\$256,230.84	-2.06%
6	\$345,217.75	\$342,922.15	(\$2,295.60)	\$341,789.16	-0.33%
7	\$128,667.00	\$131,001.20	\$2,334.20	\$131,462.47	0.35%
8	\$549,590.00	\$425,655.00	(\$123,935.00)	\$425,655.00	0.00%
9	\$73,400.00	\$42,375.00	(\$31,025.00)	\$44,242.73	4.41%
10	\$208,369.46	\$136,167.34	(\$72,202.12)	\$138,001.33	1.35%
11	\$0.00	\$722,845.00	\$722,845.00	\$710,501.86	-1.71%
12	\$0.00			\$1,658,614.91	4.44%
		\$1,588,096.50 \$540,157.00	\$1,588,096.50		
13	\$659,995.00	\$549,157.00	(\$110,838.00)	\$491,882.95	-10.43%
14	\$263,484.50	\$268,726.40	\$5,241.90	\$253,263.31	-5.75%
15	\$0.00	\$216,896.40	\$216,896.40	\$212,208.63	-2.16%
16	\$242,150.00	\$252,520.00	\$10,370.00	\$249,187.76	-1.32%
17	\$632,170.00	\$703,436.50	\$71,266.50	\$695,150.56	-1.18%
18	\$828,160.00	\$849,444.00	\$21,284.00	\$840,714.13	-1.03%
19	\$768,345.45	\$643,280.04	(\$125,065.41)	\$597,518.15	-7.11%
20	\$65,237.40	\$61,863.20	(\$3,374.20)	\$54,375 <i>.</i> 72	-12.10%
21	\$202,587.00	\$207,588.25	\$5,001.25	\$209,055.42	0.71%
22	\$402,047.10	\$487,762.00	\$85,714.90	\$466,577.38	-4.34%
23	\$491,930.00	\$494,464.00	\$2,534.00	\$473,850.69	-4.17%
24	\$178,743.00	\$163,662.00	(\$15,081.00)	\$158,993.94	-2.85%
25	\$258,262.50	\$255,885.00	(\$2,377.50)	\$251,062.69	-1.88%
26	\$147,410.00	\$129,900.00	(\$17,510.00)	\$129,278.79	-0.48%
27	\$291,035.30	\$308,292.08	\$17,256.78	\$306,221.23	-0.67%
28	\$126,093.00	\$118,123.35	(\$7,969.65)	\$116,669.38	-1.23%
29	\$311,362.00	\$306,246.40	(\$5,115.60)	\$304,843.19	-0.46%
30	\$531,474.25	\$486,327.65	(\$45,146.60)	\$463,820.87	-4.63%
31	\$0.00	\$323,778.50	\$323,778.50	\$316,687.07	-2.19%
32	\$536,394.50	\$539,665.10	\$3,270.60	\$541,259.45	0.30%
33	\$168,159.00	\$169,921.00	\$1,762.00	\$172,690.37	1.63%
34	\$136,863.80	\$138,112.65	\$1,248.85	\$165,148.68	19.58%
35	\$293,835.00	\$255,376.00	(\$38,459.00)	\$314,775.86	23.26%
36	\$0.00	\$23,163.00	\$23,163.00	\$23,037.82	-0.54%
37	\$280,290.49	\$222,697.23	(\$57,593.26)	\$218,100.68	-2.06%
38	\$159,720.00	\$156,761.00	(\$2,959.00)	\$156,362.26	-0.25%
39	\$4,264,912.25	\$3,426,952.95	(\$837,959.30)	\$3,458,463.59	and the second s
			**		0.92%
40	\$1,202,432.20	\$1,312,190.14 \$318.207.50	\$109,757.94	\$1,016,289.11	-22.55%
41	\$285,488.00	\$318,207.50	\$32,719.50	\$317,174.14	-0.32%
42	\$476,178.00	\$471,757.90	(\$4,420.10)	\$469,524.51	-0.47%
43	\$112,713.50	\$122,475.20	\$9,761.70	\$119,335.38	-2.56%
44	\$446,112.00	\$444,213.60	(\$1,898.40)	\$441,442.50	-0.62%
45	\$685,544.00	\$668,714.32	(\$16,829.68)	\$666,946.47	-0.26%
46	\$774,408.00	\$697,812.95	(\$76,595.05)	\$688,880.23	-1.28%

ID [	Ouration Contractor Number	er of Projects
1	137 Haskell Lemon Construction Co.	11
2	45 Evans & Associates Const.	4
3	62 Evans & Associates Const.	4
4	68 Bellco Materials, Inc.	16
5	60 Glover Construction Co., Inc.	30
6	90 Shawnee Asphalt Company	6
7	90 Glover Construction Co., Inc.	30
8	654 Edmond Paving & Const. Co.	3
9	58 Edmond Paving & Const. Co.	3 3 2
10	242 Shell Const. Co., Inc.	2
11	110 Shears Construction Co.	19
12	94 Haskell Lemon Construction Co.	11
13	157 Haskell Lemon Construction Co.	11
14	73 Glover Construction Co., Inc.	30
15	271 APAC-Oklahoma, Inc.	7
16	58 Bellco Materials, Inc.	16
17	61 Bellco Materials, Inc.	16
18	131 Belico Materials, Inc.	16
19	113 APAC-Oklahoma, Inc.	7
20	40 Silver Star Truck Lines, Inc.	2
21	45 Shawnee Asphalt Company	6
22	184 Glover Construction Co., Inc.	30
23	177 Glover Construction Co., Inc.	30
24	87 Glover Construction Co., Inc.	30
25	62 Glover Construction Co., Inc.	30
26	125 Glover Construction Co., Inc.	30
27	62 The Cummins Construction Co., Inc.	35
28	83 The Cummins Construction Co., Inc.	35
29	52 Bellco Materials, Inc.	16
30	137 Broce Const. Co., Inc.	18
31	169 Broce Const. Co., Inc.	18
32	40 Glover Construction Co., Inc.	30
33	312 Glover Construction Co., Inc.	30
34	219 Glover Construction Co., Inc.	30
35	83 Glover Construction Co., Inc.	30
36	74 Tiger Ind. Transp. Sys., Inc.	4
37	171 Tiger Ind. Transp. Sys., Inc.	4
38	46 Job Construction Co., Inc.	12
39	296 Haskell Lemon Construction Co.	11
40	272 T. J. Campbell Const. Co.	3
41	212 Job Construction Co., Inc.	12
42	45 Job Construction Co., Inc.	12
43	45 Shawnee Asphalt Company	6
44	60 Masters-Jackson Paving Co.	2
45	60 Shawnee Asphalt Company	6
46	130 The Cummins Construction Co., Inc.	35

ID Total (	Cost Growth Resident En	gineer Weather No of Bad	Weather Days
1:	-0.48an	No	0
2	-0.15ah	No	0
3	-0.15ah	· No	0
4	0.33 am	No	0
5	0.721	No	0
6	-0.031	No	0
7	0.721	No	0
8	0.05e	Yes	94
9	0.05a	Yes	22
10	0.07 e	Yes	61
11	-0.21 q	Yes	61
12	-0.48e	Yes	27
13	-0.48q	Yes	37
14	0.72b	No	0
15	-0.31 b	Yes	56
16	0.33 ae	Yes	56
17	0.33 ae	No	0
18	0.33 ae	No	0
19	-0.31 o	No	O
20	-0.15 p	No	0
21	-0.03s	Yes	38
22	0.72t	No	0
23	0.72 d	No	0
24	0.72 b	Yes	58
25	0.72 b	No	0
26	0.72b	Yes	61
27	-0.57 r	No	0
28	-0.57 ag	No	0
29	0.33 am	Yes	56
30	-0.35 ac	No	0
31	-0.35 ad	Yes	37
32	0.72 b	Yes	37
33	0.72 b	Yes	61
34	0.72b	Yes	50
35	0.72 b	No	0
36	-0.05 b	No	0
37	-0.05aj	No	0
38	-0.09y	No	o
39	-0.48ar	Yes	61
40	-0.31 q	Yes	61
41	-0.09 y	No	0
42	-0.09 u	No	o
43	-0.031	No	0
44	-0.021	Yes	37
45	-0.031	No	
46	-0.571	No No	0 0
-10	0.071		U

ID Bad wea	ther Days Ratio Bidding Environm	ent Plans Review Time   Unit System
1	0.00003	21 English-Metric
2	0.000027	21 English
3	0.000027	21 English
4	0.000021	21 English
5	0.000016	21 English-Metric
6	0.000020	21 English
7	0.000020	21 English
8	0.143727	21 English
9	0.379327	21 English
10	0.25216	21 English-Metric
11	0.55456	21 English-Metric
12	0.2872 16	21 English-Metric
13	0.235716	21 English-Metric
14	0.000012	21 English
15	0.20666	21 English
16	0.965520	21 English
17	0.000021	21 English
18	0.000020	21 English
19	0.000011	21 English-Metric
20	0.000020	21 English
21	0.844427	21 English
22	0.000021	21 English
23	0.000026	21 English-Metric
24	0.66676	21 English-Metric
25	0.00004	21 English
26	0.48805	21 English
27	0.000020	21 English
28	0.00009	21 English
29	1.076920	21 English
30	0.000021	21 English
31	0.218916	21 English-Metric
32	0.925011	21 English-Metric
33	0.19553	21 English
34	0.22831	21 English
35	0.000016	21 English-Metric
36	0.0006	21 English
37	0.000011	21 English-Metric
38	0.000026	21 English-Metric
39	0.2061 11	21 English-Metric
40	0.22439	21 English
41	0.00003	21 English
42	0.000026	21 English-Metric
43	0.000012	21 English
44	0.616727	21 English
45	0.000027	21 English
46	0.000016	21 English-Metric

ID Out-of-S	itate Firms Worl	Order Date Timing	of Work Order Contract	ors History
1	No	4/26/96	64	Yes
2	No	5/23/95	33	No
3	No	5/23/95	33	No
4	No	8/2/95	41	Yes
5	No	6/10/96	46	Yes
6	No	5/26/95	64	Yes
7	No	3/23/95	0	Yes
8	No	5/26/95	36	Yes
9	No	5/22/95	32	Yes
10	No	2/26/96	32	Yes
11	No	2/29/96	35	Yes
12	No	6/3/96	39	Yes
13	No	5/23/96	28	Yes
14	No	6/30/95	36	Yes
15	No	10/4/95	41	Yes
16	No	5/4/95	42	Yes
17	Yes	8/8/95	47	Yes
18	No	5/4/95	42	Yes
19	No	6/5/97	42	Yes
20	No	5/12/95	50	No
21	No	5/22/95	32	Yes
22	No	8/4/95	43	Yes
23	Yes	7/29/96	39	Yes
24	No	4/26/96	92	THE STREET COMMERCIAL PROPERTY OF THE STREET, THE STRE
2 <del>4</del> 25	No	8/22/95	26	Yes
26	No		39	Yes
27	CONTRACTOR OF THE PROPERTY OF	3/6/95	.,	Yes
	No	4/19/95	27	Yes
28	No	6/15/95	112	Yes
29	Yes	5/4/95	42	Yes
30	No	7/19/95	27	Yes
31	No	5/23/96	28	Yes
32	No	4/18/96	28	Yes
33	Yes	12/1/95	36	Yes
34	No	11/7/95	54	Yes
35	No	5/23/96	28	Yes
36	No	10/3/95	40	No
37	Yes	6/26/97	63	No
38	No	7/25/96	35	No
39	No	4/25/96	35	Yes
40	No	3/27/95	·	No
41	No	12/1/95	<b>36</b>	No
42	No	7/25/96	35	No
43	No	7/18/95	54	Yes
44	No	5/23/95	33	No
45	No	5/26/95	36	Yes
46	No	6/6/96	42	Yes

ID Proje	ects with Overrun Average No	of Projects with O/R Averag	e Overrun
1	2	0.1818	2.6800
2	0	0.0000	0.0000
3	0	0.0000	0.0000
4	5	0.3125	9.2540
5	11	0.3667	14.2400
6	1	0.1667	0.7100
7	11	0.3667	14.2400
8	2	0.6667	2.3100
9	2	0.6667	2.3100
10	2	1.0000	3.2700
11	3	0.1579	7.2733
12	2	0.1818	2.6800
13	2	0.1818	2.6800
14	11	0.3667	14.2400
15	1	0.1429	1.2200
16	5	0.3125	9.2540
17	5	0.3125	9.2540
18	5	0.3125	9.2540
19	1	0.1429	1.2200
20	0	0.0000	0.0000
21	1	0.1667	0.7100
22	11	0.3667	14.2400
23	11	0.3667	14.2400
24	11	0.3667	14.2400
25	11	0.3667	14.2400
26	11	0.3667	14.2400
27	10	0.2857	2.8000
28	10	0.2857	2.8000
29	5	0.3125	9.2540
30	1	0.0556	1.9000
31	1	0.0556	1.9000
32	11 	0.3667	14.2400
33	11	0.3667	14.2400
34 35	11	0.3667	14.2400
35 36	11	0.3667	14.2400
36 27	0	0.0000	0.0000
37	O	0.0000	0.0000
38	0	0.0000	0.0000
39 40	2	0.1818	2.6800
40	0	0.0000 0.0000	0.0000
41 42	0		0.0000
42	0	0.0000	
	1	0.1667	0.7100
44 45	0 1	0.0000 0.1667	0.0000 0.7100
45 46	10	0.2857	
40	IU .	U.200/	2.8000

ID A	verage Cost Growth Availability of L	abor
1	-0.0436	5
2	-0.0375	4.6
3	-0.0375	4.6
4	0.0206	4.8
5	0.0240	4
6	-0.0050	4.9
7	0.0240	4.9
8	0.0167	4.6
9	0.0167	4.6
10	0.0350	5.1
11	-0.0111	
	The state of the s	5.1
12	-0.0436	4
13	-0.0436	4
14	0.0240	4.9
15	-0.0443	4.3
16	0.0206	4.9
17	0.0206	4.8
18	0.0206	4.9
19	-0.0443	3.8
20	-0.0750	4.9
21	-0.0050	4.6
22	0.0240	4
23	0.0240	4
24	0.0240	5.1
25	0.0240	4.6
26	0.0240	5.7
27	-0.0163	4.9
28	-0.0163	5.5
29	0.0206	4.9
30	-0.0194	4.8
31	-0.0194	4
32	0.0240	4.1
33	0.0240	4.5
34	0.0240	4.5
35	0.0240	
36	-0.0125	4 4.3
37	-0.0125	3.8
38	-0.0075	4
39	-0.0436	4.1
40	-0.1033	5.5
41	-0.0075	4.5
42	-0.0075	4.5
43	-0.0079	4.9
44	-0.0100	4.9
44		
	-0.0050 0.0163	4.6
46	-0.0163	4

49 35(211)         Johnson         Resurfacing         6/22/95         4           50 35(222)         Johnson         Resurfacing         4/25/96         3           51 36(303)         Kay         Resurfacing         4/26/95         4           52 36(319)         Kay         Resurfacing         4/25/96         0           53 37(172)         Kingfisher         Surfacing         7/25/96         6           54 37(171)         Kingfisher         Resurfacing         4/20/95         5           55 37(177)         Kingfisher         Resurfacing         4/20/95         5           55 37(177)         Kingfisher         Resurfacing         4/25/96         4           57 27(258)         Grant         Resurfacing         4/20/95         1           55 27(265)         Grant         Surfacing         4/3/95         0           60 27(286)         Grant         Resurfacing         8/14/95         0           60 27(286)         Grant         Resurfacing         4/25/96         0           61 30N(023)         Rogers         Surfacing         1/26/95         3           62 32(167)         Hughes         Surfacing         7/25/96         3           64 32(2	ID Project No	Location (County	) Project Type	Letting Date Number of I	3ids
49 35(221)         Johnson         Resurfacing         6/22/95         4           50 35(222)         Johnson         Resurfacing         4/25/96         3           51 36(303)         Kay         Resurfacing         4/25/96         0           52 36(319)         Kay         Resurfacing         4/25/96         0           53 37(172)         Kingfisher         Surfacing         7/25/96         6           54 37(171)         Kingfisher         Resurfacing         4/20/95         5           55 37(170)         Kingfisher         Resurfacing         4/20/95         5           56 37(177)         Kingfisher         Resurfacing         4/20/95         4           57 27(258)         Grant         Resurfacing         4/20/95         1           58 27(262)         Grant         Resurfacing         4/20/95         1           59 27(265)         Grant         Resurfacing         4/25/96         0           60 27(286)         Grant         Resurfacing         4/25/96         0           61 30N(023)         Rogers         Surfacing         1/26/95         4           62 32(15)         Hughes         Surfacing         1/26/95         3           63 33	47 35-1(85)	Love	Resurfacing	1/26/95	4
50 35(222)         Johnson         Resurfacing         4/25/96         3           51 36(303)         Kay         Resurfacing         4/25/96         0           52 36(319)         Kay         Resurfacing         4/25/96         0           53 37(172)         Kingfisher         Surfacing         4/20/95         2           54 37(171)         Kingfisher         Resurfacing         4/20/95         5           55 37(170)         Kingfisher         Resurfacing         4/20/95         5           56 37(177)         Kingfisher         Resurfacing         4/25/96         4           57 27(258)         Grant         Resurfacing         4/25/96         4           58 27(262)         Grant         Resurfacing         4/39/95         0           60 27(286)         Grant         Resurfacing         4/25/96         0           60 27(286)         Grant         Resurfacing         1/25/96         0           61 30N(023)         Rogers         Surfacing         1/26/95         4           63 32(2167)         Hughes         Surfacing         1/26/95         3           64 32(219)         Hughes         Surfacing         7/22/96         3           65 338	48 35-3(241)	Oklahoma	Overlay	2/23/95	2
51 36(303)         Kay         Resurfacing         4/20/95         4           52 36(319)         Kay         Resurfacing         4/25/96         0           53 37(172)         Kingfisher         Surfacing         7/25/96         6           54 37(171)         Kingfisher         Resurfacing         4/20/95         2           55 37(170)         Kingfisher         Resurfacing         4/20/95         5           56 37(177)         Kingfisher         Resurfacing         4/20/95         4           57 27(258)         Grant         Resurfacing         4/25/96         4           57 27(265)         Grant         Surfacing         4/3/95         0           60 27(286)         Grant         Resurfacing         4/25/96         0           60 27(286)         Grant         Resurfacing         4/25/96         0           61 30N(023)         Rogers         Surfacing         1/25/96         0           63 32(167)         Hughes         Surfacing         1/26/95         3           64 32(219)         Hughes         Surfacing         7/25/96         3           65 33B(156)         Jackson         Surfacing         1/26/95         2           65 33B(156)	49 35(211)	Johnson	Resurfacing	6/22/95	4
52 36(319)         Kay         Resurfacing         4/25/96         0           53 37(172)         Kingfisher         Surfacing         7/25/96         6           54 37(171)         Kingfisher         Resurfacing         4/20/95         2           55 37(177)         Kingfisher         Resurfacing         4/25/96         4           57 27(258)         Grant         Resurfacing         4/20/95         1           57 27(265)         Grant         Surfacing         4/3/95         0           59 27(265)         Grant         Surfacing         8/14/95         0           60 27(266)         Grant         Resurfacing         4/25/96         0           60 27(266)         Grant         Resurfacing         4/25/96         0           60 27(266)         Grant         Resurfacing         4/25/96         0           61 30N(023)         Rogers         Surfacing         1/23/97         3           62 32(2167)         Hughes         Surfacing         1/26/95         4           63 32(215)         Hughes         Surfacing         7/25/96         3           65 33B(156)         Jackson         Surfacing         1/26/95         2           67 19(305)	5035(222)	Johnson	Resurfacing	4/25/96	3
5337(172)         Kingfisher         Surfacing         7/25/96         6           5437(171)         Kingfisher         Resurfacing         4/20/95         2           5537(170)         Kingfisher         Resurfacing         4/20/95         5           5637(177)         Kingfisher         Resurfacing         4/25/96         4           5727(258)         Grant         Resurfacing         4/25/96         0           5827(262)         Grant         Surfacing         4/3/95         0           5927(265)         Grant         Surfacing         4/25/96         0           6027(286)         Grant         Resurfacing         4/25/96         0           6130N(023)         Rogers         Surfacing         1/26/95         4           6332(167)         Hughes         Surfacing         1/26/95         4           6332(215)         Hughes         Surfacing         7/25/96         3           65 33B(156)         Jackson         Surfacing         1/26/95         2           65 33(165)         Jackson         Surfacing         1/26/95         2           67 19(305)         Creek         Resurfacing         6/22/95         3           68 20(240)	51 36(303)	Kay	Resurfacing	4/20/95	4
5437(171)         Kingfisher         Resurfacing         4/20/95         5           5537(170)         Kingfisher         Resurfacing         4/20/95         5           5637(177)         Kingfisher         Resurfacing         4/25/96         4           5727(258)         Grant         Resurfacing         4/30/95         0           5827(262)         Grant         Surfacing         4/30/95         0           5927(265)         Grant         Resurfacing         4/25/96         0           6027(286)         Grant         Resurfacing         4/25/96         0           6130N(023)         Rogers         Surfacing         1/23/97         3           6232(167)         Hughes         Surfacing         1/23/97         3           6332(215)         Hughes         Resurfacing         6/22/95         3           64 32(219)         Hughes         Surfacing         7/25/96         3           65 338(156)         Jackson         Surfacing         1/26/95         2           66 33(165)         Jackson         Surfacing         1/27/96         3           67 19(305)         Creek         Resurfacing         6/22/95         3           67 20(304)	52 36(319)	Kay	Resurfacing	4/25/96	0
55 37(170)         Kingfisher         Resurfacing         4/20/95         5           56 37(177)         Kingfisher         Resurfacing         4/25/96         4           57 27(258)         Grant         Resurfacing         4/20/95         1           58 27(262)         Grant         Surfacing         4/3/95         0           59 27(265)         Grant         Surfacing         4/25/96         0           60 27(286)         Grant         Resurfacing         4/25/96         0           61 30N(023)         Rogers         Surfacing         1/23/97         3           62 32(167)         Hughes         Surfacing         1/26/95         4           63 32(215)         Hughes         Resurfacing         6/22/95         3           64 32(219)         Hughes         Surfacing         1/26/95         2           65 33B(156)         Jackson         Surfacing         1/26/95         2           65 33(165)         Jackson         Surfacing         1/26/95         2           67 19(305)         Creek         Resurfacing         2/23/95         2           67 20(2404)         Custer         Surfacing         7/27/95         3           69 20(304)	5337(172)	Kingfisher	Surfacing	7/25/96	6
56 37(177)         Kingfisher         Resurfacing         4/25/96         4           57 27(258)         Grant         Resurfacing         4/20/95         1           58 27(262)         Grant         Surfacing         4/3/95         0           59 27(265)         Grant         Surfacing         8/14/95         0           60 27(286)         Grant         Resurfacing         4/25/96         0           61 30N(023)         Rogers         Surfacing         1/23/97         3           62 32(167)         Hughes         Surfacing         1/26/95         4           63 32(215)         Hughes         Resurfacing         6/22/95         3           64 32(219)         Hughes         Surfacing         7/25/96         3           65 33B(156)         Jackson         Surfacing         1/26/95         2           66 33(165)         Jackson         Surfacing         1/22/95         3           67 19(305)         Creek         Resurfacing         6/22/95         3           68 20(240)         Custer         Surfacing         7/27/95         3           69 20(304)         Custer         Resurfacing         3/23/95         2           70 21 (280)	5437(171)	Kingfisher	Resurfacing	4/20/95	2
57 27(258)         Grant         Resurfacing         4/20/95         1           58 27(262)         Grant         Surfacing         4/3/95         0           59 27(265)         Grant         Surfacing         8/14/95         0           60 27(286)         Grant         Resurfacing         4/25/96         0           61 30N(023)         Rogers         Surfacing         1/26/95         4           61 30N(023)         Rogers         Surfacing         1/26/95         4           63 32(215)         Hughes         Surfacing         6/22/95         3           64 32(219)         Hughes         Surfacing         7/25/96         3           65 33B(156)         Jackson         Surfacing         1/26/95         2           66 33(165)         Jackson         Surfacing         2/22/95         3           67 19(305)         Creek         Resurfacing         2/22/95         3           68 20(240)         Custer         Surfacing         7/22/95         3           68 20(240)         Custer         Resurfacing         2/22/96         4           70 21(2(254)         Delaware         Surfacing         3/21/96         3           712(1(280)	55 37(170)	Kingfisher	Resurfacing	4/20/95	5
58 27(262)         Grant         Surfacing         4/3/95         0           59 27(265)         Grant         Surfacing         8/14/95         0           60 27(286)         Grant         Resurfacing         4/25/96         0           61 30N(023)         Rogers         Surfacing         1/23/97         3           62 32(167)         Hughes         Surfacing         1/26/95         4           63 32(215)         Hughes         Resurfacing         6/22/95         3           64 32(219)         Hughes         Surfacing         7/25/96         3           65 33B(156)         Jackson         Surfacing         1/26/95         2           66 33(165)         Jackson         Surfacing         2/23/95         2           67 19(305)         Creek         Resurfacing         6/22/95         3           68 20(240)         Custer         Surfacing         7/27/95         3           68 20(240)         Custer         Resurfacing         3/22/96         4           70 21C(254)         Delaware         Surfacing         3/21/96         3           71 21(280)         Delaware         Resurfacing         3/21/96         3           72 21(280)	56 37(177)	Kingfisher	Resurfacing	4/25/96	4
5927(265)         Grant         Surfacing         8/14/95         0           6027(286)         Grant         Resurfacing         4/25/96         0           6130N(023)         Rogers         Surfacing         1/23/97         3           6232(167)         Hughes         Surfacing         1/26/95         4           6332(215)         Hughes         Resurfacing         6/22/95         3           64 32(219)         Hughes         Surfacing         7/25/96         3           65 33B(156)         Jackson         Surfacing         1/26/95         2           66 33(165)         Jackson         Surfacing         2/23/95         2           67 19(305)         Creek         Resurfacing         6/22/95         3           68 20(240)         Custer         Surfacing         7/27/95         3           69 20(304)         Custer         Resurfacing         2/22/96         4           70 21C(254)         Delaware         Resurfacing         3/21/96         3           712(1280)         Delaware         Resurfacing         3/21/96         3           7321(276)         Delaware         Overlay         3/23/95         2           74 23(135)	57 27(258)	Grant	Resurfacing	4/20/95	1
6027(286)         Grant         Resurfacing         4/25/96         0           6130N(023)         Rogers         Surfacing         1/23/97         3           6232(167)         Hughes         Surfacing         1/26/95         4           6332(215)         Hughes         Resurfacing         6/22/95         3           6432(219)         Hughes         Surfacing         7/25/96         3           6533B(156)         Jackson         Surfacing         1/26/95         2           6633(165)         Jackson         Surfacing         2/23/95         2           6719(305)         Creek         Resurfacing         6/22/95         3           6820(240)         Custer         Surfacing         7/27/95         3           6920(304)         Custer         Resurfacing         3/23/95         2           7021C(254)         Delaware         Surfacing         3/23/95         2           7121(280)         Delaware         Resurfacing         3/21/96         3           7221(280)         Delaware         Resurfacing         3/21/96         3           7423(375)         Ellis         Resurfacing         7/25/96         1           7524B(208) <td< td=""><td>58 27(262)</td><td>Grant</td><td>Surfacing</td><td>4/3/95</td><td>0</td></td<>	58 27(262)	Grant	Surfacing	4/3/95	0
61 30N(023) Rogers Surfacing 1/23/97 3 62 32(167) Hughes Surfacing 1/26/95 4 63 32(215) Hughes Resurfacing 6/22/95 3 64 32(219) Hughes Surfacing 7/25/96 3 65 33B(156) Jackson Surfacing 1/26/95 2 66 33(165) Jackson Surfacing 2/23/95 2 67 19(305) Creek Resurfacing 6/22/95 3 68 20(240) Custer Surfacing 7/27/95 3 69 20(304) Custer Resurfacing 2/22/96 4 70 21 C(254) Delaware Surfacing 3/23/95 2 71 21 (280) Delaware Resurfacing 3/21/96 3 72 21 (280) Delaware Resurfacing 3/21/96 3 73 21 (276) Delaware Resurfacing 3/21/96 3 73 21 (276) Delaware Resurfacing 3/21/96 3 73 21 (276) Delaware Resurfacing 3/21/96 3 75 24 (240) Garfield Resurfacing 7/25/96 1 75 24 (240) Garfield Resurfacing 7/25/96 1 77 24 (257) Garfield Resurfacing 4/20/95 1 77 24 (257) Garfield Resurfacing 3/21/96 1 79 24 (241) Garfield Resurfacing 3/21/96 1 80 25 (311) Garvin Resurfacing 4/20/95 1 81 25 (312) Garvin Resurfacing 4/20/95 3 82 25 (323) Garvin Resurfacing 4/20/95 3 82 25 (323) Garvin Resurfacing 4/20/95 3 82 25 (223) Garvin Resurfacing 4/20/95 3 3 4 26 (223) Grady Overlay 1/25/96 4 4 20/95 3 3 4 26 (223) Grady Resurfacing 4/20/95 4 4 20/95 4 4 20/95	59 27(265)	Grant	Surfacing	8/14/95	0
62 32(167) Hughes Surfacing 1/26/95 4 63 32(215) Hughes Resurfacing 6/22/95 3 64 32(219) Hughes Surfacing 7/25/96 3 65 33B(156) Jackson Surfacing 1/26/95 2 66 33(165) Jackson Surfacing 2/23/95 2 67 19(305) Creek Resurfacing 6/22/95 3 68 20(240) Custer Surfacing 7/27/95 3 69 20(304) Custer Resurfacing 2/22/96 4 70 21 C(254) Delaware Surfacing 3/23/95 2 71 21(280) Delaware Resurfacing 3/21/96 3 72 21(280) Delaware Resurfacing 3/21/96 3 73 21(276) Delaware Overlay 3/23/95 2 74 23(135) Ellis Resurfacing 7/25/96 1 75 24B(208) Garfield Surfacing 7/25/96 1 77 24(240) Garfield Resurfacing 4/20/95 1 78 24(245) Garfield Resurfacing 4/20/95 1 79 24(241) Garfield Resurfacing 4/20/95 1 80 25(311) Garvin Resurfacing 4/20/95 3 81 25(312) Garvin Resurfacing 4/20/95 3 82 25(323) Grady Surfacing 4/20/95 3 83 26C(233) Grady Surfacing 4/20/95 3 84 26(295) Grady Overlay 1/25/96 4 85 26(294) Grady Overlay 1/25/96 4 86 26(288) Grady Resurfacing 4/20/95 3 87 10(346) Carter Resurfacing 3/21/96 2 88 10(347) Jefferson Resurfacing 4/20/95 4 89 10(362) Carter Resurfacing 4/25/96 1 90 11(C(337) Cherokee Surfacing 4/25/96 1 91 11C(337) Cherokee Surfacing 4/25/96 1	6027(286)	Grant	Resurfacing	4/25/96	0
63 32(215)         Hughes         Resurfacing         6/22/95         3           64 32(219)         Hughes         Surfacing         7/25/96         3           65 33B(156)         Jackson         Surfacing         1/26/95         2           66 33(165)         Jackson         Surfacing         2/23/95         2           67 19(305)         Creek         Resurfacing         6/22/95         3           68 20(240)         Custer         Surfacing         7/27/95         3           68 20(304)         Custer         Resurfacing         2/22/96         4           70 21 C(254)         Delaware         Surfacing         3/23/95         2           70 21 (276)         Delaware         Resurfacing         3/21/96         3           71 21 (280)         Delaware         Resurfacing         3/21/96         3           72 21 (280)         Delaware         Overlay         3/23/95         2           74 23 (1276)         Delaware         Overlay         3/23/95         2           74 23 (1276)         Delaware         Overlay         3/25/96         1           75 24 B(208)         Garfield         Surfacing         7/25/96         1           75 2	61 30N(023)	Rogers	Surfacing	1/23/97	3
64 32(219)         Hughes         Surfacing         7/25/96         3           65 33B(156)         Jackson         Surfacing         1/26/95         2           66 33(165)         Jackson         Surfacing         2/23/95         2           67 19(305)         Creek         Resurfacing         6/22/95         3           68 20(240)         Custer         Surfacing         7/27/95         3           69 20(304)         Custer         Resurfacing         2/22/96         4           70 21 C(254)         Delaware         Resurfacing         3/23/95         2           71 21 (280)         Delaware         Resurfacing         3/21/96         3           72 21 (280)         Delaware         Resurfacing         3/21/96         3           73 21 (276)         Delaware         Overlay         3/23/95         2           74 23 (135)         Ellis         Resurfacing         7/25/96         1           75 24B(208)         Garfield         Surfacing         7/25/96         1           76 24(240)         Garfield         Resurfacing         4/20/95         1           77 24(257)         Garfield         Resurfacing         4/25/96         2 <td< td=""><td>62 32(167)</td><td>Hughes</td><td>Surfacing</td><td>1/26/95</td><td>4</td></td<>	62 32(167)	Hughes	Surfacing	1/26/95	4
65 33B(156)         Jackson         Surfacing         1/26/95         2           66 33(165)         Jackson         Surfacing         2/23/95         2           67 19(305)         Creek         Resurfacing         6/22/95         3           68 20(240)         Custer         Surfacing         7/27/95         3           69 20(304)         Custer         Resurfacing         2/22/96         4           70 21 C(254)         Delaware         Resurfacing         3/23/95         2           71 21(280)         Delaware         Resurfacing         3/21/96         3           72 21(280)         Delaware         Resurfacing         3/21/96         3           73 21(276)         Delaware         Overlay         3/23/95         2           74 23(135)         Ellis         Resurfacing         3/21/96         3           75 24B(208)         Garfield         Surfacing         7/25/96         1           75 24B(208)         Garfield         Resurfacing         4/20/95         1           76 24(240)         Garfield         Resurfacing         4/20/95         1           77 24(257)         Garfield         Resurfacing         3/21/96         1 <t< td=""><td>63 32(215)</td><td>Hughes</td><td>Resurfacing</td><td>6/22/95</td><td>3</td></t<>	63 32(215)	Hughes	Resurfacing	6/22/95	3
65 33B(156)         Jackson         Surfacing         1/26/95         2           66 33(165)         Jackson         Surfacing         2/23/95         2           67 19(305)         Creek         Resurfacing         6/22/95         3           68 20(240)         Custer         Surfacing         7/27/95         3           69 20(304)         Custer         Resurfacing         2/22/96         4           70 21 C(254)         Delaware         Resurfacing         3/23/95         2           71 21(280)         Delaware         Resurfacing         3/21/96         3           72 21(280)         Delaware         Resurfacing         3/21/96         3           73 21(276)         Delaware         Overlay         3/23/95         2           74 23(135)         Ellis         Resurfacing         3/21/96         3           75 24B(208)         Garfield         Surfacing         7/25/96         1           75 24B(208)         Garfield         Resurfacing         4/20/95         1           76 24(240)         Garfield         Resurfacing         4/20/95         1           77 24(257)         Garfield         Resurfacing         3/21/96         1 <t< td=""><td>64 32(219)</td><td>Hughes</td><td>Surfacing</td><td>7/25/96</td><td>3</td></t<>	64 32(219)	Hughes	Surfacing	7/25/96	3
67 19(305)         Creek         Resurfacing         6/22/95         3           68 20(240)         Custer         Surfacing         7/27/95         3           69 20(304)         Custer         Resurfacing         2/22/96         4           70 21 C(254)         Delaware         Surfacing         3/23/95         2           71 21 (280)         Delaware         Resurfacing         3/21/96         3           72 21 (280)         Delaware         Resurfacing         3/21/96         3           73 21 (276)         Delaware         Overlay         3/23/95         2           73 21 (276)         Delaware         Overlay         3/23/95         2           74 23 (135)         Ellis         Resurfacing         7/25/96         1           75 24B (208)         Garfield         Surfacing         5/25/95         1           75 24B (208)         Garfield         Resurfacing         4/20/95         1           76 24 (240)         Garfield         Resurfacing         4/25/96         2           78 24 (245)         Garfield         Resurfacing         3/21/96         1           79 24 (241)         Garfield         Resurfacing         4/20/95         1	65 33B(156)	Jackson	Surfacing	1/26/95	2
68 20(240)         Custer         Surfacing         7/27/95         3           69 20(304)         Custer         Resurfacing         2/22/96         4           70 21C(254)         Delaware         Surfacing         3/23/95         2           71 21(280)         Delaware         Resurfacing         3/21/96         3           72 21(280)         Delaware         Resurfacing         3/21/96         3           73 21(276)         Delaware         Overlay         3/23/95         2           74 23(135)         Ellis         Resurfacing         7/25/96         1           75 24B(208)         Garfield         Surfacing         5/25/95         1           75 24B(208)         Garfield         Resurfacing         4/20/95         1           76 24(240)         Garfield         Resurfacing         4/20/95         1           77 24(257)         Garfield         Resurfacing         4/25/96         2           78 24(245)         Garfield         Resurfacing         4/20/95         1           80 25(311)         Garvin         Resurfacing         4/20/95         5           81 25(312)         Garvin         Resurfacing         4/25/96         7           <	66 33(165)	Jackson		2/23/95	2
6920(304)         Custer         Resurfacing         2/22/96         4           7021C(254)         Delaware         Surfacing         3/23/95         2           7121(280)         Delaware         Resurfacing         3/21/96         3           7221(280)         Delaware         Resurfacing         3/21/96         3           7321(276)         Delaware         Overlay         3/23/95         2           7423(135)         Ellis         Resurfacing         7/25/96         1           7524B(208)         Garfield         Surfacing         5/25/95         1           7524B(208)         Garfield         Resurfacing         4/20/95         1           7524B(208)         Garfield         Resurfacing         4/25/96         2           7624(240)         Garfield         Resurfacing         4/25/96         2           7824(245)         Garfield         Resurfacing         3/21/96         1           7924(241)         Garfield         Resurfacing         4/20/95         1           8025(311)         Garvin         Resurfacing         4/20/95         5           8125(312)         Garvin         Resurfacing         4/25/96         7           8225(3	67 19(305)	Creek	Resurfacing	6/22/95	3
69 20(304)         Custer         Resurfacing         2/22/96         4           70 21C(254)         Delaware         Surfacing         3/23/95         2           71 21(280)         Delaware         Resurfacing         3/21/96         3           72 21(280)         Delaware         Resurfacing         3/21/96         3           73 21(276)         Delaware         Overlay         3/23/95         2           74 23(135)         Ellis         Resurfacing         7/25/96         1           75 24B(208)         Garfield         Surfacing         5/25/95         1           75 24B(208)         Garfield         Resurfacing         4/20/95         1           75 24B(208)         Garfield         Resurfacing         4/20/95         1           76 24(240)         Garfield         Resurfacing         4/20/95         1           77 24(257)         Garfield         Resurfacing         3/21/96         2           78 24(245)         Garfield         Resurfacing         4/20/95         1           79 24(241)         Garfield         Resurfacing         4/20/95         1           80 25(311)         Garvin         Resurfacing         4/20/95         3	6820(240)	Custer	Surfacing	7/27/95	3
7121(280)         Delaware         Resurfacing         3/21/96         3           7221(280)         Delaware         Resurfacing         3/21/96         3           7321(276)         Delaware         Overlay         3/23/95         2           7423(135)         Ellis         Resurfacing         7/25/96         1           7524B(208)         Garfield         Surfacing         5/25/95         1           7524(240)         Garfield         Resurfacing         4/20/95         1           7624(240)         Garfield         Resurfacing         4/25/96         2           7824(257)         Garfield         Resurfacing         3/21/96         1           7924(241)         Garfield         Resurfacing         3/21/96         1           7924(241)         Garfield         Resurfacing         4/20/95         1           8025(311)         Garvin         Resurfacing         4/20/95         5           8125(312)         Garvin         Resurfacing         6/22/95         3           8225(323)         Garvin         Resurfacing         4/25/96         7           8326C(233)         Grady         Surfacing         4/20/95         3           8426(295) </td <td>69 20 (304)</td> <td>Custer</td> <td>Resurfacing</td> <td>2/22/96</td> <td>4</td>	69 20 (304)	Custer	Resurfacing	2/22/96	4
7221(280)         Delaware         Resurfacing         3/21/96         3           7321(276)         Delaware         Overlay         3/23/95         2           7423(135)         Ellis         Resurfacing         7/25/96         1           7524B(208)         Garfield         Surfacing         5/25/95         1           7524B(208)         Garfield         Resurfacing         4/20/95         1           7624(240)         Garfield         Resurfacing         4/25/96         2           724(257)         Garfield         Resurfacing         3/21/96         1           7824(245)         Garfield         Resurfacing         4/20/95         1           7924(241)         Garfield         Resurfacing         4/20/95         1           8025(311)         Garvin         Resurfacing         4/20/95         5           8125(312)         Garvin         Resurfacing         6/22/95         3           8225(323)         Garvin         Resurfacing         4/25/96         7           8326C(233)         Grady         Surfacing         4/20/95         3           8426(295)         Grady         Overlay         1/25/96         4           8526(294)	7021C(254)	Delaware	Surfacing	3/23/95	2
7221(280)         Delaware         Resurfacing         3/21/96         3           7321(276)         Delaware         Overlay         3/23/95         2           7423(135)         Ellis         Resurfacing         7/25/96         1           7524B(208)         Garfield         Surfacing         5/25/95         1           7524B(208)         Garfield         Resurfacing         4/20/95         1           7624(240)         Garfield         Resurfacing         4/25/96         2           724(257)         Garfield         Resurfacing         3/21/96         1           7824(245)         Garfield         Resurfacing         4/20/95         1           7924(241)         Garfield         Resurfacing         4/20/95         1           8025(311)         Garvin         Resurfacing         4/20/95         5           8125(312)         Garvin         Resurfacing         6/22/95         3           8225(323)         Garvin         Resurfacing         4/25/96         7           8326C(233)         Grady         Surfacing         4/20/95         3           8426(295)         Grady         Overlay         1/25/96         4           8526(294)	7121(280)	Delaware	Resurfacing	3/21/96	3
74 23(135)         Ellis         Resurfacing         7/25/96         1           75 24B(208)         Garfield         Surfacing         5/25/95         1           76 24(240)         Garfield         Resurfacing         4/20/95         1           77 24(257)         Garfield         Resurfacing         4/25/96         2           78 24(245)         Garfield         Resurfacing         3/21/96         1           79 24(241)         Garfield         Resurfacing         4/20/95         1           80 25(311)         Garvin         Resurfacing         4/20/95         5           81 25(312)         Garvin         Resurfacing         6/22/95         3           82 25(323)         Garvin         Resurfacing         4/25/96         7           83 26C(233)         Grady         Surfacing         4/20/95         3           84 26(295)         Grady         Overlay         1/25/96         4           85 26(294)         Grady         Overlay         1/25/96         0           86 26(288)         Grady         Resurfacing         4/20/95         5           87 10(346)         Carter         Surfacing         4/20/95         4           88 10(347) <td>7221(280)</td> <td>Delaware</td> <td>Resurfacing</td> <td>3/21/96</td> <td>3</td>	7221(280)	Delaware	Resurfacing	3/21/96	3
7524B(208)         Garfield         Surfacing         5/25/95         1           7624(240)         Garfield         Resurfacing         4/20/95         1           7724(257)         Garfield         Resurfacing         4/25/96         2           7824(245)         Garfield         Resurfacing         3/21/96         1           7924(241)         Garfield         Resurfacing         4/20/95         1           8025(311)         Garvin         Resurfacing         4/20/95         5           8125(312)         Garvin         Resurfacing         6/22/95         3           8225(323)         Garvin         Resurfacing         4/25/96         7           8326C(233)         Grady         Surfacing         4/20/95         3           8426(295)         Grady         Overlay         1/25/96         4           8526(294)         Grady         Overlay         1/25/96         0           86 26(288)         Grady         Resurfacing         4/20/95         5           87 10(346)         Carter         Surfacing         3/21/96         2           88 10(347)         Jefferson         Resurfacing         4/20/95         4           89 10(362)	7321(276)	Delaware	Overlay	3/23/95	2
7624(240)         Garfield         Resurfacing         4/20/95         1           7724(257)         Garfield         Resurfacing         4/25/96         2           7824(245)         Garfield         Resurfacing         3/21/96         1           7924(241)         Garfield         Resurfacing         4/20/95         1           8025(311)         Garvin         Resurfacing         4/20/95         5           8125(312)         Garvin         Resurfacing         6/22/95         3           8225(323)         Garvin         Resurfacing         4/25/96         7           8326C(233)         Grady         Surfacing         4/20/95         3           8426(295)         Grady         Overlay         1/25/96         4           8526(294)         Grady         Overlay         1/25/96         0           8626(288)         Grady         Resurfacing         4/20/95         5           8710(346)         Carter         Surfacing         3/21/96         2           8810(347)         Jefferson         Resurfacing         4/20/95         4           8910(362)         Carter         Resurfacing         4/25/96         1           9010(363) <t< td=""><td>74 23(135)</td><td>Ellis</td><td>Resurfacing</td><td>7/25/96</td><td>1</td></t<>	74 23(135)	Ellis	Resurfacing	7/25/96	1
7724(257)         Garfield         Resurfacing         4/25/96         2           78 24(245)         Garfield         Resurfacing         3/21/96         1           79 24(241)         Garfield         Resurfacing         4/20/95         1           80 25(311)         Garvin         Resurfacing         4/20/95         5           81 25(312)         Garvin         Resurfacing         6/22/95         3           82 25(323)         Garvin         Resurfacing         4/25/96         7           83 26C(233)         Grady         Surfacing         4/20/95         3           84 26(295)         Grady         Overlay         1/25/96         4           85 26(294)         Grady         Overlay         1/25/96         0           86 26(288)         Grady         Resurfacing         4/20/95         5           87 10(346)         Carter         Surfacing         3/21/96         2           88 10(347)         Jefferson         Resurfacing         4/20/95         4           89 10(362)         Carter         Resurfacing         4/25/96         1           90 10(363)         Carter         Resurfacing         4/25/96         1           91 11C(337) <td>7524B(208)</td> <td>Garfield</td> <td>Surfacing</td> <td>5/25/95</td> <td>1</td>	7524B(208)	Garfield	Surfacing	5/25/95	1
78 24(245)         Garfield         Resurfacing         3/21/96         1           79 24(241)         Garfield         Resurfacing         4/20/95         1           80 25(311)         Garvin         Resurfacing         4/20/95         5           81 25(312)         Garvin         Resurfacing         6/22/95         3           82 25(323)         Garvin         Resurfacing         4/25/96         7           83 26C(233)         Grady         Surfacing         4/20/95         3           84 26(295)         Grady         Overlay         1/25/96         4           85 26(294)         Grady         Overlay         1/25/96         0           86 26(288)         Grady         Resurfacing         4/20/95         5           87 10(346)         Carter         Surfacing         3/21/96         2           88 10(347)         Jefferson         Resurfacing         4/20/95         4           89 10(362)         Carter         Resurfacing         4/25/96         1           90 10(363)         Carter         Resurfacing         4/25/96         1           91 11C(337)         Cherokee         Surfacing         1/23/97         5	7624(240)	Garfield	Resurfacing	4/20/95	1
79 24(241)         Garfield         Resurfacing         4/20/95         1           80 25(311)         Garvin         Resurfacing         4/20/95         5           81 25(312)         Garvin         Resurfacing         6/22/95         3           82 25(323)         Garvin         Resurfacing         4/25/96         7           83 26C(233)         Grady         Surfacing         4/20/95         3           84 26(295)         Grady         Overlay         1/25/96         4           85 26(294)         Grady         Overlay         1/25/96         0           86 26(288)         Grady         Resurfacing         4/20/95         5           87 10(346)         Carter         Surfacing         3/21/96         2           88 10(347)         Jefferson         Resurfacing         4/20/95         4           89 10(362)         Carter         Resurfacing         4/25/96         1           90 10(363)         Carter         Resurfacing         4/25/96         1           91 11C(337)         Cherokee         Surfacing         1/23/97         5	7724(257)	Garfield	Resurfacing	4/25/96	2
80 25(311)       Garvin       Resurfacing       4/20/95       5         81 25(312)       Garvin       Resurfacing       6/22/95       3         82 25(323)       Garvin       Resurfacing       4/25/96       7         83 26C(233)       Grady       Surfacing       4/20/95       3         84 26(295)       Grady       Overlay       1/25/96       4         85 26(294)       Grady       Overlay       1/25/96       0         86 26(288)       Grady       Resurfacing       4/20/95       5         87 10(346)       Carter       Surfacing       3/21/96       2         88 10(347)       Jefferson       Resurfacing       4/20/95       4         89 10(362)       Carter       Resurfacing       4/25/96       1         90 10(363)       Carter       Resurfacing       4/25/96       1         91 11C(337)       Cherokee       Surfacing       1/23/97       5	78 24(245)	Garfield	Resurfacing	3/21/96	1
81 25(312)       Garvin       Resurfacing       6/22/95       3         82 25(323)       Garvin       Resurfacing       4/25/96       7         83 26C(233)       Grady       Surfacing       4/20/95       3         84 26(295)       Grady       Overlay       1/25/96       4         85 26(294)       Grady       Overlay       1/25/96       0         86 26(288)       Grady       Resurfacing       4/20/95       5         87 10(346)       Carter       Surfacing       3/21/96       2         88 10(347)       Jefferson       Resurfacing       4/20/95       4         89 10(362)       Carter       Resurfacing       4/25/96       1         90 10(363)       Carter       Resurfacing       4/25/96       1         91 11C(337)       Cherokee       Surfacing       1/23/97       5	7924(241)	Garfield	Resurfacing	4/20/95	1
82 25(323)         Garvin         Resurfacing         4/25/96         7           83 26C(233)         Grady         Surfacing         4/20/95         3           84 26(295)         Grady         Overlay         1/25/96         4           85 26(294)         Grady         Overlay         1/25/96         0           86 26(288)         Grady         Resurfacing         4/20/95         5           87 10(346)         Carter         Surfacing         3/21/96         2           88 10(347)         Jefferson         Resurfacing         4/20/95         4           89 10(362)         Carter         Resurfacing         4/25/96         1           90 10(363)         Carter         Resurfacing         4/25/96         1           91 11C(337)         Cherokee         Surfacing         1/23/97         5	8025(311)	Garvin	Resurfacing	4/20/95	5
83 26C(233)       Grady       Surfacing       4/20/95       3         84 26(295)       Grady       Overlay       1/25/96       4         85 26(294)       Grady       Overlay       1/25/96       0         86 26(288)       Grady       Resurfacing       4/20/95       5         87 10(346)       Carter       Surfacing       3/21/96       2         88 10(347)       Jefferson       Resurfacing       4/20/95       4         89 10(362)       Carter       Resurfacing       4/25/96       1         90 10(363)       Carter       Resurfacing       4/25/96       1         91 11C(337)       Cherokee       Surfacing       1/23/97       5	81 25(312)	Garvin	Resurfacing	6/22/95	3
84 26(295)       Grady       Overlay       1/25/96       4         85 26(294)       Grady       Overlay       1/25/96       0         86 26(288)       Grady       Resurfacing       4/20/95       5         87 10(346)       Carter       Surfacing       3/21/96       2         88 10(347)       Jefferson       Resurfacing       4/20/95       4         89 10(362)       Carter       Resurfacing       4/25/96       1         90 10(363)       Carter       Resurfacing       4/25/96       1         91 11C(337)       Cherokee       Surfacing       1/23/97       5	82 25(323)	Garvin	Resurfacing	4/25/96	7
84 26(295)       Grady       Overlay       1/25/96       4         85 26(294)       Grady       Overlay       1/25/96       0         86 26(288)       Grady       Resurfacing       4/20/95       5         87 10(346)       Carter       Surfacing       3/21/96       2         88 10(347)       Jefferson       Resurfacing       4/20/95       4         89 10(362)       Carter       Resurfacing       4/25/96       1         90 10(363)       Carter       Resurfacing       4/25/96       1         91 11C(337)       Cherokee       Surfacing       1/23/97       5	8326C(233)	Grady	Surfacing	4/20/95	3
86 26(288)       Grady       Resurfacing       4/20/95       5         87 10(346)       Carter       Surfacing       3/21/96       2         88 10(347)       Jefferson       Resurfacing       4/20/95       4         89 10(362)       Carter       Resurfacing       4/25/96       1         90 10(363)       Carter       Resurfacing       4/25/96       1         91 11C(337)       Cherokee       Surfacing       1/23/97       5	84 26(295)	Grady	Overlay	1/25/96	4
87 10(346)       Carter       Surfacing       3/21/96       2         88 10(347)       Jefferson       Resurfacing       4/20/95       4         89 10(362)       Carter       Resurfacing       4/25/96       1         90 10(363)       Carter       Resurfacing       4/25/96       1         91 11C(337)       Cherokee       Surfacing       1/23/97       5	85 26(294)	Grady	Overlay	1/25/96	0
88 10(347)       Jefferson       Resurfacing       4/20/95       4         89 10(362)       Carter       Resurfacing       4/25/96       1         90 10(363)       Carter       Resurfacing       4/25/96       1         91 11C(337)       Cherokee       Surfacing       1/23/97       5	86 26(288)	Grady	Resurfacing	4/20/95	5
89 10(362)       Carter       Resurfacing       4/25/96       1         90 10(363)       Carter       Resurfacing       4/25/96       1         91 11C(337)       Cherokee       Surfacing       1/23/97       5	87 10(346)	Carter	Surfacing	3/21/96	2
90 10(363)         Carter         Resurfacing         4/25/96         1           91 11C(337)         Cherokee         Surfacing         1/23/97         5	88 10(347)	Jefferson	Resurfacing	4/20/95	4
91 11C(337) Cherokee Surfacing 1/23/97 5	89 10(362)	Carter	Resurfacing	4/25/96	1
		Carter			1
9211(386) Delaware Overlay 3/23/95 7	91 11C(337)	Cherokee	Surfacing	1/23/97	5
	9211(386)	Delaware	Overlay	3/23/95	7

ID	Lowest Bid	2nd Lowest Bid	Highest Bid	MLOT	Bid Range
47	\$2,157,646.21	\$2,233,859.04	\$2,714,744.45	\$76,212.83	\$557,098.24
48	\$575,394.50	\$698,457.60	\$698,457.60	\$123,063.10	\$123,063.10
49	\$463,362.50	\$477,536.70	\$564,017.90	\$14,174.20	\$100,655.40
50	\$220,110.12	\$237,394.49	\$245,369.75	\$17,284.37	\$25,259.63
51	\$1,216,269.00	\$1,243,847.50	\$1,498,185.50	\$27,578.50	\$281,916.50
52	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
53	\$95,006.70	\$98,278.00	\$135,583.00	\$3,271.30	\$40,576.30
54			\$106,669.75	\$15,206.10	\$15,206.10
	\$91,463.65	\$106,669.75 \$120,273,75			
55	\$103,528.75	\$120,273.75	\$162,355.00	\$16,745.00	\$58,826.25 \$38,705.50
56	\$314,780.00	\$324,025.00	\$343,485.50	\$9,245.00	\$28,705.50
57	\$53,271.69	\$53,271.69	\$53,271.69	\$0.00	\$0.00
58	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
59	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
60	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
61	\$389,977.19	\$534,835.66	\$595,847.85	\$144,858.47	\$205,870.66
62	\$888,210.40	\$905,175.45	\$1,132,975.20	\$16,965.05	\$244,764.80
63	\$411,630.15	\$440,377.55	\$462,922.00	\$28,747.40	\$51,291.85
64	\$246,096.72	\$251,881.81	\$284,102.65	\$5,785.09	\$38,005.93
65	\$1,835,630.78	\$1,849,131.96	\$1,849,131.96	\$13,501.18	\$13,501.18
66	\$196,828.35	\$252,919.89	\$252,919.89	\$56,091.54	\$56,091.54
67	\$693,532.00	\$728,128.00	\$835,605.50	\$34,596.00	\$142,073.50
68	\$896,891.10	\$1,025,618.50	\$1,044,942.25	\$128,727.40	\$148,051.15
69	\$995,551.00	\$997,934.95	\$1,019,688.85	\$2,383.95	\$24,137.85
70	\$843,926.21	\$914,814.57	\$914,814.57	\$70,888.36	\$70,888.36
71	\$129,097.77	\$146,858.20	\$163,857.80	\$17,760.43	\$34,760.03
72			The state of the s		
73	\$298,567.84	\$327,865.50	\$358,947.00	\$29,297.66	\$60,379.16
	\$80,324.00	\$84,545.00	\$84,545.00	\$4,221.00	\$4,221.00
74	\$418,066.95	\$418,066.95	\$418,066.95	\$0.00	\$0.00
75	\$1,920,149.45	\$1,920,149.45	\$1,920,149.45	\$0.00	\$0.00
76	\$187,315.00	\$187,315.00	\$187,315.00	\$0.00	\$0.00
	\$267,416.00	\$316,133.25	\$316,133.25	\$48,717.25	\$48,717.25
78	\$726,491.10	\$726,491.10	\$726,491.10	\$0.00	\$0.00
79	\$312,500.00	\$312,500.00	\$312,500.00	\$0.00	\$0.00
80	\$203,020.40	\$204,189.80	\$267,509.30	\$1,169.40	\$64,488.90
81	\$956,353.54	\$1,202,022.38	\$1,380,404.40	\$245,668.84	\$424,050.86
82	\$514,677.97	\$525,109.80	\$796,724.28	\$10,431.83	\$282,046.31
83	\$1,840,395.85	\$1,945,571.66	\$1,983,103.88	\$105,175.81	\$142,708.03
84	\$407,454.60	\$439,601.60	\$513,571.20	\$32,147.00	\$106,116.60
85	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
86	\$495,026.00	\$498,369.00	\$681,742.00	\$3,343.00	\$186,716.00
87	\$99,590.00	\$102,790.00	\$102,790.00	\$3,200.00	\$3,200.00
88		\$1,266,775.00	\$1,669,178.00	\$6,829.00	\$409,232.00
89	\$468,832.50	\$468,832.50	\$468,832.50	\$0.00	\$0.00
90	\$198,589.00	\$198,589.00	\$198,589.00	\$0.00	\$0.00
91	\$1,196,989.50	\$1,334,275.75	\$1,480,246.65	\$137,286.25	
		~			\$283,257.15
92	\$324,440.00	\$336,198.00	\$363,428.00	\$11,758.00	\$38,988.00

ID	Engr's Estimate	Contract Amount Co	ntract Difference	Actual Cost	Cost Growth
47	\$2,634,778.90	\$2,157,646.21	(\$477,132.69)	\$2,246,270.62	4.11%
48	\$537,887.58	\$575,394.50	\$37,506.92	\$528,335.73	-8.18%
49	\$453,382.00	\$463,362.50	\$9,980.50	\$461,121.16	-0.48%
50	\$271,125.10	\$220,110.12	(\$51,014.98)	\$219,597.16	-0.23%
51	\$1,250,973.75	\$1,216,269.00	(\$34,704.75)	\$1,182,892.36	-2.74%
52	\$0.00	\$641,414.50	\$641,414.50	\$620,163.77	-3.31%
53	\$105,695.00	\$95,006.70	(\$10,688.30)	\$95,372.44	0.38%
54	\$71,386.00	\$91,463.65	\$20,077.65	\$86,234.40	-5.72%
55	\$104,845.00	\$103,528.75	(\$1,316.25)	\$108,899.89	5.19%
56	\$359,800.00	\$314,780.00	(\$45,020.00)	\$306,346.50	-2.68%
57	\$50,658.25	\$53,271.69	\$2,613.44	\$50,688.34	-4.85%
58	\$0.00	\$151,742.00	\$151,742.00	\$151,525.28	-0.14%
59	\$0.00	\$98,075.00	\$98,075.00	\$98,075.00	0.00%
60	\$0.00	\$365,640.00	\$365,640.00	\$366,283.12	0.18%
61	\$268,308.75 \$211,710.65	\$389,977.19	\$121,668.44	\$374,183.90	-4.05% 10.16%
62	\$811,719.55	\$888,210.40	\$76,490.85	\$978,410.32	10.16%
63	\$397,821.00	\$411,630.15	\$13,809.15	\$410,002.11	-0.40%
64	\$263,772.30	\$246,096.72	(\$17,675.58)	\$239,515.54	-2.67%
65	\$1,556,192.66	\$1,835,630.78	\$279,438.12	\$1,965,604.33	7.08%
66	\$199,698.42	\$196,828.35	(\$2,870.07)	\$179,253.42	-8.93%
67	\$652,030.00	\$693,532.00	\$41,502.00	\$616,469.08	-11.11%
68	\$837,860.00	\$896,891.10	\$59,031.10	\$904,571.96	0.86%
69	\$1,017,519.10	\$995,551.00	(\$21,968.10)	\$985,563.93	-1.00%
70	\$876,044.39	\$843,926.21	(\$32,118.18)	\$721,914.92	-14.46%
71	\$125,763.00	\$129,097.77	\$3,334.77	\$127,940.40	-0.90%
72	\$279,005.00	\$298,567.84	\$19,562.84	\$299,144.56	0.19%
73	\$84,395.00	\$80,321.00	(\$4,074.00)	\$75,834.11	-5.59%
74	\$416,849.50	\$418,066.95	\$1,217.45	\$413,959.76	-0.98%
75	\$1,678,981.00	\$1,920,149.45	\$241,168.45	\$1,942,503.29	1.16%
76	\$175,100.00	\$187,315.00	\$12,215.00	\$195,648.42	4.45%
77	\$331,405.00	\$267,416.00	(\$63,989.00)	\$236,902.21	-11.41%
78	\$717,694.40	\$726,491.10	\$8,796.70	\$698,591.41	-3.84%
79	\$293,926.00	\$312,500.00	\$18,574.00	\$280,006.26	-10.40%
80	\$197,778.00	\$203,020.40	\$5,242.40	\$192,161.02	-5.35%
81	\$892,788.40	\$956,353.54	\$63,565.14	\$974,485.35	1.90%
82	\$660,714.50	\$514,677.97	(\$146,036.53)	\$501,817.68	-2.50%
83	\$1,815,922.68	\$1,840,395.85	\$24,473.17	\$1,933,481.94	5.06%
84	\$451,781.00	\$407,454.60	(\$44,326.40)	\$389,944.08	-4.30%
85	\$0.00	\$492,168.40	\$492,168.40	\$461,290.60	-6.27%
86	\$486,376.00	\$495,026.00	\$8,650.00	\$478,974.48	-3.24%
87	\$106,000.00	\$99,590.00	(\$6,410.00)	\$99,586.08	0.00%
88	\$1,123,482.50	\$1,259,946.00	\$136,463.50	\$1,234,189.35	-2.04%
89	\$547,816.25	\$468,832.50	(\$78,983.75)	\$460,989.23	-1.67%
90	\$227,238.00	\$198,589.00	(\$28,649.00)	\$194,429.82	-2.09%
91	\$1,204,445.20	\$1,196,989.50	(\$7,455.70)	\$1,221,004.36	2.01%
92	\$420,700.00	\$324,440.00	(\$96,260.00)	\$322,388.45	-0.63%
52	\$420,700.00	φ324,44U.UU	(φου,200.00)	Ψ3ZZ,300.43	-0.03%

ID I	Ouration Contractor Number	r of Projects
47	551 Interstate Contracting Corp.	2
48	366 T. J. Campbell Const. Co.	3
49	60 Northern Improvement Company	3
50	120 Shears Construction Co.	19
51	87 Shears Construction Co.	19
52	70 The Cummins Construction Co., Inc.	35
53	100 Mcconnell Construction, Inc.	3
54	60 Mcconnell Construction, Inc.	3
55	116 Shell Const. Co., Inc.	2
56	36 The Cummins Construction Co., Inc.	35
57	109 Evans & Associates Const.	4
58	118 Grant County Commissioners	1
59	20 The Cummins Construction Co., Inc.	35
60	42 The Cummins Construction Co., Inc.	35
61	162 Bemis Construction, Inc.	1
62	268 Glover Construction Co., Inc.	30
63	56 The Cummins Construction Co., Inc.	35
64	90 The Cummins Construction Co., Inc.	35
65	467 Shears Construction Co.	19
66 67	229 Shears Construction Co.	19
67	271 APAC-Oklahoma, Inc.	7
68 69	185 Comell Constr. Co., Inc.	8
70	184 Circle S Paving Co., Inc. 249 Barnhart Construction	4
71	296 The Cummins Construction Co., Inc.	35
72	296 The Cummins Construction Co., Inc.	35
73	98 Glover Construction Co., Inc.	30
74	100 Broce Const. Co., Inc.	18
75	599The Cummins Construction Co., Inc.	35
76	80 The Cummins Construction Co., Inc.	35
77	21 The Cummins Construction Co., Inc.	35
78	234 Shears Construction Co.	19
79	91 The Cummins Construction Co., Inc.	35
80	45 Haskell Lemon Construction Co.	11
81	63 Broce Const. Co., Inc.	18
82	90 Shears Construction Co.	19
83	740 Bruton Construction Co., Inc.	1
84	93 Broce Const. Co., Inc.	18
85	86 Shears Construction Co.	19
86	129 Shears Construction Co.	19
87	227 Broce Const. Co., Inc.	18
88	399 Shears Construction Co.	19
89	304 Broce Const. Co., Inc.	18
90	131 Broce Const. Co., Inc.	18
91	197 Frix & Foster Const. Co., Inc.	1
92	62 Empire Construction & Materials, Inc.	6

ID Total	Cost Growth Resident Engineer	Weather No of Ba	d Weather Days
47	0.03 ac	Yes	120
48	-0.31 q	Yes	61
49	-0.05t	No	0
50	-0.21 ap	Yes	20
51	-0.21 ah	Yes	36
52	-0.57 ah	No	0
53	0.01	No	0
54	0.01 ao	No	0
55	0.07 ao	No	0
56	-0.571	No	0
57	-0.15 ao	No	0
58	0 ab	Yes	61
59	-0.57 ao	No	0
60	-0.571	No	0
61	-0.04 am	Yes	61
62	0.721	Yes	42
63	-0.571	No	0
64	-0.571	No	. 0
65	-0.21 m	Yes	58
66	-0.21 m	Yes	61
67	-0.31 ae	Yes	17
68	0.22 aq	Yes	120
69	-0.05aq	Yes	60
70	-0.14am	Yes	45
71	-0.57 am	Yes	61
72	-0.57 am	Yes	61
73	0.72.am	No	0
74	-0.35 j	No	.0
75	-0.571	Yes	66
76	-0.57 ao	No	0
77	-0.571	No	0
78	-0.211	Yes	58
79	-0.57 ao	No.	0
80	-0.48t	Yes	37
81	-0.35 p	Yes	61
82	-0.21 p	No	0
83	0.05g	Yes	128
84	-0.35w	Yes	61
85 86	-0.21g	Yes	40
86 87	-0.21 g	Yes	38
88	-0.35ad	Yes Yes	61
	-0.21 w		96
89	-0.35ad	No	0
90	-0.35ad	No Yes	0 61
91	0.02aj		61
92	-0.21 c	Yes	61

ID Bad wea	ther Days Ratio Bidding Environ	ment Plans Review Time   Unit System
47	0.21785	21 English
48	0.16679	21 English
49	0.000021	21 English
50	0.166716	21 English-Metric
51	0.413827	21 English
52	0.000016	21 English-Metric
53	0.000011	21 English-Metric
54	0.000027	21 English
55	0.000027	21 English
56	0.000016	21 English-Metric
57	0.000027	21 English
58	0.516927	21 English
59	0.00006	21 English
60	0.000016	21 English-Metric
61	0.37655	21 English-Metric
62	0.1567.5	21 English
63	0.000021	21 English
64	0.000011	21 English-Metric
65	0.12425	21 English
66	0.26649	21 English
67	0.062721	21 English
68	0.64864	21 English
69	0.32613	21 English-Metric
70	0.180720	21 English
71	0.2061 11	21 English-Metric
72	0.2061 11	21 English-Metric
73	0.0000.20	21 English
74	0.000011	21 English-Metric
75	0.110212	21 English
76	0.000027	21 English
77	0.000016	21 English-Metric
78	0.247911	21 English-Metric
79	0.000027	21 English
80	0.822227	21 English
81	0.968321	21 English
82	0.000016	21 English-Metric
83	0.173027	21 English
84	0.65596	21 English-Metric
85 96	0.46516	21 English-Metric
86 07	0.294627	21 English
87	0.268711	21 English-Metric
88	0.240627	21 English
89	0.000016	21 English-Metric
90	0.000016	21 English-Metric
91	0.30965	21 English-Metric
92	0.983920	21 English

ID Out-c	of-State Firms   Work	Order Date Timi	ng of Work Order Contract	ors History
47	Yes	3/6/95	39	Yes
48	No	3/27/95	32	No
49	Yes	8/31/95	70	No
50	Yes	6/10/96	46	Yes
51	Yes	5/24/95	34	Yes
52	No	6/6/96	42	Yes
53	No	8/22/96	28	Yes
54	No.	5/23/95	33	Yes
55	No	5/22/95	32	Yes
56	Yes	6/6/96	42	Yes
57	No	6/15/95	56	No
58	No	4/4/95	1.	No
59	No	8/17/95	3	Yes
60	No	6/6/96	42	Yes
61	Yes	2/19/97	27	No
62	Yes	3/6/95	39	Yes
63	No	8/2/95	41	Yes
64	No	8/28/96	34	Yes
65	No	3/13/95	46	Yes
66	No	3/29/95	34	Yes
67	No	8/7/95	46	Yes
68	No	8/28/95	32	Yes
69	No	3/29/96	36	Yes
70	No	5/15/95	53	No
71	No	4/23/96	33	Yes
72	No	4/23/96	33	Yes
73	Yes	4/21/95	29	Yes
74	No	8/28/96	34	Yes
75	No	8/23/95	90	Yes
76	No	5/24/95	34	Yes
77	No	6/6/96	42	Yes
78	No	5/2/96	.42	Yes
79	No	5/26/95	36	Yes
80	No	5/23/95	33	Yes
81	No	7/27/95	35	Yes
82	Yes	5/23/96	28	Yes
83	No	6/2/95	43 .	Yes
84	No	3/1/96	36	Yes
85	No	3/1/96	36	Yes
86	No	5/22/95	32	Yes
87	No	4/22/96	32	Yes
88	Yes	5/24/95	34	Yes
89	No	5/29/96	34	Yes
90	No	5/24/96	29	Yes
91	No	4/14/97	81	Yes
92	Yes	5/1/95	39	No

ID Pi	ojects with Overrun	Average No of Projects with O/R	Average Overrun
47	1	0.5000	4.1100
48	0	0.0000	0.0000
49	0	0.0000	0.0000
50	3	0.1579	7.2733
51	3	0.1579	7.2733
52	10	0.2857	2.8000
53	2	0.6667	3.5150
54	2	0.6667	3.5150
55	2		3.2700
56	10	0.2857	2.8000
57	0	0.0000	0.0000
58	0	0.0000	0.0000
59	10	0.2857	2.8000
60	10	0.2857	2.8000
61	. 0	0.0000	0.0000
62	11	0.3667	14.2400
63	10	0.2857	2.8000
64	10		2.8000
65	3	0.1579	7.2733
66	3	0.1579	7.2733
67	1	0.1429	1.2200
68	4	0.5000	7.1575
69	1	0.2500	0.0200
70	0	0.0000	0.0000
71	10	0.2857	2.8000
72	10	0.2857	2.8000
73	11	0.3667	14.2400
74	1	0.0556	1.9000
75	10		2.8000
76	10		2.8000
77	10		2.8000
78	3		7.2733
79	10		2.8000
80	2	And the second s	2.6800
81	1	0.0556	1.9000
82	3		7.2733
83	1	1.0000	5.0600
84		0.0556	1.9000
85	3	0.1579	7.2733
86	3	0.1579	7.2733
87	1.	0.0556	1.9000
88	3	0.1579	7.2733
89		0.0556	1.9000
90	<u> </u>	0.0556	1.9000
91	1	1.0000	2.0100
92	0	0.0000	0.0000

ID Av	rerage Cost Growth Availabili	ity of Labor
47	0.0150	5.7
48	-0.1033	5.5
49	-0.0167	4.8
50	-0.0111	4
51	-0.0111	4.6
52	-0.0163	4
53	0.0033	3.8
54	0.0033	4.6
55	0.0350	4.6
56	-0.0163	4
57	-0.0375	4.6
58	0.0000	4.6
59	-0.0163	4.3
60	-0.0163	. 4
61	-0.0400	4.8
62	0.0240	5.7
63	-0.0163	4.8
64	-0.0163	3.8
65	-0.0111	5.7
66	-0.0111	5.5
67	-0.0443	4.8
68	0.0275	4.6
69	-0.0125	5
70	-0.1400	4.9
71	-0.0163	4.1
72	-0.0163	4.1
73	0.0240	4.9
74	-0.0194	3.8
75	-0.0163	4.9
76	-0.0163	4.6
77	-0.0163	4
78	-0.0111	4.1
79	-0.0163	4.6
80	-0.0436	4.6
81	-0.0194	4.8
82	-0.0111	4
83	0.0500	4.6
84	-0.0194	5.1
85 86	-0.0111	5.1
86	-0.0111	4.6
87	-0.0194	4.1
88	-0.0111	4.6
89	-0.0194 0.0194	4
90 91	-0.0194	4
<b></b>	0.0200	4.8
92	-0.0350	4.9

ID Project No	Location (County)	Project Type	Letting Date Number of	Bids
93 11(376)	Cherokee	Overlay	2/23/95	7
94 12(211)	Choctaw	Resurfacing	6/22/95	2
95 13(131)	Cimarron	Overlay	1/26/95	2
96 13(136)	Cimarron	Overlay	3/23/95	2
97 13(138)	Cimarron	Resurfacing	6/22/95	1
98 14(256)	Cleveland	Surfacing	2/23/95	7
99 14(393)	Cleveland	Resurfacing	4/20/95	9
100 14(423)	Cleveland	Resurfacing	7/25/96	4
101 15(149)	Coal	Resurfacing	4/20/95	3
102 16(312)	Comanche	Resurfacing	5/25/95	2
103 16(309)	Comanche	Resurfacing	8/24/95	1
104 16(315)	Comanche	Overlay	3/23/95	2
105 18(148)	Craig	Resurfacing	3/21/96	1
106 18(148)	Craig	Resurfacing	3/21/96	1
107 18(145)	Craig	Resurfacing	4/20/95	4
108 18(144)	Craig	Resurfacing	11/16/95	1
109 18(142)	Craig	Resurfacing	7/27/95	2
1101(168)	Adair	Resurfacing	2/22/96	3
111 1(164)	Adair	Resurfacing	4/20/95	5
1122C(182)	Alfalfa	Resurfacing	6/22/95	1
1132(225)	Alfalfa	Resurfacing	5/23/96	2
1143(250)	Atoka	Resurfacing	6/22/95	2
1143(230) 1154C(146)	Beaver	Surfacing	6/22/95	3
1164(173)	Beaver	Resurfacing	6/22/95	2
1175(194)	Beckham	Resurfacing	6/22/95	1
	Washita	Resurfacing	6/22/95	3
1185(223)	Beckham	Resurfacing	6/22/95	ა 3
1195(222)				3
1206(197)	Dewey	Overlay	2/23/95	
1217(229)	Bryan	Surfacing	3/23/95	2
1227(325)	Bryan	Resurfacing	3/23/95	1
1237(332)	Bryan	Resurfacing	6/22/95	3
1247(342)	Bryan	Resurfacing	6/20/96	5
125.8(366)	Caddo	Resurfacing	1/25/96	0
126 9(239)	Canadian	Surfacing	4/25/96	5
12767(246)	Seminole	Surfacing	5/23/96	3
12867(226)	Seminole	Resurfacing	4/20/95	2
12967(227)	Seminole	Resurfacing	4/20/95	2 3
13067(224)	Seminole	Overlay	3/23/95	
131 64(263)	Pushmataha	Resurfacing	6/20/96	2
13262(274)	Pontotoc	Resurfacing	6/22/95	4
13361(416)	Pittsburg	Resurfacing	6/20/96	3
13461(409)	Pittsburg	Resurfacing	10/26/95	3 3
13560(308)	Payne	Resurfacing	4/25/96	
136 60 (302)	Payne	Resurfacing	6/22/95	1
13760(301)	Payne	Resurfacing	3/21/96	3
13860(299)	Payne	Resurfacing	4/20/95	1

ID	Lowest Bid	2nd Lowest Bid	Highest Bid	MLOT	Bid Range
93	\$322,796.22	\$326,205.20	\$373,993.74	\$3,408.98	\$51,197.52
94	\$675,361.50	\$830,429.50	\$830,429.50	\$155,068.00	\$155,068.00
95	\$523,588.00	\$650,728.00	\$650,728.00	\$127,140.00	\$127,140.00
96	\$648,893.02	\$745,616.10	\$745,616.10	\$96,723.08	\$96,723.08
97	\$396,257.16	\$396,257.16	\$396,257.16	\$0.00	\$0.00
98	\$288,691.58	\$289,577.05	\$370,363.42	\$885.47	\$81,671.84
99	\$238,088.20	\$259,194.00	\$353,615.70	\$21,105.80	\$115,527.50
100	\$538,515.30	\$570,842.00	\$613,340.25	\$32,326.70	\$74,824.95
101	\$491,871.80	\$521,967.10	\$581,108.20	\$30,095.30	\$89,236.40
102					
	\$18,805.00	\$20,548.10	\$20,548.10	\$1,743.10	\$1,743.10
103	\$79,682.50	\$79,682.50	\$79,682.50	\$0.00	\$0.00
104	\$773,653.73	\$818,863.00	\$818,863.00	\$45,209.27	\$45,209.27
105	\$42,135.50	\$42,135.50	\$42,135.50	\$0.00	\$0.00
106	\$304,466.50	\$304,466.50	\$304,466.50	\$0.00	\$0.00
107	\$362,313.80	\$404,699.20	\$0.00	\$42,385.40	(\$362,313.80)
108	\$34,811.50	\$34,811.50	\$34,811.50	\$0.00	\$0.00
109	\$465,177.88	\$527,000.20	\$527,000.20	\$61,822.32	\$61,822.32
110	\$85,468.50	\$90,642.00	\$97,666.50	\$5,173.50	\$12,198.00
111	\$1,027,032.50	\$1,058,237.50	\$1,165,654.00	\$31,205.00	\$138,621.50
112	\$490,372.80	\$490,372.80	\$490,372.80	\$0.00	\$0.00
113	\$330,415.45	\$347,659.90	\$347,659.90	\$17,244.45	\$17,244.45
114	\$204,245.00	\$206,569.50	\$206,569.50	\$2,324.50	\$2,324.50
115	\$2,397,807.06	\$2,441,176.69	\$2,685,376.13	\$43,369.63	\$287,569.07
116	\$605,787.04	\$625,027.36	\$625,027.36	\$19,240.32	\$19,240.32
117	\$448,402.00	\$448,402.00	\$448,402.00	\$0.00	\$0.00
118	\$1,073,466.10	\$1,162,708.91	\$1,173,794.30	\$89,242.81	\$100,328.20
119	\$485,207.00	\$531,702.63	\$543,917.57	\$46,495.63	\$58,710.57
120	\$1,463,736.92	\$1,616,960.56	\$1,661,216.22	\$153,223.64	\$197,479.30
121	\$686,789.74	\$769,787.47	\$769,787.47	\$82,997.73	\$82,997.73
122	\$141,424.37	\$141,424.37	\$141,424.37	\$0.00	\$0.00
123	\$168,490.50	\$211,316.56	\$211,380.60	\$42,826.06	\$42,890.10
124	\$719,882.40	\$762,803.00	\$960,286.20	\$42,920.60	\$240,403.80
125	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
126	\$821,583.63	\$846,049.85	\$1,185,765.75	\$24,466.22	\$364,182.12
127	\$61,687.00	\$69,656.50	\$92,143.00	\$7,969.50	\$30,456.00
128	\$38,815.10	\$39,080.40	\$39,080.40	\$265.30	\$265.30
129	\$48,514.35	\$49,275.85	\$49,275.85	\$761.50	\$761.50
130	\$49,653.20	\$53,813.30	\$56,523.47	\$4,160.10	
131	\$195,650.00	\$223,594.00	\$223,594.00		\$6,870.27
-				\$27,944.00	\$27,944.00
132	\$442,922.85	\$449,342.05	\$598,046.72	\$6,419.20	\$155,123.87
133	\$409,725.06	\$410,408.35	\$448,629.20	\$683.29	\$38,904.14
134	\$435,327.70	\$444,744.01	\$464,647.14	\$9,416.31	\$29,319.44
135	\$827,312.95	\$845,237.47	\$874,410.45	\$17,924.52	\$47,097.50
136	\$278,742.50	\$278,742.50	\$278,742.50	\$0.00	\$0.00
137	\$368,405.32	\$405,296.63	\$464,377.20	\$36,891.31	\$95,971.88
138	\$221,516.25	\$221,516.25	\$221,516.25	\$0.00	\$0.00

ID	Engr's Estimate	Contract Amount C	Contract Difference	Actual Cost	Cost Growth
93	\$412,282.80	\$322,796.22	(\$89,486.58)	\$339,490.45	5.17%
94	\$692,509.50	\$675,361.50	(\$17,148.00)	\$660,758.70	-2.16%
95	\$786,640.00	\$523,588.00	(\$263,052.00)	\$520,117.51	-0.66%
96	\$687,756.00	\$648,893.02	(\$38,862.98)	\$646,121.17	-0.43%
97	\$353,776.00	\$396,257.16	\$42,481.16	\$395,219.28	-0.26%
98	\$306,819.69	\$288,691.58	(\$18,128.11)	\$279,496.47	-3.19%
99	\$240,081.00	\$238,088.20	(\$1,992.80)	\$238,591.68	0.21%
100	\$558,982.50	\$538,515.30	(\$20,467.20)	\$595,581.51	10.60%
101	\$483,422.00	\$491,871.80	\$8,449.80	\$488,368.44	-0.71%
102	\$15,760.00	\$18,805.00	\$3,045.00	\$17,382.54	-7.56%
103	\$0.00	\$79,682.50	\$79,682.50	\$71,268.48	-10.56%
104	\$683,905.00	\$773,653.73	\$89,748.73	\$742,615.76	-4.01%
105	\$43,340.00	\$42,135.50	(\$1,204.50)	\$39,378.96	-6.54%
106	\$272,640.00	\$304,466.50	\$31,826.50	\$297,529.23	-2.28%
107	\$389,495.00	\$362,313.80	(\$27,181.20)	\$347,727.04	-4.03%
108	\$31,813.00	\$34,811.50	\$2,998.50	\$31,490.72	-9.54%
	\$411,413.40				
109		\$465,177.88 \$95,469.50	\$53,764.48	\$463,206.92	-0.42%
110	\$93,730.00	\$85,468.50	(\$8,261.50)	\$85,402.00	-0.08%
111	\$1,025,360.00	\$1,027,032.50	\$1,672.50	\$1,029,901.55	0.28%
112	\$424,440.80	\$490,372.80	\$65,932.00	\$461,575.91	-5.87%
113	\$303,410.04	\$330,415.45	\$27,005.41	\$320,563.34	-2.98%
114	\$190,655.50	\$204,245.00	\$13,589.50	\$206,448.98	1.08%
115	\$2,448,609.20	\$2,397,807.06	(\$50,802.14)	\$2,442,376.93	1.86%
116	\$567,308.00	\$605,787.04	\$38,479.04	\$605,806.17	0.00%
117	\$410,226.00	\$448,402.00	\$38,176.00	\$431,310.44	-3.81%
118	\$1,159,483.00	\$1,073,466.10	(\$86,016.90)	\$1,073,149.63	-0.03%
119	\$492,605.00	\$485,207.00	(\$7,398.00)	\$473,628.15	-2.39%
120	\$1,333,009.73	\$1,463,736.92	\$130,727.19	\$1,463,736.92	0.00%
121	\$551,023.54	\$686,789.74	\$135,766.20	\$686,760.29	0.00%
122	\$107,838.20	\$141,424.37	\$33,586.17	\$138,300.11	-2.21%
123	\$166,981.40	\$168,490.50	\$1,509.10	\$168,248.76	-0.14%
124	\$882,274.50	\$719,882.40	(\$162,392.10)	\$714,130.08	-0.80%
125	\$0.00	\$379,880.51	\$379,880.51	\$363,253.63	-4.38%
126	\$891,363.00	\$821,583.63	(\$69,779.37)	\$842,972.72	2.60%
127	\$61,101.25	\$61,687.00	\$585.75	\$65,614.92	6.37%
128	\$34,452.25	\$38,815.10	\$4,362.85	\$38,764.44	-0.13%
129	\$46,790.00	\$48,514.35	\$1,724.35	\$48,295.82	-0.45%
130	\$52,615.20	\$49,653.20	(\$2,962.00)	\$46,310.39	-6.73%
131	\$203,280.00	\$195,650.00	(\$7,630.00)	\$192,396.55	-1.66%
132	\$430,776.40	\$442,922.85	\$12,146.45	\$421,176.19	-4.91%
133	\$419,305.00	\$409,725.06	(\$9,579.94)	\$402,853.89	-1.68%
134	\$424,784.07	\$435,327.70	\$10,543.63	\$428,013.98	-1.68%
135	\$876,080.80	\$827,312.95	(\$48,767.85)	\$923,174.50	11.59%
136	\$248,640.00	\$278,742.50	\$30,102.50	\$275,226.19	-1.26%
137	\$396,823.80	\$368,405.32	(\$28,418.48)	\$365,313.26	-0.84%
	7550,520.00	\$221,516.25	\$29,403.25	\$236,549.69	6.79%

a a	uration Contractor Number	er of Projects
93	158 S. G. & S. Construction, Inc.	2
94	194 The Cummins Construction Co., Inc.	35
95	60 J. & R. Sand Company, Inc.	3
96	45 Highway Contractors, Inc.	8
97	60 Highway Contractors, Inc.	. 8
98	130 Silver Star Truck Lines, Inc.	2
99	60 Edmond Paving & Const. Co.	3
100	94 Shears Construction Co.	19
101	60 AMIS/OTAC	4
102	38T & G Construction Co., Inc.	6
103	53T & G Construction Co., Inc.	6
104	188 Shears Construction Co.	19
105	266 Tri-State Asphalt, Inc.	3
106 107	266 Tri-State Asphalt, Inc.	3 7
107	179 Vinita Rock Company 59 Glover Construction Co., Inc.	30
109	93 Belico Materials, Inc.	16
110	75 Glover Construction Co., Inc.	30
111	375 Glover Construction Co., Inc.	30
112	62 The Cummins Construction Co., Inc.	35
113	100 Broce Const. Co., Inc.	18
114	134 The Cummins Construction Co., Inc.	35
115	428 J. & R. Sand Company, Inc.	3
116	90 Highway Contractors, Inc.	8
117	75 Broce Const. Co., Inc.	18
118	90 Comell Constr. Co., Inc.	8
119	90 Comell Constr. Co., Inc.	8
120	100 Comell Constr. Co., Inc.	8
121	363 M. L. Young Construction Corporation	1
122	99 Vantage Paving, Inc.	1
123	168 The Cummins Construction Co., Inc.	35
124	234 The Cummins Construction Co., Inc.	35
125	97T & G Construction Co., Inc.	6
126	170 Sewell Brothers, Inc.	1
127	30 The Cummins Construction Co., Inc.	35
128	45 Shawnee Asphalt Company	6
129	45 Shawnee Asphalt Company	6
130	30 The Cummins Construction Co., Inc.	35
131	96 The Cummins Construction Co., Inc.	35
132 133	56 Broce Const. Co., Inc.	18
134	176 Job Construction Co., Inc. 239 AMIS/OTAC	12
135	188 The Quapaw Company	4 10
136	42 The Quapaw Company	10
137	84 The Quapaw Company	10
138	30The Quapaw Company	10
	. Journa adaptive Company	

ID	Total Cost Growth Resident Engineer	Weather No of Bad Wea	ther Days
93	0.04b	Yes	61
94	-0.57 t	No	0
95	0ai	No	0
96	-0.01 ai	Yes	58
97		No.	0
98	AND DESCRIPTION OF THE PROPERTY OF THE PROPERT	No	0
99		Yes	34
100		· No	0
101	-0.05 t	No	0
102		No	0
103		No	0
104		Yes	61
105		No	0
106		No .	0
107	-0.28am	Yes	15
108	a. The state of th	No	0
109		No	0
110	AND THE PROPERTY OF THE PROPER	Yes	36
111	0.72c	Yes	79
112		No	0
113		No	0
114		No	0
115		Yes	120
116	PF Same count for the spin of the properties and the resident for the spin of the properties and the resident for the properties and the properties of the p	No .	0
117	and the same of the same species are the same should be same and the same same same same same same same sam	No	0
118		Yes	61
119	0.22 aq	Yes	61
120 121	AND REPORT OF THE PROPERTY OF	No	0
122	0 ag	No Yes	0
123	-0.02 ag -0.57 ag	No	34
123	COMPANIES AND ADDRESS OF THE PARTY OF THE PA	No	0
125		No	0
126	, 10 marin 1	Yes	96
127		No	90 0
128		No	0
129	Trial from the grant of the first Month of Companies and Spage are community for the trial that Wide Triangle Month Triangle Months on the paper and the first product of the community for the community of the community for the c	No	0
130		No	0
131	-0.57 d	No.	0
132		NO	0
133		: No	0
134	***************************************	Yes	61
135		Yes	38
136		No	
137		Yes	21
138		No	0
			<u> </u>

ID Bad we	ather Days Ratio Bidding Environme	ent Plans Review Time Unit System
93	0.38619	21 English
94	0.000021	21 English
95	0.00005	21 English
96	1.288920	21 English
97	0.000021	21 English
98	0.00009	21 English
99	0.566727	21 English
100	0.000011	21 English-Metric
101	0.000027	21 English
102	0.000012	21 English
103	0.0006	21 English
104	0.324520	21 English
105	0.000011	21 English-Metric
106	0.000011	21 English-Metric
107	0.083827	21 English
108	0.00002	21 English
109	0.00002	21 English
110	0.48003	21 English-Metric
	t a la grande constituti del maj paper a l'agra l'agra l'agra di distributa di agrada de la companya del la companya de la com	CONTROL OF PROPERTY OF THE ASSESSMENT OF THE LONG COLUMN TO THE WORLD CONTROL ASSESSMENT OF THE CONTROL OF THE
111	0.210727	21 English
112	0.000021	21 English
113	0.00002	21 English-Metric
114	0.000021	21 English
115	0.280421	21 English
116	0.000021	21 English
117	0.0000 21	21 English
118	0.677821	21 English
119	0.677821	21 English
120	0.00009	21 English
121	0.000020	21 English
122	0.343420	21 English
123	0.000021	21 English
124	0.000026	21 English-Metric
125	0.00006	21 English-Metric
126	0.564716	21 English-Metric
127	0.00002	21 English-Metric
128	0.000027	21 English
129	0.000027	21 English
130	0.000020	21 English
131	0.000026	21 English-Metric
132	0.000021	21 English
133	0.000026	21 English-Metric
134	0.25523	21 English
135	0.2021 16	21 English-Metric
136	0.000021	21 English
137	0.250011	21 English-Metric
138	0.000027	21 English

ID Out-of	-State Firms Wo	rk Order Date Tim	ing of Work Order Contract	ors History
93	Yes	4/13/95	49	Yes
94	No	8/7/95	46	Yes
95	Yes	3/15/95	48	Yes
96	Yes	4/19/95	27	Yes
97	No	7/18/95	26	Yes
98	No	6/15/95	112	No
99	No	5/26/95	36	Yes
100	No	8/22/96	28	Yes
101	No	5/23/95	33	No
102	No	7/14/95	50	Yes
103	No	10/3/95	40	Yes
104	. No	4/17/95	25	Yes
105	No	4/26/96	36	No
106	No	4/26/96	36	No
107	No	6/15/95		No
108	No	1/18/96	63	Yes
109	No	9/5/95	40	Yes
110	No	3/25/96	32	Yes
111	Yes	5/23/95	33	Yes
	No	8/7/95	DISTRICT OF STREET, ST	
112 113	No	7/11/96	46 49	Yes
114	No			Yes
	The state of the s	7/27/95	35	Yes
115	Yes	8/7/95	46	Yes
116	No	8/22/95	61	Yes
117	No	7/21/95	29	Yes
118	No .	7/27/95	35	Yes
119	No	7/27/95	35	Yes
120	No	3/20/95	25	Yes
121	No	6/20/95	89	No
122	No	5/26/95	64	No
123	No	8/2/95	41	Yes
124	Yes	7/23/96	33	Yes
125	No	3/4/96	39	Yes
126	No	5/24/96	29	Yes
127	No	7/8/96	46	Yes
128	No	6/20/95	61 .	Yes
129	No	6/20/95	61	Yes
130	No	6/15/95	84	Yes
131	No	7/23/96	33	Yes
132	No	8/2/95	41	Yes
133	No	7/25/96	35	No
134	No	12/1/95	36	No
135	No	5/22/96	27	Yes
136	No	8/4/95	43	Yes
137	No	5/2/96	42	Yes
138	No	5/26/95	36	Yes

ID Projec	cts with Overrun	Average No of Projects with O/R	Average Overrun
93	1	0.5000	5.1700
94	10	0.2857	2.8000
95	1	0.3333	1.8600
96	1	0.1250	0.0000
97	1	0.1250	0.0000
98	0	0.0000	0.0000
99	2	0.6667	2.3100
100	3	0.1579	7.2733
101	0	0.0000	0.0000
102	1	0.1667	12.1100
103	1	0.1667	12.1100
104	3	0.1579	7.2733
105	0	0.0000	0.0000
106	0	0.0000	0.0000
107	0	0.0000	0.0000
108	11	0.3667	14.2400
109	5	0.3125	9.2540
110	11	0.3667	14.2400
111	11	0.3667	14.2400
112	10	0.2857	2.8000
113	1	0.0556	1.9000
114	10	0.2857	2.8000
115	1	0.3333	1.8600
116	1	0.1250	0.0000
117	1	0.0556	1.9000
118	4	0.5000	7.1575
119	4	0.5000	7.1575
120	4	0.5000	7.1575
121	0	0.0000	0.0000
122	0	0.0000	0.0000
123	10	0.2857	2.8000
124	10	0.2857	2.8000
125	1.	0.1667	12.1100
126	1	1.0000	2.6000
127	10	0.2857	2.8000
128	1	0.1667	0.7100
129	1	0.1667	0.7100
130	10	0.2857	2.8000
131	10	0.2857	2.8000
132	1	0.0556	1.9000
133	0	0.0000	0.0000
134	0	0.0000	0.0000
135	3	0.3000	12.5000
136	3	0.3000	12.5000
137	3	0.3000	12.5000
138	3	0.3000	12.5000

ID A	verage Cost Growth Availability of La	bor
93	0.0200	5.5
94	-0.0163	4.8
95	0.0000	5.7
96	-0.0012	4.9
97	-0.0012	4.8
98	-0.0750	5.5
99	0.0167	4.6
100	-0.0111	3.8
101	-0.0171	4.6
102	-0.0333	4.9
	A CASE OF COLUMN STREET, A N. P. STREET, A STREET, AS A S	4.3
103	-0.0333	
104	-0.0111	4.9
105	-0.0333	4.1
106	-0.0333	4.1
107	-0.0400	4.6
108	0.0240	4.1
109	0.0206	4.6
110	0.0240	5
111	0.0240	4.6
112	-0.0163	4.8
113	-0.0194	4.2
114	-0.0163	4.8
115	0.0000	4.8
116	-0.0012	4.8
117	-0.0194	4.8
118	0.0275	4.8
119	0.0275	4.8
120	0.0275	5.5
121	0.000	4.9
122	-0.0200	4.9
123	-0.0163	4.8
124	-0.0163	4
125	-0.0333	5.1
126	0.0300	3.1
	-0.0163	
127	COLUMN TO THE PROPERTY OF THE	4.2
128	-0.0050	4.6
129	-0.0050	4.6
130	-0.0163	4.9
131	-0.0163	4
132	-0.0194	4.8
133	-0.0075	4
134	-0.0125	4.5
135	-0.0130	4
136	-0.0130	4.8
137	-0.0130	4.1
138	-0.0130	4.6

ID Project No	Location (County)	Project Type	Letting Date Number	of Bids
13960(297)	Payne	Overlay	3/23/95	1
140 59(183)	Pawnee	Resurfacing	3/21/96	3
141 58(283)	Ottawa	Resurfacing	4/24/97	2
142 58(279)	Ottawa	Overlay	3/23/95	2
143 58(278)	Ottawa	Resurfacing	3/23/95	2
144 76D(110)	Woods	Surfacing	7/27/95	6
145 75(198)	Washita	Resurfacing	7/25/96	4
14674(167)	Washington	Resurfacing	3/21/96	2
14773(370)	Wagoner	Resurfacing	8/24/95	3
14873(358)	wagoner	Overlay	2/23/95	6
14972(566)	Tulsa	Resurfacing	5/25/95	4
15072E(503)	Tulsa	Surfacing	4/20/95	3
15171(153)	Tillman	Overlay	2/23/95	
15270(210)	Texas	Resurfacing	6/22/95	2
15370(207)	Texas	Resurfacing	5/25/95	2
15469(269)	Stephens	Resurfacing	8/24/95	4
15569(267)	Stephens	Resurfacing	4/20/95	
15669(217)	Stephens	Overlay	3/23/95	2
15768(294)	Sequoyah	Resurfacing	9/25/97	2
15868(275)	Sequoyah	Resurfacing	5/25/95	5
15968(272)	Sequoyah	Resurfacing	3/23/95	4
16068(227)	Sequoyah	Resurfacing	11/16/95	4
161 177C(003)	Woodward	Resurfacing	4/24/97	
162 177A(001)	Woodward	Resurfacing	6/20/96	2
163 176C(008)	Woods	Resurfacing	5/22/97	
164 176C(004)	Woods	Resurfacing	9/25/97	3
165 176D(003)	Woods	Resurfacing	7/24/97	
166 176C(001)	Woods	Resurfacing	4/24/97	
167 175D(002)	Washita	Resurfacing	7/25/96	
168 174N(001)	Washington	Resurfacing	2/20/97	
169 173N(012)	Wagoner	Surfacing	8/22/96	
170 173A(004)	Wagoner	Resurfacing	6/20/96	5
171 172N(022)	Tulsa	Resurfacing	7/24/97	
172 172N(007)	Tulsa	Resurfacing	7/25/96	2
173 171D(010)	Tillman	Resurfacing	2/20/97	4
174 171D(006)	Tillman	Resurfacing	7/25/96	3
175 171C(003)	Tillman	Resurfacing	6/20/96	
176 170C(008)	Texas	Resurfacing	10/23/97	2
177 170C(001)	Texas	Resurfacing	6/20/96	
178 168A(018)	Sequoyah	Resurfacing	7/24/97	
179 168C(4,12)	Sequoyah	Resurfacing	7/24/97	3
180 167C(0020	Seminole	Resurfacing	3/27/97	
181 166C(008)	Rogers	Resurfacing	6/26/97	
182 166C(003)	Rogers	Resurfacing	6/20/96	
183 163C(006)	Pottawatomie	Resurfacing	3/27/97	3 3
		CARROLL CHEST CHEST		

ID	Lowest Bid	2nd Lowest Bid	Highest Bid	MLOT	Bid Range
139	\$153,340.00	\$153,340.00	\$153,340.00	\$0.00	\$0.00
140	\$269,925.00	\$293,784.00	\$317,322.00	\$23,859.00	\$47,397.00
141	\$349,914.80	\$397,790.95	\$397,790.95	\$47,876.15	\$47,876.15
142	\$401,876.80	\$469,882.50	\$469,882.50	\$68,005.70	\$68,005.70
143	\$196,261.00	\$234,710.50	\$234,710.50	\$38,449.50	\$38,449.50
144	\$332,323.00	\$348,851.00	\$397,742.65	\$16,528.00	\$65,419.65
145					
	\$500,682.25	\$552,466.50 \$245,038,00	\$564,773.75	\$51,784.25	\$64,091.50
146	\$217,660.00	\$245,038.90	\$245,038.90	\$27,378.90	\$27,378.90
147	\$315,197.00	\$355,418.00	\$439,029.50	\$40,221.00	\$123,832.50
148	\$220,814.00	\$237,107.50	\$279,765.50	\$16,293.50	\$58,951.50
149	\$1,030,439.70	\$1,079,614.50	\$1,486,939.50	\$49,174.80	\$456,499.80
150	\$565,601.36	\$609,807.80	\$814,227.26	\$44,206.44	\$248,625.90
151	\$252,324.00	\$293,510.52	\$297,466.72	\$41,186.52	\$45,142.72
152	\$937,448.50	\$963,597.30	\$963,597.30	\$26,148.80	\$26,148.80
153	\$596,116.40	\$628,478.02	\$628,478.02	\$32,361.62	\$32,361.62
154	\$482,200.00	\$511,407.00	\$643,285.00	\$29,207.00	\$161,085.00
155	\$217,969.70	\$371,990.50	\$371,990.50	\$154,020.80	\$154,020.80
156	\$393,896.92	\$397,030.65	\$509,785.68	\$3,133.73	\$115,888.76
157	\$39,683.58	\$55,800.50	\$55,800.50	\$16,116.92	\$16,116.92
158	\$84,762.32	\$88,304.85	\$109,739.00	\$3,542.53	\$24,976.68
159	\$76,788.16	\$82,332.00	\$94,587.68	\$5,543.84	\$17,799.52
160	\$134,946.80	\$136,799.06	\$151,792.93	\$1,852.26	\$16,846.13
161	\$392,365.40	\$406,706.88	\$406,706.88	\$14,341.48	\$14,341.48
162	\$599,976.91	\$619,704.33	\$619,704.33	\$19,727.42	\$19,727.42
163	\$558,509.80	\$595,556.00	\$645,287.50	\$37,046.20	\$86,777.70
164	\$179,871.85	\$187,159.05	\$187,159.05	\$7,287.20	\$7,287.20
165	\$152,840.50	\$152,840.50	\$152,840.50	\$0.00	\$0.00
166	\$60,843.03	\$60,843.03	\$60,843.03	\$0.00	\$0.00
167	\$66,045.00	\$84,150.00	\$88,995.00	\$18,105.00	\$22,950.00
168	\$352,866.87	\$452,368.23	\$452,368.23	\$99,501.36	\$99,501.36
169	\$307,383.75	\$325,144.00	\$447,702.80	\$17,760.25	\$140,319.05
170	\$560,836.00	\$563,200.00	\$678,127.70	\$2,364.00	\$117,291.70
171	\$2,132,314.53	\$2,526,163.27	\$2,526,163.27	\$393,848.74	\$393,848.74
172	\$135,310.00	\$136,414.00	\$136,414.00	\$1,104.00	\$1,104.00
173	\$198,224.70	\$203,292.00	\$242,734.50	\$5,067.30	\$44,509.80
174	\$53,077.90	\$64,715.50	\$65,181.75	\$11,637.60	\$12,103.85
175	\$391,063.33	\$431,065.08	\$501,772.44	\$40,001.75	\$110,709.11
176	\$536,307.80	\$614,613.50	\$614,613.50	\$78,305.70	\$78,305.70
	\$538,649.00				
177		\$538,649.00	\$538,649.00	\$0.00	\$0.00
178	\$208,650.00	\$223,672.50	\$257,360.00	\$15,022.50	\$48,710.00
179	\$293,000.00	\$323,059.12	\$366,047.20	\$30,059.12	\$73,047.20
180	\$781,886.46	\$821,927.64	\$967,355.68	\$40,041.18	\$185,469.22
181	\$490,537.20	\$609,849.83	\$725,647.10	\$119,312.63	\$235,109.90
182	\$599,439.40	\$633,939.30	\$664,980.20	\$34,499.90	\$65,540.80
183	\$539,600.84	\$563,915.61	\$667,828.00	\$24,314.77	\$128,227.16
184	\$490,967.20	\$517,468.30	\$528,836.47	\$26,501.10	\$37,869.27

ID	Engr's Estimate	Contract Amount	Contract Difference	Actual Cost	Cost Growth
139	\$132,680.00	\$153,340.00	\$20,660.00	\$107,736.69	-29.74%
140	\$260,875.00	\$269,925.00	\$9,050.00	\$283,713.42	5.11%
141	\$358,900.00	\$349,914.80	(\$8,985.20)	\$346,213.20	-1.06%
142	\$401,418.50	\$401,876.80	\$458.30	\$393,766.35	-2.02%
143	\$186,900.00	\$196,261.00	\$9,361.00	\$192,903.40	-1.71%
144	\$334,451.00	\$332,323.00	(\$2,128.00)	\$323,147.42	-2.76%
145	\$608,810.00	\$500,682.25	(\$108,127.75)	\$497,549.15	-0.63%
146	\$191,220.00	\$217,660.00	\$26,440.00	\$219,255.32	0.73%
147	\$0.00	\$315,197.00	\$315,197.00	\$310,997.70	-1.33%
148	\$268,045.00	\$220,814.00	(\$47,231.00)	\$208,452.95	-5.60%
149	\$1,209,980.00	\$1,030,439.70	(\$179,540.30)	\$1,025,925.85	-0.44%
150	\$735,329.90	\$565,601.36	(\$169,728.54)	\$576,817.62	1.98%
151	\$229,225.00	\$252,324.00	\$23,099.00	\$252,323.83	0.00%
152		\$937,448.50	\$56,169.50	- The state of the	-0.05%
	\$881,279.00			\$936,985.27 \$588 302 63	
153	\$691,129.20	\$596,116.40	(\$95,012.80)	\$588,392.63 \$479.745.53	-1.30%
154	\$0.00	\$482,200.00	\$482,200.00	\$478,745.53	-0.72%
155	\$163,753.00	\$217,969.70	\$54,216.70	\$210,355.15	-3.49%
156	\$378,032.40	\$393,896.92	\$15,864.52	\$390,703.49	-0.81%
157	\$36,023.00	\$39,683.58	\$3,660.58	\$39,589.13	-0.24%
158	\$90,509.00	\$84,762.32	(\$5,746.68)	\$83,037.49	-2.03%
159	\$82,884.00	\$76,788.16	(\$6,095.84)	\$74,556.21	-2.91%
160	\$154,527.00	\$134,946.80	(\$19,580.20)	\$133,881.22	-0.79%
161	\$385,695.60	\$392,365.40	\$6,669.80	\$392,285.11	-0.02%
162	\$591,171.00	\$599,976.91	\$8,805.91	\$599,833.34	-0.02%
163	\$460,308.00	\$558,509.80	\$98,201.80	\$557,475.47	-0.19%
164	\$139,990.95	\$179,871.85	\$39,880.90	\$177,603.05	-1.26%
165	\$172,550.00	\$152,840.50	(\$19,709.50)	\$140,371.41	-8.16%
166	\$35,425.25	\$60,843.03	\$25,417.78	\$55,526.92	-8.74%
167	\$94,987.50	\$66,045.00	(\$28,942.50)	\$65,729.53	-0.48%
168	\$389,988.78	\$352,866.87	(\$37,121.91)	\$346,942.53	-1.68%
169	\$266,536.00	\$307,383.75	\$40,847.75	\$302,254.03	-1.67%
170	\$627,200.00	\$560,836.00	(\$66,364.00)	\$536,155.50	-4.40%
171	\$1,949,791.96	\$2,132,314.53	\$182,522.57	\$1,876,259.78	-12.01%
172	\$182,075.00	\$135,310.00	(\$46,765.00)	\$134,056.90	-0.93%
173	\$223,530.00	\$198,224.70	(\$25,305.30)	\$184,954.05	-6.69%
174	\$74,600.00	\$53,077.90	(\$21,522.10)	\$53,077.90	0.00%
175	\$343,052.94	\$391,063.33	\$48,010.39	\$379,915.67	-2.85%
176	\$573,905.00	\$536,307.80	(\$37,597.20)	\$536,300.37	0.00%
177	\$494,039.00	\$538,649.00	\$44,610.00	\$538,040.53	-0.11%
178	\$194,600.00	\$208,650.00	\$14,050.00	\$206,179.95	-1.18%
179	\$288,218.28	\$293,000.00	\$4,781.72	\$289,198.98	-1.30%
180	\$755,200.00	\$781,886.46	\$26,686.46	\$772,251.91	-1.23%
181	\$524,898.40	\$490,537.20	(\$34,361.20)	\$493,823.90	
					0.67%
182	\$667,050.00	\$599,439.40 \$530,600.84	(\$67,610.60)	\$603,156.05	0.62%
183	\$498,304.00	\$539,600.84	\$41,296.84	\$528,092.59	-2.13%
184	\$664,886.25	\$490,967.20	(\$173,919.05)	\$477,245.04	-2.79%

ID D	ration Contractor Numbe	r of Projects
139	72 The Quapaw Company	10
140	159 The Cummins Construction Co., Inc.	35
141	77 Tri-State Asphalt, Inc.	3
142	202 Vinita Rock Company	7
143	39 Vinita Rock Company	7
144	191 Romine Construction Co.	1
145	23 Shears Construction Co.	19
146	87 Bellco Materials, Inc.	16
147	68S. G. & S. Construction, Inc.	2
148	53 Vinita Rock Company	7
149	107 APAC-Oklahoma, Inc.	7
150	403 Becco Contractors, Inc.	1
151	158 J. H. Shears' Sons, Inc.	1
152	150 Highway Contractors, Inc.	8
153	60 J. & R. Sand Company, Inc.	3
154	199 Broce Const. Co., Inc.	18
155	115 Shears Construction Co.	19
156	117 Interstate Contracting Corp.	2
157	30 Job Construction Co., Inc.	12
158	347 Job Construction Co., Inc.	12
159	74 Job Construction Co., Inc.	12
160	206 Glover Construction Co., Inc.	30
161	114 Broce Const. Co., Inc.	18
162	102 Broce Const. Co., Inc.	18
163	80 Broce Const. Co., Inc.	18
164	47 The Cummins Construction Co., Inc.	35
165	30 Broce Const. Co., Inc.	18
166	30 OBC, Inc.	1
167	30 Circle S Paving Co., Inc.	4
168	139 Bellco Materials, Inc.	16
169	127 Empire Construction & Materials, Inc.	6
170	195 Empire Construction & Materials, Inc.	6
171	101 Empire Construction & Materials, Inc.	6
172	431 APAC-Oklahoma, Inc.	7
173	77T & G Construction Co., Inc.	6
174	72 Shears Construction Co.	19
175	98 T & G Construction Co., Inc.	6
176	108 Highway Contractors, Inc.	8
177	82 Highway Contractors, Inc.	8
178	206Tiger Ind. Transp. Sys., Inc.	4
179	68 Forsgren, Inc.	1
180	180 Shears Construction Co.	19
181	44 Bellco Materials, Inc.	16
182	112 Bellco Materials, Inc.	16
183	90 The Cummins Construction Co., Inc.	35
184	90 Northern Improvement Company	3

ID Tota	Cost Growth Resident En	gineer   Weather   No of Bad \	<b>Neather Days</b>
139	-0.13z	No	. 0
140	-0.57 ae	Yes	37
141	-0.1 am	No	0
142	-0.28 am	Yes	48
143	-0.28 am	Yes	43
144	-0.03 r	No	O
145	-0.21 aq	No	. 0
146	0.33 am	Yes	51
147	0.04 b	No	0
148	-0.28b	No	0
149	-0.31 ae	No	O
150	0.02ae	No	o
151	. Om	Yes	43
152	-0.01 ai	No	0
153	0ai	No	0
154	-0.35w	No	0
155	-0.21 w	No	O
156	0.03w	Yes	61
157	-0.09ak	No	0
158	-0.09 c	Yes	34
159	-0.09 c	No	0
160	0.72c	Yes	36
161	-0.35h	No	0
162	-0.35 j	No	0
163	-0.35h	No	0
164	-0.57 h	Yes	61
165	-0.35h	Yes	
166	-0.09 h	No	52
167	-0.05 aq	No	0
168	0.33 ae	Yes	
169	-0.21 aj	No	36
170	-0.21b		0
		No	
171 172	-0.21 o -0.31 o	No Vos	0
		Yes	61
173	-0.2 m	Yes	30
174	-0.21 m	No	0
175	-0.2 m	No	0
176	-0.01 ai	Yes	29
177	-0.01 ai	No.	0
178	-0.05 ak	Yes	4
179	-0.01ak	No.	0
180	-0.21x	Yes	56
181	0.33 am	No	0
182	0.33 am	No.	0
183	-0.57 x	No	0
184	-0.05 ap	No	0

ID Bad we	ather Days Ratio Bidding Env	ironment Plans Review Time   Unit System
139	0.000020	21 English
140	0.2327 11	21 English-Metric
141 .	0.000011	21 English-Metric
142	0.237620	21 English
143	1.1026.20	21 English
144	0.00004	21 English
145	0.000011	21 English-Metric
146	0.5862 11	21 English-Metric
147	0.00006	21 English
148	0.00009	21 English
149	0.000012	21 English
150	0.000027	21 English
151	0.27229	21 English
152	0.000021	21 English
153	0.000012	21 English
154	0.00006	21 English
155	0.000027	21 English
156	0.521420	21 English
157	0.00002	21 English-Metric
158	0.0980 12	21 English
159	0.000020	21 English
160	0.17482	21 English
161	0.000011	21 English-Metric
162	0.000026	21 English-Metric
163	0.0006	21 English-Metric
164	1.29792	21 English-Metric
165	1.73337	21 English-Metric
166	0.000011	21 English-Metric
167	0.0000 11	21 English-Metric
168	0.259011	21 English-Metric
169	0.0004	21 English-Metric
170	0.000026	21 English-Metric
171	0.00007	21 English-Metric
172	0.141511	21 English-Metric
173	0.389611	21 English-Metric
174	0.000011	21 English-Metric
175	0.000026	21 English-Metric
176	0.26852	21 English-Metric
177	0.000026	21 English-Metric
178	0.01947	21 English-Metric
179	0.00007	21 English-Metric
180	0.31119	21 English-Metric
181	0.0009	21 English-Metric
182	0.000026	21 English-Metric
183	0.00009	21 English-Metric
184	0.000026	21 English-Metric

ID Out-of-S	State Firms Wor	k Order Date Timin	g of Work Order Contract	ors History
139	No	6/15/95	84	Yes
140	No	4/23/96	33	Yes
141	No	6/5/97	42	No
142	No	5/4/95	42	No
143	No	5/9/95	47	No
144	No	9/5/95	40	No
145	Yes	9/9/96	46	Yes
146	No	4/22/96	32	Yes
147	No	9/27/95	34	Yes
148	Yes	6/15/95	112	No
149	Yes	6/30/95	36	Yes
150	No	8/23/95	125	Yes
151	No	3/27/95	32	No
152	No	8/8/95	47	Yes
153	Yes	7/19/95	55	Yes
154	No	10/3/95	40	Yes
155	. No	5/24/95	34	Yes
156	No	4/28/95	36	Yes
157	No	10/23/97	28	No
158	Yes	6/27/95	33	No
159	Yes	6/15/95	84	No
160	Yes	1/12/96	57	Yes
161	No	5/21/97	27	Yes
162	No	7/11/96	21	Yes
163	No	6/20/97	29	Yes
164	No	11/6/97	42	Yes
165	No	8/28/97	35	Yes
166	No	6/5/97	42	
167	No	8/30/96	36	No
168	No	3/13/97	21	Yes
	without the control of the control o	and the second s	age consistency and the first P. France and the Windows Samuel and the Windows State of the Consistency of the	Yes
169	Yes	9/27/96	36	No
170	Yes	7/31/96	41	No
171	No	8/22/97	29	No
172	No	8/22/96	28	Yes
173	No	3/27/97	35	Yes
174	No	8/28/96	34	Yes
175	Yes	7/26/96	36	Yes
176	No	12/3/97	41	Yes
177	No	7/19/96	29	Yes
178	Yes	8/26/97	33.	No
179	Yes	8/20/97	27	No
180	No	4/22/97	26	Yes
181	No	7/17/97	21	Yes
182	No	7/26/96	36	Yes
183	No	5/6/97	40	Yes
184	Yes	8/6/96	47	No.

ID Project:	s with Overrun Average No	of Projects with O/R Avera	ge Overrun
139	3	0.3000	12.5000
140	. 10	0.2857	2.8000
141	· · · 0	0.0000	0.0000
142	0	0.0000	0.0000
143	0	0.000	0.0000
144	. 0	0.0000	0.0000
145	3	0.1579	7.2733
146	5	0.3125	9.2540
147	1	0.5000	5.1700
148	0	0.0000	0.0000
149	1	0.1429	1.2200
150	1	1.0000	1.9800
151	. 0	0.0000	0.0000
152	1	0.1250	0.0000
153		0.3333	1.8600
154	1	0.0556	1.9000
155	3	0.0556	7.2733
156	1	0.5000	4.1100
157	e de long authorité départe des maniers des maniers de la company de la	0.0000	0.0000
158	0	0.0000	0.0000
159	0	0.0000	
160	garaga ang ang ang ang ang ang ang ang ang		0.0000
A MANAGEMENT AND A STREET AND A	· 11	0.3667	14.2400
161		0.0556	1.9000
162	<u> </u>	0.0556	1.9000
163	1	0.0556	1.9000
164	10	0.2857	2.8000
165	1	0.0556	1.9000
166	O CONTRACTOR CONTRACTO	0.0000	0.0000
167	<u> </u>	0.2500	0.0200
168	5	0.3125	9.2540
169	0	0.0000	0.0000
170		0.0000	0.0000
171		0.0000	0.0000
172	<u> </u>	0.1429	1.2200
173	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	0.1667	12.1100
174	3	0.1579	7.2733
175	<u> </u>	0.1667	12.1100
176	1	0.1250	0.0000
177	1	0.1250	0.0000
178	0	0.0000	0.0000
179	0	0.0000	0.0000
180	3	0.1579	7.2733
181	5	0.3125	9.2540
182	5	0.3125	9.2540
183	10	0.2857	2.8000
184	0	0.0000	0.0000

ID Avera	ge Cost Growth Availabil	ity of Labor
139	-0.0130	4.9
140	-0.0163	4.1
141	-0.0333	3.8
142	-0.0400	4.9
143	-0.0400	4.9
144	-0.0300	4.6
145	-0.0111	4.6
146	0.0206	4.1
147	0.0200	4.3
148	-0.0400	5.5
149	-0.0443	4.9
150	0.0200	4.6
151	0.0000	<del></del> .5 5.5
152	-0.0012	4.8
153	0.0000	4.0 4.9
154	-0.0194	4.3
155	-0.0194 -0.0111	4.6
156	0.0150	4.9
157	-0.0075	4.9 4.1
158	an an and de la company of the surface and the surface of the surf	4.1 4.9
159	-0.0075 0.0075	
\$	-0.0075	4.9
160	0.0240	4.1
161	-0.0194	3.8
162	-0.0194	4
163	-0.0194	4.2
164	-0.0163	4.1
165	-0.0194	4
166	-0.0900	3.8
167	-0.0125	3.8
168	0.0206	4.4
169	-0.0350	3.6
170	-0.0350	4
171	-0.0350	4
172	-0.0443	3.8
173	-0.0333	4.4
174	-0.0111	3.8
175	-0.0333	4
176	-0.0012	4.1
177	-0.0012	4
178	-0.0125	4
179	-0.0100	4
180	-0.0111	4
181	0.0206	4.2
182	0.0206	4
183	-0.0163	4.2 4 4 4
184	-0.0167	. 4

ID Project No	Location (Cou	nty) Project Type	Letting Date Num	ber of Bids
185 161N(28)	Pittsburg	Resurfacing	11/20/97	3
186 160B(12)	Payne	Resurfacing	7/24/97	1
187 160C(008)	Payne	Resurfacing	3/27/97	2
188 160D(005)	Payne	Resurfacing	4/24/97	1
189 159C(004)	Pawnee	Resurfacing	2/20/97	4
190 158B(004)	Ottawa	Resurfacing	6/26/97	2
191 158C(002)	Ottawa	Resurfacing	7/25/96	3
192 158B(001)	Ottawa	Resurfacing	6/20/96	2
193 157N(007)	Osage	Resurfacing	6/26/97	1
194 157C(006)	Osage	Resurfacing	4/24/97	4
195 157B(003)	Osage	Resurfacing	7/25/96	5
196 156N(017)	Okmulgee	Resurfacing	4/23/98	0
197 156N(3)	Okmulgee	Resurfacing	6/20/96	3
198 155N(026)	Oklahoma	Resurfacing	7/24/97	2
199 154C(001)	Okfuskee	Resurfacing	6/20/96	3
200 152C(008)	Noble	Resurfacing	5/22/97	0
201 152B(007)	Noble	Resurfacing	5/22/97	0
202 151B(46)	Muskogee	THE RESIDENCE PROPERTY AND ADDRESS OF THE PARTY OF THE PA	6/25/98	
	THE RESERVE AND ADDRESS OF THE PARTY OF THE	Resurfacing		3
203 151B(035)	Muskogee	Surfacing	10/23/97	4
204 151D(18)	Muskogee	Resurfacing	1/22/98	0
205 151N(012)	Muskogee	Resurfacing	6/20/96	2
206 150D(002)	Murray	Resurfacing	1/23/97	4
207 149N(004)	Mayes	Resurfacing	2/20/97	5
208 149B(002)	Mayes	Resurfacing	6/20/96	4
209 148D(006)	Marshall	Resurfacing	1/23/97	3
210 148D(005)	Marshall	Resurfacing	1/23/97	4
211 147N(002)	Major	Resurfacing	5/22/97	1
212 146C(006)	Mcintosh	Resurfacing	6/26/97	3
213146C(005)	Mcintosh	Resurfacing	8/22/96	3
214 146N(004)	Mcintosh	Resurfacing	6/20/96	2
215 145A(26)	McCurtain	Resurfacing	5/21/98	3 2
216 145N(018)	McCurtain	Resurfacing	2/19/98	
217 145N(003)	McCurtain	Resurfacing	11/21/96	2
218 144C(13)	McClain	Resurfacing	3/26/98	4
219144D(012)	McClain	Resurfacing	7/24/97	4
220 144C(7)	McClain	Resurfacing	6/20/96	6
221 142C(004)	Logan	Resurfacing	3/27/97	3 0
222 136B(007)	Kay	Resurfacing	5/22/97	
223 136D(005)	Kay	Surfacing	8/22/96	2
224 135C(06)	Johnson	Resurfacing	6/26/97	2 3 5
225 135B(001)	Johnson	Resurfacing	6/20/96	5
226 133N(004)	Jackson	Resurfacing	6/20/96	4
227 132D(002)	Hughes	Surfacing	8/22/96	
228 131B(12)	Haskell	Resurfacing	8/21/97	3
229 130B(003)	Harper	Resurfacing	7/25/96	1
230 128B(10)	Greer	Resurfacing	6/26/97	7

ID	Lowest Bid	2nd Lowest Bid	Highest Bid	MLOT	Bid Range
185	\$635,442.50	\$667,428.20	\$695,847.00	\$31,985.70	\$60,404.50
186	\$1,228,850.00	\$1,228,850.00	\$1,228,850.00	\$0.00	\$0.00
187	\$429,080.00	\$435,830.00	\$435,830.00	\$6,750.00	\$6,750.00
188		\$272,665.00	\$272,665.00	\$0.00	\$0.00
189		\$538,273.90	\$620,669.09	\$26,919.85	\$109,315.04
190		\$139,337.60	\$139,337.60	\$21,499.90	\$21,499.90
191	\$377,052.00	\$429,855.75	\$455,592.54	\$52,803.75	\$78,540.54
192		\$633,450.50	\$633,450.50	\$126,239.25	\$126,239.25
193		\$758,695.00	\$758,695.00	\$0.00	\$0.00
194		\$735,873.75	\$829,531.25	\$138,689.25	\$232,346.75
195		\$498,750.75	\$617,624.20	\$23,882.50	\$142,755.95
196		\$0.00	\$0.00	\$0.00	\$0.00
197				\$84,822.05	\$211,318.10
		\$992,989.45	\$1,119,485.50		
198		\$150,855.00	\$150,855.00 \$201,577.50	\$23,320.00	\$23,320.00
199		\$284,923.10	\$291,577.50	\$14,711.60	\$21,366.00
200		\$0.00	\$0.00	\$0.00	\$0.00
201	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
202		\$513,500.00	\$528,635.00	\$28,600.00	\$43,735.00
203		\$248,272.10	\$290,573.00	\$18,358.80	\$60,659.70
204		\$0.00	\$0.00	\$0.00	\$0.00
205		\$388,370.00	\$388,370.00	\$37,940.00	\$37,940.00
206	\$272,585.76	\$317,047.50	\$393,192.96	\$44,461.74	\$120,607.20
207	\$333,110.51	\$355,576.97	\$387,147.74	\$22,466.46	\$54,037.23
208	\$134,364.00	\$135,488.00	\$182,210.00	\$1,124.00	\$47,846.00
209	\$41,249.40	\$47,575.30	\$49,684.56	\$6,325.90	\$8,435.16
210	\$159,788.56	\$195,328.30	\$255,053.40	\$35,539.74	\$95,264.84
211	\$212,021.05	\$212,021.05	\$212,021.05	\$0.00	\$0.00
212	\$161,755.00	\$191,900.00	\$223,715.00	\$30,145.00	\$61,960.00
213	\$116,289.00	\$129,720.00	\$136,901.50	\$13,431.00	\$20,612.50
214	\$124,350.00	\$155,150.00	\$155,150.00	\$30,800.00	\$30,800.00
215	\$509,683.50	\$544,200.80	\$613,580.00	\$34,517.30	\$103,896.50
216	\$297,762.56	\$318,606.80	\$318,606.80	\$20,844.24	\$20,844.24
217	\$319,543.84	\$368,587.85	\$368,587.85	\$49,044.01	\$49,044.01
218	\$559,525.00	\$581,704.63	\$838,422.76	\$22,179.63	\$278,897.76
219	\$203,302.46	\$227,010.99	\$248,279.90	\$23,708.53	\$44,977.44
220	\$722,514.07	\$787,558.17	\$909,557.76	\$65,044.10	\$187,043.69
221	\$295,500.00	\$339,970.00	\$363,700.00	\$44,470.00	\$68,200.00
222		\$0.00	\$0.00	\$0.00	\$0.00
223	**	\$59,750.00	\$59,750.00	\$15,473.00	\$15,473.00
224		\$625,119.00	\$680,092.65	\$64,296.00	\$119,269.65
225	****	\$305,787.99	\$351,414.11	\$28,706.15	\$74,332.27
226	e el coma sensioni de la large de coma de la large de	\$392,462.33	\$438,378.62	\$1,939.43	\$47,855.72
227		\$49,887.00	\$62,480.30	\$3,532.60	\$16,125.90
228	The second secon	\$506,642.50	\$516,100.00	\$9,987.50	\$19,445.00
229		\$90,765.40	\$90,765.40	\$0.00	\$0.00
230	THE RESIDENCE OF THE PERSON NAMED IN COLUMN 1991	\$759,617.00	\$948,660.00	\$92,441.80	\$281,484.80
200	φοσι, 175.20	Ψ1 J3,011.00	ψοτο,000.00	ψ <del>3</del> 2, <del>11</del> 1.00	Ψ201,404.00

ID	Engrs Estimate	Contract Amount Co	ntract Difference	Actual Cost	Cost Growth
185	\$637,502.00	\$635,442.50	(\$2,059.50)	\$620,027.26	-2.43%
186	\$1,102,390.00	\$1,228,850.00	\$126,460.00	\$1,188,599.06	-3.28%
187	\$358,780.00	\$429,080.00	\$70,300.00	\$434,312.48	1.22%
188	\$304,640.00	\$272,665.00	(\$31,975.00)	\$324,826.27	19.13%
189	\$533,649.68	\$511,354.05	(\$22,295.63)	\$495,504.34	-3.10%
190	\$127,072.60	\$117,837.70	(\$9,234.90)	\$117,463.81	-0.32%
191	\$496,503.00	\$377,052.00	(\$119,451.00)	\$370,597.90	-1.71%
192	\$563,000.00	\$507,211.25	(\$55,788.75)	\$502,569.88	-0.92%
193	\$749,260.00	\$758,695.00	\$9,435.00	\$747,270.30	-1.51%
194	\$631,073.50	\$597,184.50	(\$33,889.00)	\$587,865.73	-1.56%
195	\$560,450.00	\$474,868.25	(\$85,581.75)	\$472,515.31	-0.50%
196	\$0.00	\$178,764.00	\$178,764.00	\$159,390.78	-10.84%
197	\$1,187,710.00	\$908,167.40	(\$279,542.60)	\$893,511.94	-1.61%
198	\$117,869.00	\$127,535.00	\$9,666.00	\$108,331.82	-15.06%
199	\$250,656.50	\$270,211.50	\$19,555.00	\$279,651.07	3.49%
200	\$0.00	\$514,894.60	\$514,894.60	\$572,746.83	11.24%
201				\$709,629.83	33.01%
	\$0.00	\$533,536.00 \$484.000.00	\$533,536.00 \$31,125.00		
202 203	\$453,775.00 \$268,825.50	\$484,900.00 \$220.013.30		\$419,002.66	-13.59%
		\$229,913.30	(\$38,912.20)	\$244,742.30	6.45%
204	\$0.00	\$25,449.85	\$25,449.85	\$24,969.03	-1.89%
205	\$401,400.00	\$350,430.00	(\$50,970.00)	\$232,787.91	-33.57%
206	\$292,017.30	\$272,585.76	(\$19,431.54)	\$242,614.63	-11.00%
207	\$381,265.52	\$333,110.51	(\$48,155.01)	\$332,496.82	-0.18%
208	\$148,895.00	\$134,364.00	(\$14,531.00)	\$126,130.49	-6.13%
209	\$42,166.40	\$41,249.40	(\$917.00)	\$40,888.18	-0.88%
210	\$189,972.25	\$159,788.56	(\$30,183.69)	\$158,404.88	-0.87%
211	\$191,493.68	\$212,021.05	\$20,527.37	\$227,369.47	7.24%
212	\$176,700.00	\$161,755.00	(\$14,945.00)	\$161,664.74	-0.06%
213	\$116,068.00	\$116,289.00	\$221.00	\$115,296.57	-0.85%
214	\$139,000.00	\$124,350.00	(\$14,650.00)	\$236,888.85	90.50%
215	\$503,236.80	\$509,683.50	\$6,446.70	\$502,570.06	-1.40%
216	\$264,234.00	\$297,962.56	\$33,728.56	\$296,656.13	-0.44%
217	\$302,835.98	\$319,543.84	\$16,707.86	\$321,577.11	0.64%
218	\$507,693.25	\$559,525.00	\$51,831.75	\$554,427.60	-0.91%
219	\$205,800.58	\$203,302.46	(\$2,498.12)	\$198,316.75	-2.45%
220	\$830,922.10	\$722,514.07	(\$108,408.03)	\$717,420.35	-0.70%
221	\$245,200.00	\$295,500.00	\$50,300.00	\$293,683.60	-0.61%
222	\$0.00	\$945,665.00	\$945,665.00	\$928,844.88	-1.78%
223	\$49,525.00	\$44,277.00	(\$5,248.00)	\$41,919.00	-5.33%
224	\$533,314.00	\$560,823.00	\$27,509.00	\$567,179.65	1.13%
225	\$364,951.35	\$277,081.84	(\$87,869.51)	\$273,562.49	-1.27%
226	\$413,069.00	\$390,522.90	(\$22,546.10)	\$383,981.90	-1.67%
227	\$49,127.75	\$46,354.40	(\$2,773.35)	\$48,274.74	4.14%
228	\$475,200.00	\$496,655.00	\$21,455.00	\$483,172.28	-2.71%
229	\$84,628.00	\$90,765.40	\$6,137.40	\$106,179.60	16.98%
230	\$834,416.00	\$667,175.20	(\$167,240.80)	\$723,763.27	8.48%

ID D	uration Contractor Numbe	r of Projects
185	60 The Cummins Construction Co., Inc.	35
186	323 The Quapaw Company	10
187	38 APAC-Oklahoma, Inc.	7
188	47 The Quapaw Company	10
189	151 Belico Materials, Inc.	16
190	58 Vinita Rock Company	7
191	48 Masters-Jackson Paving Co.	2
192	338 Vinita Rock Company	7
193	64 Bellco Materials, Inc.	16
194	133 Bellco Materials, Inc.	16
195	68 Bellco Materials, Inc.	16
196	43APAC-Oklahoma, Inc.	7
197	124 Empire Construction & Materials, Inc.	6
198	95 Haskell Lemon Construction Co.	11
199	60 Glover Construction Co., Inc.	30
200	161 Bellco Materials, Inc.	16
201	148 Bellco Materials, Inc.	16
202	45 Vinita Rock Company	7
203	186 Glover Construction Co., Inc.	30
204	128 Glover Construction Co., Inc.	30
205	388 Glover Construction Co., Inc.	30
206	74 Overland Corporation	5
207	143 Empire Construction & Materials, Inc.	6
208	53 Glover Construction Co., Inc.	30
209	69 Overland Corporation	5
210	60 Overland Corporation	5
211	79 The Cummins Construction Co., Inc.	35
212	244 Glover Construction Co., Inc.	30
213	52 Tiger Ind. Transp. Sys., Inc.	4
214	156 Glover Construction Co., Inc.	30
215	73 Glover Construction Co., Inc.	30
216	84 Glover Construction Co., Inc.	30
217	218 Glover Construction Co., Inc.	30
218	60 Haskell Lemon Construction Co.	11
219	30 Haskell Lemon Construction Co.	11
220	90 Shears Construction Co.	19
221	77T. J. Campbell Const. Co.	3
222	228 Pavers, Inc.	1
223	50 Evans & Associates Const.	4
224	60The Cummins Construction Co., Inc.	35
225	60 Northern Improvement Company	3
226	309 Shears Construction Co.	19
227	31 Shears Construction Co.	19
228	72 Glover Construction Co., Inc.	30
229	63 Behne Construction Co., Inc.	1
230	398 Cornell Constr. Co., Inc.	8

ID Total	Cost Growth Resident Eng	ineer Weather No of Bad	Weather Days
185	-0.57 y	Yes	61
186	-0.13z	Yes	61
187	-0.31z	Yes	55
188	-0.13z	No	0
189	0.33ae	Yes	36
190	-0.28am	No	0
191	-0.02 am	No	0
192	-0.28am	Yes	61
193	0.33ae	No	0
194	0.33 ae	Yes	22
195	0.33 ae	No	0
196	-0.31 aj	No	0
197	-0.21 b	No	0
198	-0.48v	No	0
199	0.72al	No	0
200	0.33 f	No	0
201	0.33 f	No	0
202	-0.28aj	No	0
203	0.72aj	Yes	61
204	0.720	Yes	61
205	0.72b	Yes	61
206	-0.29 ad	Yes	61
207	-0.21 am	No	0
208	0.72 am	No	0
209	-0.29ag	Yes	61
210	-0.29 ag	Yes	61
211	-0.57 h	No	0
212	0.72aj	No	0
213	-0.05aj	No	0
214	0.72 b	No	0
215	0.72d	NO	
216	0.72d		0 61
217		Yes	
218	0.72d -0.48p	Yes	61
	THE PERSON NAMED OF PERSONS ASSESSED TO SERVICE AND PROPERTY OF PERSONS ASSESSED.	No.	0
219	-0.48p	No.	0
220	-0.21p	No	0
221	-0.31z	No	0
222	-0.02f	No.	0
223	-0.15ah	No.	
224	-0.57 af	No.	0
225	-0.05ap	No	0
226	-0.21 m	Yes	61
227	-0.211	No	0
228	0.72ak	Yes	46
229	0.17j	No	0
230	0.22 aq	No	0

ID Bad we	eather Days Ratio Bidding Enviro	nment Plans Review Time Unit System
185	1.0167 1	21 English-Metric
186	0.18897	21 English-Metric
187	1.44749	21 English-Metric
188	0.000011	21 English-Metric
189	0.238411	21 English-Metric
190	0.00009	21 English-Metric
191	0.000011	21 English-Metric
192	0.180526	21 English-Metric
193	0.00009	21 English-Metric
194	0,165411	21 English-Metric
195	0.000011	21 English-Metric
196	0.00002	21 English-Metric
197	0.000026	21 English-Metric
198	0.00007	21 English-Metric
199	0.000026	21 English-Metric
200	0.00006	21 English-Metric
201	0.0006	21 English-Metric
202	0.00001	21 English-Metric
203	0.32802	21 English-Metric
204	0.47661	21 English-Metric
205	0.1572.26	21 English-Metric
206	0.82435	21 English-Metric
207	0.000011	21 English-Metric
208	0.000026	21 English-Metric
209	0.88415	21 English-Metric
210	1.01675	21 English-Metric
211	0.0006	21 English-Metric
212	0.00009	21 English-Metric
213	0.00004	21 English-Metric
214	0.000026	21 English-Metric
215	0.00002	21 English-Metric
216	0.72623	21 English-Metric
217	0.2798.1	21 English-Metric
218	0.00003	21 English-Metric
219	0.00007	21 English-Metric
220	0.00007	21 English-Metric
221	0.000020	21 English-Metric
222	0.00006	21 English-Metric
223	0.00004	21 English-Metric
224	0.0009	21 English-Metric
225	0.000026	21 English-Metric
226	0.197426	21 English-Metric
227	0.00004	21 English-Metric
228	0.63891	21 English-Metric
229	0.000011	21 English-Metric
230	0.000011	21 English-Metric
೭೦೮	0.0000	Z I English-Metric

ID Out-of-Stat	e Firms Worl	k Order Date	Timing of Work Order	Contractors History
185	No	12/19/97	29	Yes
186	No	9/9/97	47	Yes
187	No	5/5/97	39	Yes
188	No	5/28/97	34	Yes
189	No	3/13/97	21	Yes
190	No	7/18/97	22	No
191	No	9/9/96	46	No
192	No	7/24/96	34	No
193	No	7/17/97	21	Yes
194	No	5/14/97	20	Yes
195	No	8/22/96	28	Yes
196	No	6/2/98	40	Yes
197	No	7/24/96	34	No
198	No	8/26/97	33	Yes
199	Yes	7/29/96	39	Yes
200	No No	6/12/97	21	Yes
201	No	6/12/97	21	Yes
202	Yes	7/23/98	28	No
203	No	12/4/97	42	Yes
204	No	3/4/98	41	Yes
205	Yes	7/29/96	39	Yes
206	Yes	2/26/97	34	No.
207	nes No	3/24/97	32	
208	No		THE PROPERTY AND ADDRESS OF THE PROPERTY AND ADDRESS OF THE PARTY AND ADDRESS OF THE PARTY AND ADDRESS OF THE PARTY ADDRESS OF THE PART	No
		7/29/96	39	Yes
209	Yes	2/27/97	35	No
210	Yes	2/27/97	35	No
211	No	6/26/97	35	Yes
212	No	7/18/97	22	Yes
213	No V	9/23/96	32	No
214	Yes	7/29/96	39	Yes
215	No	6/22/98	32	Yes
216	No	3/19/98	28	Yes
217	No	12/19/96	28	Yes
218	No	4/30/98	35	Yes
219	No	9/25/97	63	Yes
220	No	7/31/96	. 41	Yes
221	No	5/5/97	39	No
222	No	6/20/97	29	No
223	No	9/17/96	26	No
224	No	7/17/97	21.	Yes
225	Yes	8/6/96	47	No
226	No	7/29/96	39	Yes
227	No	9/27/96	36	Yes
228	No	9/24/97	34	Yes
229	No	8/29/96	35	Yes
230	No	7/15/97	19	Yes

ID Project	s with Overrun Average No	of Projects with O/R	Average Overrun
185	10	0.2857	2.8000
186	3	0.3000	12.5000
187	. 1	0.1429	1.2200
188	3	0.3000	12.5000
189	5	0.3125	9.2540
190	0	0.0000	0.0000
191	0	0.0000	0.0000
192	0	0.0000	0.0000
193	5	0.3125	9.2540
194	5	0.3125	9.2540
195	5	0.3125	9.2540
196		0.1429	1.2200
197	0	0.0000	0.0000
198	2	0.1818	2.6800
190	11	0.3667	14.2400
200	5	0.3667	9.2540
200	5	0.3125	9.2540
201	0	0.0000	
202	11	at a conservation of the contract of the contr	0.0000
203		0.3667	14.2400
	11 	0.3667	14.2400
205	<b>11</b>	0.3667	14.2400
206	0	0.0000	0.0000
207	0	0.0000	0.0000
208	11	0.3667	14.2400
209	0	0.0000	0.0000
210	0	0.0000	0.0000
211	10	0.2857	2.8000
212	11	0.3667	14.2400
213	0	0.0000	0.0000
214	11	0.3667	14.2400
215	11 	0.3667	14.2400
216	. 11	0.3667	14.2400
217	11	0.3667	14.2400
218	2	0.1818	2.6800
219	2	0.1818	2.6800
220	3	0.1579	7.2733
221	0	0.0000	0.0000
222	0	0.0000	0.0000
223	0	0.0000	0.0000
224	10	0.2857	2.8000
225	0	0.0000	0.0000
226	3	0.1579	7.2733
227	3	0.1579	7.2733
228	11	0.3667	14.2400
229	1	1.0000	16.9800
230	4	0.5000	7.1575

ID A	verage Cost Growth Availability of Labor
185	-0.0163 3.9
186	-0.0130
187	-0.0443
188	-0.0130 3.8
189	0.0206 4.4
190	-0.0400 4.2
191	-0.0100 3.8
192	-0.0400
193	0.0206 4.2
194	0.0206 3.8
195	0.0206 3.8
196	-0.0443 4.4
197	-0.0350
198	-0.0330 2
199	0.0240
ļ	
200	0.0206 4.2 0.0206 4.2
	and a supplementation of the COST and the contract of the cost of
202	
203	0.0240 4.1
204	0.0240 4.7
205	0.0240
206	-0.0580 4.8
207	-0.0350 4.4
208	0.0240 4
209	-0.0580 4.8
210	-0.0580 4.8
211	-0.0163 4.2
212	0.0240 4.2
213	-0.0125 3.6
214	0.0240
215	0.0240 4.6
216	0.0240 4.9
217	0.0240 3.7
218	-0.0436 4.5
219	-0.0436 4
220	-0.0111
221	-0.1033
222	-0.0200 4.2
223	-0.0375 3.6
224	-0.0163 4.2
225	-0.0163 4.2 -0.0167 4
226	-0.0111 4
227	-0.0111 3.6
228	0.0240 3.8
229	0.1700 3.8
230	0.0275 4.2

ID Project No	Location (County)	Project Type	Letting Date	Number of Bids
231 127B(008)	Grant	Resurfacing	4/24/97	1
232126D(004)	Grady	Resurfacing	3/27/97	
233 124C(002)	Garfield	Resurfacing	3/27/97	1
234 123B(001)	Ellis	Resurfacing	6/20/96	2
235 121B(11)	Delaware	Resurfacing	6/26/97	
236 120D(010)	Custer	Resurfacing	3/26/98	
237 120C(1)	Custer	Resurfacing	6/20/96	2
238 119C(005)	Creek	Resurfacing	2/20/97	1
239119C(004)	Creek	Resurfacing	2/20/97	1
240119C(004)	Creek	Resurfacing	2/20/97	
241115B(006)	Coal	Resurfacing	6/26/97	
242115N(005)	Coal	Resurfacing	3/27/97	3 2
243 115D(002)	Coal	Resurfacing	4/24/97	2
244 113A(003)	Cimarron	Resurfacing	6/20/96	. 1
245111D(017)	Cherokee	Resurfacing	5/21/98	0
246111C(13)	Cherokee	Resurfacing	4/24/97	
247 110D(003)	Carter	Resurfacing	2/20/97	2
248110D(002)	Carter	Resurfacing	2/20/97	2
249109A(005)	Canadian	Resurfacing	3/27/97	2
250 109C(06)	Canadian	Resurfacing	3/27/97	2 2 2 2 2 3
251 108B(014)	Caddo	Resurfacing	4/24/97	3
252 108(002)	LeFlore	Overlay	5/25/95	1
253 108(002)	LeFlore	Overlay	5/25/95	1
254 108(002)	LeFlore	Overlay	5/25/95	1
255 108(002)	LeFlore	Overlay	5/25/95	1
256 108(002)	LeFlore	Overlay	5/25/95	1
257 108N(001)	Caddo	Resurfacing	6/20/96	3
258 106D(16)	Blaine	Resurfacing	3/26/98	
259106D(008)	Blaine	Resurfacing	2/19/98	
260 106C(002)	Blaine	Resurfacing	2/20/97	3
261 105C(15)	Beckham	Resurfacing	6/26/97	6
262105B(14)	Beckham	Resurfacing	2/20/97	1
263 104B(008)	Beaver	Resurfacing	2/19/98	2
264 103N(017)	Atoka	Resurfacing	4/23/98	
265 102C(006)	Alfalfa	Resurfacing	5/22/97	. 0
266 102C(002)	Alfalfa	Resurfacing	6/20/96	1

ID	Lowest Bid	2nd Lowest Bid	Highest Bid	MLOT	Bid Range
231	\$239,080.00	\$239,080.00	\$239,080.00	\$0.00	\$0.00
232	\$84,694.40	\$93,717.81	\$155,456.00	\$9,023.41	\$70,761.60
233	\$463,065.00	\$463,065.00	\$463,065.00	\$0.00	\$0.00
234	\$314,860.75	\$337,741.75	\$337,741.75	\$22,881.00	\$22,881.00
235	\$862,339.95	\$880,385.75	\$900,900.75	\$18,045.80	\$38,560.80
236	\$116,767.60	\$145,745.00	\$159,390.90	\$28,977.40	\$42,623.30
237	\$1,176,889.53	\$1,229,166.15	\$1,229,166.15	\$52,276.62	\$52,276.62
238	\$319,285.90	\$319,285.90	\$319,285.90	\$0.00	\$0.00
239	\$176,597.30	\$176,597.30	\$176,597.30	\$0.00	\$0.00
240	\$294,266.10	\$294,266.10	\$294,266.10	\$0.00	\$0.00
241	\$598,378.50	\$740,690.00	\$794,656.00	\$142,311.50	\$196,277.50
242	\$789,329.77	\$836,123.18	\$998,591.64	\$46,793.41	\$209,261.87
243	\$82,631.93	\$99,173.40	\$99,173.40	\$16,541.47	\$16,541.47
244	\$265,585.50	\$265,585.50	\$265,585.50	\$0.00	\$0.00
245	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
246	\$301,977.75	\$310,713.75	\$386,388.00	\$8,736.00	\$84,410.25
247	\$31,483.85	\$53,319.30	\$53,319.30	\$21,835.45	\$21,835.45
248	\$179,860.38	\$189,807.90	\$189,807.90	\$9,947.52	\$9,947.52
249	\$141,540.00	\$196,650.00	\$196,650.00	\$55,110.00	\$55,110.00
250	\$339,415.00	\$346,810.00	\$346,810.00	\$7,395.00	\$7,395.00
251	\$416,637.41	\$423,954.75	\$481,269.58	\$7,317.34	\$64,632.17
252	\$321,756.95	\$321,756.95	\$321,756.95	\$0.00	\$0.00
253	\$350,524.41	\$350,524.41	\$350,524.41	\$0.00	\$0.00
254	\$203,939.55	\$203,939.55	\$203,939.55	\$0.00	\$0.00
255	\$366,892.80	\$366,892.80	\$366,892.80	\$0.00	\$0.00
256	\$358,927.80	\$358,927.80	\$358,927.80	\$0.00	\$0.00
257	\$178,101.84	\$206,511.79	\$207,391.71	\$28,409.95	\$29,289.87
258	\$207,770.00	\$215,800.60	\$314,305.00	\$8,030.60	\$106,535.00
259	\$75,985.00	\$99,937.50	\$99,937.50	\$23,952.50	\$23,952.50
260	\$491,838.65	\$562,305.89	\$785,043.90	\$70,467.24	\$293,205.25
261	\$372,802.98	\$437,497.00	\$509,314.00	\$64,694.02	\$136,511.02
262	\$372,275.12	\$372,275.12	\$372,275.12	\$0.00	\$0.00
263	\$719,863.10	\$737,777.50	\$737,777.50	\$17,914.40	\$17,914.40
264	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
265	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
266	\$211,626.15	\$211,626.15	\$211,626.15	\$0.00	\$0.00

ID	Engr's Estimate	Contract Amount	<b>Contract Difference</b>	<b>Actual Cost</b>	Cost Growth
231	\$222,540.00	\$239,080.00	\$16,540.00	\$208,237.68	-12.90%
232	\$79,960.96	\$84,694.40	\$4,733.44	\$94,953.85	12.11%
233	\$389,900.00	\$463,065.00	\$73,165.00	\$445,068.19	-3.89%
234	\$286,005.00	\$314,860.75	\$28,855.75	\$314,785.40	-0.02%
235	\$750,405.00	\$862,339.95	\$111,934.95	\$828,235.57	-3.95%
236	\$125,610.00	\$116,767.60	(\$8,842.40)	\$113,172.44	-3.08%
237	\$1,073,453.00	\$1,176,889.53	\$103,436.53	\$1,200,910.13	2.04%
238	\$326,161.18	\$319,285.90	(\$6,875.28)	\$310,764.64	-2.67%
239	\$175,995.92	\$176,597.30	\$601.38	\$165,326.50	-6.38%
240	\$289,151.68	\$294,266.10	\$5,114.42	\$276,943.31	-5.89%
241	\$560,024.00	\$598,378.50	\$38,354.50	\$589,308.00	-1.52%
242	\$834,200.30	\$789,329.77	(\$44,870.53)	\$777,198.29	-1.54%
243	\$63,016.85	\$82,631.93	\$19,615.08	\$83,702.88	1.30%
244	\$245,031.00	\$265,585.50	\$20,554.50	\$265,122.58	-0.17%
245	\$0.00	\$60,028.90	\$60,028.90	\$59,157.73	-1.45%
246	\$312,500.25	\$301,977.75	(\$10,522.50)	\$298,669.59	-1.10%
247	\$38,105.26	\$31,483.85	(\$6,621.41)	\$27,395.86	-12.98%
248	\$173,509.83	\$179,860.38	\$6,350.55	\$173,276.43	-3.66%
249	\$168,720.00	\$141,540.00	(\$27,180.00)	\$150,950.30	6.65%
250	\$341,920.00	\$339,415.00	(\$2,505.00)	\$316,573.31	-6.73%
251	\$359,128.96	\$416,637.41	\$57,508.45	\$387,021.02	-7.11%
252	\$345,952.50	\$321,756.95	(\$24,195.55)	\$320,758.37	-0.31%
253	\$392,257.50	\$350,524.41	(\$41,733.09)	\$350,059.38	-0.13%
254	\$228,730.00	\$203,939.55	(\$24,790.45)	\$203,407.61	-0.26%
255	\$404,610.00	\$366,892.80	(\$37,717.20)	\$366,738.68	-0.04%
256	\$404,610.00	\$358,927.80	(\$45,682.20)	\$358,927.62	0.00%
257	\$174,412.00	\$178,101.84	\$3,689.84	\$175,877.82	-1.25%
258	\$214,780.00	\$207,770.00	(\$7,010.00)	\$207,817.33	0.02%
259	\$65,000.00	\$75,985.00	\$10,985.00	\$89,093.69	17.25%
260	\$407,966.29	\$491,838.65	\$83,872.36	\$497,180.71	1.09%
261	\$455,322.40	\$372,802.98	(\$82,519.42)	\$358,253.79	-3.90%
262	\$333,141.52	\$372,275.12	\$39,133.60	\$370,684.37	-0.43%
263	\$647,862.50	\$719,863.10	\$72,000.60	\$719,082.05	-0.11%
264	\$0.00	\$197,749.65	\$197,749.65	\$184,798.72	-6.55%
265	\$0.00	\$293,030.08	\$293,030.08	\$292,918.77	-0.04%
266	\$186,650.00	\$211,626.15	\$24,976.15	\$211,626.15	0.00%

ID I	Ouration Contractor N	lumber of Projects
231	30 The Cummins Construction Co., Inc.	35
232	76T & G Construction Co., Inc.	6
233	55 The Cummins Construction Co., Inc.	35
234	95 Broce Const. Co., Inc.	18
235	103 The Cummins Construction Co., Inc.	35
236	66 Circle S Paving Co., Inc.	4
237	139 Comell Constr. Co., Inc.	8
238	121 The Quapaw Company	10
239	114 The Quapaw Company	10
240	107 The Quapaw Company	10
241	50 AMIS/OTAC	4
242	90 AMIS/OTAC	4
243	75 Bryan Adair Const., Co.	1
244	89 Highway Contractors, Inc.	8
245	42 Patton Construction Company	1
246	289 Glover Construction Co., Inc.	30
247	97 Overland Corporation	5
248	164 Overland Corporation	5 5 3
249	272 Mcconnell Construction, Inc.	3
250	91 Haskell Lemon Construction Co.	11
251	62 Haskell Lemon Construction Co.	11
252	130 Job Construction Co., Inc.	12
253	130 Job Construction Co., Inc.	12
254	130 Job Construction Co., Inc.	12
255	214 Job Construction Co., Inc.	12
256	214 Job Construction Co., Inc.	12
257	87 Haskell Lemon Construction Co.	11
258	98 Circle S Paving Co., Inc.	4
259	79.Comell Constr. Co., Inc.	8
260	185 The Cummins Construction Co., Inc.	35
261	368 Comell Constr. Co., Inc.	8
262	199 Caswell-Orth Contracting, Inc.	1
263	85 Highway Contractors, Inc.	8
264	62 The Cummins Construction Co., Inc.	35
265	87 Broce Const. Co., Inc.	18
266	75 The Cummins Construction Co., Inc.	35

ID To	tal Cost Growth	Resident Engineer	Weather	No of Bad Weather Days
231	-0.57		No	0
232	-0.2	n	No	0
233	-0.57	արիակությանը գրագացած աչատացած շագու բիմոն բանական համագործ հիմայական կին դատաստանատում հագագանակայացնում և բա -	No	. 0
234	-0.35		No	0
235	-0.57	am	No	0
236	-0.05	aq	No	O
237	0.22	aq	No	0
238	-0.13	ae	Yes	61
239	-0.13	ae	Yes	61
240	-0.13	ae	Yes	61
241	-0.05	K	Yes	28
242	-0.05	k	Yes	55
243	0.01	k	No	O
244	-0.01	ai	No	0
245	-0.01	aj	No	0
246	0.72	aj	Yes	38
247	-0.29	ad	Yes	61
248	-0.29	ad	No	0
249	0.01	an	No	O
250	-0.48	an	No	0
251	-0.48	n .	No	0
252	-0.09	U	Yes	61
253	-0.09	U	Yes	61
254	-0.09	U	Yes	61
255	-0.09	U	No	O
256	-0.09	U	No	0
257	-0.48	an	No	0
258	-0.05	aq	Yes	37
259	0.22	aq	Yes	21
260	-0.57		Yes	22
261	0.22	aq	No	. 0
262		aq	Yes	61
263	-0.011	h	Yes	59
264	-0.57		No	0
265	-0.35	h .	No	0
266	-0.57 j		No	0

ID	Bad weather Days Ratio	<b>Bidding Environment</b>	Plans Review Time	Unit System
231	0.0000	11	21	English-Metric
232	0.0000	9	21	English-Metric
233	0.0000	9	21	English-Metric
234	0.0000	26	21	English-Metric
235	0.0000	9	21	English-Metric
236	0.0000	3	21	English-Metric
237	0.0000	26	21	English-Metric
238	0.5041	11	21	English-Metric
239	0.5351	11	21	English-Metric
240	0.5701	11	. 21	English-Metric
241	0.5600	9	21	English-Metric
242	0.6111	9	21	English-Metric
243	0.0000	11	21	English-Metric
244	0.0000	26	21	English-Metric
245	0.0000	2	21	English-Metric
246	0.1315	11	21	English-Metric
247	0.6289	11	21	English-Metric
248	0.0000	11	21	English-Metric
249	0.0000	9	21	English-Metric
250	0.0000	9	21	English-Metric
251	0.0000	11	21	English-Metric
252	0.4692	12	21	English
253	0.4692	12	21	English
254	0.4692	12	21	English
255	0.0000	12	. 21	English
256	0.0000	12	21	English
257	0.0000	26	21	English-Metric
258	0.3776	3	21	English-Metric
259	0.2658	3	21	English-Metric
260	0.1189	11	21	English-Metric
261	0.0000	9	21	English-Metric
262	0.3065	11	21	English-Metric
263	0.6941	3	21	English-Metric
264	0.0000	2	21	English-Metric
265	0.0000	6	21	English-Metric
266	0.0000	26	21	English-Metric

ID Out-of-S	tate Firms Work	Order Date	Timing of Work Order Contrac	tors History
231	No	5/22/97	28	Yes
232	No	4/24/97	28	Yes
233	No	5/6/97	40	Yes
234	No	7/11/96	21	Yes
235	No	7/17/97	21	Yes
236	No	5/21/98	56	Yes
237	No	7/23/96	33	Yes
238	No	3/24/97	32	Yes
239	No	3/24/97	32	Yes
240	No	3/24/97	32	Yes
241	No	7/25/97	29	No
242	No	5/5/97	39	No
243	No	6/5/97	42	Yes
244	No	7/19/96	29	Yes
245	No	7/14/98	54	No
246	Yes	5/22/97	28	Yes
247	No	3/20/97	28	No
248	No	3/20/97	28	No
249	No	5/5/97	39	Yes
250	No	4/22/97	26	Yes
251	No	5/19/97	25	Yes
252	No	6/30/95	36	No
253	No	6/30/95	36	No
254	No	6/30/95	. 36	No
255	No	6/30/95	36	No
256	No	6/30/95	36	No
257	No	7/23/96	33	Yes
258	No	5/6/98	41	Yes
259	No	3/27/98	36	Yes
260	No	3/25/97	33	Yes
261	No	7/14/97	18	Yes
262	No	3/13/97	21	No
263	No	3/18/98	27	Yes
264	No	6/2/98	40	Yes
265	No	6/20/97	29	Yes
266	No	7/31/96	41	Yes

ID	Projects with Overrun	Average No of Projects with O/R	Average Overrun
231	10	0.2857	2.8000
232	1	0.1667	12.1100
233	10	0.2857	2.8000
234	The second secon	0.0556	1.9000
235	10	0.2857	2.8000
236	1	0.2500	0.0200
237	4	0.5000	7.1575
238		And the second s	12.5000
239		A CONTRACTOR OF THE PROPERTY O	12.5000
240		0.3000	12.5000
241	0	0.0000	0.0000
242		COLOR CONTRACTOR OF THE PROPERTY OF THE PROPER	0.0000
243	1	1.0000	1.3000
244	. 1	0.1250	0.0000
245	Committee of the Commit		0.0000
246	AND THE PROPERTY OF THE PROPER	0.3667	14.2400
247			0.0000
248			0.0000
249	E ANNA DESCRIPTION OF THE PROPERTY OF THE PARTY OF THE PA	graphy and the state of the sta	3.5150
250	TANAN AND THE RESEARCE AND AND AND ADDRESS OF THE AND THE PARTY OF THE	The suppose of the second seco	2.6800
251	e carbonar e vers a veng e page e e encarada arra e encaração e el base e el brez Prope e e encarada en	- Marchael 1994 (1	2.6800
252		September 19 State	0.0000
253	to contribute a compared and a contract the second contract and described the contract of the second contract of	CONTRACTOR SECURITIES FOR THE SECOND CONTRACTOR SECURITIES SECOND	0.0000
254			0.0000
255		THE RESIDENCE PROPERTY AND THE PROPERTY OF THE	0.0000
256	er begele mannet de met er en meddengge mellet blade menne erberen er benedelt besend det met de de blade bl	AND THE RESIDENCE OF THE PROPERTY OF THE PROPE	0.0000
257	A AND COMMENT OF THE PARTY OF T	AND AND ADMINISTRATION OF THE PROPERTY OF THE	2.6800
258	To a service to the control of the c	0.2500	0.0200
259	to a series and the series of		7.1575
260	. A part has a contract many of the property and the part of the p	The state of the s	2.8000
261	a series and the series of the		7.1575
262		0.0000	0.0000
263		0.1250	0.0000
264	*	**************************************	2.8000
265		0.0556	1.9000
266	10	0.2857	2.8000

ID Av	erage Cost Growth Availabi	lity of Labor
231	-0.0163	3.8
232	-0.0333	4
233	-0.0163	4
234	-0.0194	4
235	-0.0163	4.2
236	-0.0125	4.5
237	0.0275	4
238	-0.0130	4.4
239	-0.0130	4.4
240	-0.0130	4.4
241	-0.0125	4.2
242	-0.0125	4
243	0.0100	3.8
244	-0.0012	4
245	-0.0100	4.6
246	0.0240	3.8
247	-0.0580	4.4
248	-0.0580	4.4
249	0.0033	4
250	-0.0436	4
251	-0.0436	3.8
252	-0.0075	4.9
253	-0.0075	4.9
254	-0.0075	4.9
255	-0.0075	4.9
256	-0.0075	4.9
257	-0.0436	4
258	-0.0125	4.5
259	0.0275	4.9
260	-0.0163	4.4
261	0.0275	4.2
262	0.0000	4.4
263	-0.0012	4.9
264	-0.0163	4.4
265	-0.0194	4.2
266	-0.0163	4

#### APPENDIX D

#### THE CORRELATION MATRIX

## Correlation Matrix

	X1	X2	ХЗ	X4	Х5	Х6	Х7	X8
X1	1.0000	0.0570	0.0844	1112	0.0982	0.0660	0189	0.0664
X2	0.0570	1.0000	0.4416	0702	0.3299	0.0271	0.0706	0069
ХЗ	0.0844	0.4416	1.0000	0553	0.4964	0737	0.0337	0.0690
X4	1112	0702	0553	1.0000	0781	0569	0443	0701
X5	0.0982	0.3299	0.4964	0781	1.0000	0.6802	1167	0779
X6	0.0660	0.0271	0737	0569	0.6802	1.0000	1143	0964
X7	0189	0.0706	0.0337	0443	1167	1143	1.0000	0.0458
X8	0.0664	0069	0.0690	0701	0779	0964	0.0458	1.0000
X9	0339	0671	0098	0.9093	0235	0436	0677	0400
X10	0.1818	0.0905	0.1972	0.1629	0.1680	0.0045	0.0259	0.0408
X11	0058	0286	0.0310	0.4199	0.1010	0.0256	0917	1030
X12	0.0621	0.0423	0.1017	0.1494	0.1146	0.0296	0.0236	0970
X13	0.1133	0.1236	0.1179	1159	0.2686	0.1850	0.0056	0.3176
X14	0287	1009	0484	1262	0265	0.0319	0358	0668
X15	0.4745	0392	0.1239	1941	0.0919	0.0446	0255	0190
X16	3397	0.0096	1180	0.1143	0524	0096	0458	0407

# Correlation Matrix (Contd')

	Х9	X10	X11	X12	X13	X14	X15	X16
X1	0339	0.1818	0058	0.0621	0.1133	0287	0.4745	3397
X2	0671	0.0905	0286	0.0423	0.1236	1009	0392	0.0096
ХЗ	0098	0.1972	0.0310	0.1017	0.1179	0484	0.1239	1180
X4	0.9093	0.1629	0.4199	0.1494	1159	1262	1941	0.1143
X5	0235	0.1680	0.1010	0.1146	0.2686	0265	0.0919	0524
X6	0436	0.0045	0.0256	0.0296	0.1850	0.0319	0.0446	0096
X7	0677	0.0259	0917	0.0236	0.0056	0358	0255	0458
X8	0400	0.0408	1030	0970	0.3176	- , 0668	0190	0407
X9	1.0000	0.4088	0.5918	0.3274	0748	0942	1173	0.0882
X10	0.4088	1.0000	0.4545	0.6587	0.0252	0.0248	0.2337	1109
X11	0.5918	0.4545	1.0000	0.5505	0300	0660	0603	0.0469
X12	0.3274	0.6587	0.5505	1.0000	0.0110	0042	0.0643	0917
X13	0748	0.0252	0300	0.0110	1.0000	0.0327	0.0371	0.0440
X14	0942	0.0248	0660	0042	0.0327	1.0000	0.5361	1246
X15	1173	0.2337	0603	0.0643	0.0371	0.5361	1.0000	3505
X16	0.0882	1109	0.0469	0917	0.0440	1246	3505	1.0000

# APPENDIX E SAS PROGRAM

```
* Predicting Construction Cost Growth in ODOT's Paving Projects *
         using Information Available at the Bidding Time
dm 'output; clear; log; clear;';
options ls=66 ps=44 pageno=1 nodate;
title;
title 'Predicting Cost Growth in ODOTs Paving Projects';
data a;
input id x17 $ x18 $ x1 x2 y x3 x19 $ x4 x20 $ x5 x6 x7
      x21 $ x22 $ x8 x9 x10 x11 x12 x13 x14 x15 x16;
if x20='a' then d1=1; else d1=0;
if x20='b' then d2=1; else d2=0;
if x20='c' then d3=1; else d3=0;
if x20='d' then d4=1; else d4=0;
if x20='e' then d5=1; else d5=0;
if x20='f' then d6=1; else d6=0;
if x20='g' then d7=1; else d7=0;
if x20='h' then d8=1; else d8=0;
if x20='i' then d9=1; else d9=0;
if x20='j' then d10=1; else d10=0;
if x20='k' then d11=1; else d11=0;
if x20='l' then d12=1; else d12=0;
if x20='m' then d13=1; else d13=0;
if x20='n' then d14=1; else d14=0;
if x20='o' then d15=1; else d15=0;
if x20='p' then d16=1; else d16=0;
if x20='q' then d17=1; else d17=0;
if x20='r' then d18=1; else d18=0;
if x20='s' then d19=1; else d19=0;
if x20='t' then d20=1; else d20=0;
if x20='u' then d21=1; else d21=0;
if x20='v' then d22=1; else d22=0;
if x20='w' then d23=1; else d23=0;
```

```
if x20='x' then d24=1; else d24=0;
if x20='y' then d25=1; else d25=0;
if x20='z' then d26=1; else d26=0;
if x20='ab' then d27=1; else d27=0;
if x20='ac' then d28=1; else d28=0;
if x20='ad' then d29=1; else d29=0;
if x20='ae' then d30=1; else d30=0;
if x20='af' then d31=1; else d31=0;
if x20='ag' then d32=1; else d32=0;
if x20='ah' then d33=1; else d33=0;
if x20='ai' then d34=1; else d34=0;
if x20='aj' then d35=1; else d35=0;
if x20='ak' then d36=1; else d36=0;
if x20='al' then d37=1; else d37=0;
if x20='am' then d38=1; else d38=0;
if x20='an' then d39=1; else d39=0;
if x20='ao' then d40=1; else d40=0;
if x20='ap' then d41=1; else d41=0;
if x20='aq' then d42=1; else d42=0;
if x20='ar' then d43=1; else d43=0;
if n =34 then delete;
if n_=35 then delete;
if n =40 then delete;
if _n_=71 then delete;
if n =139 then delete;
if _n_=188 then delete;
if n =201 then delete;
if n =205 then delete;
if n =214 then delete;
if n =229 then delete;
if n =259 then delete;
/* id = project identification number */
/* x1 = number of bids */
/* x2 = contract amount */
/* x3 = duration */
/* x4 = number of projects */
/* x5 = bad weather days */
/* x6 = ratio of bad weather days */
/* x7 = bidding environment */
/* x8 = timing of notice to proceed */
/* x9 = number of projects with overrun */
```

```
/* x10 = ratio of projects with overrun */
/* x11 = average overrun */
/* x12 = average cost growth */
/* x13 = unemployment rate */
/* x14 = MLOT ratio */
/* x15 = bid range ratio */
/* x16 = contract difference ratio */
/* x17 = location */
/* x18 = project type */
/* x19 = contractor */
/* x20 = resident engineer */
/* x21 = unit system */
/* x22 = existence of out-of-state firm */
/* y = cost growth */
cards;
1
                      Resurfacing
                                        3
                                               149181.50
                                                               -0.043
       Canadian
                                     2
                                                            -0.0513
2
       Noble
                   Resurfacing
                                            313700.00
3
       Noble
                   Resurfacing
                                     2
                                            565917.65
                                                            0.0000
4
       Nowata
                    Resurfacing
                                      2
                                             870893.75
                                                             -0.0005
5
       Okfuskee
                                                             -0.0206
                      Surfacing
                                      4
                                             261618.90
6
       Okfuskee
                      Surfacing
                                             342922.15
                                                             -0.0033
7
       Okfuskee
                      Overlay
                                           131001.20
                                                           0.0035
8
       Oklahoma
                      Resurfacing
                                               425655.00
                                                               0.0000
                                        6
9
                                               42375.00
                                                              0.0441
       Oklahoma
                      Resurfacing
                                        6
10
        Oklahoma
                       Resurfacing
                                                136167.34
                                                                0.013
                                         6
                                            722845.00
                                                            -0.0171
11
        Oklahoma
                       Overlay
12
                                         2
        Oklahoma
                       Resurfacing
                                                1588096.50
                                                                 0.04
13
        Oklahoma
                       Resurfacing
                                         3
                                                549157.00
                                                                -0.10
14
        Okmulgee
                       Resurfacing
                                         3
                                                268726.40
                                                                -0.05
15
        Okmulgee
                       Resurfacing
                                         3
                                                216896.40
                                                                -0.02
                                         252520.00
16
        Osage
                    Overlay
                                                         -0.0132
17
                    Resurfacing
                                      2
                                             703436.50
                                                             -0.0118
        Osage
18
        Osage
                    Overlay
                                 5
                                         849444.00
                                                         -0.0103
                                      3
19
        Tulsa
                    Resurfacing
                                             643280.04
                                                             -0.0711
20
        McClain
                      Resurfacing
                                        5
                                               61863.20
                                                              -0.1210
21
        McClain
                      Resurfacing
                                        6
                                               207588.25
                                                               0.0071
22
        McCurtain
                        Resurfacing
                                          2
                                                 487762.00
                                                                 -0.0
23
                                          3
                                                 494464.00
                                                                 -0.0
        McCurtain
                        Resurfacing
24
        Mcintosh
                       Resurfacing
                                         3
                                                163662.00
                                                                -0.02
25
        Mcintosh
                       Resurfacing
                                         3
                                                255885.00
                                                                -0.01
26
                                     3
                                            129900.00
        Mcintosh
                       Overlay
                                                            -0.0048
27
        Major
                    Overlay
                                         308292.08
                                                         -0.0067
```

28	Marshall	Resurfacing	4	118123.3	5 -0.01
29	Mayes	Overlay 4	30	06246.40	-0.0046
30	Murray	Resurfacing	2	486327.65	-0.0463
31	Murray	Resurfacing	4	323778.50	-0.0219
32	Muskogee	Resurfacing	3	539665.1	0.003
33	Muskogee	Surfacing	3	169921.00	0.0163
34	Muskogee	Resurfacing	4	138112.6	5 0.195
35	Muskogee	Resurfacing	2	255376.0	0 0.232
36	Muskogee	Resurfacing	3	23163.00	-0.005
37	Muskogee	Resurfacing	3	222697.2	3 -0.02
38	Latimer	Resurfacing	1	156761.00	-0.002
39	Canadian	Resurfacing	4	3426952.	95 0.00
40	Oklahoma	Resurfacing	2	1312190.	14 -0.2
41	LeFlore	Resurfacing	. 2	318207.50	-0.003
42	LeFlore	Resurfacing	- 1	471757.90	-0.004
43	Lincoln	Resurfacing	2	122475.20	-0.025
44	Lincoln	Resurfacing	3	444213.60	-0.006
45	Lincoln	Resurfacing	4	668714.32	-0.002
46	Lincoln	Resurfacing	4	697812.95	-0.012
47	Love	Resurfacing	4	2157646.21	0.0411
48	Oklahoma	<b>Overlay</b>	2	575394.50	-0.0818
49	Johnson	Resurfacing	4	463362.50	-0.004
50	Johnson	Resurfacing	3	220110.12	-0.002
51	Kay f	Resurfacing	4	1216269.00	-0.0274
52	Kay F	Resurfacing	5	641414.50	-0.0331
53	Kingfisher	Surfacing	6	95006.70	0.0038
54	Kingfisher	Resurfaci	ng .	2 91463.	65 -0.0
55	Kingfisher	r Resurfaci	ng	5 103528	.75 0.0
56	Kingfisher	r Resurfaci	ng	4 314780	.00 -0.
<b>57</b>	Grant	Resurfacing	1	53271.69	-0.0485
58	Grant	Surfacing	3	151742.00	-0.0014
59	Grant	Surfacing	3	98075.00	0.0000
60	Grant	Resurfacing	2	365640.00	0.0018
61	Rogers	Surfacing	3	389977.19	-0.0405
62	Hughes	Surfacing	4	888210.40	0.1016
63	Hughes	Resurfacing	3	411630.15	-0.0040
64	Hughes	Surfacing	3	246096.72	-0.0267
65	Jackson	Surfacing	2	1835630.78	0.0708
66	Jackson	Surfacing	2	196828.35	-0.0893
67	Creek	Resurfacing	. 3	693532.00	-0.1111
68	Custer	Surfacing	3	896891.10	0.0086
69	Custer	Resurfacing	4	995551.00	-0.0100
70	Delaware	Surfacing	2	843926.21	-0.1446

71	Delaware	Resurfacing		3	129097.77	-0.00
72	Delaware	Resurfacing		3	298567.84	
73	Delaware -	Overlay 2			0321.00	-0.0559
74	Ellis	-	1		418066.95	-0.0098
75	Garfield	Surfacing	1		1920149.45	0.0116
76	Garfield	Resurfacing		1	187315.00	
77	Garfield	Resurfacing		2	267416.00	
78	Garfield	Resurfacing		1	726491.10	
79	Garfield	Resurfacing		1	312500.00	
80	Garvin	Resurfacing	5		203020.40	-0.0535
81	Garvin	Resurfacing	3		956353.54	0.0190
82	Garvin	Resurfacing	7		514677.97	-0.0250
83	Grady	Surfacing 3		18	40395.85	0.0506
84	Grady	Overlay 4		4074	54.60 -	0.0430
85	Grady	Overlay 5		4921	68.40 -	0.0627
86	Grady	_	5		495026.00	-0.0324
87	Carter	Surfacing 2		9	9590.00	0.0000
88	Jefferson	Resurfacing		4	1259946.	00 -0.
89	Carter	Resurfacing	1		468832.50	-0.0167
90	Carter	Resurfacing	1		198589.00	-0.0209
91	Cherokee	Surfacing	5		1196989.50	0.0201
92	Delaware	Overlay 7		3	24440.00	-0.0063
93	Cherokee	Overlay 7		3	322796.22	0.0517
94	Choctaw	Resurfacing	:	2	675361.50	-0.021
95	Cimarron	Overlay 2		5	23588.00	-0.0066
96	Cimarron	Overlay 2		6	48893.02	-0.0043
97	Cimarron	Resurfacing		1	396257.16	-0.00
98	Cleveland	Surfacing	•	7	288691.58	-0.031
99	Cleveland	Resurfacing		9	238088.2	0.00
100	Cleveland	Resurfacing		4	538515.	30 0.1
101	Coal	Resurfacing	3		491871.80	-0.0071
102	Comanche	Resurfacing		2	18805.00	-0.07
103	Comanche	Resurfacing		1	79682.50	-0.10
104	Comanche	Overlay	2		773653.73	-0.0401
105	Craig	Resurfacing	1		42135.50	-0.0654
106	Craig	Resurfacing	1		304466.50	-0.0228
107	Craig	Resurfacing	4		362313.80	-0.0403
108	Craig	Resurfacing	1		34811.50	-0.0954
109	Craig	Resurfacing	2		465177.88	-0.0042
110	Adair	Resurfacing	3		85468.50	-0.0008
111 .	Adair	Resurfacing	5		1027032.50	0.0028
112	Alfalfa	Resurfacing		1	490372.80	
113	Alfalfa	Resurfacing		2	330415.45	-0.02

114	Atoka	Resurfacing	2	204245.00	0.0108
115	Beaver	Surfacing	3	2397807.06	0.0186
116	Beaver	Resurfacing	2	605787.04	0.0000
117	Beckham	Resurfacing	1	448402.00	-0.03
118	Washita	Resurfacing	3	1073466.1	0 -0.0
119	Beckham	Resurfacing	3	485207.00	-0.02
120	Dewey	Overlay 3	3 .	1463736.92	0.0000
121	Bryan	Surfacing	2	686789.74	0.0000
122	Bryan	Resurfacing	1	141424.37	-0.0221
123	Bryan	Resurfacing	3	168490.50	-0.0014
124	Bryan	Resurfacing	5	719882.40	-0.0080
125	Caddo	Resurfacing	5	379880.51	-0.0438
126	Canadian	Surfacing	- 5	821583.63	0.0260
127	Seminole	Surfacing	3	61687.00	0.0637
128	Seminole	Resurfacing	g 2	38815.10	-0.00
129	Seminole	Resurfacing	g 2	2 48514.35	-0.00
130	Seminole	Overlay	3	49653.20	-0.0673
131	Pushmataha	Resurfac:	ing	2 195650	-0
132	Pontotoc	Resurfacing	g . 4	442922.8	5 -0.0
133	Pittsburg	Resurfaci	ng	3 409725.	06 -0.
134	Pittsburg	Resurfaci	ng	3 435327.	70 -0.
135	Payne	Resurfacing	3	827312.95	0.1159
136	Payne	Resurfacing	1	278742.50	-0.0126
137	Payne	Resurfacing	3	368405.32	-0.0084
138	Payne	Resurfacing	1	221516.25	0.0679
139	Payne	Overlay	1 .	153340.00	-0.2974
140	Pawnee	Resurfacing	3	269925.00	0.0511
141	Ottawa	Resurfacing	2	349914.80	-0.010
142	Ottawa	Overlay	2	401876.80	-0.0202
143	Ottawa	Resurfacing	2	196261.00	-0.017
144	Woods	Surfacing	6	332323.00	-0.0276
145	Washita	Resurfacing	4	500682.25	-0.00
146	Washington	Resurfac	ing	2 217660	0.00
147	Wagoner	Resurfacing	3	315197.00	-0.01
148	Wagoner	Overlay	6	220814.00	-0.0560
149	Tulsa	Resurfacing	4	1030439.70	-0.004
150	Tulsa	Surfacing	3	565601.36	0.0198
151	Tillman	Overlay	3	252324.00	0.0000
152	Texas	Resurfacing	2	937448.50	-0.0005
153	Texas	Resurfacing	2	596116.40	-0.0130
154	Stephens	Resurfacin	-	482200.0	0.0
155	Stephens	Resurfacin	g 2	2 217969.7	
156	Stephens	Overlay	6	393896.92	-0.0081

157	Sequoyah	Resurfacing		2		39683.58	-0.00
158	Sequoyah	Resurfacing		5		84762.32	-0.02
159	Sequoyah	Resurfacing		4		76788.16	-0.02
160	Sequoyah	Resurfacing		•		134946.80	-0.0
161	Woodward	Resurfacing		2		392365.40	-0.0
162	Woodward	Resurfacing		2		599976.91	-0.0
163	Woods	Resurfacing	3			558509.80	-0.0019
164	Woods	Resurfacing	2			179871.85	-0.0126
165	Woods	Resurfacing	1			152840.50	-0.0816
166	Woods	Resurfacing	1			60843.03	-0.0874
167	Washita	Resurfacing		3		66045.00	-0.004
168	Washington	Resurfacing			2	352866.87	-0
169	Wagoner	Surfacing	5			307383.75	-0.0167
170	Wagoner	Resurfacing		5		560836.00	-0.04
171	Tulsa	Resurfacing	2			2132314.53	-0.120
172	Tulsa	Resurfacing	2			135310.00	-0.0093
173	Tillman	Resurfacing		4		198224.70	-0.06
174	Tillman	Resurfacing		3		53077.90	0.0000
175	Tillman	Resurfacing		4		391063.33	-0.02
176	Texas	Resurfacing	2			536307.80	0.0000
177	Texas	Resurfacing	1			538649.00	-0.0011
178	Sequoyah	Resurfacing		4		208650.00	-0.0
179	Sequoyah	Resurfacing		3		293000.00	-0.0
180	Seminole	Resurfacing		4		781886.46	-0.0
181	Rogers	Resurfacing	4	1		490537.20	0.0067
182	Rogers	Resurfacing	3	3		599439.40	0.0062
183	Pottawatom:	ie Resurfacii	ng			3 539600.8	84
184	Pontotoc	Resurfacing	•	3		490967.20	-0.0
185	Pittsburg	Resurfacing		3	3	635442.50	-0.
186	Payne	Resurfacing	1			1228850.00	-0.032
187	Payne	Resurfacing	2			429080.00	0.0122
188	Payne	Resurfacing	1			272665.00	0.1913
189	Pawnee	Resurfacing	4	1		511354.05	-0.031
190	Ottawa	Resurfacing	2	2		117837.70	-0.003
191	Ottawa	Resurfacing		3		377052.00	-0.017
192	Ottawa	Resurfacing	. 2			507211.25	-0.009
193	<b>Osage</b>	Resurfacing	1			758695.00	-0.0151
194	Osage	Resurfacing	4			597184.50	-0.0156
195	Osage	Resurfacing	5			474868.25	-0.0050
196	Okmulgee	Resurfacing	-	5		178764.00	-0.1
197	Okmulgee	Resurfacing		3		908167.40	-0.0
198	Oklahoma	Resurfacing		2		127535.00	-0.1
199	0kfuskee	Resurfacing		3		270211.50	0.03
				_			

200	Noble	Resurfacing	1		514894.60	0.1124
201	Noble	Resurfacing	2		533536.00	0.3301
202	Muskogee	Resurfacing		3	484900.00	-0.1
203	Muskogee	Surfacing	4	Ļ	229913.30	0.0645
204	Muskogee	Resurfacing		4	25449.85	-0.01
205	Muskogee	Resurfacing		2	350430.00	-0.3
206	Murray	Resurfacing	4	ļ	272585.76	-0.110
207	Mayes	Resurfacing	5		333110.51	-0.0018
208	Mayes	Resurfacing	4		134364.00	-0.0613
209	Marshall	Resurfacing		3	41249.40	-0.00
210	Marshall	Resurfacing		4	159788.56	-0.0
211	Major	Resurfacing	1		212021.05	0.0724
212	Mcintosh	Resurfacing		3	161755.00	-0.0
213	Mcintosh	Resurfacing		3	116289.00	-0.0
214	Mcintosh	Resurfacing		2	124350.00	0.90
215	McCurtain	Resurfacing	1	3	509683.5	0 -0.
216	McCurtain	Resurfacing	}	2	297962.50	6 -0.
217	McCurtain	Resurfacing	)	2	319543.84	4 0.0
218	McClain	Resurfacing		4	559525.00	-0.00
219	McClain	Resurfacing		4	203302.46	-0.02
220	McClain	Resurfacing		6	722514.07	-0.00
221	Logan	Resurfacing	3		295500.00	-0.0061
222	Kay F	Resurfacing	5	- 9	945665.00	-0.0178
223	Kay S	Surfacing 2		44	277.00 -0	.0533
224	Johnson	Resurfacing		3	560823.00	0.011
225	Johnson	Resurfacing		5	277081.84	-0.01
226	Jackson	Resurfacing		4	390522.90	-0.01
227	Hughes	Surfacing	3		46354.40	0.0414
228	Haskell	Resurfacing		3	496655.00	-0.02
229	Harper	Resurfacing	. 1		90765.40	0.1698
230	Greer	Resurfacing	7		667175.20	0.0848
231	Grant	Resurfacing	1		239080.00	-0.1290
232	Grady	Resurfacing	3		84694.40	0.1211
233	Garfield	Resurfacing		1	463065.00	-0.0
234	Ellis	Resurfacing	2		314860.75	-0.0002
235	Delaware	Resurfacing		4	862339.95	-0.0
236	Custer	Resurfacing	3	3	116767.60	-0.030
237	Custer	Resurfacing	2	2	1176889.53	0.020
238	Creek	Resurfacing	1		319285.90	-0.0267
239	Creek	Resurfacing	1		176597.30	-0.0638
240	Creek	Resurfacing	1		294266.10	-0.0589
241	Coal	Resurfacing	3		598378.50	-0.0152
242	Coal	Resurfacing	3		789329.77	-0.0154

243	Coal	Resurfacing	2	2		82631.93	0.0130
244	Cimarron	Resurfacing			1	265585.50	-0.0
245	Cherokee	Resurfacing			4	60028.90	-0.01
246	Cherokee	Resurfacing			4	301977.75	-0.0
247	Carter	Resurfacing		2		31483.85	-0.1298
248	Carter	Resurfacing		2		179860.38	-0.036
249	Canadian	Resurfacing			2	141540.00	0.06
250	Canadian	Resurfacing			2	339415.00	-0.0
251	Caddo	Resurfacing		3		416637.41	-0.0711
252	LeFlore	0verlay	1			321756.95	-0.0031
253	LeFlore	0verlay	1			350524.41	-0.0013
254	LeFlore	0verlay	1			203939.55	-0.0026
255	LeFlore	Overlay	1			366892.80	-0.0004
256	LeFlore	0verlay	1			358927.80	0.0000
257	Caddo	Resurfacing		3		178101.84	-0.0125
258	Blaine	Resurfacing		4		207770.00	0.0002
259	Blaine	Resurfacing		2		75985.00	0.1725
260	Blaine	Resurfacing		3		491838.65	0.0109
261	Beckham	Resurfacing		•	6	372802.98	-0.03
262	Beckham	Resurfacing		•	1	372275.12	-0.00
263	Beaver	Resurfacing		2		719863.10	-0.001
264	Atoka	Resurfacing		5		197749.65	-0.0655
265	Alfalfa	Resurfacing		4	4	293030.08	-0.00
266	Alfalfa	Resurfacing		•	1	211626.15	0.000

proc princomp out=one data=a; var x1 x2 x3 x4 x5 x6 x7 x8 x9 x10 x11 x12 x13 x14 x15 x16;

proc plot data=one; plot prin2\*prin1=prin3 / contour=10;

proc factor data=a rotate=varimax nfact=8 scree out=b; var x1-x16;

data combined;
merge a b;

proc glm data=combined;

classes x17 x18 x19 x20 x21 x22;
model y=factor1 factor4 factor5 x20;

proc reg data=combined;

model y=factor1 factor4 factor5 d1 d2 d3 d4 d5 d6 d7 d8 d9 d10 d11 d12 d13 d14 d15 d16 d17 d18 d19 d20 d21 d22 d23 d24 d25 d26 d27 d28 d29 d30 d31 d32 d33 d34 d35 d36 d37 d38 d39 d40 d41 d42 d43;

run;

# APPENDIX F SAS OUTPUT

#### 255 Observations 16 Variables

#### Simple Statistics

	X1	X2	Х3	X4
Mean	2.996078431	445694.5272	132.3490196	14.67843137
StD	1.486151398	421696.3384	110.1611550	11.46436303
	X5	Х6	<b>X7</b>	Х8
		λ0	Α,	λο
Mean	21.67058824	0.1842745098	13.87450980	38.61176471
StD	29.65061175	0.3061806938	8.37130088	15.90084491
	Х9	X10	X11	X12
Mean	3.564705882	0.2164705882	4.324627451	0113725490
StD	4.053132527	0.2097807585	4.826807906	0.0257654172
	X13	X14	X15	X16
Mean	4.432941176	0.0830388235	0.1887062745	0190717647
StD	0.475060270	0.1089492984	0.2014787448	0.1422478540

#### Correlation Matrix

	X1	X2	ХЗ	X4	X5	Х6
X1	1.0000	0.0450	0.0794	1209	0.0848	0.0534
X2	0.0450	1.0000	0.4555	0640	0.3367	0.0222
ХЗ	0.0794	0.4555	1.0000	0893	0.4848	0801
X4	1209	0640	0893	1.0000	1003	0572
X5	0.0848	0.3367	0.4848	1003	1.0000	0.6825
X6	0.0534	0.0222	0801	0572	0.6825	1.0000
X7	0127	0.0699	0.0255	0560	1185	1122
X8	0.0736	0.0004	0.0746	0695	0811	0978
Х9	0304	0527	0424	0.9081	0405	0394
X10	0.2227	0.1193	0.2117	0.1773	0.1867	0.0177
X11	0.0391	0.0021	0.0284	0.4334	0.1235	0.0518
X12	0.1202	0.0837	0.1238	0.1839	0.1509	0.0559
X13	0.1022	0.1201	0.1302	1068	0.2738	0.1785
X14	0258	0997	0587	1452	0263	0.0335
X15	0.4730	0448	0.1214	2054	0.0876	0.0386
X16	3549	0.0164	1129	0.1360	0591	0175
	X7	X8	Х9	X10	X11	X12
	XI	λO	λo	X10	XII	X12
X1	0127	0.0736	0304	0.2227	0.0391	0.1202
X2	0.0699	0.0004	0527	0.1193	0.0021	0.0837
ХЗ	0.0255	0.0746	0424	0.2117	0.0284	0.1238
X4	0560	0695	0.9081	0.1773	0.4334	0.1839
X5	1185	0811	0405	0.1867	0.1235	0.1509
X6	1122	0978	0394	0.0177	0.0518	0.0559
X7	1.0000	0.0396	0796	0.0360	1048	0.0405
X8	0.0396	1.0000	0398	0.0449	1242	0998
X9	0796	0398	1.0000	0.4230	0.5969	0.3588
X10	0.0360	0.0449	0.4230	1.0000	0.4278	0.6309
X11	1048	1242	0.5969	0.4278	1.0000	0.5276
X12	0.0405	0998	0.3588	0.6309	0.5276	1.0000
X13	0.0138	0.3109	0592	0.0501	0.0026	0.0561
X14	0301	0505	1189	0.0208	0766	0120
X15	0197	0083	1236	0.2576	0397	0.0952
X16	0404	0650	0.1110	1232	0.0654	1075

#### Correlation Matrix

	X13	X14	X15	X16
X1	0.1022	0258	0.4730	3549
X2	0.1201	0997	0448	0.0164
ХЗ	0.1302	0587	0.1214	1129
X4	1068	1452	2054	0.1360
X5	0.2738	0263	0.0876	0591
X6	0.1785	0.0335	0.0386	0175
X7	0.0138	0301	0197	0404
X8	0.3109	0505	0083	0650
X9	0592	1189	1236	0.1110
X10	0.0501	0.0208	0.2576	1232
X11	0.0026	0766	0397	0.0654
X12	0.0561	0120	0.0952	1075
X13	1.0000	0.0324	0.0296	0.0247
X14	0.0324	1.0000	0.5332	1165
X15	0.0296	0.5332	1.0000	3571
X16	0.0247	1165	3571	1.0000

#### Eigenvalues of the Correlation Matrix

	Eigenvalue	Difference	Proportion	Cumulative
PRIN1	2.95192	0.411360	0.184495	0.18450
PRIN2	2.54056	0.647996	0.158785	0.34328
PRIN3	1.89256	0.415849	0.118285	0.46157
PRIN4	1.47672	0.238840	0.092295	0.55386
PRIN5	1.23788	0.194781	0.077367	0.63123
PRIN6	1.04309	0.049113	0.065193	0.69642
PRIN7	0.99398	0.147653	0.062124	0.75854
PRIN8	0.84633	0.139435	0.052895	0.81144
PRIN9	0.70689	0.110006	0.044181	0.85562
PRIN10	0.59689	0.048227	0.037305	0.89293
PRIN11	0.54866	0.103186	0.034291	0.92722
PRIN12	0.44547	0.134873	0.027842	0.95506
PRIN13	0.31060	0.064590	0.019413	0.97447
PRIN14	0.24601	0.131343	0.015376	0.98985
PRIN15	0.11467	0.066897	0.007167	0.99701
PRIN16	0.04777	•	0.002986	1.00000


#### Eigenvectors

			DDTNO	DD THA	DDTNE	DDTNO
	PRIN1	PRIN2	PRIN3	PRIN4	PRIN5	PRIN6
X1	0.056826	0.318674	285201	0.081309	0.137965	495270
X2	0.067830	0.235451	0.335810	0.310093	292900	0.101180
ХЗ	0.096188	0.330002	0.245373	0.339276	253302	0.121283
X4	0.398864	303594	003775	027272	0.096290	003345
X5	0.134888	0.404963	0.410763	261959	029507	031967
X6	0.057073	0.237911	0.281905	557273	0.164459	145964
X7	048540	0.002282	045285	0.358019	121465	0.119405
<b>X8</b>	065224	0.065524	0.007594	0.378947	0.639673	0.076235
X9	0.490947	222781	050098	009589	0.118904	0.022978
X10	0.406299	0.206417	155387	0.141638	015662	0.085916
X11	0.462080	047222	023654	081854	0.005670	0.026549
X12	0.410732	0.138599	101740	0.055602	089131	0.060158
X13	0.011768	0.227739	0.202543	0.085440	0.587403	0.242760
X14	084111	0.169559	341109	273598	035709	0.659260
X15	007796	0.377117	450166	113853	029465	0.160680
X16	0.012778	283780	0.312684	073219	0.018527	0.394645
	PRIN7	PRIN8	PRIN9	PRIN10	PRIN11	PRIN12
X1	073833	0.042686	0.555706	0.085862	038640	0.095685
X2	177240	0.112723	0.263725	112735	0.700735	0.063097
ХЗ	329815	0.060309	173882	0.048538	527599	0.040761
X4	233492	0.469069	0.025646	039257	0.002294	158848
X5	007165	0.134937	116326	0.118194	163526	0.035838
X6	0.245137	0.205858	077902	0.211735	0.180387	0.024521
X7	0.711538	0.528518	0.075036	0.074199	134766	0.146284
X8	115864	011236	310862	0.417986	0.208654	0.278130
Х9	172252	0.299252	0.028521	0.028132	0.000958	117891
X10	0.156841	227172	078093	0.340952	0.073766	412003
X11	0.050808	195695	0.046996	187773	082266	0.770502
X12	0.342325	376674	139256	128789	0.113981	120279
X13	0.104641	032636	0.250280	567090	154164	230834
X14	105397	0.154471	058232	071101	0.152969	0.119021
X15	148770	0.122682	0.194420	0.166367	102319	0.002442
X16	0.041900	245863	0.580120	0.462378	159046	0.009253

## Eigenvectors

	PRIN13	PRIN14	PRIN15	PRIN16
X1	0.236579	0.389520	017158	0.029110
X2	057891	094443	0.032451	017107
ХЗ	0.168731	0.089896	0.407517	0.002936
X4	0.175781	085388	044869	0.629693
X5	012925	0.050839	708357	016140
X6	0.062901	038011	0.556605	0.006582
X7	022358	0.009974	033309	019390
X8	0.141629	054077	061843	0.014204
Х9	006363	0.039670	0.007152	745439
X10	519134	0.247149	0.059743	0.180520
X11	286584	020647	0.058552	0.107164
X12	0.656044	176959	051699	014003
X13	127726	044803	0.062607	0.012664
X14	0.162831	0.478428	014199	0.021762
X15	104065	700432	014190	025564
X16	0.144592	032043	003455	0.014896

Contour plot of PRIN2\*PRIN1.



Symbol	PRIN3	Symbol	PRIN3	Symbol	PRIN3
	-54	++++	-1 - 0	****	3 - 4
1111	-43	00000	0 - 1	#####	4 - 5
	-32	XXXXX	1 - 2		
=====	-21	wwww	2 - 3		

NOTE: 80 obs hidden.


Prior Communality Estimates: ONE

Eigenvalues of	the Correlation	Matrix:	Total = 16	Average = 1
	1	2	3	4
Eigenvalue	2.9519	2.5406	1.8926	1.4767
Difference	0.4114	0.6480	0.4158	0.2388
Proportion	0.1845	0.1588	0.1183	0.0923
Cumulative	0.1845	0.3433	0.4616	0.5539
	5	6	7	8
Eigenvalue	1.2379	1.0431	0.9940	0.8463
Difference	0.1948	0.0491	0.1477	0.1394
Proportion	0.0774	0.0652	0.0621	0.0529
Cumulative	0.6312	0.6964	0.7585	0.8114
	9	10	11	12
Eigenvalue	0.7069	0.5969	0.5487	0.4455
Difference	0.1100	0.0482	0.1032	0.1349
Proportion	0.0442	0.0373	0.0343	0.0278
Cumulative	0.8556	0.8929	0.9272	0.9551
	13	14	15	16
Eigenvalue	0.3106	0.2460	0.1147	0.0478
Difference	0.0646	0.1313	0.0669	
Proportion	0.0194	0.0154	0.0072	0.0030
Cumulative	0.9745	0.9898	0.9970	1.0000

<sup>8</sup> factors will be retained by the NFACTOR criterion.

Initial Factor Method: Principal Components

#### Scree Plot of Eigenvalues



#### Factor Pattern

	FACTOR1	FACTOR2	FACTOR3	FACTOR4
X1	0.09763	0.50794	-0.39235	0.09881
X2	0.11654	0.37529	0.46198	0.37683
Х3	0.16526	0.52599	0.33756	0.41229
X4	0.68529	-0.48390	-0.00519	-0.03314
X5	0.23175	0.64548	0.56509	-0.31833
X6	0.09806	0.37921	0.38782	-0.67720
X7	-0.08340	0.00364	-0.06230	0.43507
X8	-0.11206	0.10444	0.01045	0.46050
X9	0.84350	-0.35509	-0.06892	-0.01165
X10	0.69807	0.32901	-0.21377	0.17212
X11	0.79391	-0.07527	-0.03254	-0.09947
X12	0.70568	0.22091	-0.13996	0.06757
X13	0.02022	0.36300	0.27864	0.10383
X14	-0.14451	0.27026	-0.46927	-0.33248
X15	-0.01339	0.60109	-0.61930	-0.13835
X16	0.02195	-0.45232	0.43016	-0.08898

#### Factor Pattern

	FACTOR5	FACTOR6	FACTOR7	FACTOR8
X1	0.15350	-0.50583	-0.07361	0.03927
X2	-0.32588	0.10334	-0.17671	0.10370
ХЗ	-0.28182	0.12387	-0.32882	0.05548
X4	0.10713	-0.00342	-0.23279	0.43153
X5	-0.03283	-0.03265	-0.00714	0.12414
X6	0.18298	-0.14908	0.24440	0.18938
X7	-0.13514	0.12195	0.70939	0.48622
X8	0.71170	0.07786	-0.11551	-0.01034
Х9	0.13229	0.02347	-0.17173	0.27530
X10	-0.01743	0.08775	0.15637	-0.20899
X11	0.00631	0.02711	0.05065	-0.18003
X12	-0.09917	0.06144	0.34129	-0.34653
X13	0.65354	0.24794	0.10433	-0.03002
X14	-0.03973	0.67332	-0.10508	0.14211
X15	-0.03278	0.16411	-0.14832	0.11286
X16	0.02061	0.40306	0.04177	-0.22618

Variance explained by each factor

FACTOR1 FACTOR2 FACTOR3 FACTOR4 2.951921 2.540561 1.892564 1.476715

FACTOR5 FACTOR6 FACTOR7 FACTOR8
1.237875 1.043094 0.993981 0.846328

Final Communality Estimates: Total = 12.983040

X1	X2	X3	X4	X5	X6
0.717622	0.668697	0.793881	0.956809	0.908616	0.913718
X7	X8	X9	X10	X11	X12
0.972911	0.761661	0.965810	0.746999	0.682658	0.821119
	X14 0.910845	X15 0.826901	X16 0.613818		

# Orthogonal Transformation Matrix

	1	2	3	4
1	0.72997	0.64875	0.12671	0.13368
2	0.21309	-0.39076	0.42430	0.46422
3	-0.16824	-0.03146	0.48169	0.45781
4	0.07703	-0.03809	-0.65552	0.45948
5	-0.06362	0.15669	0.13859	-0.40304
6	0.10961	0.00279	-0.11862	0.16238
7	0.35651	-0.31314	0.23637	-0.37393
8	-0.49430	0.54897	0.23028	0.13150
	5	6	7	8
	5	,	•	
1	5 0.02827	6	7	8 -0.06416
1 2		,	•	
•	0.02827	-0.07722	-0.03825	-0.06416
2	0.02827 0.50966	-0.07722 0.32218	-0.03825 0.20676	-0.06416 -0.00812
2	0.02827 0.50966 -0.51714	-0.07722 0.32218 -0.49112	-0.03825 0.20676 0.13582	-0.06416 -0.00812 -0.04485
2 3 4	0.02827 0.50966 -0.51714 0.11764	-0.07722 0.32218 -0.49112 -0.29796	-0.03825 0.20676 0.13582 0.35050	-0.06416 -0.00812 -0.04485 0.35540
2 3 4 5	0.02827 0.50966 -0.51714 0.11764 0.07653	-0.07722 0.32218 -0.49112 -0.29796 -0.05518	-0.03825 0.20676 0.13582 0.35050 0.87452	-0.06416 -0.00812 -0.04485 0.35540 -0.12676
2 3 4 5 6	0.02827 0.50966 -0.51714 0.11764 0.07653 -0.62386	-0.07722 0.32218 -0.49112 -0.29796 -0.05518 0.70296	-0.03825 0.20676 0.13582 0.35050 0.87452 0.21862	-0.06416 -0.00812 -0.04485 0.35540 -0.12676 0.12806

#### Rotated Factor Pattern

	FACTOR1	FACTOR2	FACTOR3	FACTOR4
X1	0.14226	-0.05931	0.04705	0.00331
X2	0.03415	-0.03844	0.07420	0.80227
ХЗ	0.09454	-0.03504	0.01776	0.87420
X4	0.09196	0.96167	-0.03967	-0.05058
X5	0.12173	-0.04238	0.81033	0.46998
X6	0.00052	-0.01528	0.94847	-0.10891
X7	0.01842	-0.04619	-0.07778	0.03487
X8	-0.09865	0.01085	-0.20700	0.01751
Х9	0.34761	0.91430	-0.03099	-0.03808
X10	0.79868	0.15830	-0.01173	0.16259
X11	0.67092	0.43564	0.08636	-0.03017
X12	0.89696	0.06085	0.05128	0.04061
X13	0.09086	-0.08751	0.30165	0.08038
X14	-0.02594	-0.06537	0.01078	-0.07814
X15	0.12325	-0.11510	0.01265	0.04032
X16	0.00998	0.04795	-0.01077	-0.03921

# Rotated Factor Pattern

	FACTOR5	FACTOR6	FACTOR7	FACTOR8
X1	0.82107	-0.02518	0.10634	-0.07443
X2	-0.04510	-0.08800	0.00533	0.08430
ХЗ	0.10011	0.03495	0.07824	-0.04263
X4	-0.09496	-0.08436	-0.05725	-0.00073
X5	0.05185	0.01110	0.04932	-0.09610
X6	0.03464	0.00727	0.00498	-0.02725
X7	0.01681	-0.02124	0.02283	0.98077
X8	0.11654	-0.06769	0.83096	-0.00102
X9	-0.04596	-0.05245	-0.00522	-0.04168
X10	0.19716	0.10304	0.08126	0.03730
X11	-0.07295	-0.06385	-0.06795	-0.14267
X12	0.04922	-0.00789	-0.04388	0.06470
X13	-0.07028	0.06308	0.77320	0.02915
X14	-0.04184	0.94754	-0.00962	0.00176
X15	0.54795	0.70298	-0.00179	-0.04737
X16	-0.76748	-0.09996	0.04680	-0.09246

## Variance explained by each factor

FACTOR1	FACTOR2	FACTOR3	FACTOR4
2.101303	2.017275	1.717327	1.690859
FACTOR5	FACTOR6	FACTOR7	FACTOR8
1.657682	1.445420	1.327499	1.025676

Final Communality Estimates: Total = 12.983040

X1 X2 ХЗ X4 X5 X6 0.717622 0.668697 0.793881 0.956809 0.908616 0.913718 X7 X8 Х9 X10 X11 X12 0.972911 0.761661 0.965810 0.746999 0.682658 0.821119 X13 X14 X15 X16 0.720972 0.910845 0.826901 0.613818

Scoring Coefficients Estimated by Regression

Squared Multiple Correlations of the Variables with each Factor

FACTOR1 FACTOR2 FACTOR3 FACTOR4
1.000000 1.000000 1.000000

FACTOR5 FACTOR6 FACTOR7 FACTOR8
1.000000 1.000000 1.000000

## Standardized Scoring Coefficients

	FACTOR1	FACTOR2	FACTOR3	FACTOR4
X1	-0.00360	0.01405	0.01319	-0.06186
X2	-0.05746	0.03245	-0.04406	0.50763
Х3	-0.04636	0.04341	-0.11090	0.55690
X4	-0.21379	0.59278	0.03643	0.05025
X5	-0.03220	0.02900	0.43500	0.19366
X6	-0.06176	0.04286	0.61395	-0.18847
X7	-0.00187	0.04605	0.06003	-0.01115
X8	-0.05965	0.06724	-0.14858	-0.01793
X9	-0.04240	0.49093	0.01074	0.02098
X10	0.41646	-0.08487	-0.07751	0.02161
X11	0.31356	0.05730	0.01806	-0.06148
X12	0.54536	-0.22299	-0.02965	-0.08089
X13	0.06351	-0.02765	0.14794	-0.05115
X14	-0.03659	0.06510	-0.00025	0.00523
X15	-0.00525	0.03469	-0.02329	0.02592
X16	0.11299	-0.08665	-0.02076	-0.00011

## Standardized Scoring Coefficients

	FACTOR5	FACTOR6	FACTOR7	FACTOR8
X1	0.54915	-0.18305	0.03758	-0.07745
X2	-0.05317	-0.01481	-0.05787	0.05864
ХЗ	0.01093	0.05414	-0.00591	-0.07667
X4	0.05750	0.05720	0.00390	0.07401
X5	0.00254	0.00201	-0.02097	-0.02297
X6	0.03675	-0.02452	-0.01906	0.08978
X7	0.00953	0.01238	-0.00683	0.97341
X8	0.06263	-0.04207	0.64204	-0.04248
Х9	0.04141	0.05334	0.04203	0.02185
X10	0.01783	0.03131	0.05545	0.02336
X11	-0.07530	-0.03272	-0.02515	-0.11624
X12	-0.07998	-0.05611	-0.03393	0.04945
X13	-0.12332	0.06630	0.58673	0.03787
X14	-0.20081	0.73174	0.02013	0.03426
X15	0.22597	0.42706	-0.01891	-0.03334
X16	-0.51878	0.06124	0.08104	-0.09831

# General Linear Models Procedure Class Level Information

Class	Levels	Values
X17	72	Adair Alfalfa Atoka Beaver Beckham Blaine Bryan Caddo Canadian Carter Cherokee Choctaw Cimarron Clevelan Coal Comanche Craig Creek Custer Delaware Dewey Ellis Garfield Garvin Grady Grant Greer Haskell Hughes Jackson Jefferso Johnson Kay Kingfish Latimer LeFlore Lincoln Logan Love Major Marshall Mayes McClain McCurtai Mcintosh Murray Muskogee Noble Nowata Okfuskee Oklahoma Okmulgee Osage Ottawa Pawnee Payne Pittsbur Pontotoc Pottawat Pushmata Rogers Seminole Sequoyah Stephens Texas Tillman Tulsa Wagoner Washingt Washita Woods Woodward
X18	3	Overlay Resurfac Surfacin
X19	48	a ab ac ad ae af ag ah ai aj ak al am an ao ap aq ar as at au av aw ax b c d f g h i j k l m n o p q r s t u v w x y z
X20	44	a ab ac ad ae af ag ah ai aj ak al am an ao ap aq ar as b c d e f g h i j k l m n o p q r s t u v w x y z
X21	2	English EnglishM
X22	2	FALSE TRUE

Number of observations in data set = 255

#### General Linear Models Procedure

Dependent Variable: Y

Source	DF	Sum of Squares	F Value	Pr > F
Model	159	0.31321238	1.40	0.0370
Error	95	0.13365632		
Corrected Total	254	0.44686871		
	R-Square	C.V.		Y Mean
	0.700905	-237.2325	-0.	01581098
Source	DF	Type I SS	F Value	Pr > F
FACTOR1	1	0.05753182	40.89	0.0001
FACTOR2	1	0.00028285	0.20	0.6549
FACTOR3	1	0.00000449	0.00	0.9551
FACTOR4	1	0.01378888	9.80	0.0023
FACTOR5	1	0.00425945	3.03	0.0851
FACTOR6	1	0.00000584	0.00	0.9487
FACTOR7	1	0.00193581	1.38	0.2437
FACTOR8	1	0.00041728	0.30	0.5873
X17	71	0.12063844	1.21	0.1943
X18	2	0.00111905	0.40	0.6730
X19	46	0.04901517	0.76	0.8512
X20	30	0.06240888	1.48	0.0795
X21	1	0.00000362	0.00	0.9597
X22	1	0.00180080	1.28	0.2608
Source	DF	Type III SS	F Value	Pr > F
FACTOR1	1	0.0000013	0.00	0.9922
FACTOR2	1	0.00000932	0.01	0.9353
FACTOR3	1	0.00063776	0.45	0.5024
FACTOR4	1	0.00492327	3.50	0.0645
FACTOR5	1	0.00002707	0.02	0.8900

#### General Linear Models Procedure

Dependent Variable: Y

Source	DF	Type III SS	F Value	Pr > F
FACTOR6	1	0.0000560	0.00	0.9498
FACTOR7	· 1	0.0000002	0.00	0.9968
FACTOR8	1	0.00007128	0.05	0.8224
X17	58	0.06924514	0.85	0.7487
X18	2	0.00555325	1.97	0.1446
X19	45	0.05230091	0.83	0.7594
X20	30	0.06386979	1.51	0.0679
X21	1	0.0000632	0.00	0.9467
X22	• 1	0.00180080	1.28	0.2608

# General Linear Models Procedure Class Level Information

Class	Levels	Values
X17	72	Adair Alfalfa Atoka Beaver Beckham Blaine Bryan Caddo Canadian Carter Cherokee Choctaw Cimarron Clevelan Coal Comanche Craig Creek Custer Delaware Dewey Ellis Garfield Garvin Grady Grant Greer Haskell Hughes Jackson Jefferso Johnson Kay Kingfish Latimer LeFlore Lincoln Logan Love Major Marshall Mayes McClain McCurtai Mcintosh Murray Muskogee Noble Nowata Okfuskee Oklahoma Okmulgee Osage Ottawa Pawnee Payne Pittsbur Pontotoc Pottawat Pushmata Rogers Seminole Sequoyah Stephens Texas Tillman Tulsa Wagoner Washingt Washita Woods Woodward
X18	3	Overlay Resurfac Surfacin
X19	48	a ab ac ad ae af ag ah ai aj ak al am an ao ap aq ar as at au av aw ax b c d f g h i j k l m n o p q r s t u v w x y z
X20	44	a ab ac ad ae af ag ah ai aj ak al am an ao ap aq ar as b c d e f g h i j k l m n o p q r s t u v w x y z
X21	2	English EnglishM
X22	2	FALSE TRUE

Number of observations in data set = 255

#### General Linear Models Procedure

Dependent Variable: Y

Source	DF	Sum of Squares	F Value	Pr > F
Model	46	0.17513113	2.91	0.0001
Error	208	0.27173758		
Corrected Total	254	0.44686871		
· .	R-Square	c.v.		Y Mean
	0.391907	-228.6043	-0.0	01581098
0	DE		E Value	D
Source	DF	Type I SS	F Value	Pr > F
FACTOR1	1	0.05753182	44.04	0.0001
FACTOR4	1	0.01378888	10.55	0.0014
FACTOR5	1	0.00425945	3.26	0.0724
X20	43	0.09955098	1.77	0.0045
Source	DF	Type III SS	F Value	Pr > F
FACTOR1	1	0.04634461	35.47	0.0001
FACTOR4	1	0.02410857	18.45	0.0001
FACTOR5	. 1	0.00289323	2.21	0.1382
X20	43	0.09955098	1.77	0.0045

Model: MODEL1

Dependent Variable: Y

#### Analysis of Variance

Source Prob>F	DF	Sum Squar		Mean Square	F Value
Model 0.0001	46	0.175	13	0.00381	2.914
Error	208	0.271	74	0.00131	
C Total	254	0.446	87	•	
Root MSE Dep Mean C.V.	-0.	03614 01581 60429	R-squ Adj F		0.3919 0.2574

# Parameter Estimates

INTERCEP 1 -0.021884 0.01635636 -1.333 FACTOR1 1 0.016076 0.00269917 5.95 FACTOR4 1 0.011505 0.00267824 4.296 FACTOR5 1 0.004255 0.00285926 1.486 D1 1 0.044729 0.04111842 1.086 D2 1 0.000822 0.01923396 0.046 D3 1 0.004939 0.02210944 0.225 D4 1 -0.003938 0.02335150 -0.166 D5 1 -0.000225 0.02792194 -0.006 D6 1 0.058595 0.03060656 1.916 D7 1 -0.034200 0.02249098 -1.526 D8 1 0.027047 0.02085936 1.296 D9 1 -0.012897 0.02040902 -0.636 D10 1 0.027271 0.02312012 1.186 D11 1 0.025768 0.01918347 1.346 D13 1 -0.001298 0.02144332 -0.066 D14 1 0.053369 0.03028749 1.766 D15 1 -0.036057 0.02457192 -1.466 D16 1 0.018909 0.02032278 0.936 D17 1 -0.037976 0.02673819 -1.426 D18 1 0.001535 0.02652006 0.056 D19 1 0.034770 0.03976844 0.876 D20 1 -0.019107 0.03066193 -0.626					· ·
INTERCEP 1 -0.021884 0.01635636 -1.333 FACTOR1 1 0.016076 0.00269917 5.95 FACTOR4 1 0.011505 0.00267824 4.296 FACTOR5 1 0.004255 0.00285926 1.486 D1 1 0.044729 0.04111842 1.086 D2 1 0.000822 0.01923396 0.046 D3 1 0.004939 0.02210944 0.225 D4 1 -0.003938 0.02335150 -0.166 D5 1 -0.000225 0.02792194 -0.006 D6 1 0.058595 0.03060656 1.916 D7 1 -0.034200 0.02249098 -1.526 D8 1 0.027047 0.02085936 1.296 D9 1 -0.012897 0.02040902 -0.636 D10 1 0.027271 0.02312012 1.186 D11 1 0.025768 0.01918347 1.346 D13 1 -0.001298 0.02144332 -0.066 D14 1 0.053369 0.03028749 1.766 D15 1 -0.036057 0.02457192 -1.466 D16 1 0.018909 0.02032278 0.936 D17 1 -0.037976 0.02673819 -1.426 D18 1 0.001535 0.02652006 0.056 D19 1 0.034770 0.03976844 0.876 D20 1 -0.019107 0.03066193 -0.626		1	Parameter	Standard	T for HO:
FACTOR1 1 0.016076 0.00269917 5.95 FACTOR4 1 0.011505 0.00267824 4.29 FACTOR5 1 0.004255 0.00285926 1.48 D1 1 0.044729 0.04111842 1.08 D2 1 0.000822 0.01923396 0.04 D3 1 0.004939 0.02210944 0.22 D4 1 -0.003938 0.02335150 -0.16 D5 1 -0.000225 0.02792194 -0.00 D6 1 0.058595 0.03060656 1.91 D7 1 -0.034200 0.02249098 -1.52 D8 1 0.027047 0.02085936 1.29 D9 1 -0.012897 0.02040902 -0.63 D10 1 0.027271 0.02312012 1.18 D11 1 0.015430 0.02663478 0.57 D12 1 0.025768 0.01918347 1.34 D13 1 -0.001298 0.02144332 -0.06 D14 1 0.053369 0.03028749 1.76 D15 1 -0.036057 0.02457192 -1.46 D16 1 0.018909 0.02032278 0.93 D17 1 -0.037976 0.02673819 -1.42 D18 1 0.001535 0.02652006 0.05 D19 1 0.034770 0.03066193 -0.62 D21 1 0.031827 0.02213363 1.43	Variable	DF	Estimate	Error	Parameter=0
FACTOR1 1 0.016076 0.00269917 5.95 FACTOR4 1 0.011505 0.00267824 4.29 FACTOR5 1 0.004255 0.00285926 1.48 D1 1 0.044729 0.04111842 1.08 D2 1 0.000822 0.01923396 0.04 D3 1 0.004939 0.02210944 0.22 D4 1 -0.003938 0.02335150 -0.16 D5 1 -0.000225 0.02792194 -0.00 D6 1 0.058595 0.03060656 1.91 D7 1 -0.034200 0.02249098 -1.52 D8 1 0.027047 0.02085936 1.29 D9 1 -0.012897 0.02040902 -0.63 D10 1 0.027271 0.02312012 1.18 D11 1 0.015430 0.02663478 0.57 D12 1 0.025768 0.01918347 1.34 D13 1 -0.001298 0.02144332 -0.06 D14 1 0.053369 0.03028749 1.76 D15 1 -0.036057 0.02457192 -1.46 D16 1 0.018909 0.02032278 0.93 D17 1 -0.037976 0.02673819 -1.42 D18 1 0.001535 0.02652006 0.05 D19 1 0.034770 0.03066193 -0.62 D21 1 0.031827 0.02213363 1.43					
FACTOR4 1 0.011505 0.00267824 4.29 FACTOR5 1 0.004255 0.00285926 1.48 D1 1 0.044729 0.04111842 1.08 D2 1 0.000822 0.01923396 0.04 D3 1 0.004939 0.02210944 0.22 D4 1 -0.003938 0.02335150 -0.16 D5 1 -0.000225 0.02792194 -0.00 D6 1 0.058595 0.03060656 1.91 D7 1 -0.034200 0.02249098 -1.52 D8 1 0.027047 0.02085936 1.29 D9 1 -0.012897 0.02040902 -0.63 D10 1 0.027271 0.02312012 1.18 D11 1 0.015430 0.02663478 0.57 D12 1 0.025768 0.01918347 1.34 D13 1 -0.001298 0.02144332 -0.06 D14 1 0.053369 0.03028749 1.76 D15 1 -0.036057 0.02457192 -1.46 D16 1 0.018909 0.02032278 0.93 D17 1 -0.037976 0.02673819 -1.42 D18 1 0.001535 0.02652006 0.05 D19 1 0.034770 0.03976844 0.87 D20 1 -0.019107 0.03066193 -0.62 D21 1 0.031827 0.02213363 1.43	INTERCEP	1	-0.021884	0.01635636	-1.338
FACTOR5 1 0.004255 0.00285926 1.488   D1 1 0.044729 0.04111842 1.088   D2 1 0.000822 0.01923396 0.048   D3 1 0.004939 0.02210944 0.22   D4 1 -0.003938 0.02335150 -0.168   D5 1 -0.000225 0.02792194 -0.000   D6 1 0.058595 0.03060656 1.91   D7 1 -0.034200 0.02249098 -1.52   D8 1 0.027047 0.02085936 1.29   D9 1 -0.012897 0.02040902 -0.63   D10 1 0.027271 0.02312012 1.188   D11 1 0.015430 0.02663478 0.57   D12 1 0.025768 0.01918347 1.34   D13 1 -0.001298 0.02144332 -0.06   D14 1 0.053369 0.03028749 1.76   D15 1 -0.036057 0.02457192 -1.46   D16 1 0.018909 0.02032278 0.93   D17 1 -0.037976 0.02673819 -1.42   D18 1 0.001535 0.02652006 0.05   D19 1 0.034770 0.03976844 0.87   D20 1 -0.019107 0.03066193 -0.62   D21 1 0.031827 0.02213363 1.43   D33	FACTOR1	1	0.016076	0.00269917	5.956
D1         1         0.044729         0.04111842         1.08           D2         1         0.000822         0.01923396         0.04           D3         1         0.004939         0.02210944         0.22           D4         1         -0.003938         0.02335150         -0.16           D5         1         -0.000225         0.02792194         -0.00           D6         1         0.058595         0.03060656         1.91           D7         1         -0.034200         0.02249098         -1.52           D8         1         0.027047         0.02085936         1.29           D9         1         -0.012897         0.02040902         -0.63           D10         1         0.027271         0.02312012         1.18           D11         1         0.015430         0.02663478         0.57           D12         1         0.025768         0.01918347         1.34           D13         1         -0.001298         0.02144332         -0.06           D14         1         0.053369         0.03028749         1.76           D15         1         -0.036057         0.02457192         -1.46	FACTOR4	1	0.011505	0.00267824	4.296
D2       1       0.000822       0.01923396       0.04         D3       1       0.004939       0.02210944       0.22         D4       1       -0.003938       0.02335150       -0.16         D5       1       -0.000225       0.02792194       -0.00         D6       1       0.058595       0.03060656       1.91         D7       1       -0.034200       0.02249098       -1.52         D8       1       0.027047       0.02085936       1.29         D9       1       -0.012897       0.02040902       -0.63         D10       1       0.027271       0.02312012       1.18         D11       1       0.015430       0.02663478       0.57         D12       1       0.025768       0.01918347       1.34         D13       1       -0.001298       0.02144332       -0.06         D14       1       0.053369       0.03028749       1.76         D15       1       -0.036057       0.02457192       -1.46         D16       1       0.018909       0.02032278       0.93         D17       1       -0.037976       0.02652006       0.05         D19	FACTOR5	1 .	0.004255	0.00285926	1.488
D3       1       0.004939       0.02210944       0.22         D4       1       -0.003938       0.02335150       -0.16         D5       1       -0.000225       0.02792194       -0.00         D6       1       0.058595       0.03060656       1.91         D7       1       -0.034200       0.02249098       -1.52         D8       1       0.027047       0.02085936       1.29         D9       1       -0.012897       0.02040902       -0.63         D10       1       0.027271       0.02312012       1.18         D11       1       0.015430       0.02663478       0.57         D12       1       0.025768       0.01918347       1.34         D13       1       -0.001298       0.02144332       -0.06         D14       1       0.053369       0.03028749       1.76         D15       1       -0.036057       0.02457192       -1.46         D16       1       0.018909       0.02032278       0.93         D17       1       -0.037976       0.02652006       0.05         D19       1       0.034770       0.03976844       0.87         D20	D1	1	0.044729	0.04111842	1.088
D4       1       -0.003938       0.02335150       -0.166         D5       1       -0.000225       0.02792194       -0.006         D6       1       0.058595       0.03060656       1.91         D7       1       -0.034200       0.02249098       -1.52         D8       1       0.027047       0.02085936       1.29         D9       1       -0.012897       0.02040902       -0.63         D10       1       0.027271       0.02312012       1.18         D11       1       0.015430       0.02663478       0.57         D12       1       0.025768       0.01918347       1.34         D13       1       -0.001298       0.02144332       -0.06         D14       1       0.053369       0.03028749       1.76         D15       1       -0.036057       0.02457192       -1.46         D16       1       0.018909       0.02032278       0.93         D17       1       -0.037976       0.02673819       -1.42         D18       1       0.034770       0.03976844       0.87         D20       1       -0.019107       0.03066193       -0.62         D21	D2	1 '	0.000822	0.01923396	0.043
D5       1       -0.000225       0.02792194       -0.000         D6       1       0.058595       0.03060656       1.91         D7       1       -0.034200       0.02249098       -1.52         D8       1       0.027047       0.02085936       1.29         D9       1       -0.012897       0.02040902       -0.63         D10       1       0.027271       0.02312012       1.18         D11       1       0.015430       0.02663478       0.57         D12       1       0.025768       0.01918347       1.34         D13       1       -0.001298       0.02144332       -0.06         D14       1       0.053369       0.03028749       1.76         D15       1       -0.036057       0.02457192       -1.46         D16       1       0.018909       0.02032278       0.93         D17       1       -0.037976       0.02673819       -1.42         D18       1       0.001535       0.02652006       0.05         D19       1       0.034770       0.03976844       0.87         D20       1       -0.019107       0.03066193       -0.62         D21 </td <td>D3</td> <td>1</td> <td>0.004939</td> <td>0.02210944</td> <td>0.223</td>	D3	1	0.004939	0.02210944	0.223
D6       1       0.058595       0.03060656       1.91         D7       1       -0.034200       0.02249098       -1.52         D8       1       0.027047       0.02085936       1.29         D9       1       -0.012897       0.02040902       -0.63         D10       1       0.027271       0.02312012       1.18         D11       1       0.015430       0.02663478       0.57         D12       1       0.025768       0.01918347       1.34         D13       1       -0.001298       0.02144332       -0.06         D14       1       0.053369       0.03028749       1.76         D15       1       -0.036057       0.02457192       -1.46         D16       1       0.018909       0.02032278       0.93         D17       1       -0.037976       0.02673819       -1.42         D18       1       0.034770       0.03976844       0.87         D20       1       -0.019107       0.03066193       -0.62         D21       1       0.031827       0.02213363       1.43	D4	1	-0.003938	0.02335150	-0.169
D7       1       -0.034200       0.02249098       -1.52         D8       1       0.027047       0.02085936       1.29         D9       1       -0.012897       0.02040902       -0.63         D10       1       0.027271       0.02312012       1.18         D11       1       0.015430       0.02663478       0.57         D12       1       0.025768       0.01918347       1.34         D13       1       -0.001298       0.02144332       -0.06         D14       1       0.053369       0.03028749       1.76         D15       1       -0.036057       0.02457192       -1.46         D16       1       0.018909       0.02032278       0.93         D17       1       -0.037976       0.02673819       -1.42         D18       1       0.034770       0.03976844       0.87         D20       1       -0.019107       0.03066193       -0.62         D21       1       0.031827       0.02213363       1.43	D5	1	-0.000225	0.02792194	-0.008
D8       1       0.027047       0.02085936       1.29         D9       1       -0.012897       0.02040902       -0.63         D10       1       0.027271       0.02312012       1.18         D11       1       0.015430       0.02663478       0.57         D12       1       0.025768       0.01918347       1.34         D13       1       -0.001298       0.02144332       -0.06         D14       1       0.053369       0.03028749       1.76         D15       1       -0.036057       0.02457192       -1.46         D16       1       0.018909       0.02032278       0.93         D17       1       -0.037976       0.02673819       -1.42         D18       1       0.001535       0.02652006       0.05         D19       1       0.034770       0.03976844       0.87         D20       1       -0.019107       0.03066193       -0.62         D21       1       0.031827       0.02213363       1.43	D6	1	0.058595	0.03060656	1.914
D9       1       -0.012897       0.02040902       -0.63         D10       1       0.027271       0.02312012       1.18         D11       1       0.015430       0.02663478       0.57         D12       1       0.025768       0.01918347       1.34         D13       1       -0.001298       0.02144332       -0.06         D14       1       0.053369       0.03028749       1.76         D15       1       -0.036057       0.02457192       -1.46         D16       1       0.018909       0.02032278       0.93         D17       1       -0.037976       0.02673819       -1.42         D18       1       0.001535       0.02652006       0.05         D19       1       0.034770       0.03976844       0.87         D20       1       -0.019107       0.03066193       -0.62         D21       1       0.031827       0.02213363       1.43	D7	1	-0.034200	0.02249098	-1.521
D10       1       0.027271       0.02312012       1.186         D11       1       0.015430       0.02663478       0.576         D12       1       0.025768       0.01918347       1.346         D13       1       -0.001298       0.02144332       -0.06         D14       1       0.053369       0.03028749       1.766         D15       1       -0.036057       0.02457192       -1.466         D16       1       0.018909       0.02032278       0.936         D17       1       -0.037976       0.02673819       -1.426         D18       1       0.001535       0.02652006       0.056         D19       1       0.034770       0.03976844       0.876         D20       1       -0.019107       0.03066193       -0.626         D21       1       0.031827       0.02213363       1.436	D8	1	0.027047	0.02085936	1.297
D11       1       0.015430       0.02663478       0.57         D12       1       0.025768       0.01918347       1.34         D13       1       -0.001298       0.02144332       -0.06         D14       1       0.053369       0.03028749       1.76         D15       1       -0.036057       0.02457192       -1.46         D16       1       0.018909       0.02032278       0.93         D17       1       -0.037976       0.02673819       -1.42         D18       1       0.001535       0.02652006       0.05         D19       1       0.034770       0.03976844       0.87         D20       1       -0.019107       0.03066193       -0.62         D21       1       0.031827       0.02213363       1.43	D9	1	-0.012897	0.02040902	-0.632
D12       1       0.025768       0.01918347       1.34         D13       1       -0.001298       0.02144332       -0.06         D14       1       0.053369       0.03028749       1.76         D15       1       -0.036057       0.02457192       -1.46         D16       1       0.018909       0.02032278       0.93         D17       1       -0.037976       0.02673819       -1.42         D18       1       0.001535       0.02652006       0.05         D19       1       0.034770       0.03976844       0.87         D20       1       -0.019107       0.03066193       -0.62         D21       1       0.031827       0.02213363       1.43	D10	1	0.027271	0.02312012	1.180
D13       1       -0.001298       0.02144332       -0.06         D14       1       0.053369       0.03028749       1.76         D15       1       -0.036057       0.02457192       -1.46         D16       1       0.018909       0.02032278       0.93         D17       1       -0.037976       0.02673819       -1.42         D18       1       0.001535       0.02652006       0.05         D19       1       0.034770       0.03976844       0.87         D20       1       -0.019107       0.03066193       -0.62         D21       1       0.031827       0.02213363       1.43	D11	1	0.015430	0.02663478	0.579
D14       1       0.053369       0.03028749       1.76         D15       1       -0.036057       0.02457192       -1.46         D16       1       0.018909       0.02032278       0.93         D17       1       -0.037976       0.02673819       -1.42         D18       1       0.001535       0.02652006       0.05         D19       1       0.034770       0.03976844       0.87         D20       1       -0.019107       0.03066193       -0.62         D21       1       0.031827       0.02213363       1.43	D12	1	0.025768	0.01918347	1.343
D15       1       -0.036057       0.02457192       -1.46         D16       1       0.018909       0.02032278       0.93         D17       1       -0.037976       0.02673819       -1.42         D18       1       0.001535       0.02652006       0.05         D19       1       0.034770       0.03976844       0.87         D20       1       -0.019107       0.03066193       -0.62         D21       1       0.031827       0.02213363       1.43	D13	1	-0.001298	0.02144332	-0.061
D16       1       0.018909       0.02032278       0.936         D17       1       -0.037976       0.02673819       -1.426         D18       1       0.001535       0.02652006       0.056         D19       1       0.034770       0.03976844       0.876         D20       1       -0.019107       0.03066193       -0.626         D21       1       0.031827       0.02213363       1.436	D14	1	0.053369	0.03028749	1.762
D17       1       -0.037976       0.02673819       -1.426         D18       1       0.001535       0.02652006       0.056         D19       1       0.034770       0.03976844       0.876         D20       1       -0.019107       0.03066193       -0.626         D21       1       0.031827       0.02213363       1.436	D15	1	-0.036057	0.02457192	-1.467
D18       1       0.001535       0.02652006       0.05         D19       1       0.034770       0.03976844       0.87         D20       1       -0.019107       0.03066193       -0.62         D21       1       0.031827       0.02213363       1.43	D16	1	0.018909	0.02032278	0.930
D19       1       0.034770       0.03976844       0.876         D20       1       -0.019107       0.03066193       -0.62         D21       1       0.031827       0.02213363       1.436	D17	1 .	-0.037976	0.02673819	-1.420
D20       1       -0.019107       0.03066193       -0.62         D21       1       0.031827       0.02213363       1.43	D18	1	0.001535	0.02652006	0.058
D21 1 0.031827 0.02213363 1.43	D19	1	0.034770	0.03976844	0.874
	D20	1	-0.019107	0.03066193	-0.623
D22 1 -0 111702 0 03072848 -2 91	D21	1	0.031827	0.02213363	1.438
0.111102 0.003120 <del>4</del> 0 •2.01	D22	1 .	-0.111702	0.03972848	-2.812
D23 1 -0.011804 0.02211216 -0.53	D23	1	-0.011804	0.02211216	-0.534
D24 1 0.003557 0.03040019 0.11	D24	1	0.003557	0.03040019	0.117
D25 1 0.014693 0.02129474 0.69	D25	1	0.014693	0.02129474	0.690
	D26	1	0.042427		1.969
D27 1 0.027879 0.03966828 0.700	D27	1	0.027879	0.03966828	0.703
D28 1 -0.008194 0.03133662 -0.26	D28	1	-0.008194	0.03133662	-0.261
D29 1 -0.008718 0.02134196 -0.40	D29	1	-0.008718	0.02134196	-0.408
D30 1 -0.010547 0.01911444 -0.55	D30	1 -	-0.010547	0.01911444	-0.552
		1	0.040807	0.03965707	1.029
	D31	•			
		-		0.02124506	1.297

Variable	DF	Parameter Estimate	Standard Error	T for HO: Parameter=0
D34	1	0.018827	0.02019526	0.932
D35	1	-0.004841	0.01994832	-0.243
D36	1	0.014308	0.02437254	0.587
D37	1	0.044036	0.03997889	1.101
D38	1	-0.000863	0.01801838	-0.048
D39	1	0.009202	0.02305219	0.399
D40	1	0.004821	0.02221163	0.217
D41	1	0.037630	0.02434978	1.545
D42	1	0.003495	0.01930866	0.181
D43	1	-0.006613	0.04236188	-0.156
			•	
Variable	DF	Prob >  T		

Variable	DF	Prob >  T
INTERCEP	1	0.1824
FACTOR1	1	0.0001
FACTOR4	1 -	0.0001
FACTOR5	1	0.1382
D1 .	1	0.2779
D2	1	0.9659
D3	1	0.8235
D4	1	0.8663
D5	1	0.9936
D6	1	0.0569
D7	1	0.1299
D8	. 1	0.1962
D9	1	0.5281
D10	1	0.2395
D11	1	0.5630
D12	1	0.1807
D13	1	0.9518
D14	1	0.0795
D15	1	0.1438
D16	1	0.3532
D17	1	0.1570
D18	1	0.9539
D19	1	0.3830
D20	1	0.5339
D21	1	0.1520

Variable	DF	Prob >  T
D22	1	0.0054
D23	1	0.5940
D24	1	0.9070
D25	1	0.4910
D26	1	0.0503
D27	1	0.4830
D28	1	0.7940
D29	1	0.6833
D30	1	0.5817
D31	1	0.3047
D32	1	0.1962
D33	1	0.9116
D34	1	0.3523
D35	1	0.8085
D36	1	0.5578
D37	1	0.2720
D38	1	0.9618
D39	1	0.6902
D40	1	0.8284
D41	1	0.1238
D42	1	0.8565
D43	1	0.8761

#### VITA

#### Bassam A. Ghulman

#### Candidate for the Degree of

#### Doctor of Philosophy

Thesis: PREDICTING CONSTRUCTION COST GROWTH IN ODOT'S PAVING PROJECTS USING INFORMATION AVAILABLE AT THE BIDDING TIME

Major Field: Civil Engineering

Biographical:

Personal Data: Born in Makkah, Saudi Arabia on June 11, 1968; the son of Ahmed M. Ghulman and Seham A. Shukri.

Education: Graduated from King Faisal High School, Makkah, Saudi Arabia in 1986; received Bachelor of Science degree in Civil Engineering from Umm Al-Qura University, Makkah, Saudi Arabia in August, 1991; received Master of Science degree in Civil Engineering from Oklahoma State University, Stillwater, Oklahoma in May, 1997; completed requirements for Doctor of Philosophy degree in Civil Engineering at Oklahoma State University in May, 2000.

Professional Experience: Teaching Assistant, 1994 to 1995; Senior Civil Engineer, 1993 to 1994; Project Engineer, 1991 to 1993.

Professional Affiliations: Phi Kappa Phi Honor Society; Association for the Advancement of Cost Engineering International; American Society of Civil Engineers; American Concrete Institute; National Geographic Society; Saudi Computer Society; Al-Umran Saudi Association.